

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	A1-GE	GABLE	1	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:49 2023 Page 1
 ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-MAihl16AzvjEgk2lsTDFgDIOMx1UsGaWA9XzFki

-0-11-0	6-8-13	11-9-2	16-6-6	24-11-8	30-6-14	33-4-10	41-9-4	51-9-4	61-11-0	62-10-0
0-11-0	6-8-13	5-0-5	4-9-4	8-5-2	5-7-6	2-9-12	8-4-10	10-0-0	10-1-12	0-11-0

Scale = 1:112.5




Plate Offsets (X,Y)--	[8:0-2-8,0-3-12], [10:0-3-0,0-4-4], [14:0-2-12,Edge], [18:0-6-5,0-2-14], [34:0-1-9,0-1-8], [37:0-1-9,0-1-8], [39:0-1-9,0-1-8]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.57	Vert(LL) -0.27 19-21 >999 360	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.60	Vert(CT) -0.36 19-21 >999 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.85	Horz(CT) 0.03 14 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-S	Wind(LL) 0.16 14-16 >999 240		Weight: 476 lb FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x6 SP No.1	TOP CHORD Structural wood sheathing directly applied or 5-11-9 oc purlins. Except: 1 Row at midpt 9-18
BOT CHORD 2x6 SP No.1	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.2	WEBS 1 Row at midpt 13-18
OTHERS 2x4 SP No.2	JOINTS 1 Brace at Jt(s): 9

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 23=1945/0-3-8 (min. 0-2-5), 18=2517/0-3-8 (min. 0-3-0), 14=566/0-3-0 (min. 0-1-8)
 Max Horz 23=-240(LC 17)
 Max Uplift 23=-452(LC 12), 18=-746(LC 13), 14=-393(LC 9)
 Max Grav 23=1945(LC 1), 18=2532(LC 2), 14=567(LC 24)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1006/1018, 3-4=-1187/1349, 4-5=-1611/216, 5-6=-1575/287, 6-7=-1447/338, 7-8=-1440/249, 8-9=-2214/763, 9-18=-2232/761, 8-10=-693/1050, 10-11=-706/970, 11-12=-812/1056, 12-13=-838/925, 13-14=-809/686
 BOT CHORD 2-23=-928/1009, 22-23=-134/1252, 21-22=-134/1252, 21-48=0/1022, 48-49=0/1022, 20-49=0/1022, 19-20=0/1022, 19-50=0/1193, 50-51=0/1193, 18-51=0/1193, 17-18=-587/720, 16-17=-587/720, 14-16=-587/720
 WEBS 3-23=-527/397, 4-23=-2185/871, 4-21=-450/633, 5-21=-496/382, 7-21=-192/792, 7-19=0/613, 11-18=-679/480, 13-18=-1722/1626, 13-16=-348/424

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left exposed; porch right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - WARNING:** This long span truss requires extreme care and experience for proper and safe handling and erection. For general handling and erection guidance, see Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses ("BCSI"), jointly produced by SBCA and TPI. The building owner or the owner's authorized agent shall contract with a qualified registered design professional for the design and inspection of the temporary installation restraint/bracing and the permanent individual truss member restraint/bracing. MiTek assumes no responsibility for truss manufacture, handling, erection, or bracing.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 23=452, 18=746, 14=393.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	A1-GE	GABLE	1	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:50 2023 Page 2
ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-qxk4u51kxH1asqKwc0NimSDOUoiA1Uj?UEGjhzzFlkh

NOTES-

- 10) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	A2	ROOF SPECIAL	11	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:50 2023 Page 1
 ID: ?qFv7n9eCfLamv6Bqf9VgwzG_Yq-qxk4u51kxH1asqKwc0NimSDPUoic1UW?UEGjhzZFlkh

0-11-0	6-8-13	11-9-2	16-6-6	24-11-8	30-11-8	36-3-8	41-9-4	51-9-4	61-11-0	62-10-0
0-11-0	6-8-13	5-0-5	4-9-4	8-5-2	6-0-0	5-4-0	5-5-12	10-0-0	10-1-12	0-11-0

Scale = 1:108.0




Plate Offsets (X,Y)-- [14:0-2-12,Edge]	8-1-12	19-4-2	30-11-8	41-9-4	51-9-4	61-11-0
	8-1-12	11-2-6	11-7-6	10-9-12	10-0-0	10-1-12

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.50	Vert(LL)	-0.32	19-21	>999	360	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.63	Vert(CT)	-0.43	19-21	>930	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.87	Horz(CT)	0.02	14	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S	Wind(LL)	0.15	14-16	>999	240		
									Weight: 435 lb	FT = 20%

LUMBER-
 TOP CHORD 2x6 SP No.1
 BOT CHORD 2x6 SP No.1
 WEBS 2x4 SP No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
 WEBS 1 Row at midpt 9-18, 13-18

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 23=1938/0-3-8 (min. 0-2-5), 18=2553/0-3-8 (min. 0-3-1), 14=536/0-3-0 (min. 0-1-8)
 Max Horz 23=-182(LC 10)
 Max Uplift 23=-160(LC 12), 18=-443(LC 9), 14=-255(LC 9)
 Max Grav 23=1938(LC 1), 18=2605(LC 2), 14=551(LC 24)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-24=-1016/961, 3-24=-1000/1021, 3-4=-1159/1351, 4-5=-1544/96, 5-6=-1504/143,
 6-25=-1434/154, 7-25=-1378/194, 7-8=-1315/200, 8-9=-1110/99, 9-10=-507/1160,
 10-11=-521/1088, 11-12=-589/1204, 12-13=-605/1073, 13-26=-691/678, 14-26=-769/661
 BOT CHORD 2-23=-931/1020, 22-23=-69/1070, 21-22=-69/1070, 21-27=0/918, 27-28=0/918, 20-28=0/918,
 19-20=0/918, 19-29=0/441, 29-30=0/441, 18-30=0/441, 17-18=-576/683, 16-17=-576/683,
 14-16=-576/683
 WEBS 3-23=-527/322, 4-23=-2162/743, 4-21=-480/633, 5-21=-498/309, 7-21=-82/768,
 7-19=-97/517, 8-19=-670/205, 9-19=-177/1049, 9-18=-1991/472, 11-18=-512/233,
 13-18=-1784/1365, 13-16=-350/427


- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCCL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) -0-7-11 to 5-4-5, Interior(1) 5-4-5 to 24-11-8, Exterior(2) 24-11-8 to 30-11-8, Interior(1) 30-11-8 to 62-6-11 zone; cantilever left exposed; porch right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - WARNING:** This long span truss requires extreme care and experience for proper and safe handling and erection. For general handling and erection guidance, see Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses ("BCSI"), jointly produced by SBCA and TPI. The building owner or the owner's authorized agent shall contract with a qualified registered design professional for the design and inspection of the temporary installation restraint/bracing and the permanent individual truss member restraint/bracing. MiTek assumes no responsibility for truss manufacture, handling, erection, or bracing.
 - All plates are 4x6 MT20 unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCCL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 23=160, 18=443, 14=255.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	A3	ROOF SPECIAL	1	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:51 2023 Page 1
 ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-l8IS6R2Mib9RT_u6AjuXlgbGC1VmwR9ju?HEPzFkq



Scale = 1:77.7




Plate Offsets (X,Y)-- [11:0-1-12,0-2-0]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.37	Vert(LL)	-0.32 12-14	>999	360	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.65	Vert(CT)	-0.44 12-14	>924	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.95	Horz(CT)	0.03 11	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S	Wind(LL)	0.05 12-14	>999	240		
								Weight: 324 lb	FT = 20%

LUMBER-
 TOP CHORD 2x6 SP No.1
 BOT CHORD 2x6 SP No.1
 WEBS 2x4 SP No.2 *Except*
 W10: 2x6 SP No.1

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 5-8-8 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 2-16.
 WEBS 1 Row at midpt 9-11

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 16=2120/0-3-8 (min. 0-2-8), 11=1253/Mechanical
 Max Horz 16=249(LC 12)
 Max Uplift 16=-151(LC 12), 11=-85(LC 13)
 Max Grav 16=2120(LC 1), 11=1433(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-17=-995/958, 3-17=-979/1018, 3-4=-1126/1349, 4-5=-1780/161, 5-6=-1740/217,
 6-18=-1625/239, 7-18=-1614/268, 7-19=-1703/415, 8-19=-1802/386, 8-9=-1545/252
 BOT CHORD 2-16=-928/997, 15-16=-164/1203, 14-15=-164/1203, 14-21=-64/1083, 13-21=-64/1083,
 13-22=-64/1083, 12-22=-64/1083, 12-23=-170/1024, 23-24=-170/1024, 11-24=-170/1024
 WEBS 3-16=-529/298, 4-16=-2436/855, 4-14=-477/667, 5-14=-497/296, 7-14=-85/755,
 7-12=-191/1017, 8-12=-834/282, 9-12=0/725, 9-11=-1537/266


- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCCL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) -0-7-11 to 3-9-2, Interior(1) 3-9-2 to 24-11-8, Exterior(2) 24-11-8 to 29-4-5, Interior(1) 29-4-5 to 41-8-4 zone; cantilever left exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCCL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 11 except (jt=lb) 16=151.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	A4	ROOF SPECIAL	3	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:51 2023 Page 1
 ID: ?qFv7n9eCfLamv6Bqf9VgwzG_Yq-l8lS6R2Mib9RT_u6Ajuxlglg?C1bmw99ju?HEPzFkq



Scale = 1:75.0




Plate Offsets (X,Y)-- [9:0-1-12,0-2-0]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.39	Vert(LL)	-0.23 10-13	>999	360	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.65	Vert(CT)	-0.32 10-13	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.90	Horz(CT)	0.04 9	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S	Wind(LL)	0.05 2-13	>999	240		
								Weight: 286 lb	FT = 20%

LUMBER-
 TOP CHORD 2x6 SP No.1
 BOT CHORD 2x6 SP No.1
 WEBS 2x4 SP No.2 *Except*
 W7: 2x6 SP No.1
 WEDGE
 Left: 2x4 SP No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 4-11-14 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 7-9

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=1398/0-3-8 (min. 0-1-15), 9=1341/Mechanical
 Max Horz 2=248(LC 12)
 Max Uplift 2=-75(LC 12), 9=-82(LC 13)
 Max Grav 2=1632(LC 19), 9=1522(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-16=-2211/336, 3-16=-2134/371, 3-4=-2064/428, 4-17=-1950/450, 5-17=-1930/479,
 5-18=-1875/508, 6-18=-1923/479, 6-7=-1646/331
 BOT CHORD 2-20=-363/1877, 20-21=-363/1877, 13-21=-363/1877, 13-22=-144/1207, 12-22=-144/1207,
 11-12=-144/1207, 11-23=-144/1207, 10-23=-144/1207, 10-24=-216/1084, 24-25=-216/1084,
 9-25=-216/1084
 WEBS 3-13=-534/330, 5-13=-176/1095, 5-10=-181/961, 6-10=-895/328, 7-10=-26/785,
 7-9=-1625/337


- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCCL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) -0-9-7 to 3-7-6, Interior(1) 3-7-6 to 16-11-8, Exterior(2) 16-11-8 to 21-4-5, Interior(1) 21-4-5 to 33-8-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCCL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 9.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	A5	COMMON	6	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:52 2023 Page 1
 ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-nKrqJm3_TuHl58TjKkRQArtlhcNKVTJlyYlqmszFkF



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.39	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.62	Vert(LL) -0.18 9-12 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.53	Vert(CT) -0.25 9-12 >999 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.05 8 n/a n/a		
	Code IRC2015/TPI2014		Wind(LL) 0.05 2-12 >999 240		
				Weight: 254 lb	FT = 20%

LUMBER-
 TOP CHORD 2x6 SP No.1
 BOT CHORD 2x6 SP No.1
 WEBS 2x4 SP No.2
 WEDGE
 Left: 2x4 SP No.2 , Right: 2x4 SP No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 4-11-3 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=1402/0-3-8 (min. 0-1-15), 8=1344/0-3-8 (min. 0-1-14)
 Max Horz 2=283(LC 9)
 Max Uplift 2=-83(LC 12), 8=-69(LC 13)
 Max Grav 2=1641(LC 19), 8=1588(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-15=-2218/362, 3-15=-2140/396, 3-4=-2072/453, 4-16=-1957/475, 5-16=-1937/504,
 5-17=-1940/512, 6-17=-1960/483, 6-7=-2075/461, 7-18=-2116/402, 8-18=-2221/368
 BOT CHORD 2-19=-184/1918, 19-20=-184/1918, 12-20=-184/1918, 12-21=0/1260, 11-21=0/1260,
 10-11=0/1260, 10-22=0/1260, 9-22=0/1260, 9-23=-185/1724, 23-24=-185/1724,
 8-24=-185/1724
 WEBS 5-9=-178/1071, 7-9=-530/333, 5-12=-178/1067, 3-12=-528/328


- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) 0-9-7 to 3-7-6, Interior(1) 3-7-6 to 16-11-8, Exterior(2) 16-11-8 to 21-4-5, Interior(1) 21-4-5 to 33-9-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 8.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	A6-GE	GABLE	1	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:52 2023 Page 1
ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-nKrQJm3_TuHl58TjKkRQArtr0cWVSVZ2lyYlqmszFkK



Scale = 1:72.5



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.05	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.03	Vert(LL) -0.00 1 n/r 120		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.16	Vert(CT) 0.00 1 n/r 120		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.01 20 n/a n/a		
	Code IRC2015/TPI2014				Weight: 321 lb FT = 20%

LUMBER-
TOP CHORD 2x6 SP No.1
BOT CHORD 2x6 SP No.1
OTHERS 2x4 SP No.2
WEDGE
Left: 2x4 SP No.2 , Right: 2x4 SP No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS T-Brace: 2x4 SPF No.2 - 11-29, 10-30, 9-32, 12-28, 13-26
Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c., with 3in minimum end distance.
Brace must cover 90% of web length.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 33-11-0.
(lb) - Max Horz 2=354(LC 9)
Max Uplift All uplift 100 lb or less at joint(s) 2, 20, 30, 33, 34, 35, 36, 28, 25, 24, 23, 22 except 32=-100(LC 12), 37=-177(LC 12), 26=-104(LC 13), 21=-173(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 2, 20, 29, 30, 32, 33, 34, 35, 36, 28, 26, 25, 24, 23, 22 except 37=277(LC 19), 21=278(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-377/283, 3-4=-251/214, 9-10=-239/279, 10-11=-271/302, 11-12=-271/302, 12-13=-239/260, 19-20=-298/195
BOT CHORD 2-37=-175/276, 36-37=-175/276, 35-36=-175/276, 34-35=-175/276, 33-34=-175/276, 32-33=-175/276, 31-32=-175/276, 30-31=-175/276, 29-30=-175/276, 28-29=-175/276, 27-28=-175/276, 26-27=-175/276, 25-26=-175/276, 24-25=-175/276, 23-24=-175/276, 22-23=-175/276, 21-22=-175/276, 20-21=-175/276

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 20, 30, 33, 34, 35, 36, 28, 25, 24, 23, 22 except (jt=lb) 32=100, 37=177, 26=104, 21=173.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	A6-GE	GABLE	1	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams


Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:53 2023 Page 2
ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-FWPCX64cECP9jH2VH8xPO5r0m?shE0ISBCUNIlzFlke

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	A7	COMMON	9	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:53 2023 Page 1
 ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-FWPCX64cECP9jH2VH8xPO5rwO?jVjEweSBCUNIlzFlke



Scale = 1:72.4



LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.40	Vert(LL) -0.20 10-13 >999 360	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.62	Vert(CT) -0.27 10-13 >999 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.52	Horz(CT) 0.05 8 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-S	Wind(LL) 0.05 2-13 >999 240		
				Weight: 238 lb	FT = 20%

LUMBER-
 TOP CHORD 2x6 SP No.1
 BOT CHORD 2x6 SP No.1
 WEBS 2x4 SP No.2
 WEDGE
 Left: 2x4 SP No.2 , Right: 2x4 SP No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 4-11-8 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=1401/0-3-8 (min. 0-1-15), 8=1401/0-3-8 (min. 0-1-15)
 Max Horz 2=-284(LC 10)
 Max Uplift 2=-83(LC 12), 8=-83(LC 13)
 Max Grav 2=1651(LC 19), 8=1651(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-14=-2237/361, 3-14=-2159/395, 3-4=-2090/452, 4-15=-1975/474, 5-15=-1955/503,
 5-16=-1955/503, 6-16=-1975/474, 6-7=-2090/452, 7-17=-2159/395, 8-17=-2237/361
 BOT CHORD 2-18=-180/1934, 18-19=-180/1934, 13-19=-180/1934, 13-20=0/1271, 12-20=0/1271,
 11-12=0/1271, 11-21=0/1271, 10-21=0/1271, 10-22=-180/1739, 22-23=-180/1739,
 8-23=-180/1739
 WEBS 5-10=-177/1079, 7-10=-528/328, 5-13=-177/1079, 3-13=-528/328

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) 0-9-7 to 3-7-6, Interior(1) 3-7-6 to 16-11-8, Exterior(2) 16-11-8 to 21-4-5, Interior(1) 21-4-5 to 34-8-7 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 8.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	A8-GE	GABLE	1	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:54 2023 Page 1
ID: ?qFv7n9eCfLamv6Bqf9VgwzG_Yq-jjzks4E?WYOKRdhrsSew/NBWPCtzTXbPsExrkzFlk

-0-11-0	16-11-8	33-11-0	34-10-0
0-11-0	16-11-8	16-11-8	0-11-0

Scale = 1:73.5



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.05	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.04	Vert(LL) 0.00 20 n/r 120		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.16	Vert(CT) 0.00 20 n/r 120		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.01 20 n/a n/a		
	Code IRC2015/TPI2014				
				Weight: 323 lb	FT = 20%

LUMBER-
 TOP CHORD 2x6 SP No.1
 BOT CHORD 2x6 SP No.1
 OTHERS 2x4 SP No.2
 WEDGE
 Left: 2x4 SP No.2 , Right: 2x4 SP No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS T-Brace: 2x4 SPF No.2 - 11-30, 10-31, 9-33, 12-29, 13-27
 Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c., with 3in minimum end distance.
 Brace must cover 90% of web length.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 33-11-0.
 (lb) - Max Horz 2=-354(LC 10)
 Max Uplift All uplift 100 lb or less at joint(s) 2, 20, 31, 34, 35, 36, 37, 29, 26, 25, 24, 23 except 33=-100(LC 12), 38=-177(LC 12), 27=-104(LC 13), 22=-168(LC 13)
 Max Grav All reactions 250 lb or less at joint(s) 2, 20, 30, 31, 33, 34, 35, 36, 37, 29, 27, 26, 25, 24, 23 except 38=277(LC 19), 22=267(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-377/284, 3-4=-251/214, 9-10=-240/280, 10-11=-271/304, 11-12=-271/304, 12-13=-240/261, 19-20=-293/194
 BOT CHORD 2-38=-177/278, 37-38=-177/278, 36-37=-177/278, 35-36=-177/278, 34-35=-177/278, 33-34=-177/278, 32-33=-177/278, 31-32=-177/278, 30-31=-177/278, 29-30=-177/278, 28-29=-177/278, 27-28=-177/278, 26-27=-177/278, 25-26=-177/278, 24-25=-177/278, 23-24=-177/278, 22-23=-177/278, 20-22=-177/278

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCCL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 20, 31, 34, 35, 36, 37, 29, 26, 25, 24, 23 except (jt=lb) 33=100, 38=177, 27=104, 22=168.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	A8-GE	GABLE	1	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams



Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:54 2023 Page 2
ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-jjzkbS4E?WY0KRdhrsSewNBWPCtzTXbPsExrkzFlkd

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	A9-GE	MONOPITCH SUPPORTED	2	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:55 2023 Page 1
ID: ?qFv7n9eCfLamv6Bqf9VgwzG_Yq-BvXzYo5tmpgtybCuPZztTWwlSpY?iyVkeWzUNAZfIk



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.30	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.04	Vert(LL) 0.03 6 n/r 120		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.05	Vert(CT) -0.01 6 n/r 120		
BCDL 10.0	Rep Stress Incr YES	Matrix-P	Horz(CT) 0.00 n/a n/a		
	Code IRC2015/TPI2014			Weight: 55 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x6 SP No.1	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x6 SP No.1	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.2	
OTHERS 2x4 SP No.2	

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 8-3-8.
 (lb) - Max Horz 2=141(LC 8)
 Max Uplift All uplift 100 lb or less at joint(s) 2 except 7=-283(LC 9), 9=-128(LC 12), 8=-169(LC 1)
 Max Grav All reactions 250 lb or less at joint(s) 2, 8 except 7=527(LC 1), 9=373(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 5-7=-508/621
 WEBS 3-9=-289/284, 4-8=-273/195

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCCL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Gable studs spaced at 2-0-0 oc.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 7=283, 9=128, 8=169.
 - 8) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	B1-GE	GABLE	1	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:56 2023 Page 1
 ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-f55L986VW7okaln4zHU6?jTMDdgPRCrutAj1vdzFlbk

0-11-0 5-8-12 9-8-6 12-11-8 16-2-10 20-2-4 25-11-0 26-10-0
 0-11-0 5-8-12 3-11-10 3-3-2 3-3-2 3-11-10 5-8-12 0-11-0

Scale = 1:80.2




Plate Offsets (X,Y)-- [2:0-2-12,0-2-4], [3:0-4-0,Edge], [4:0-9-9,0-0-0], [6:0-4-0,0-4-4], [8:0-9-9,0-0-0], [9:0-4-0,Edge], [10:0-2-12,0-2-4], [13:0-5-0,0-6-4], [15:0-5-0,0-6-4], [22:0-1-9,0-1-0], [25:0-1-9,0-1-0], [34:0-1-9,0-1-0], [37:0-1-9,0-1-0]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.74	Vert(LL)	-0.30 13-15	>999	360	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.93	Vert(CT)	-0.48 13-15	>638	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.88	Horz(CT)	0.01 12	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S	Wind(LL)	0.07 13-15	>999	240		
								Weight: 318 lb	FT = 20%

LUMBER-
 TOP CHORD 2x10 SP No.1 *Except*
 T1: 2x6 SP No.1
 BOT CHORD 2x10 SP No.1
 WEBS 2x6 SP No.1 *Except*
 W2: 2x4 SP No.2
 OTHERS 2x4 SP No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 3-6-8 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 16=1428/0-3-8 (min. 0-2-1), 12=1428/0-3-8 (min. 0-2-1)
 Max Horz 16=-270(LC 10)
 Max Grav 16=1763(LC 20), 12=1763(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-2109/0, 3-4=-1934/0, 4-5=-1441/197, 5-6=-3/436, 6-7=-3/436, 7-8=-1441/197,
 8-9=-1934/0, 9-10=-2109/0, 2-16=-1939/44, 10-12=-1940/44
 BOT CHORD 15-16=-276/532, 14-15=0/1481, 13-14=0/1481, 12-13=-71/334
 WEBS 5-7=-1858/220, 4-15=0/940, 8-13=0/940, 2-15=0/1307, 10-13=0/1311


- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Corner(3) 0-9-6 to 3-7-6, Exterior(2) 3-7-6 to 12-11-8, Corner(3) 12-11-8 to 17-4-5, Exterior(2) 17-4-5 to 26-8-6 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Ceiling dead load (10.0 psf) on member(s). 4-5, 7-8, 5-7; Wall dead load (5.0psf) on member(s).4-15, 8-13
 - Bottom chord live load (40.0 psf) and additional bottom chord dead load (10.0 psf) applied only to room. 13-15
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	B2	ATTIC	1	2	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:56 2023 Page 1
 ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-f55L986VW7okaln4zHU6?jTouDjyRM3utAj1vdzFfk



Scale = 1:76.2




Plate Offsets (X,Y)-- [2:0-1-0,0-2-0], [3:0-4-0,Edge], [6:0-4-0,Edge], [9:0-4-0,Edge], [10:0-1-0,0-2-0], [13:0-4-0,0-4-12], [15:0-4-0,0-4-12]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	3-0-0	TC 0.63	Vert(LL)	-0.22	13-15	>999	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.76	Vert(CT)	-0.36	13-15	>850		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.22	Horz(CT)	0.01	12	n/a		
BCDL 10.0	Rep Stress Incr NO	Matrix-S	Wind(LL)	0.05	13-15	>999		
	Code IRC2015/TPI2014						Weight: 571 lb	FT = 20%

LUMBER-

TOP CHORD 2x10 SP No.1 *Except*
 T1: 2x6 SP No.1
 BOT CHORD 2x10 SP No.1
 WEBS 2x6 SP No.1 *Except*
 W2: 2x4 SP No.2

BRACING-

TOP CHORD 2-0-0 oc purlins (6-0-0 max.), except end verticals
 (Switched from sheeted: Spacing > 2-0-0).
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 16=2143/0-3-8 (min. 0-1-9), 12=2143/0-3-8 (min. 0-1-9)
 Max Horz 16=405(LC 11)
 Max Grav 16=2644(LC 20), 12=2644(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-17=-3164/0, 3-17=-2964/0, 3-4=-2902/0, 4-18=-2161/137, 5-18=-1952/209, 5-6=-3/655,
 6-7=-3/655, 7-19=-1951/209, 8-19=-2161/137, 8-9=-2901/0, 9-20=-2964/0, 10-20=-3164/0,
 2-16=-2909/0, 10-12=-2910/0
 BOT CHORD 15-16=-414/799, 14-15=0/2222, 13-14=0/2222, 12-13=-71/502
 WEBS 5-7=-2789/171, 4-15=0/1411, 8-13=0/1411, 2-15=0/1960, 10-13=0/1966

NOTES-


- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x10 - 2 rows staggered at 0-9-0 oc.
 Bottom chords connected as follows: 2x10 - 2 rows staggered at 0-9-0 oc.
 Webs connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCCL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) 0-9-6 to 3-7-6, Interior(1) 3-7-6 to 12-11-8, Exterior(2) 12-11-8 to 17-4-5, Interior(1) 17-4-5 to 26-8-6 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Ceiling dead load (10.0 psf) on member(s). 4-5, 7-8, 5-7; Wall dead load (5.0psf) on member(s).4-15, 8-13
- Bottom chord live load (40.0 psf) and additional bottom chord dead load (10.0 psf) applied only to room. 13-15
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	B3	ATTIC	7	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:57 2023 Page 1
 ID: ?qFv7n9eCfLamv6Bqf9VgwzG_Yq-7lfjMU77HRwbBvMGW_?LYx?Xzd0eAf415qSbR3zFlka



Scale = 1:76.2




Plate Offsets (X,Y)-- [2:0-2-12,0-2-4], [3:0-4-0,Edge], [4:0-9-9,0-0-0], [6:0-4-0,Edge], [8:0-9-9,0-0-0], [9:0-4-0,Edge], [10:0-2-12,0-2-4], [13:0-5-0,0-6-4], [15:0-5-0,0-6-4]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.74	Vert(LL)	-0.30	13-15	>999	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.93	Vert(CT)	-0.48	13-15	>638		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.88	Horz(CT)	0.01	12	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Wind(LL)	0.07	13-15	>999		
	Code IRC2015/TPI2014							Weight: 285 lb FT = 20%

LUMBER-
 TOP CHORD 2x10 SP No.1 *Except*
 T1: 2x6 SP No.1
 BOT CHORD 2x10 SP No.1
 WEBS 2x6 SP No.1 *Except*
 W2: 2x4 SP No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 3-7-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
 MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 16=1428/0-3-8 (min. 0-2-1), 12=1428/0-3-8 (min. 0-2-1)
 Max Horz 16=-270(LC 10)
 Max Grav 16=1763(LC 20), 12=1763(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-17=-2109/0, 3-17=-1976/0, 3-4=-1934/0, 4-18=-1441/92, 5-18=-1301/139, 5-6=-3/436,
 6-7=-3/436, 7-19=-1301/139, 8-19=-1440/92, 8-9=-1934/0, 9-20=-1975/0, 10-20=-2109/0,
 2-16=-1939/0, 10-12=-1940/0
 BOT CHORD 15-16=-276/532, 14-15=0/1481, 13-14=0/1481, 12-13=-47/334
 WEBS 5-7=-1858/114, 4-15=0/940, 8-13=0/940, 2-15=0/1307, 10-13=0/1311


- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TC DL=6.0psf; BC DL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) -0-9-6 to 3-7-6, Interior(1) 3-7-6 to 12-11-8, Exterior(2) 12-11-8 to 17-4-5, Interior(1) 17-4-5 to 26-8-6 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Ceiling dead load (10.0 psf) on member(s). 4-5, 7-8, 5-7; Wall dead load (5.0psf) on member(s). 4-15, 8-13
 - Bottom chord live load (40.0 psf) and additional bottom chord dead load (10.0 psf) applied only to room. 13-15
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	B4	ATTIC	6	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:57 2023 Page 1
 ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-7lfjMU77HRwbBvMGW_?LYx?Xkd0cAft15qSbR3zFlka



6x8 =

Scale = 1:76.2




Plate Offsets (X,Y)-- [1:0-1-4,0-2-0], [2:0-4-0,Edge], [5:0-4-0,Edge], [8:0-4-0,Edge], [9:0-2-12,0-2-4], [12:0-4-0,0-6-0], [14:0-4-0,0-6-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.76	Vert(LL)	-0.30	12-14	>999	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.93	Vert(CT)	-0.48	12-14	>632		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.89	Horz(CT)	0.01	11	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Wind(LL)	0.07	12-14	>999		
	Code IRC2015/TPI2014						Weight: 283 lb	FT = 20%

LUMBER-

TOP CHORD 2x10 SP No.1 *Except*
 T1,T3: 2x6 SP No.1
 BOT CHORD 2x10 SP No.1
 WEBS 2x6 SP No.1 *Except*
 W2: 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-5-2 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 15=1366/0-3-8 (min. 0-2-0), 11=1430/0-3-8 (min. 0-2-1)
 Max Horz 15=-263(LC 8)
 Max Grav 15=1705(LC 20), 11=1764(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-2094/0, 2-3=-1922/0, 3-16=-1446/94, 4-16=-1307/142, 4-5=0/444, 5-6=0/448,
 6-17=-1302/138, 7-17=-1442/90, 7-8=-1941/0, 8-18=-1983/0, 9-18=-2116/0, 1-15=-1895/0,
 9-11=-1947/0
 BOT CHORD 14-15=-262/422, 13-14=0/1486, 12-13=0/1486, 11-12=-48/333
 WEBS 4-6=-1880/121, 3-14=0/904, 7-12=0/947, 1-14=0/1388, 9-12=0/1318

NOTES-


- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TC DL=6.0psf; BC DL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) 0-2-12 to 4-7-9, Interior(1) 4-7-9 to 12-11-8, Exterior(2) 12-11-8 to 17-4-5, Interior(1) 17-4-5 to 26-8-6 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Ceiling dead load (10.0 psf) on member(s). 3-4, 6-7, 4-6; Wall dead load (5.0psf) on member(s).3-14, 7-12
- Bottom chord live load (40.0 psf) and additional bottom chord dead load (10.0 psf) applied only to room. 12-14
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	C1	Common	4	1	Job Reference (optional)


Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:58 2023 Page 1
ID: ?qFv7n9eCfLamv6Bqf9VgwzG_Yq-bUD5aq8l2k2Sp3xT4hWa58Ysh0W7vFYBKUC8_VzFlkZ



5x5 =

Scale = 1:58.6



LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.10	Vert(LL) -0.05 9-11 >999 360	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.21	Vert(CT) -0.06 9-11 >999 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.29	Horz(CT) 0.01 7 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-S	Wind(LL) 0.01 11 >999 240		
				Weight: 172 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SP No.1
BOT CHORD 2x6 SP No.1
WEBS 2x4 SP No.2
SLIDER Left 2x4 SP No.2 -p 3-6-2, Right 2x4 SP No.2 -p 3-6-2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=849/0-3-8 (min. 0-1-8), 7=898/0-3-8 (min. 0-1-8)
Max Horz 1=-227(LC 10)
Max Uplift1=-34(LC 12), 7=-45(LC 13)
Max Grav 1=861(LC 19), 7=906(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-1080/223, 2-12=-989/229, 3-12=-916/251, 3-13=-992/343, 4-13=-957/379,
4-14=-958/370, 5-14=-992/333, 5-15=-953/245, 6-15=-988/224, 6-7=-1079/218
BOT CHORD 1-11=-68/854, 11-16=0/587, 10-16=0/587, 10-17=0/587, 9-17=0/587, 7-9=-59/740
WEBS 4-9=-166/521, 5-9=-340/256, 4-11=-167/525, 3-11=-339/259


- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCCL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) 0-0-0 to 4-4-13, Interior(1) 4-4-13 to 10-7-8, Exterior(2) 10-7-8 to 15-0-5, Interior(1) 15-0-5 to 22-0-6 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCCL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 7.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job B0523-2291	Truss C2	Truss Type Common Girder	Qty 1	Ply 2	Hamilton Residence
-------------------	-------------	-----------------------------	----------	----------	--------------------

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:59 2023 Page 1
ID: ?qFv7n9eCfLamv6Bqf9VgwzG_Yq-3gmUnA8Np2AJRCWfeP2pdM5qaQmoebuKZ8xiWyzFkY



Scale = 1:59.1

Plate Offsets (X,Y)-- [6:0-5-0,0-6-4], [8:0-5-0,0-6-4]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.93	Vert(LL) -0.11	5-6	>999	360	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.63	Vert(CT) -0.19	5-6	>999	240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.73	Horz(CT) 0.03	5	n/a	n/a		
BCDL 10.0	Rep Stress Incr NO	Matrix-S	Wind(LL) 0.06	5-6	>999	240		
	Code IRC2015/TPI2014						Weight: 353 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SP No.1
BOT CHORD 2x8 SP 2400F 2.0E
WEBS 2x4 SP No.2
WEDGE
Left: 2x6 SP No.1 , Right: 2x6 SP No.1

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-2-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 1=7176/0-3-8 (min. 0-3-5), 5=7642/0-3-8 (min. 0-3-8)
Max Horz 1=225(LC 24)
Max Uplift 1=-469(LC 8), 5=-464(LC 9)
Max Grav 1=8003(LC 2), 5=8523(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-9124/558, 2-3=-8798/648, 3-4=-8884/634, 4-5=-9208/544
BOT CHORD 1-9=-418/6576, 9-10=-418/6576, 10-11=-418/6576, 8-11=-418/6576, 8-12=-231/4710,
12-13=-231/4710, 13-14=-231/4710, 7-14=-231/4710, 7-15=-231/4710, 6-15=-231/4710,
6-16=-332/6643, 16-17=-332/6643, 17-18=-332/6643, 5-18=-332/6643
WEBS 3-6=-418/5937, 4-6=-249/544, 3-8=-449/5751, 2-8=-249/547

- NOTES-**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-6-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=469, 5=464.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1396 lb down and 105 lb up at 1-10-12, 1513 lb down and 102 lb up at 3-10-12, 1513 lb down and 102 lb up at 5-10-12, 1508 lb down and 102 lb up at 7-10-12, 1461 lb down and 89 lb up at 9-10-12, 1468 lb down and 89 lb up at 11-10-12, 1506 lb down and 89 lb up at 13-10-12, 1506 lb down and 89 lb up at 15-10-12, and 1506 lb down and 89 lb up at 17-10-12, and 1506 lb down and 89 lb up at 19-10-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard
Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	C2	Common Girder	1	2	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:59 2023 Page 2
 ID:?qFv7n9eCfLamv6Bqf9VgwgzG_Yq-3gmUnA8Np2AJRCWfeP2pdM5qaQmoebuKZ8xiWyzFlkY

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-3=-60, 3-5=-60, 1-5=-20


Concentrated Loads (lb)

Vert: 7=-1324(F) 6=-1324(F) 9=-1233(F) 10=-1321(F) 11=-1321(F) 12=-1321(F) 14=-1324(F) 16=-1324(F) 17=-1324(F) 18=-1324(F)

Job B0523-2291	Truss VC-1	Truss Type GABLE	Qty 1	Ply 1	Hamilton Residence Job Reference (optional)
-------------------	---------------	---------------------	----------	----------	--

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:48:59 2023 Page 1
ID: ?qFv7n9eCfLamv6Bqf9VgwzG_Yq-3gmUnA8Np2AJRCWfeP2pdM50aQtLekgKZ8xiWyzFkY



Scale = 1:46.9

Plate Offsets (X,Y)-- [4:0-2-0,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.16	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.14	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.17	Horz(CT)	0.00	7	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S						
								Weight: 70 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.1
BOT CHORD 2x4 SP No.1
WEBS 2x4 SP No.2
OTHERS 2x4 SP No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 12-0-9.
(lb) - Max Horz 1=201(LC 12)
Max Uplift All uplift 100 lb or less at joint(s) 1, 7, 9 except 10=-138(LC 12)
Max Grav All reactions 250 lb or less at joint(s) 1, 7 except 9=508(LC 19), 10=404(LC 19), 8=272(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 3-9=-261/173, 2-10=-353/270

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) 0-4-13 to 4-9-10, Interior(1) 4-9-10 to 9-4-9, Exterior(2) 9-4-9 to 11-10-13 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 7, 9 except (jt=lb) 10=138.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job B0523-2291	Truss VC-2	Truss Type GABLE	Qty 1	Ply 1	Hamilton Residence
-------------------	---------------	---------------------	----------	----------	--------------------

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:49:00 2023 Page 1
ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-YsKs?W9?aMIA2M4rC6Z2AZdBiqEKNCvUoohF2OzFkX




Plate Offsets (X,Y)-- [4:0-2-0,Edge]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.13	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.10	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.10	Horz(CT)	0.00	7	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-S					Weight: 56 lb	FT = 20%
	Code IRC2015/TPI2014							

LUMBER-
 TOP CHORD 2x4 SP No.1
 BOT CHORD 2x4 SP No.1
 WEBS 2x4 SP No.2
 OTHERS 2x4 SP No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 10-5-6.
 (lb) - Max Horz 1=157(LC 12)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 7, 9 except 10=-118(LC 12)
 Max Grav All reactions 250 lb or less at joint(s) 1, 7 except 9=422(LC 19), 10=291(LC 19), 8=300(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 WEBS 3-9=-268/183, 2-10=-311/257


- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) 0-4-13 to 4-9-10, Interior(1) 4-9-10 to 7-9-6, Exterior(2) 7-9-6 to 10-3-10 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 7, 9 except (jt=lb) 10=118.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job B0523-2291	Truss VC-3	Truss Type GABLE	Qty 1	Ply 1	Hamilton Residence Job Reference (optional)
-------------------	---------------	---------------------	----------	----------	--

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:49:00 2023 Page 1
ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-YsKs?W9?aMIA2M4rC6Z2AZdBFqEINDXUoohF2OzFlkX



Scale = 1:32.4

Plate Offsets (X,Y)-- [3:0-2-0,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.16	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.10	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.06	Horz(CT)	0.00	6	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S							
									Weight: 43 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SP No.1
 BOT CHORD 2x4 SP No.1
 WEBS 2x4 SP No.2
 OTHERS 2x4 SP No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 8-10-3.
 (lb) - Max Horz 1=114(LC 12)
 Max Uplift All uplift 100 lb or less at joint(s) 6 except 8=-104(LC 12)
 Max Grav All reactions 250 lb or less at joint(s) 1, 6 except 8=448(LC 19), 7=257(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 WEBS 2-8=-313/224

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) 0-4-13 to 4-6-7, Interior(1) 4-6-7 to 6-2-3, Exterior(2) 6-2-3 to 8-8-7 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6 except (jt=lb) 8=104.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job B0523-2291	Truss VC-4	Truss Type GABLE	Qty 1	Ply 1	Hamilton Residence Job Reference (optional)
-------------------	---------------	---------------------	----------	----------	--

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:49:00 2023 Page 1
ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-YsKs?W9?aMIA2M4rC6Z2AZdCnqFzND5UoohF2OzFlkX




Plate Offsets (X,Y)-- [3:0-2-0,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.05	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	6	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S						Weight: 32 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SP No.1
 BOT CHORD 2x4 SP No.1
 WEBS 2x4 SP No.2
 OTHERS 2x4 SP No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 7-3-0.
 (lb) - Max Horz 1=82(LC 9)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 6, 8, 7
 Max Grav All reactions 250 lb or less at joint(s) 1, 6, 7 except 8=269(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Gable requires continuous bottom chord bearing.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 6, 8, 7.
 - 7) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Hamilton Residence
B0523-2291	VC-5	Valley	1	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Anthony Williams

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:49:01 2023 Page 1
ID:?qFv7n9eCfLamv6Bqf9VgwzG_Yq-03uECrAdLfQ1gWf1Iq4HinAN5EbH6gYd0S0QoqzFikW



Scale = 1:17.1



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.09	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.05	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.01	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-P					Weight: 22 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.1
BOT CHORD 2x4 SP No.1
OTHERS 2x4 SP No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-7-12 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=119/5-10-10 (min. 0-1-8), 3=119/5-10-10 (min. 0-1-8), 4=174/5-10-10 (min. 0-1-8)
Max Horz 1=-52(LC 10)
Max Uplift 1=-18(LC 13), 3=-23(LC 13)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job B0523-2291	Truss VC-6	Truss Type Valley	Qty 1	Ply 1	Hamilton Residence
Comtech, Inc., Fayetteville, NC 28309, Anthony Williams					Job Reference (optional)

Run: 8.430 s May 12 2021 Print: 8.430 s May 12 2021 MiTek Industries, Inc. Thu May 18 10:49:01 2023 Page 1
ID: ?qFv7n9eCfLamv6Bqf9VgwzG_Yq-03uECrAdLfQ1gWf1lq4HinAOLEbZ6gmd0S0aoqzFkV



Scale = 1:8.4

Plate Offsets (X,Y)-- [2:0-2-0,Edge]									
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.01	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-P					Weight: 8 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.1
BOT CHORD 2x4 SP No.1

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-9-2 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=78/2-8-4 (min. 0-1-8), 3=78/2-8-4 (min. 0-1-8)
Max Horz 1=-20(LC 8)
Max Uplift 1=-3(LC 12), 3=-3(LC 13)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCCL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard