


GDH Kerto-S LVL 1.750" X 14.000" 2-Ply - PASSED

Level: Level



Member Information

| | | | |
|---------------------|---------------|----------------|--------------|
| Type: | Girder | Application: | Floor |
| Plies: | 2 | Design Method: | ASD |
| Moisture Condition: | Dry | Building Code: | IBC/IRC 2015 |
| Deflection LL: | 480 | Load Sharing: | No |
| Deflection TL: | 240 | Deck: | Not Checked |
| Importance: | Normal | | |
| Temperature: | Temp <= 100°F | | |

Reactions UNPATTERNED lb (Uplift)

| Brg | Live | Dead | Snow | Wind | Const |
|-----|------|------|------|------|-------|
| 1 | 0 | 3069 | 0 | 0 | 0 |
| 2 | 0 | 3069 | 0 | 0 | 0 |

Bearings

| Bearing | Length | Cap. React | D/L lb | Total | Ld. Case | Ld. Comb. |
|-------------------|--------|------------|----------|-------|----------|-----------|
| 1 - SPF End Grain | 3.500" | 29% | 3069 / 0 | 3069 | Uniform | D |
| 2 - SPF End Grain | 3.500" | 29% | 3069 / 0 | 3069 | Uniform | D |

Analysis Results

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|---------------|-----------|---------------|--------------|-------|---------|
| Moment | 15746 ft-lb | 9'5" | 24299 ft-lb | 0.648 (65%) | D | Uniform |
| Unbraced | 15746 ft-lb | 9'5" | 15799 ft-lb | 0.997 (100%) | D | Uniform |
| Shear | 2774 lb | 1'4 3/4" | 9408 lb | 0.295 (29%) | D | Uniform |
| LL Defl inch | 0.000 (L/999) | 0 | 999.000 (L/0) | 0.000 (0%) | | |
| TL Defl inch | 0.624 (L/354) | 9'5 1/16" | 0.919 (L/240) | 0.680 (68%) | D | Uniform |

Design Notes

- 1 Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at a maximum of 6'2 1/4" o.c.
- 6 Bottom braced at bearings.
- 7 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|---------------|----------|------------|------|----------|--------|-----------|----------|-------------|----------|
| 1 | Tapered Start | 0-0-0 | | Top | 180 PLF | 0 PLF | 0 PLF | 0 PLF | 0 PLF | |
| | End | 9-5-0 | | | 450 PLF | 0 PLF | 0 PLF | 0 PLF | 0 PLF | |
| 2 | Tapered Start | 9-5-0 | | Top | 450 PLF | 0 PLF | 0 PLF | 0 PLF | 0 PLF | |
| | End | 18-10-0 | | | 180 PLF | 0 PLF | 0 PLF | 0 PLF | 0 PLF | |
| | Self Weight | | | | 11 PLF | | | | | |

Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

chemicals

Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

Manufacturer Info

Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
 www.metsawood.com/us
 ICC-ES: ESR-3633


Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS



This design is valid until 2/26/2023

GDH Kerto-S LVL 1.750" X 14.000" 2-Ply - PASSED

Level: Level



Multi-Ply Analysis

Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6"

| | |
|--------------------------|-----------|
| Capacity | 0.0 % |
| Load | 0.0 PLF |
| Yield Limit per Foot | 245.6 PLF |
| Yield Limit per Fastener | 81.9 lb. |
| Yield Mode | IV |
| Edge Distance | 1 1/2" |
| Min. End Distance | 3" |
| Load Combination | |
| Duration Factor | 1.00 |

Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive

chemicals

Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/26/2023

Manufacturer Info

Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
 www.metsawood.com/us
 ICC-ES: ESR-3633

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS

