PLAN SEAL DATE: 1.9.24

ob Estimate	
	ROOF & FLOOR
ComTech	ROOF & FLOOR TRUSSES & BEAMS
Pailly Poad Industrial	Park PO Box 10108

Fayetteville, N.C. 28309 (910) 864-TRUS

		. D/(12)	71700721 17102 1
REQ. QUOTE DATE	/ /	ORDER #	J1123-6628
ORDER DATE	11/22/23	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT#	0000006995
DATE OF INVOICE	/ /	CUSTOMER PO#	
ORDERED BY		INVOICE #	
SUPERINTENDANT		SALES REP	Bob Lewis
JOBSITE PHONE #			
DESIGNER	BL	TRACKING	Johnnie Baggett

Thomas Properties of Harnett DO NOT SELL THIS

MODEL:Roof TAG: DW-Mill Creek Farm 1988 JOB CATEGORY:

DELIVERY INSTRUCTIONS:

SPECIAL INSTRUCTIONS:

ROOF TRUSSES

BROADWAY, NC

	QTY	PIT	СН		SPAN	1 1 1 1 1	/BER	OVE	RHANG	CANT	LEVER	1
PROFILE	PLY	TOP	ВОТ	ID	FT-IN-16	TOP		LEFT	RIGHT	LEFT	RIGHT	NOTES
	3	4.00	12.00	A1	51-04-00	2 X 6	2 X 6	00-10-08	00-10-08			
	6	4.00	12.00	A2	43-04-00	2 X 6	2 X 6	00-10-08				
	1	4.00	0.00	A2SGE	34-04-00	2 X 6	2 X 8					
	8	12.00	0.00	B1	31-09-00	2 X 6	2 X 6					
	1	12.00	0.00	B1GE	31-09-00	2 X 6	2 X 6					
	1	12.00	0.00	B2SGE	29-04-00	2 X 6	2 X 6					
	5	12.00	0.00	C1	22-00-00	2 X	2 X 10	00-10-08	00-10-08			
	1	12.00	0.00	C1A	22-00-00	2 X	2 X 10					
	1	12.00	0.00	C1GE	22-00-00	2 X	2 X 10	00-10-08	00-10-08			
	1 3 Ply	12.00	0.00	C1GR	22-00-00	2 X	2 X 10					
	4	12.00	0.00	C2	20-07-08	2 X	2 X 10	00-10-08				
	2 2 Ply	12.00	0.00	C2-2P	20-07-08	2 X	2 X 10	00-10-08				
	2 Ply	12.00	0.00	C2A-2P	20-07-08	2 X	2 X 10	00-10-08				
	1	12.00	0.00	C2GE	20-07-08	2 X	2 X 10	00-10-08				
	1	12.00	0.00	C3GE	12-00-00	2 X 6	2 X 6	00-10-08	00-10-08			
	2	12.00	0.00	D1	25-08-00	2 X 6	2 X 6		00-10-08			
	1	12.00	0.00	D1GE	25-08-00	2 X 6	2 X 6		00-10-08			
Â	3	12.00	0.00	D2	25-08-00	2 X 6	2 X 6					
	4	12.00	0.00	E1	18-04-08	2 X	2 X 10	00-10-08	04-06-00			
	1 2 Ply	12.00	0.00	E1GR	18-04-08	2 X	2 X 10	00-10-08	04-06-00			
	1	12.00	8.00	F1	16-08-00	2 X 6	2 X 6	00-10-08	00-10-08			
	1	12.00	8.00	F1GE	16-08-00	2 X 6	2 X 6	00-10-08	00-10-08			
	4	12.00	8.00	F2	16-08-00	2 X 6	2 X 6	00-10-08				
	2	12.00	8.00	F3	16-08-00	2 X 6	2 X 6					
	1 2 Ply	12.00	0.00	F4GR	16-08-00	2 X 6	2 X 10					
	3	12.00	0.00	G1	17-00-00	2 X 6	2 X 6	00-10-08				
						•			1			

Job Estimate ROOF & FLOOR TRUSSES & BEAMS

REQ. QUOTE DATE ORDER# J1123-6628 ORDER DATE 11/22/23 **QUOTE**# 0000006995 **DELIVERY DATE** // CUSTOMER ACCT# / / DATE OF INVOICE **CUSTOMER PO#** ORDERED BY **INVOICE # SALES REP Bob Lewis** SUPERINTENDANT JOBSITE PHONE # DESIGNER BL **TRACKING** Johnnie Baggett

Reilly Road Industrial Park P.O. Box 40408 Fayetteville, N.C. 28309 (910) 864-TRUS

Thomas Properties of Harnett	JOB NAME:		LOT#	SUBDIV:
DO NOT SELL THIS	MODEL:Roof	TAG: DW-Mill Creek Farm 1988	JOB CATEGO	ORY:
	DELIVERY INSTRUCTIONS:			
(919) 258-9327/9064069				
CASH: THOMAS				
CAGII: IIIOMAG	SPECIAL INSTRUCTIONS:			
BROADWAY, NC				
Bitoribititi, ito				PLAN SEAL DATE: 1.9.24

ROOF TRUSSES

SOLD HO

SHIP TO

	QTY	PIT	сн		SPAN	1 1118	/BER	OVE	RHANG	CANTI	LEVER	
PROFILE	PLY	TOP	вот	ID	FT-IN-16		BOT	LEFT	RIGHT	LEFT	RIGHT	NOTES
	1	12.00	0.00	G1GE	17-00-00	2 X 6	2 X 6	00-10-08				
	1 2 Ply	12.00	0.00	G2GR	17-00-00	2 X 6	2 X 10					
	1	12.00	0.00	J1GE	11-08-00	2 X 6	2 X 6	00-10-08	00-10-08			
\triangle	1 2 Ply	12.00	0.00	J1GR	11-08-00	2 X 6	2 X 8	00-10-08	00-10-08			
	1	12.00	0.00	K1GE	11-08-00	2 X 6	2 X 6	00-10-08	00-10-08			
A	2	4.00	0.00	L1	10-09-00	2 X 4	2 X 6	00-10-08				
	6	12.00	0.00	M1	04-08-08	2 X	2 X 6	00-10-08	06-03-08			
	2	12.00	0.00	M2	04-08-08	2 X	2 X 6	00-10-08	06-03-08			
	1 2 Ply	0.00	0.00	N1	03-06-00	2 X 6	2 X 10					
	1 2 Ply	0.00	0.00	N2	03-06-00	2 X 8	2 X 8					
	18	12.00	0.00	PA1	12-04-07	2 X 4	2 X 4					
	2	12.00	0.00	PA1GE	12-04-07	2 X 4	2 X 4					
	5	12.00	0.00	PB1	03-08-07	2 X 4	2 X 4					
	1	12.00	0.00	PB1GE	03-08-07	2 X 4	2 X 4					
	1	12.00	0.00	Q1GE	11-07-08	2 X 6	2 X 6	00-10-08				
	1 2 Ply	12.00	0.00	Q1GR	11-07-08	2 X 6	2 X 8	00-10-08				
	1 2 Ply	0.00	0.00	T1GR	12-01-00	2 X 6	2 X 6					
	1 2 Ply	0.00	0.00	T2GR	12-01-00	2 X 6	2 X 10					
	1	12.00	0.00	V1	07-11-08	2 X 4	2 X 4					
	1	12.00	0.00	V2	03-11-08	2 X 4	2 X 4					
	1	12.00	0.00	VA1	13-04-00	2 X 4	2 X 4					
	1	12.00	0.00	VA2	09-04-00	2 X 4	2 X 4					
	1	12.00	0.00	VA3	05-04-00	2 X 4	2 X 4					
	1	12.00	0.00	VB1	11-08-00	2 X 6	2 X 6	00-10-08	00-10-08			
	1	12.00	0.00	VB2	11-08-00	2 X 4	2 X 4					
	1	12.00	0.00	VB3	09-05-15	2 X 4	2 X 4					

Job Estimate

ROOF & FLOOR
TRUSSES & BEAMS
Reilly Road Industrial Park P.O. Box 40408

Fayetteville, N.C. 28309 (910) 864-TRUS

		DATE	71/03/24 FAGE 3
REQ. QUOTE DATE	/ /	ORDER #	J1123-6628
ORDER DATE	11/22/23	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT#	0000006995
DATE OF INVOICE	/ /	CUSTOMER PO#	
ORDERED BY		INVOICE #	
SUPERINTENDANT		SALES REP	Bob Lewis
JOBSITE PHONE #			
DESIGNER	BL	TRACKING	Johnnie Baggett

ı	Thomas Properties of Harnett	JOB NAME:		LOT#	SUBDIV:
l	DO NOT SELL THIS	MODEL:Roof	TAG: DW-Mill Creek Farm 1988	JOB CATEG	ORY:
ı		DELIVERY INSTRUCTIONS:			
	(919) 258-9327/9064069				
1	CASH: THOMAS				
ı	GAGII. IIIOMAG	SPECIAL INSTRUCTIONS:			
	BROADWAY, NC				PLAN SEAL DATE: 1.9.24

ROOF TRUSSES

DDOE!! E	QTY PITCH ID SPAN LUMBER OVERHANG		RHANG	CANTILEVER NOTES								
PROFILE	PLY	TOP	вот	ID	FT-IN-16	TOP		LEFT	RIGHT	LEFT	RIGHT	NOTES
	1	12.00	0.00	VB4	05-05-15	2 X 4	2 X 4					
	1	12.00	0.00	VC1	10-06-00	2 X 4	2 X 4					
	1	12.00	0.00	VC2	06-06-00	2 X 4	2 X 4					
	1	3.00	0.00	W1	06-03-08	2 X 6	2 X 6	00-10-08				
	1	3.00	0.00	W2	06-03-08	2 X 6	2 X 6	00-10-08				
	10	3.00	0.00	X1	06-00-00	2 X 6	2 X 6	00-10-08				
	1 2 Ply	3.00	0.00	X1GR	06-00-00	2 X 6	2 X 6	00-10-08				
	1	3.00	0.00	X2	06-00-00	2 X 6	2 X 6					
	2	3.00	0.00	Х3	03-06-08	2 X 6	2 X 6	00-10-08				
	1	4.00	0.00	X4	07-00-00	2 X 6	2 X 6	00-10-08				
	1	2.12	0.00	Z1	04-10-10	2 X 6	2 X 6	01-02-14				
	1	Truss	Drawing	gs With B-1 and	B-3 Bracing	And H	andlin	g Instructio	ons (Includ	led in trus	s price)	

ROOF SUB-TOTAL: \$ 24,033.41

ITEMS

QTY	ITEM TYPE	SIZE	LENGTH FT-IN-16	PART NUMBER	NOTES
26	Hangers, USP	HUS 26			SIMPSON (HUS26)
20	Hangers, USP	JUS26			SIMPSON (LUS26)
4	Hangers, USP	JUS26-2			SIMPSON (LUS26-2)
3	LVL Beams (Not Sized)	LVL, 1-3/4" X 11-7/8"	20-00-00		NOT SIZED BY COMTECH. DB1
3	LVL Beams (Not Sized)	LVL, 1-3/4" X 11-7/8"	13-00-00		NOT SIZED BY COMTECH. GDH2
3	LVL Beams (Not Sized)	LVL, 1-3/4" X 14" (NS)	21-00-00		NOT SIZED BY COMTECH. GDH1
10	LVL Beams (Not Sized)	LVL, 1-3/4" X 9-1/4" (NS)	08-00-00		NOT SIZED BY COMTECH. H1
2	LVL Beams (Sized)	LVL, 1-3/4" x 11-7/8" (S)	06-00-00		H2
4	Hangers, USP	THD410			SIMPSON (HHUS410)
2	Hangers, USP	THDH210-2			SIMPSON (HGUS210-2)

ITEMS SUB-TOTAL: \$ 2,160.98

Prices quoted are valid for jobs released for production within thirty Additional design time made necessary by incorrect foundation inst This estimate includes sealed engineering of individual truss drawin	SOR-IOTAL	\$26,194.39	
will be billed in quarter hour increments as costs are incurred.	DELIVERY	\$600.00	
ACCEPTED BY SELLER	ACCEPTED BY BUYER	SUB-TOTAL	\$26,794.39
	PURCHASER:	SALES TAX 7.00%	\$1,833.60
BY:	BY: TITLE:	GRAND TOTAL	\$28627.99
TITLE:	ADDRESS:		
DATE OF ACCEPTANCE:			
	PHONE: DATE:		

WARNING: As part of this proposal, we warn that trusses can be dangerous and cause property damage or personal injury if improperly installed and / or braced. Customer acceptance hereof shall constitute his affirmative representation to us that he is trained in the proper and safe methods of truss installation and bracing, and will use such methods. Customer acknowledges receipt of instructional pamphlet entitle: 'Bracing Wood Trusses: Commentary and recommendations', HIB-91, as published by the Truss Plate Institute, Inc., and also the engineering drawings showing the required lateral bracing. By his acceptance, Customer agrees, for himself, his agents and employees, to hold Comtech Inc. harmless from any and all actions for property damage, personal injury, or wrongful death resulting from improper installation and / or bracing during erection of the trusses comprehended hereby.