

1 Truss Placement Plan
Scale: 3/16"=1'

All Truss Reactions are Less than 3,000 lbs. Unless Noted Otherwise.
-- Denotes Reaction Greater than 3,000 lbs. Reaction / # of Studs

All Headers Are Considered 2X10 Beams Unless Otherwise Noted

All Walls Shown Are Considered Load Bearing

Plumbing Drop Notes

1. Plumbing drop locations shown are NOT exact.
2. Contractor to verify ALL plumbing drop locations prior to setting Floor Trusses.
3. Adjust spacing as needed not to exceed 24"oc.

Dimension Notes

1. All exterior wall to wall dimensions are to face of stud unless noted otherwise
2. All interior wall dimensions are to face of stud unless noted otherwise
3. All exterior wall to truss dimensions are to face of stud unless noted otherwise

Hatch Legend

- Second Floor Walls
- Box Storage
- Drop Beam
- Flush Beam

Connector Information					Nail Information	
Sym	Product	Manuf	Qty	Supported Member	Header	Truss
	HUS410	USP	7	NA	16d/3-1/2"	16d/3-1/2"
	THD410	USP	1	NA	16d/3-1/2"	10d/3"

Products

PlotID	Length	Product	Plies	Net Qty
BM1	14' 0"	1-3/4"x 14" LVL Kerto-S	2	2
BM2	16' 0"	1-3/4"x 14" LVL Kerto-S	2	2
BM3	14' 0"	1-3/4"x 14" LVL Kerto-S	2	2
BM4	4' 0"	1-3/4"x 9-1/4" LVL Kerto-S	2	2
BM5	13' 0"	1-3/4"x 9-1/4" LVL Kerto-S	2	2
BM6	8' 0"	2x12 SPF No.1	2	4
GDH	22' 0"	1-3/4"x 18" LVL Kerto-S	3	3
GDH2	13' 0"	1-3/4"x 11-7/8" LVL Kerto-S	2	2

▲= Denotes Left End of Truss
(Reference Engineered Truss Drawing)

COMTECH
ROOF & FLOOR TRUSSES & BEAMS
Reilly Road Industrial Park
Fayetteville, N.C. 28309
Phone: (910) 864-8787
Fax: (910) 864-4444

Bearing reactions less than or equal to 3000# are deemed to comply with the prescriptive Code requirements. The contractor shall refer to the attached Tables (derived from the prescriptive Code requirements) to determine the minimum foundation size and number of wood studs required to support reactions greater than 3000# but not greater than 15000#. A registered design professional shall be retained to design the support system for any reaction that exceeds those specified in the attached Tables. A registered design professional shall be retained to design the support system for all reactions that exceed 15000#.

Signature Jonathan Landry
Jonathan Landry

LOAD CHART FOR JACK STUDS

(BASED ON TABLES R502.5(1) & (b))
NUMBER OF JACK STUDS REQUIRED @ EA END OF HEADER/GIRDER

END REACTION (LBS TOT)	REQ'D STUDS FOR (2) 1.5" HEADER	END REACTION (LBS TOT)	REQ'D STUDS FOR (3) 1.5" HEADER	END REACTION (LBS TOT)	REQ'D STUDS FOR (4) 1.5" HEADER
1700	1	2550	1	3400	1
3400	2	5100	2	6800	2
5100	3	7650	3	10200	3
6800	4	10200	4	13600	4
8500	5	12750	5	17000	5
10200	6	15300	6		
11900	7				
13600	8				
15300	9				

BUILDER	Glover Design Build
JOB NAME	Lot 44 Purfoy Place
PLAN	Newport / 3GRF, CP
SEAL DATE	N/A
QUOTE #	
JOB #	J0923-5486
CITY / CO.	Fuquay Varina / Harnett
ADDRESS	169 Lambert Lane
MODEL	Floor
DATE REV.	10/17/23
DRAWN BY	Jonathan Landry
SALES REP.	Lenny Norris

THIS IS A TRUSS PLACEMENT DIAGRAM ONLY.
These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designer is responsible for temporary and permanent bracing of the roof and floor system and for the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer. For general guidance regarding bracing, consult BCSI-B1 and BCSI-B3 provided with the truss delivery package or online @ sbcindustry.com