




TYPICAL WALL: 8" BLOCK W/ 16" X 12" FOOTING  
 BRICK 4 8" BLOCK W/24" X 12" FOOTING  
 BRICK 4 4" BLOCK W/16" X 12" FOOTING  
 3-2 X 10'S GIRDER  
 2 X 10'S 16' OC JOIST  
 2-2 X 10'S DBL JOIST

FOUNDATION NOTES:  
 ALL FOOTINGS SHALL BEAR ON ORIGINAL UNDISTURBED SOIL.  
 THE 28 DAY COMPRESSIVE STRENGTH OF ALL FOOTINGS IS 3000 PSI.  
 PROVIDE WATER PROOFING AND PERIMETER DRAINS AS REQUIRED.  
 FOUNDATION CONCRETE MIX TO HAVE 1-1/2" MAX AGGREGATE SIZE. CONCRETE FILL MIX TO HAVE 1/2" MAX AGGREGATE SIZE.  
 FOOTING WIDTHS ARE BASED ON A LOAD-BEARING SOIL CAPACITY OF 2000 PSI.  
 PROVIDE 6 MIL POLY VAPOR BARRIER TO COVER GROUND SURFACE IN CRAWL SPACE.  
 ALL ANCHOR BOLTS TO BE 1/2" LONG, 1/2" DIA. A36 UNO ANCHOR BOLTS SHALL BE SPACE AT A MAX OF 6' OC AND NO MORE THAN 1' FROM EA CORNER.

Termiticidal Soil Treatment: Treat entire slab area soil or crawl space surface before vapor barrier is installed and also is poured with a state approved termiticide. Termiticide should be applied by a licensed and certified pest control professional by the state of North Carolina.




CONCRETE BLOCK PIER DETAIL  
 NOT TO SCALE



FOUNDATION & BASEMENT PLAN

SCALE: 1" = 3/16"

AREA SCHEDULE	
NAME	AREA
Heated	763 sq. ft.



FOOTING & FOUNDATION DETAIL

not to scale