



**Plumbing Drop Notes**

1. Plumbing drop locations shown are NOT exact.
2. Contractor to verify ALL plumbing drop locations prior to setting Floor Trusses.
3. Adjust spacing as needed not to exceed 19.2" oc.

**Dimension Notes**

1. All exterior wall to wall dimensions are to face of sheathing unless noted otherwise.
2. All interior wall dimensions are to face of stud unless noted otherwise.
3. All exterior wall to truss dimensions are to face of stud unless noted otherwise.

All Walls Shown Are Considered Load Bearing

▲ = Indicates Left End of Truss (Reference Engineered Truss Drawing)  
Do Not Erect Trusses Backwards

**WALL SCHEDULE**

	1st Floor Walls
	2nd Floor Walls
	Non-Bearing Walls
	Garage Walls Dropped

Connector Information					Nail Information	
Sym	Product	Manuf	Qty	Supported Member	Header	Truss
●	HUS410	USP	3	NA	16d/3-1/2"	16d/3-1/2"

Products					
PlotID	Length	Product	Plies	Net Qty	
FB3	12' 0"	1-3/4"x 14" LVL Kerto-S	2	2	
FB4	5' 0"	1-3/4"x 14" LVL Kerto-S	2	2	
FB5	4' 0"	1-3/4"x 14" LVL Kerto-S	1	1	
FB6	4' 0"	1-3/4"x 14" LVL Kerto-S	2	2	
FB1	20' 0"	1-3/4"x 18" LVL Kerto-S	3	3	
FB2	16' 0"	1-3/4"x 18" LVL Kerto-S	3	3	

Truss Placement Plan  
SCALE: NTS

▲ = Indicates Left End of Truss (Reference Engineered Truss Drawing)  
Do NOT Erect Truss Backwards

**LOAD CHART FOR JACK STUDS**  
(BASED ON TABLES R502.5(1) & (2))  
NUMBER OF JACK STUDS REQUIRED @ EA END OF HEADERS/BEAM

END REACTION (UP TO) @ END OF HEADERS/BEAM	END REACTION (UP TO) @ END OF HEADERS/BEAM	END REACTION (UP TO) @ END OF HEADERS/BEAM
1700	2550	3400
3400	5100	6800
5100	7650	10200
6800	10200	13600
8500	12750	17000
10200	15300	
11900		
13600		
15300		

<b>BUILDER</b>	New Home Inc.
<b>JOB NAME</b>	Lot 12 Heritage @ NC
<b>PLAN</b>	The Clayton - Craftsman
<b>SEAL DATE</b>	Seal Date
<b>QUOTE #</b>	Quote #
<b>JOB #</b>	J1123-6762

<b>CITY / CO.</b>	Lillington / Harnett
<b>ADDRESS</b>	Lot 12 Heritage @ NC
<b>MODEL</b>	Floor
<b>DATE REV.</b>	12/5/23
<b>DRAWN BY</b>	Johnnie Baggett
<b>SALES REP.</b>	Johnnie Baggett

**THIS IS A TRUSS PLACEMENT DIAGRAM ONLY.**  
These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designer is responsible for temporary and permanent bracing of the roof and floor system and for the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer. For general guidance regarding bracing, consult BCSH-B1 and BCSH-B3 provided with the truss delivery package or online @ sbcindustry.com

Bearing reactions less than or equal to 3000# are deemed to comply with the prescriptive Code requirements. The contractor shall refer to the attached Tables (derived from the prescriptive Code requirements) to determine the minimum foundation size and number of wood studs required to support reactions greater than 3000# but not greater than 15000#. A registered design professional shall be retained to design the support system for any reaction that exceeds those specified in the attached Tables. A registered design professional shall be retained to design the support system for all reactions that exceed 15000#.

Signature: Johnnie Baggett  
**Johnnie Baggett**

**comTECH**  
**ROOF & FLOOR TRUSSES & BEAMS**  
Reilly Road Industrial Park  
Fayetteville, N.C. 28309  
Phone: (910) 864-8787  
Fax: (910) 864-4444