



- *Keep tanks and drain lines 10' from property lines.
- *Not a survey.
- *Not a guarantee of a septic permit.
- *Keep supply lines >5' from property lines.
- *Some lines are flagged longer in the field than lengths indicate.
- *No grading septic area.

System: Gravity to Serial Dist.
 Lines: 3-6, (380')
 Accepted Status System
 0.325 Soil LTAR
 24" Trench Bottom

Repair: Pressure Manifold
 Lines: 1,2,7,8 (260')
 T&J Panel 50% Reduction
 0.325 Soil LTAR
 24" Trench Bottom

System: 
 Repair: 

GRAPHIC SCALE
 1" = 50'



Central Carolina Soil Consulting, PLLC
 1900 South Main Street, Suite 110
 Wake Forest, North Carolina 27587
 Phone (919)569-6704 Fax (919)569-6703

4-Bedroom Septic Layout
 Lot 173, Birchwood Subdivision
 Harnett County, North Carolina

Job# : 3753
Drawn By : LW
Date : 05/9/2023
Revision: