

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: J0324-1638
Lot 41 Woodbridge South

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Comtech, Inc - Fayetteville.

Pages or sheets covered by this seal: I64359475 thru I64359493

My license renewal date for the state of North Carolina is December 31, 2024.

North Carolina COA: C-0844



March 21, 2024



Gilbert, Eric

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job J0324-1638	Truss F01	Truss Type Floor	Qty 5	Ply 1	Lot 41 Woodbridge South 164359475
-------------------	--------------	---------------------	----------	----------	--------------------------------------

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:25 2024 Page 1
ID:6XJu5EDhIOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



LOADING (psf)	SPACING-	CSL	DEFL.	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.59	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.62	Vert(LL) -0.14 23-24 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.37	Vert(CT) -0.19 23-24 >859 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.03 15 n/a n/a		
	Code IRC2015/TPI2014			Weight: 111 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. (size) 25=0-3-8, 15=0-3-8, 19=0-3-8
 Max Grav 25=686(LC 10), 15=405(LC 4), 19=1439(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1506/0, 3-4=-2025/0, 4-5=-2025/0, 5-6=-2025/0, 6-7=-1060/2, 7-8=0/1109,
 8-9=0/1108, 9-11=-407/304, 11-12=-714/61, 12-13=-714/61
 BOT CHORD 24-25=0/1057, 23-24=0/1898, 22-23=0/2025, 20-22=0/1621, 19-20=-201/491,
 18-19=-505/86, 17-18=-61/714, 16-17=-61/714, 15-16=0/450
 WEBS 2-25=-1219/0, 2-24=0/584, 3-24=-510/0, 3-23=-86/307, 7-19=-1462/0, 7-20=0/781,
 6-20=-784/0, 6-22=0/723, 5-22=-333/0, 13-15=-561/0, 13-16=-101/336, 9-19=-886/0,
 9-18=0/544, 11-18=-584/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backwards.



March 21, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
 Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Lot 41 Woodbridge South	I64359476
J0324-1638	F02	FLOOR	2	1		
					Job Reference (optional)	

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:26 2024 Page 1
 ID:6XJu5EDhLOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.79	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.76	Vert(LL) -0.22 23-24 >973 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.50	Vert(CT) -0.30 23-24 >709 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.04 19 n/a n/a		
	Code IRC2015/TPI2014			Weight: 118 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. (size) 28=0-3-8, 16=0-3-8, 19=0-3-8
 Max Uplift 16=249(LC 3)
 Max Grav 28=719(LC 10), 16=101(LC 4), 19=1357(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1630/0, 3-4=-2766/0, 4-5=-2766/0, 5-6=-2766/0, 6-8=-2581/0, 8-9=-1826/0, 9-10=-1826/0, 10-11=-492/0, 11-12=0/1325, 12-13=0/1324, 13-14=-15/569
 BOT CHORD 27-28=0/1085, 25-27=0/2240, 24-25=0/2768, 23-24=0/2786, 22-23=0/2322, 20-22=0/1251, 19-20=-387/0, 18-19=-569/15, 17-18=-569/15, 16-17=-569/15
 WEBS 2-28=-1267/0, 2-27=0/710, 3-27=-792/0, 3-25=0/792, 11-19=-1283/0, 11-20=0/1046, 10-20=-997/0, 10-22=0/742, 8-22=-640/0, 8-23=0/344, 6-23=-276/0, 6-24=-180/296, 14-16=-14/710, 13-19=-1050/0, 13-18=0/255

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 16=249.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.



March 21, 2024

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPH Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)</p>	 818 Soundside Road Edenton, NC 27932
--	---

Job J0324-1638	Truss F03	Truss Type Floor	Qty 4	Ply 1	Lot 41 Woodbridge South I64359477
-------------------	--------------	---------------------	----------	----------	--------------------------------------

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:27 2024 Page 1
ID:6XJu5EDhIOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f





Plate Offsets (X, Y)--	[6:0-3-0,Edge], [7:0-3-0,0-0-0], [18:0-3-0,Edge], [19:0-3-0,Edge]
------------------------	---


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 40.0	Plate Grip DOL	1.00	TC 0.28	Vert(LL)	-0.23	18-19	>957	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.65	Vert(CT)	-0.31	18-19	>695	360	M18AHS	186/179
BCLL 0.0	Rep Stress Incr	YES	WB 0.53	Horz(CT)	0.06	14	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S							
									Weight: 116 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 24=0-3-8, 14=0-3-8
Max Grav 24=989(LC 1), 14=983(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-2035/0, 3-4=-3611/0, 4-5=-3617/0, 5-6=-4741/0, 6-7=-4741/0, 7-8=-4741/0, 8-10=-3647/0, 10-11=-3643/0, 11-12=-2076/0
 BOT CHORD 23-24=0/1178, 21-23=0/2922, 19-21=0/4361, 18-19=0/4741, 17-18=0/4412, 15-17=0/2955, 14-15=0/1228
 WEBS 2-24=-1504/0, 2-23=0/1114, 3-23=-1155/0, 3-21=0/860, 5-21=-915/0, 5-19=0/798, 6-19=-335/0, 12-14=-1538/0, 12-15=0/1104, 11-15=-1144/0, 11-17=0/858, 8-17=-939/0, 8-18=-37/759, 7-18=-312/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) All plates are 4x6 MT20 unless otherwise indicated.
 - 4) Plates checked for a plus or minus 1 degree rotation about its center.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



March 21, 2024

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPH Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)</p>	<p>ENGINEERING BY</p> <p>TRENCO</p> <p>A MITTEK AFFILIATE</p> <p>818 Soundside Road Edenton, NC 27932</p>
--	--

Job J0324-1638	Truss F04	Truss Type Floor	Qty 3	Ply 1	Lot 41 Woodbridge South 164359478 Job Reference (optional)
-------------------	--------------	---------------------	----------	----------	--

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:27 2024 Page 1
ID:6XJu5EDhIOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f






Plate Offsets (X,Y)--	[18:0-3-0,Edge], [19:0-3-0,Edge]						
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP		
TCLL 40.0	Plate Grip DOL 1.00	TC 0.46	Vert(LL) -0.25 18-19 >839 480	MT20	244/190		
TCDL 10.0	Lumber DOL 1.00	BC 0.63	Vert(CT) -0.35 18-19 >610 360				
BCLL 0.0	Rep Stress Incr YES	WB 0.52	Horz(CT) 0.05 14 n/a n/a				
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S					Weight: 104 lb FT = 20%F, 11%E

LUMBER-		BRACING-	
TOP CHORD 2x4 SP No.1(flat)		TOP CHORD	Structural wood sheathing directly applied or 5-11-12 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)		BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)			

REACTIONS. (size) 24=0-3-8, 14=Mechanical
Max Grav 24=973(LC 1), 14=973(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1996/0, 3-4=-3526/0, 4-5=-3526/0, 5-6=-4319/0, 6-7=-4319/0, 7-8=-4319/0, 8-10=-3552/0, 10-11=-3552/0, 11-12=-2037/0
BOT CHORD 23-24=0/1159, 21-23=0/2860, 19-21=0/4013, 18-19=0/4319, 17-18=0/4027, 15-17=0/2894, 14-15=0/1208
WEBS 2-24=-1480/0, 2-23=0/1090, 3-23=-1124/0, 3-21=0/832, 5-21=-607/0, 5-19=0/662, 12-14=-1515/0, 12-15=0/1080, 11-15=-1115/0, 11-17=0/822, 8-17=-594/0, 8-18=-5/650

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.




March 21, 2024

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE. Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPH Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)</p>	<p>ENGINEERING BY TRENCO A MiTek Affiliate</p> <p>818 Soundside Road Edenton, NC 27932</p>
--	--

Job J0324-1638	Truss F05	Truss Type FLOOR	Qty 1	Ply 1	Lot 41 Woodbridge South I64359479
Comtech, Inc. Fayetteville, NC - 28314,					Job Reference (optional)

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:28 2024 Page 1
 ID:6XJu5EDhIOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:29.1





Plate Offsets (X,Y)-- [1:Edge,0-1-8], [17:0-1-8,Edge], [18:0-1-8,Edge]


LOADING (psf)	SPACING-	1-7-3	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.36	Vert(LL)	-0.22	17-18	>958	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.62	Vert(CT)	-0.30	17-18	>698		
BCLL 0.0	Rep Stress Incr	YES	WB 0.41	Horz(CT)	0.05	14	n/a		
BCDL 5.0	Code	IRC2015/TPI2014	Matrix-S						
								Weight: 91 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 22=Mechanical, 14=Mechanical
 Max Grav 22=768(LC 1), 14=768(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1614/0, 3-4=-2683/0, 4-5=-2683/0, 5-6=-3186/0, 6-7=-3186/0, 7-8=-3186/0,
 8-9=-2683/0, 9-10=-2683/0, 10-12=-1614/0
 BOT CHORD 21-22=0/959, 19-21=0/2242, 18-19=0/3000, 17-18=0/3186, 16-17=0/3000, 15-16=0/2242,
 14-15=0/959
 WEBS 12-14=-1203/0, 2-22=-1203/0, 12-15=0/853, 2-21=0/853, 10-15=-818/0, 3-21=-818/0,
 10-16=0/563, 3-19=0/563, 8-16=-405/0, 5-19=-405/0, 8-17=-68/488, 5-18=-68/488

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.




March 21, 2024

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE. Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPH Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)</p>	<p>ENGINEERING BY TRENCO A MiTek Affiliate</p> <p>818 Soundside Road Edenton, NC 27932</p>
--	--


Job J0324-1638	Truss F06	Truss Type Floor	Qty 1	Ply 1	Lot 41 Woodbridge South I64359480 Job Reference (optional)
-------------------	--------------	---------------------	----------	----------	--

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:28 2024 Page 1
ID:6XJu5EDhIOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:31.4



	17-2-12	18-6-0
	17-2-12	1-3-4
Plate Offsets (X,Y)--	[1:Edge,0-1-8], [7:0-1-8,Edge], [18:0-3-0,Edge]	


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.59	Vert(LL)	-0.23	19	>894	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.61	Vert(CT)	-0.32	19	>650	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.49	Horz(CT)	0.05	14	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S							
									Weight: 107 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 24=Mechanical, 14=0-4-15
Max Grav 24=938(LC 3), 14=1072(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1950/0, 3-4=-3382/0, 4-5=-3382/0, 5-6=-4002/0, 6-7=-4002/0, 7-8=-3429/0, 8-10=-2179/0
BOT CHORD 23-24=0/1162, 21-23=0/2767, 19-21=0/3788, 18-19=0/4002, 17-18=0/4002, 15-17=0/2941, 14-15=0/1437
WEBS 10-14=-1652/0, 10-15=0/972, 8-15=-997/0, 8-17=0/633, 7-17=-921/0, 7-18=-108/349, 2-24=-1458/0, 2-23=0/1025, 3-23=-1064/0, 3-21=0/767, 5-21=-529/0, 5-19=-45/573

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x6 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.



March 21, 2024


<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPH Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)</p>	<p>ENGINEERING BY</p> <p>TRENCO</p> <p>A MITek Affiliate</p> <p>818 Soundside Road Edenton, NC 27932</p>
--	---

Job J0324-1638	Truss F07	Truss Type Floor	Qty 5	Ply 1	Lot 41 Woodbridge South Job Reference (optional)	I64359481
-------------------	--------------	---------------------	----------	----------	---	-----------


Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:29 2024 Page 1

ID:6XJu5EDhIOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:31.0



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.53	Vert(LL)	-0.19 20-21	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.64	Vert(CT)	-0.26 20-21	>739	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.53	Horz(CT)	0.02 15	n/a	n/a		
BCDL 5.0	Code IRC2015/TP12014		Matrix-S						
								Weight: 109 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 15-17,14-15.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 24=Mechanical, 14=Mechanical, 15=0-3-8
 Max Uplift 14=726(LC 3)
 Max Grav 24=760(LC 3), 15=1882(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1499/0, 3-5=-2496/0, 5-6=-2496/0, 6-7=-2350/0, 7-8=-2350/0, 8-9=-2350/0,
 9-10=-607/0, 10-11=0/1683, 11-12=0/1681
 BOT CHORD 23-24=0/926, 21-23=0/2113, 20-21=0/2558, 19-20=0/2350, 17-19=0/1536, 14-15=-833/0
 WEBS 2-24=-1162/0, 2-23=0/746, 3-23=-798/0, 3-21=0/479, 6-20=-364/149, 10-15=-1716/0,
 10-17=0/1027, 9-17=-1181/0, 9-19=0/1074, 8-19=-305/0, 12-14=0/1113, 12-15=-1207/0


- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 14=726.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 7) CAUTION, Do not erect truss backwards.



March 21, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932

Job J0324-1638	Truss F08	Truss Type FLOOR	Qty 1	Ply 1	Lot 41 Woodbridge South 164359482 Job Reference (optional)
-------------------	--------------	---------------------	----------	----------	--

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:30 2024 Page 1
ID:6XJu5EDhIOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f





Plate Offsets (X, Y)--	[16:0-1-8,Edge], [30:0-1-8,Edge], [31:0-1-8,Edge], [35:0-1-8,Edge], [43:0-3-0,0-0-0], [44:0-3-0,Edge]
------------------------	---

LOADING (psf)	SPACING-	1-7-3	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.82	Vert(LL)	-0.28	44	>892	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.58	Vert(CT)	-0.38	44	>654		
BCLL 0.0	Rep Stress Incr	YES	WB 0.57	Horz(CT)	0.05	37	n/a		
BCDL 5.0	Code IRC2015/TP12014		Matrix-S						
								Weight: 221 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. All bearings 0-3-8.
(lb) - Max Grav All reactions 250 lb or less at joint(s) except 49=827(LC 3), 37=1380(LC 3), 33=936(LC 4), 28=459(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD
2-3=-1998/0, 3-4=-3261/0, 4-5=-3261/0, 5-7=-3958/0, 7-8=-4114/0, 8-10=-3526/0,
10-11=-2397/0, 11-13=-2397/0, 13-14=-711/0, 14-15=0/2024, 15-16=0/2024,
16-17=0/1661, 17-18=0/1661, 18-19=0/1585, 19-20=0/1585, 20-22=-317/732,
22-23=-1117/207, 23-24=-1117/207, 24-25=-1117/207, 25-26=-861/0

BOT CHORD
48-49=0/1312, 46-48=0/2705, 45-46=0/3676, 44-45=0/4114, 43-44=0/4114, 42-43=0/4114,
40-42=0/3011, 38-40=0/1615, 37-38=-454/0, 36-37=-1661/0, 35-36=-1661/0,
33-35=-1480/0, 32-33=-950/0, 31-32=-493/780, 30-31=-207/1117, 29-30=-26/1112,
28-29=0/561

WEBS
2-49=-1515/0, 2-48=0/892, 3-48=-921/0, 3-46=0/693, 14-37=-1886/0, 14-38=0/1191,
13-38=-1192/0, 13-40=0/989, 10-40=-781/0, 10-42=0/662, 8-42=-890/0, 5-46=-518/0,
5-45=0/418, 7-45=-471/184, 7-44=-251/97, 8-43=-87/260, 18-33=-401/81, 16-37=-742/0,
20-33=-1023/0, 20-32=0/675, 22-32=-711/0, 22-31=0/688, 23-31=-299/0, 26-28=-702/0,
26-29=-2/391, 25-29=-327/77, 25-30=-282/5

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backwards.



March 21, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



Job	Truss	Truss Type	Qty	Ply	Lot 41 Woodbridge South	I64359483
J0324-1638	F09	Floor	6	1	Job Reference (optional)	

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:31 2024 Page 1
 ID:6XJu5EDhIOALdYBK4rF8nKyOFED-RIC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f





Plate Offsets (X, Y)--	[8:0-3-0,Edge], [31:0-1-8,Edge], [32:0-1-8,Edge], [42:0-3-0,0-0-0], [43:0-3-0,Edge]
------------------------	---

LOADING (psf)	SPACING-	1-7-3	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.87	Vert(LL)	-0.27	43	>939	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.58	Vert(CT)	-0.35	43	>721	M18AHS	186/179
BCLL 0.0	Rep Stress Incr	YES	WB 0.64	Horz(CT)	0.04	28	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S						
								Weight: 216 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP 2400F 2.0E(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 48=0-5-8, 36=0-3-8, 28=0-3-8
 Max Grav 48=803(LC 3), 36=2108(LC 1), 28=701(LC 4)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1942/0, 3-4=-2996/0, 4-5=-2996/0, 5-7=-3653/0, 7-8=-3821/0, 8-11=-3024/121, 11-12=-1714/600, 12-13=-1714/600, 13-14=0/1300, 14-15=0/3395, 15-16=0/3396, 16-18=-242/1391, 18-19=-1628/785, 19-20=-1628/785, 20-21=-2607/162, 21-22=-2607/162, 22-23=-2607/162, 23-24=-2476/0, 24-25=-2476/0, 25-26=-1638/0, 47-48=0/1280, 46-47=0/2562, 44-46=0/3385, 43-44=0/3821, 42-43=0/3821, 41-42=0/3821, 38-41=-357/2391, 37-38=-912/937, 36-37=-2035/0, 35-36=-1831/0, 33-35=-1076/1023, 32-33=-522/2125, 31-32=-162/2607, 30-31=0/2656, 29-30=0/2156, 28-29=0/1101

BOT CHORD 14-36=-1701/0, 14-37=0/1353, 13-37=-1326/0, 13-38=0/1085, 11-38=-930/0, 11-41=0/852, 8-41=-1214/0, 8-42=0/402, 2-48=-1477/0, 2-47=0/861, 3-47=-808/0, 3-46=0/553, 5-46=-497/0, 5-44=-58/335, 7-44=-277/361, 7-43=-321/27, 16-36=-1836/0, 16-35=0/1178, 18-35=-1130/0, 18-33=0/892, 26-28=-1270/0, 26-29=0/699, 25-29=-674/0, 25-30=-34/409, 23-31=-506/31, 20-33=-769/0, 20-32=0/1006, 21-32=-419/0

WEBS

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 unless otherwise indicated.
 - 3) All plates are 3x4 MT20 unless otherwise indicated.
 - 4) Plates checked for a plus or minus 1 degree rotation about its center.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.




March 21, 2024

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPH Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)</p>	<p>ENGINEERING BY</p> <p>TRENCO</p> <p>A MiTek Affiliate</p> <p>818 Soundside Road Edenton, NC 27932</p>
--	--

Job	Truss	Truss Type	Qty	Ply	Lot 41 Woodbridge South
J0324-1638	F12	Floor	1	1	I64359485
					Job Reference (optional)

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:32 2024 Page 1
 ID:6XJu5EDhLOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



	4-3-8	4-5-4	6-9-4	6-11-0	12-10-12	20-10-0
	4-3-8	0-1-12	2-4-0	0-1-12	5-11-12	7-11-4
Plate Offsets (X, Y)--	[2:0-1-8,Edge], [7:0-1-8,Edge], [17:0-1-8,Edge], [18:0-1-8,Edge], [21:0-1-8,Edge]					

LOADING (psf)	SPACING-	1-7-3	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.25	Vert(LL)	-0.03 16-17	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.19	Vert(CT)	-0.04 16-17	>999	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.19	Horz(CT)	0.01 16	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S						
								Weight: 105 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 19-21,18-19.
WEBS 2x4 SP No.3(flat)	

REACTIONS. All bearings 0-3-8 except (jt=length) 16=Mechanical.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 24 except 26=258(LC 6), 19=686(LC 16), 16=327(LC 7), 23=477(LC 15)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-348/0, 3-5=-348/0, 7-8=-417/0, 8-9=-417/0, 9-10=0/288, 10-11=0/288, 11-12=-552/0, 12-13=-552/0, 13-14=-552/0
 BOT CHORD 25-26=0/348, 24-25=0/348, 23-24=0/277, 22-23=0/417, 21-22=0/417, 19-21=-29/259, 18-19=-22/276, 17-18=0/552, 16-17=0/355
 WEBS 2-26=-395/0, 7-23=-331/0, 9-19=-400/0, 5-23=-295/0, 11-19=-487/0, 11-18=0/392, 14-16=-445/0, 14-17=0/252

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.




March 21, 2024

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPH Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)</p>	<p>818 Soundside Road Edenton, NC 27932</p>
--	---

Job	Truss	Truss Type	Qty	Ply	Lot 41 Woodbridge South
J0324-1638	F13	Floor	1	1	I64359486
					Job Reference (optional)

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:33 2024 Page 1
ID:6XJu5EDhLOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



	4-5-4	12-10-12	20-10-0
	4-5-4	8-5-8	7-11-4
Plate Offsets (X, Y)--	[2:0-1-8,Edge], [6:0-1-8,Edge], [16:0-1-8,Edge], [17:0-1-8,Edge], [20:0-1-8,Edge]		


LOADING (psf)	SPACING-	1-7-3	CSL.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.29	Vert(LL)	-0.05	21-22	>999	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.39	Vert(CT)	-0.06	21-22	>999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.23	Horz(CT)	0.01	15	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S						
								Weight: 103 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. All bearings 0-3-8 except (jt=length) 15=Mechanical.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 25 except 23=511(LC 16), 15=347(LC 13), 19=746(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-301/0, 3-5=-301/0, 5-6=-748/0, 6-7=-852/0, 7-8=-852/0, 10-11=-628/0, 11-12=-628/0, 12-13=-628/0
BOT CHORD 24-25=0/301, 23-24=0/301, 22-23=0/607, 21-22=0/852, 20-21=0/852, 19-20=0/523, 17-19=0/394, 16-17=0/628, 15-16=0/382
WEBS 2-25=-341/0, 5-23=-512/0, 8-19=-562/0, 8-20=0/492, 13-15=-479/0, 13-16=0/314, 10-19=-469/0, 10-17=0/360

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.





March 21, 2024

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPH Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)</p>	<p>818 Soundside Road Edenton, NC 27932</p>
--	---

Job J0324-1638	Truss F14-GR	Truss Type Floor Girder	Qty 1	Ply 1	Lot 41 Woodbridge South 164359487
-------------------	-----------------	----------------------------	----------	----------	--------------------------------------

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:34 2024 Page 1
ID:6XJu5EDhLOALdYBK4rF8nKyOFED-RIC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



4-5-4	12-10-12	25-7-0
4-5-4	8-5-8	12-8-4

Plate Offsets (X,Y)-- [2:0-1-8,Edge], [3:0-1-8,Edge], [10:0-3-12,Edge], [19:Edge,0-1-8], [26:0-1-8,Edge], [27:0-1-8,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.79	Vert(LL)	0.18	21-22	>827	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.70	Vert(CT)	0.22	21-22	>689	M18AHS	186/179
BCLL 0.0	Rep Stress Incr	NO	WB 0.84	Horz(CT)	-0.05	19	n/a		
BCDL 5.0	Code IRC2015/TP12014		Matrix-S						

Weight: 162 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing, Except:
WEBS 2x4 SP No.3(flat)	10-0-0 oc bracing: 26-27
	5-1-3 oc bracing: 21-22
	5-7-10 oc bracing: 20-21.

REACTIONS. All bearings 0-3-8.
 (lb) - Max Uplift All uplift 100 lb or less at joint(s) 31 except 19=-1575(LC 21), 24=-1397(LC 23)
 Max Grav All reactions 250 lb or less at joint(s) except 31=321(LC 23), 19=335(LC 13), 28=775(LC 21), 24=866(LC 11)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-420/75, 3-4=-390/304, 4-5=-389/306, 5-6=-1788/0, 6-7=-1788/0, 7-8=-1788/0, 8-9=-1582/632, 9-10=-1615/604, 10-12=-269/2756, 12-13=-652/5312, 13-14=-653/5339, 14-15=-1005/5339, 15-16=-1005/5339, 16-17=-634/3630
 BOT CHORD 30-31=-75/420, 29-30=-75/420, 28-29=-75/420, 27-28=-19/1187, 26-27=0/1788, 24-26=-124/1847, 23-24=-1006/50, 22-23=-4528/454, 21-22=-5632/780, 20-21=-5035/897, 19-20=-2388/358
 WEBS 9-24=-326/0, 2-31=-516/94, 3-28=-454/147, 5-28=-990/0, 5-27=0/772, 6-27=-377/0, 8-24=-796/183, 8-26=-277/444, 17-19=-435/2940, 17-20=-1607/357, 16-20=-328/1755, 16-21=-380/135, 15-21=-261/0, 10-24=-434/3211, 10-23=-2223/320, 12-23=-282/2252, 12-22=-998/292, 13-22=-24/397, 14-22=-209/384, 14-21=0/437

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) All plates are 3x4 MT20 unless otherwise indicated.
 - 4) Plates checked for a plus or minus 1 degree rotation about its center.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 31 except (jt=lb) 19=1575, 24=1397.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 7) CAUTION, Do not erect truss backwards.
 - 8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 826 lb up at 15-5-4, 826 lb up at 17-5-4, 826 lb up at 19-5-4, 336 lb down at 20-11-12, and 826 lb up at 21-5-4, and 826 lb up at 23-5-4 on top chord. The design/selection of such connection device(s) is the responsibility of others.
 - 9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

Continued on page 2



March 21, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job J0324-1638	Truss F14-GR	Truss Type Floor Girder	Qty 1	Ply 1	Lot 41 Woodbridge South Job Reference (optional)	I64359487
-------------------	-----------------	----------------------------	----------	----------	---	-----------

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:34 2024 Page 2
ID:6XJu5EDhIOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

LOAD CASE(S) Standard

1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00

Uniform Loads (plf)

Vert: 19-31=-10, 1-18=-100

Concentrated Loads (lb)

Vert: 16=192(B) 14=192(B) 34=192(B) 35=192(B) 36=-272(F) 37=192(B)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
Edenton, NC 27932


Job J0324-1638	Truss F15-GR	Truss Type FLOOR GIRDER	Qty 1	Ply 1	Lot 41 Woodbridge South Job Reference (optional)	I64359488
-------------------	-----------------	----------------------------	----------	----------	---	-----------

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:34 2024 Page 1



Scale = 1:8.5



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.12	Vert(LL)	-0.00	7	>999	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.10	Vert(CT)	-0.00	7	>999		
BCLL 0.0	Lumber DOL 1.00	WB 0.11	Horz(CT)	0.00	5	n/a		
BCDL 5.0	Rep Stbrs Incr NO	Matrix-S						
	Code IRC2015/TPI2014						Weight: 29 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 3-10-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	


REACTIONS. (size) 8=Mechanical, 5=0-3-8
Max Grav 8=352(LC 1), 5=529(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 4-5=-255/0, 2-3=-400/0
BOT CHORD 7-8=0/400, 6-7=0/400, 5-6=0/400
WEBS 3-5=-484/0, 2-8=-484/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Plates checked for a plus or minus 1 degree rotation about its center.
 - 3) Refer to girder(s) for truss to truss connections.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backwards.
 - 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 314 lb down at 1-4-12, and 318 lb down at 3-4-12 on top chord. The design/selection of such connection device(s) is the responsibility of others.
 - 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 5-8=-8, 1-4=-80
Concentrated Loads (lb)
Vert: 2=-283(F) 9=-283(F)




March 21, 2024

Job J0324-1638	Truss F16	Truss Type Floor	Qty 4	Ply 1	Lot 41 Woodbridge South I64359489
-------------------	--------------	---------------------	----------	----------	--------------------------------------

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:35 2024 Page 1
ID:6XJu5EDhIOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



0-5-8 0-5-8	6-11-12 6-6-4	19-5-0 12-5-4
Plate Offsets (X, Y)--	[2:0-1-8,Edge], [16:0-1-8,Edge], [17:0-1-8,Edge], [21:0-1-8,Edge]	

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.52	Vert(LL)	-0.09 15-16	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.92	Vert(CT)	-0.12 15-16	>999	360		
BCLL 0.0	Rep Stress Incr	NO	WB 0.35	Horz(CT)	0.02 14	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S						
								Weight: 96 lb	FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 19=0-3-8, 14=0-3-8, 23=0-3-8
Max Grav 19=1230(LC 1), 14=619(LC 5), 23=610(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-24=-375/0, 4-5=0/910, 5-6=0/910, 6-7=-817/161, 7-8=-1658/0, 8-9=-1658/0, 9-10=-1658/0, 10-12=-1183/0
BOT CHORD 19-21=-409/0, 18-19=-363/280, 17-18=0/1334, 16-17=0/1658, 15-16=0/1558, 14-15=0/760
WEBS 4-19=-655/0, 4-21=0/504, 12-14=-951/0, 12-15=0/551, 10-15=-487/0, 10-16=-127/258, 6-19=-1137/0, 6-18=0/735, 7-18=-723/0, 7-17=0/628, 8-17=-282/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Magnitude of user added load(s) on this truss have been applied uniformly across all gravity load cases with no adjustments.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 14-24=-10, 1-13=-100
Concentrated Loads (lb)
Vert: 1=-300



March 21, 2024

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPH Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbccomponents.com)</p>	 818 Soundside Road Edenton, NC 27932
---	---

Job	Truss	Truss Type	Qty	Ply	Lot 41 Woodbridge South
J0324-1638	FKW1	Floor Supported Gable	1	1	I64359490
					Job Reference (optional)


Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:35 2024 Page 1
 ID:6XJu5EDhIOLdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

0-1-8

0-1-8

Scale = 1:37.7



22-7-8
22-7-8

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	20	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-R						
								Weight: 94 lb	FT = 20%F, 11%E

LUMBER-

TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)
 OTHERS 2x4 SP No.3(flat)

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 22-7-8.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 38, 20, 37, 36, 35, 34, 33, 32, 30, 29, 28, 27, 26, 25, 24, 23, 22, 21

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- All plates are 1.5x3 MT20 unless otherwise indicated.
- Plates checked for a plus or minus 1 degree rotation about its center.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 1-4-0 oc.
- Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



March 21, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
 Edenton, NC 27932


Job J0324-1638	Truss FKW2	Truss Type Floor Supported Gable	Qty 1	Ply 1	Lot 41 Woodbridge South I64359491 Job Reference (optional)
-------------------	---------------	-------------------------------------	----------	----------	--

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:36 2024 Page 1
ID:6XJu5EDhIOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

0-1/8

Scale = 1:30.8



18-6-0
18-6-0

Plate Offsets (X, Y)--	[1:Edge,0-1-8], [32:Edge,0-1-8]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.06	Vert(LL) n/a - n/a 999	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.01	Vert(CT) n/a - n/a 999		
BCLL 0.0	Rep Stress Incr YES	WB 0.03	Horz(CT) 0.00 17 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-R		Weight: 78 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 18-6-0.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 32, 17, 31, 30, 29, 27, 26, 25, 24, 23, 22, 21, 20, 19, 18

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- All plates are 1.5x3 MT20 unless otherwise indicated.
 - Plates checked for a plus or minus 1 degree rotation about its center.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.



March 21, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbccomponents.com)



818 Soundside Road
Edenton, NC 27932

Job J0324-1638	Truss FKW3	Truss Type Floor Supported Gable	Qty 1	Ply 1	Lot 41 Woodbridge South I64359492 Job Reference (optional)
-------------------	---------------	-------------------------------------	----------	----------	--

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:36 2024 Page 1
ID:6XJu5EDhIOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

0-1/8

0-1/8

Scale = 1:20.7





Plate Offsets (X,Y)-- [1:Edge,0-1-8]		12-6-8		12-6-8	
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.06	Vert(LL) n/a - n/a 999	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.02	Vert(CT) n/a - n/a 999		
BCLL 0.0	Rep Stress Incr YES	WB 0.03	Horz(CT) 0.00 12 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-R		Weight: 55 lb	FT = 20%F, 11%E

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS. All bearings 12-6-8.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 22, 12, 21, 20, 19, 18, 17, 16, 15, 14, 13

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- All plates are 1.5x3 MT20 unless otherwise indicated.
 - Plates checked for a plus or minus 1 degree rotation about its center.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



March 21, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932

Job J0324-1638	Truss FKW4	Truss Type Floor Supported Gable	Qty 1	Ply 1	Lot 41 Woodbridge South I64359493 Job Reference (optional)
-------------------	---------------	-------------------------------------	----------	----------	--

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 20 08:57:37 2024 Page 1
ID:6XJu5EDhIOALdYBK4rF8nKyOFED-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

0-1-8

Scale = 1:20.3





Plate Offsets (X, Y)-- [1:Edge,0-1-8], [20:Edge,0-1-8]		12-3-8 12-3-8					
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d
TCLL 40.0	Plate Grip DOL	1.00	TC 0.10	Vert(LL)	n/a	-	n/a 999
TCDL 10.0	Lumber DOL	1.00	BC 0.02	Vert(CT)	n/a	-	n/a 999
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	11	n/a n/a
BCDL 5.0	Code IRC2015/TPI2014		Matrix-R				
				PLATES			GRIP
				MT20			244/190
						Weight: 52 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 12-3-8.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 20, 11, 19, 18, 17, 16, 15, 14, 13, 12

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 2) Plates checked for a plus or minus 1 degree rotation about its center.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 5) Gable studs spaced at 1-4-0 oc.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 7) CAUTION, Do not erect truss backwards.




March 21, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)


ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Symbols


PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16\" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.


* Plate location details available in MITek software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.


Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



1 TOP CHORDS
2
3 Joint ID typ.



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 section 6.3. These truss designs rely on Lumber values established by others.

© 2023 MITek® All Rights Reserved

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability/bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.

MITek

ENGINEERING BY
TRENGO
A MITek Affiliate

MITek Engineering Reference Sheet: MIL-7473 rev. 1/2/2023