


Job 23110135	Truss A01	Truss Type Piggyback Base Supported Gable	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	--	----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 Print: 8.630 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:16

Page: 1

ID: EzXy6lDd59oDB8CIWfcVKnyEWca-PTLvgmDj9v3hi00NqdcAbWAEJILYJJx?tfuN5yE6tE



Scale = 1:83.4

Plate Offsets (X, Y): [11:0-3-0,0-3-12], [19:0-4-0,0-3-3]

Loading	(psf)	Spacing	1-11-4	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.17	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.12	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	-0.01	31	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 417 lb	FT = 20%

- LUMBER**
TOP CHORD 2x6 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3
- BRACING**
TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins, except 2-0-0 oc purlins (10-0-0 max.): 11-19.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 19-38, 18-39, 17-40, 16-41, 15-42, 14-43, 13-44, 12-45, 10-47, 20-36
- REACTIONS** All bearings 46-8-0.
(lb) - Max Horiz 2=-184 (LC 13), 54=-184 (LC 13)
Max Uplift All uplift 100 (lb) or less at joint(s) 2, 31, 32, 33, 34, 35, 36, 39, 40, 41, 42, 43, 44, 48, 49, 50, 51, 52, 53, 54
Max Grav All reactions 250 (lb) or less at joint (s) 2, 31, 32, 33, 34, 35, 36, 38, 39, 40, 41, 42, 43, 44, 45, 47, 48, 49, 50, 51, 52, 54 except 30=360 (LC 2), 53=261 (LC 29)
- FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-155/272, 10-11=-115/259, 11-12=-103/250, 12-13=-103/250, 13-14=-103/250, 14-63=-103/250, 15-63=-103/250, 15-16=-103/250, 16-17=-103/250, 17-18=-103/250, 19-20=-115/267
WEBS 27-30=-267/78
- NOTES**
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) -0-9-9 to 3-11-11, Exterior(2N) 3-11-11 to 16-6-0, Corner(3R) 16-6-0 to 21-2-0, Exterior(2N) 21-2-0 to 31-2-0, Corner(3R) 31-2-0 to 35-11-3, Exterior(2N) 35-11-3 to 48-5-9 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0; Min. flat roof snow load governs. Rain surcharge applied to all exposed surfaces with slopes less than 0.500/12 in accordance with IBC 1608.3.4.
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
7) Provide adequate drainage to prevent water ponding.
8) All plates are 2x4 MT20 unless otherwise indicated.
9) Gable studs spaced at 2-0-0 oc.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
11) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2, 39, 40, 41, 42, 43, 44, 48, 49, 50, 51, 52, 53, 36, 35, 34, 33, 32, and 31. This connection is for uplift only and does not consider lateral forces.
12) Non Standard bearing condition. Review required.
13) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
LOAD CASE(S) Standard


Job 23110135	Truss A02	Truss Type Piggyback Base	Qty 6	Ply 1	Job Reference (optional)
-----------------	--------------	------------------------------	----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 Print: 8.630 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:17

Page: 1

ID: ?mYPMIXJCrygh_d6UPZMr3yEWcB-tfulu6ELwCByK9baOKgrjo2EoiuDHe75EXOSvXyE6tD



Scale = 1:83.4

Plate Offsets (X, Y): [14:0-3-8,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	I/defl	L/d	PLATES	GRIP		
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.63	Vert(LL)	-0.15	18-19	>999	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.91	Vert(CT)	-0.27	18-19	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.74	Horz(CT)	0.08	13	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 339 lb	FT = 20%

LUMBER
 TOP CHORD 2x6 SP No.2
 BOT CHORD 2x4 SP No.2
 WEBS 2x4 SP No.3 *Except* W5:2x4 SP No.2

BRACING
 TOP CHORD Structural wood sheathing directly applied or 4-3-9 oc purlins, except 2-0-0 oc purlins (5-3-5 max.): 5-7.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 2-22.
 WEBS 1 Row at midpt 3-22, 6-19, 6-16, 9-16

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=56/0-3-0, (min. 0-1-8), 13=1523/0-3-8, (min. 0-2-4), 22=1871/0-3-8, (min. 0-2-13)
 Max Horiz 2=-190 (LC 13)
 Max Uplift 2=-93 (LC 53)
 Max Grav 2=143 (LC 55), 13=1896 (LC 30), 22=2384 (LC 46)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-29=-48/508, 29-30=-20/521, 3-30=0/641, 3-31=-1673/125, 4-31=-1637/128, 4-5=-1555/169, 5-32=-1332/170, 32-33=-1332/170, 6-33=-1332/170, 6-34=-1724/188, 34-35=-1724/188, 7-35=-1724/188, 7-8=-2014/153, 8-36=-2040/123, 9-36=-2117/109, 9-37=-2378/96, 37-38=-2404/94, 38-39=-2494/78, 10-39=-2571/66, 10-11=-445/0
 BOT CHORD 2-22=-463/89, 21-22=-83/660, 20-21=-49/741, 19-20=-49/741, 19-40=0/1877, 18-40=0/1877, 17-18=0/1877, 17-41=0/1877, 16-41=0/1877, 15-16=-8/2154, 14-15=-8/2154, 13-14=0/427, 11-13=0/427

WEBS 3-22=-2343/106, 3-19=0/942, 5-19=0/482, 6-19=-905/56, 6-18=0/444, 6-16=-325/132, 7-16=0/666, 9-16=-680/111, 10-13=-1525/223, 10-14=-65/1783

LOAD CASE(S) Standard

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -0-9-9 to 3-11-11, Interior (1) 3-11-11 to 16-6-0, Exterior(2R) 16-6-0 to 23-2-14, Interior (1) 23-2-14 to 31-2-0, Exterior(2R) 31-2-0 to 37-10-14, Interior (1) 37-10-14 to 48-5-9 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
 - 3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0; Min. flat roof snow load governs. Rain surcharge applied to all exposed surfaces with slopes less than 0.500/12 in accordance with IBC 1608.3.4.
 - 4) Unbalanced snow loads have been considered for this design.
 - 5) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
 - 6) Provide adequate drainage to prevent water ponding.
 - 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 8) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2. This connection is for uplift only and does not consider lateral forces.
 - 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Job 23110135	Truss A03	Truss Type Piggyback Base	Qty 3	Ply 1	Job Reference (optional)
-----------------	--------------	------------------------------	----------	----------	--------------------------



Scale = 1:83.4

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.57	Vert(LL)	-0.20	12-13	>617	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.83	Vert(CT)	-0.38	12-13	>316	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.04	12	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 342 lb	FT = 20%

LUMBER
TOP CHORD 2x6 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* W5:2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 5-7.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 2-21,13-15.
WEBS 1 Row at midpt 6-18, 6-15, 7-15, 9-12

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS All bearings 0-3-0, except 21=0-3-8, 13=0-3-8
(lb) - Max Horiz 2=190 (LC 14)
Max Uplift All uplift 100 (lb) or less at joint(s) 2, 12
Max Grav All reactions 250 (lb) or less at joint (s) except 2=265 (LC 55), 12=748 (LC 30), 13=1603 (LC 46), 21=1821 (LC 48)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-29=-47/319, 3-30=-1302/112, 4-30=-1247/115, 4-5=-1207/157, 5-31=-1035/170, 31-32=-1035/170, 6-32=-1035/170, 6-33=-815/161, 33-34=-815/161, 7-34=-815/161, 7-8=-950/142, 8-35=-965/112, 9-35=-1016/98, 9-36=-501/4, 36-37=-592/0, 10-37=-683/0
BOT CHORD 20-21=-76/688, 19-20=-41/771, 18-19=-41/771, 18-38=0/1303, 17-38=0/1303, 16-17=0/1303, 16-39=0/1303, 15-39=0/1303, 12-13=0/462, 10-12=0/489
WEBS 3-21=-1725/108, 3-18=-26/578, 5-18=0/312, 6-18=-454/89, 6-17=0/466, 6-15=-799/54, 9-15=-9/1252, 9-13=-1476/167

NOTES
1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -0-9-9 to 3-11-11, Interior (1) 3-11-11 to 16-6-0, Exterior(2R) 16-6-0 to 23-2-14, Interior (1) 23-2-14 to 31-2-0, Exterior(2R) 31-2-0 to 37-10-14, Interior (1) 37-10-14 to 48-5-9 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0; Min. flat roof snow load governs. Rain surcharge applied to all exposed surfaces with slopes less than 0.500/12 in accordance with IBC 1608.3.4.
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 12. This connection is for uplift only and does not consider lateral forces.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
23110135	A04	Piggyback Base	6	1	



Scale = 1:95.5

Plate Offsets (X, Y): [2:0-0-5,0-0-4], [6:0-3-12,0-3-0], [11:0-2-4,0-2-12], [16:0-3-8,0-2-0], [20:0-3-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	0.56	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.56	Vert(LL)	-0.38	18-20	>999	240	MT20 244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.89	Vert(CT)	-0.57	18-20	>887	180	
TCDL	10.0	Rep Stress Incr	YES	WB	0.99	Horz(CT)	0.11	15	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							
BCDL	10.0										Weight: 356 lb FT = 20%

LUMBER
 TOP CHORD 2x6 SP No.2
 BOT CHORD 2x4 SP 2400F 2.0E *Except* B4,B3:2x4 SP No.2, B2:2x4 SP No.1
 WEBS 2x4 SP No.3 *Except* W10,W5,W13:2x4 SP No.2

BRACING
 TOP CHORD Structural wood sheathing directly applied or 3-7-12 oc purlins, except 2-0-0 oc purlins (4-0-7 max.): 6-8.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 15-16,14-15,12-14.
 WEBS 1 Row at midpt 7-21, 8-18, 9-16
 JOINTS 1 Brace at Jt(s): 24, 22, 21, 26

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=1640/0-3-8, (min. 0-1-13), 14=-389/0-3-0, (min. 0-1-8), 15=2565/0-3-8, (min. 0-3-0)
 Max Horiz 2=-190 (LC 13)
 Max Uplift 14=-1163 (LC 51), 15=-25 (LC 11)
 Max Grav 2=2220 (LC 48), 14=314 (LC 11), 15=3657 (LC 58)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 6-37=-2344/0, 37-38=-2344/0, 7-38=-2344/0, 7-39=-2342/0, 39-40=-2342/0, 8-40=-2342/0, 2-44=-3766/0, 3-44=-3694/0, 3-45=-3364/0, 4-45=-3301/0, 4-5=-3210/0, 5-6=-2940/0, 8-9=-2088/17, 9-10=-1644/35, 10-46=-1722/18, 11-46=-1823/17, 11-47=-94/621, 12-47=-119/559

BOT CHORD 2-30=0/3313, 29-30=0/3313, 28-29=0/2954, 27-28=0/2954, 27-41=0/2416, 25-41=0/2416, 23-25=0/3219, 20-23=0/2367, 19-20=0/1758, 19-42=0/1758, 18-42=0/1758, 17-18=0/1519, 17-43=0/1519, 16-43=0/1519, 15-16=-1805/429, 14-15=-1759/427, 12-14=-460/122, 26-48=-965/0, 24-48=-965/0, 22-24=-965/0, 21-22=-965/0, 20-21=-823/0, 7-21=-604/139, 8-20=0/1325, 8-18=-632/54, 26-27=-30/842, 6-26=0/1242, 24-25=-255/0, 21-23=0/1050, 25-26=0/1134, 5-29=0/417, 3-29=-434/69, 9-16=-1369/41, 9-18=0/1150, 11-15=-3399/80, 11-16=0/2903, 5-27=-826/117, 11-14=-377/1607


WEBS

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -0-9-9 to 3-11-11, Interior (1) 3-11-11 to 16-6-0, Exterior(2R) 16-6-0 to 23-2-14, Interior (1) 23-2-14 to 31-2-0, Exterior(2R) 31-2-0 to 37-10-14, Interior (1) 37-10-14 to 48-5-9 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
 - 3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0; Min. flat roof snow load governs. Rain surcharge applied to all exposed surfaces with slopes less than 0.500/12 in accordance with IBC 1608.3.4.
 - 4) Unbalanced snow loads have been considered for this design.
 - 5) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
 - 6) 200.0lb AC unit load placed on the bottom chord, 19-10-0 from left end, supported at two points, 5-0-0 apart.
 - 7) Provide adequate drainage to prevent water ponding.

- 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1163 lb uplift at joint 14.
- 10) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 15. This connection is for uplift only and does not consider lateral forces.
- 11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 13) This truss has large uplift reaction(s) from gravity load case(s). Proper connection is required to secure truss against upward movement at the bearings. Building designer must provide for uplift reactions indicated.

LOAD CASE(S) Standard

Job 23110135	Truss A05	Truss Type Piggyback Base	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	------------------------------	----------	----------	--------------------------



Scale = 1:99.3

Plate Offsets (X, Y): [6:0-3-12,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.69	Vert(LL)	-0.25	26-28	>999	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.63	Vert(CT)	-0.45	26-28	>637	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.67	Horz(CT)	0.14	12	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 347 lb	FT = 20%

LUMBER
TOP CHORD 2x6 SP No.2
BOT CHORD 2x4 SP 2400F 2.0E *Except* B3:2x4 SP No.2
WEBS 2x4 SP No.3 *Except* W10:2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-9-12 oc purlins, except 2-0-0 oc purlins (4-6-1 max.): 6-8.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing. Except: 5-5-0 oc bracing: 20-25
WEBS 1 Row at midpt 7-19, 8-19, 9-17, 5-26

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=1500/0-3-8, (min. 0-1-12), 12=1433/0-3-8, (min. 0-1-10), 19=883/0-3-8, (min. 0-1-8)
Max Horiz 2=-190 (LC 13)
Max Uplift 19=-47 (LC 11)
Max Grav 2=2136 (LC 48), 12=1942 (LC 50), 19=1303 (LC 51)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-36=-3604/0, 3-36=-3531/0, 3-37=-3208/0, 4-37=-3145/0, 4-5=-3055/0, 5-6=-2765/0, 6-38=-2164/0, 38-39=-2164/0, 7-39=-2164/0, 7-40=-2153/0, 40-41=-2153/0, 8-41=-2153/0, 8-9=-2439/4, 9-10=-2745/0, 10-42=-2836/0, 11-42=-2898/0, 11-43=-3199/0, 12-43=-3272/0
BOT CHORD 2-29=0/3174, 28-29=0/3174, 27-28=0/2822, 26-27=0/2822, 26-44=0/2323, 24-44=0/2323, 22-24=0/3072, 19-22=0/2079, 18-19=0/2042, 18-45=0/2042, 17-45=0/2042, 16-17=0/2484, 16-46=0/2484, 15-46=0/2484, 14-15=0/2766, 12-14=0/2766, 25-47=-1007/0, 23-47=-1007/0, 21-23=-1007/0, 20-21=-1007/0

WEBS 8-17=-12/928, 19-20=-1098/0, 7-20=-817/110, 8-19=-195/405, 25-26=-31/823, 6-25=0/1225, 24-25=0/1021, 21-22=-318/0, 20-22=0/1228, 3-28=-422/73, 5-28=0/449, 9-17=-853/105, 9-15=0/458, 11-15=-454/75, 5-26=-887/105

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -0-9-9 to 3-11-11, Interior (1) 3-11-11 to 16-6-0, Exterior(2R) 16-6-0 to 23-2-14, Interior (1) 23-2-14 to 31-2-0, Exterior(2R) 31-2-0 to 37-10-14, Interior (1) 37-10-14 to 48-5-9 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0; Min. flat roof snow load governs. Rain surcharge applied to all exposed surfaces with slopes less than 0.500/12 in accordance with IBC 1608.3.4.
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
 - 200.0lb AC unit load placed on the bottom chord, 19-10-0 from left end, supported at two points, 5-0-0 apart.
 - Provide adequate drainage to prevent water ponding.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 19. This connection is for uplift only and does not consider lateral forces.

10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard


Job 23110135	Truss A07	Truss Type Piggyback Base Supported Gable	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	--	----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 Print: 8.630 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:19

Page: 1

ID:EzXy6lDd59oDB8CIWfcVKnyEWca-IEaQW7GDD7Z7BdK93SDYLrGsdw7HU7JXwVd6WsyE6tA



Scale = 1:83.4

Plate Offsets (X, Y): [11:0-3-0,0-3-12], [19:0-4-0,0-3-3]

Loading	(psf)	Spacing	1-11-4	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.17	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.12	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	-0.01	31	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 417 lb	FT = 20%

LUMBER
 TOP CHORD 2x6 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins, except 2-0-0 oc purlins (10-0-0 max.): 11-19.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
 WEBS 1 Row at midpt 19-38, 18-39, 17-40, 16-41, 15-42, 14-43, 13-44, 12-45, 10-47, 20-36

REACTIONS All bearings 47-8-0.
 (lb) - Max Horiz 2--184 (LC 13), 54--184 (LC 13)
 Max Uplift All uplift 100 (lb) or less at joint(s) 2, 31, 32, 33, 34, 35, 36, 39, 40, 41, 42, 43, 44, 48, 49, 50, 51, 52, 53, 54
 Max Grav All reactions 250 (lb) or less at joint (s) 2, 31, 32, 33, 34, 35, 36, 38, 39, 40, 41, 42, 43, 44, 45, 47, 48, 49, 50, 51, 52, 54 except 30=360 (LC 2), 53=261 (LC 29)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-155/270, 10-11=-115/258, 19-20=-115/267
 WEBS 27-30=-267/178

NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) -0-9-9 to 3-11-11, Exterior(2N) 3-11-11 to 16-6-0, Corner(3R) 16-6-0 to 21-2-0, Exterior(2N) 21-2-0 to 31-2-0, Corner(3R) 31-2-0 to 35-11-3, Exterior(2N) 35-11-3 to 48-5-9 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0; Min. flat roof snow load governs. Rain surcharge applied to all exposed surfaces with slopes less than 0.500/12 in accordance with IBC 1608.3.4.
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint (s) 2, 39, 40, 41, 42, 43, 44, 48, 49, 50, 51, 52, 53, 36, 35, 34, 33, 32, 31, 2.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard


Job 23110135	Truss PB2	Truss Type Piggyback	Qty 25	Ply 1	Job Reference (optional)
-----------------	--------------	-------------------------	-----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 Print: 8.630 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:20

Page: 1

ID:jQdmuRwsh3fMvalZRwj3ayEWcl-mQ8ojTHR_Rh_ onvLdAlnteD01KT8Ddmg98Mf2lyE6t9



Scale = 1:36.4

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.06	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 53 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS

All bearings 12-11-10.
(lb) - Max Horiz 2=-77 (LC 13), 11=-77 (LC 13)
Max Uplift All uplift 100 (lb) or less at joint(s) 2, 8, 10, 11
Max Grav All reactions 250 (lb) or less at joint (s) 2, 6, 11, 15 except 8=347 (LC 23), 9=274 (LC 2), 10=347 (LC 22)

FORCES

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS

3-10=-286/140, 5-8=-286/141

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-3-11 to 3-4-0, Interior (1) 3-4-0 to 7-4-0, Exterior(2R) 7-4-0 to 10-4-0, Interior (1) 10-4-0 to 14-4-5 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

- 5) Unbalanced snow loads have been considered for this design.
- 6) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- 7) Gable requires continuous bottom chord bearing.
- 8) Gable studs spaced at 4-0-0 oc.
- 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 10) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2, 10, and 8. This connection is for uplift only and does not consider lateral forces.
- 11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 12) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S)

Standard


Job 23110135	Truss VL1	Truss Type Valley	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	----------------------	----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:20

Page: 1

ID:BdB85ESYc?CWz39y78SyboyEWcH-mQ8ojTHr_Rh_onvLdAlnteD2OKTzDbgg98Mf2lyE6t9



Scale = 1:59.1

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.09	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.13	Horiz(TL)	0.00	11	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 137 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.
 WEBS 1 Row at midpt 6-17

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-06"-00 tall by 2'-00"-00 wide will fit between the bottom chord and any other members.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint (s) 1, 18, 19, 20, 21, 15, 14, 13, 12.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

REACTIONS All bearings 21-8-8.

(lb) - Max Horiz 1=167 (LC 10)
 Max Uplift All uplift 100 (lb) or less at joint(s) 1, 12, 13, 14, 15, 18, 19, 20, 21
 Max Grav All reactions 250 (lb) or less at joint (s) 1, 11, 12, 13, 14, 15, 17, 18, 19, 20, 21

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-0-5 to 2-10-4, Interior (1) 2-10-4 to 10-10-9, Exterior(2R) 10-10-9 to 13-10-9, Interior (1) 13-10-9 to 21-4-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- 3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 4) All plates are 2x4 MT20 unless otherwise indicated.
- 5) Gable requires continuous bottom chord bearing.


Job 23110135	Truss VL2	Truss Type Valley	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	----------------------	----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 Print: 8.630 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:20

Page: 1

ID:BdB85ESYc?CWz39y78SyboyEWcH-mQ8ojTfR_rh_onyLdAlnteD0VKsJDbtg98Mf2lyE6t9



Scale = 1:53.9

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.17	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.18	Horiz(TL)	0.00	7	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
										Weight: 92 lb	FT = 20%	

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint (s) 1, 7, 12, 13, 9, 8.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

REACTIONS All bearings 19-6-10.
(lb) - Max Horiz 1=150 (LC 10)
Max Uplift All uplift 100 (lb) or less at joint(s) 1, 7, 8, 9, 12, 13
Max Grav All reactions 250 (lb) or less at joint (s) 1, 7 except 8=318 (LC 25), 9=459 (LC 25), 11=355 (LC 27), 12=462 (LC 24), 13=321 (LC 24)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS 3-12=-286/175, 5-9=-284/173

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-0-5 to 3-0-5, Interior (1) 3-0-5 to 9-9-10, Exterior(2R) 9-9-10 to 12-9-10, Interior (1) 12-9-10 to 19-2-6 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.


Job 23110135	Truss VL3	Truss Type Valley	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	----------------------	----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 Print: 8.630 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:20

Page: 1

ID:qOrqTjBloEQeKhUjrX2oi9yEWcd-mQ8ojTHr_Rh_onvLdAlnteD1RKTzDZTg98Mf2lyE6t9



Scale = 1:50.3

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.14	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.09	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.27	Horiz(TL)	0.00	9	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 98 lb	FT = 20%

LUMBER
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint (s) 1, 15, 16, 17, 12, 11, 10.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

REACTIONS All bearings 17-5-0.
 (lb) - Max Horiz 1=133 (LC 9)
 Max Uplift All uplift 100 (lb) or less at joint(s) 1, 9, 10, 11, 12, 15, 16, 17, 22
 Max Grav All reactions 250 (lb) or less at joint (s) 1, 10, 11, 12, 15, 16, 17 except 14=331 (LC 27)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-101/257
 WEBS 5-14=-292/0

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-0-5 to 3-0-5, Interior (1) 3-0-5 to 8-8-13, Exterior(2R) 8-8-13 to 11-8-13, Interior (1) 11-8-13 to 17-5-5 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.


Job 23110135	Truss VL4	Truss Type Valley	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	----------------------	----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 Print: 8.630 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:20

Page: 1

ID: BdB85ESYc?CWz39y78SyboyEWcH-mQ8oJThR_Rh_onvLdAlnteD?FKSuDYmg98Mf2lyE6t9



Scale = 1:48

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.28	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.16	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.38	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 71 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint (s) 1, 9, 6.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

REACTIONS All bearings 16-0-3.
(lb) - Max Horiz 1=-122 (LC 11)
Max Uplift All uplift 100 (lb) or less at joint(s) 1, 5, 6, 9, 14
Max Grav All reactions 250 (lb) or less at joint (s) 1, 5, 14 except 6=469 (LC 25), 8=672 (LC 24), 9=461 (LC 24)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-71/358, 3-15=0/305, 3-16=0/287, 4-5=-20/301
WEBS 3-8=-486/0, 2-9=-285/180, 4-6=-288/179

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-0-5 to 3-0-5, Interior (1) 3-0-5 to 8-0-6, Exterior(2R) 8-0-6 to 11-0-6, Interior (1) 11-0-6 to 16-0-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Gable requires continuous bottom chord bearing.


Job 23110135	Truss VL5	Truss Type Valley	Qty 2	Ply 1	Job Reference (optional)
-----------------	--------------	----------------------	----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 Print: 8.630 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:20

Page: 1

ID:BdB85ESYc?CWz39y78SyboyEWcH-mQ8ojTHr_Rh_0nvLdAnteD1gKT8Dcag98Mf2lyE6t9



Scale = 1:44.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.19	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.08	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.12	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 60 lb	FT = 20%

LUMBER
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS All bearings 13-11-6.
 (lb) - Max Horiz 1=-106 (LC 9)
 Max Uplift 100 (lb) or less at joint(s) 1, 6, 8
 Max Grav All reactions 250 (lb) or less at joint (s) 1, 5 except 6=344 (LC 25), 7=280 (LC 2), 8=347 (LC 24)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 WEBS 2-8=-262/191, 4-6=-259/188

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-0-5 to 2-11-11, Interior (1) 2-11-11 to 7-0-0, Exterior(2R) 7-0-0 to 10-0-0, Interior (1) 10-0-0 to 13-11-11 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
 - 3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - 4) Gable requires continuous bottom chord bearing.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint (s) 1, 8, 6.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job 23110135	Truss VL6	Truss Type Valley	Qty 2	Ply 1	Job Reference (optional)
-----------------	--------------	----------------------	----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 Print: 8.630 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:21

Page: 1

ID:fpkWlaTANIKNBdK8hszB8?yEWcG-EdiBxpHUllprQxUXAtG0QslCQjoCy3hqOo6DakyE6t8



Scale = 1:42.3

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.19	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.09	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 45 lb	FT = 20%

LUMBER
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS All bearings 11-1-13.
 (lb) - Max Horiz 1=-84 (LC 11)
 Max Uplift All uplift 100 (lb) or less at joint(s) 1, 5, 6, 8
 Max Grav All reactions 250 (lb) or less at joint (s) 1, 5, 7 except 6=311 (LC 25), 8=318 (LC 24)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 WEBS 2-8=-284/267, 4-6=-273/257

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-0-5 to 3-0-5, Interior (1) 3-0-5 to 5-7-3, Exterior(2R) 5-7-3 to 8-7-3, Interior (1) 8-7-3 to 11-2-2 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
 - 3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - 4) Gable requires continuous bottom chord bearing.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint (s) 1, 5, 8, 6.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job 23110135	Truss VL7	Truss Type Valley	Qty 2	Ply 1	Job Reference (optional)
-----------------	--------------	----------------------	----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 Print: 8.630 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:21

Page: 1

ID:fpkWlaTANIKNbDk8hszB8?yEWcG-EdiBxpHUllprQxUXAtG0QsIBnjmLy33qOo6DakyE6t8



Scale = 1:34.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.21	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.12	Horiz(TL)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0											
										Weight: 31 lb	FT = 20%	

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 8-4-3 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 22 lb uplift at joint 1, 19 lb uplift at joint 3 and 19 lb uplift at joint 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

REACTIONS (lb/size)
1=22/8-4-3, (min. 0-1-8),
3=26/8-4-3, (min. 0-1-8),
4=518/8-4-3, (min. 0-1-8)
Max Horiz 1=-62 (LC 9)
Max Uplift 1=-22 (LC 31), 3=-19 (LC 30),
4=-19 (LC 13)
Max Grav 1=62 (LC 30), 3=65 (LC 31), 4=612 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-9=-119/253
WEBS 2-4=-448/255

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-0-5 to 3-0-5, Interior (1) 3-0-5 to 4-2-6, Exterior(2R) 4-2-6 to 7-2-6, Interior (1) 7-2-6 to 8-4-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Gable requires continuous bottom chord bearing.


Job 23110135	Truss VL8	Truss Type Valley	Qty 2	Ply 1	Job Reference (optional)
-----------------	--------------	----------------------	----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 Print: 8.630 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:21

Page: 1

ID:fpkWlaTANIKNbDk8hszB8?yEWcG-EdiBxpHUIlprQxUXAtG0QslD8Jo2y48qOo6DakyE6t8



Scale = 1:30.4

Loading	(psf)	Spacing	2-0-0	CSI	0.08	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.10	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.05	Horiz(TL)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 20 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-6-10 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 1=41/5-6-10, (min. 0-1-8), 3=43/5-6-10, (min. 0-1-8), 4=292/5-6-10, (min. 0-1-8)
Max Horiz 1=40 (LC 11)
Max Uplift 4=-1 (LC 13)
Max Grav 1=64 (LC 30), 3=66 (LC 31), 4=344 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
 - 3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - 4) Gable requires continuous bottom chord bearing.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1 lb uplift at joint 4.


Job 23110135	Truss VL9	Truss Type Valley	Qty 2	Ply 1	Job Reference (optional)
-----------------	--------------	----------------------	----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 Print: 8.630 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:21

Page: 1

ID:fpkWlaTANIKNbDk8hszB8?yEWcG-EdiBxpHUllprQxUXAtG0QsIESjpy4wqOo6DakyE6t8



Scale = 1:30.1

Plate Offsets (X, Y): [2:0-2-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.05	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 8 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-9-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 1=93/2-9-0, (min. 0-1-8),
3=93/2-9-0, (min. 0-1-8)
Max Horiz 1=18 (LC 12)
Max Grav 1=110 (LC 2), 3=110 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- 3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 4) Gable requires continuous bottom chord bearing.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job 23110135	Truss VL10	Truss Type Valley	Qty 1	Ply 1	Job Reference (optional)
-----------------	---------------	----------------------	----------	----------	--------------------------

Carter Components, Sanford, NC, user

Run: 8.63 S Dec 22 2022 Print: 8.630 S Dec 22 2022 MiTek Industries, Inc. Thu Nov 30 16:28:21

Page: 1

ID:BdB85ESYc?CWz39y78SyboyEWcH-EdiBxpHUIlprQxUXAtG0QslAXjnoy_3qOo6DakyE6t8



Scale = 1:49.2

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.18	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.44	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 75 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint (s) 1, 9, 6.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

REACTIONS All bearings 16-9-0.
(lb) - Max Horiz 1=128 (LC 10)
Max Uplift All uplift 100 (lb) or less at joint(s) 1, 5, 6, 9, 14
Max Grav All reactions 250 (lb) or less at joint (s) 1, 5, 14 except 6=497 (LC 25), 8=695 (LC 24), 9=492 (LC 24)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-15=-70/317, 2-15=-36/390, 3-16=0/328, 3-17=0/310, 4-18=0/333, 5-18=-19/259
WEBS 3-8=-512/0, 2-9=-298/178, 4-6=-300/177

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-0-5 to 3-0-5, Interior (1) 3-0-5 to 8-4-13, Exterior(2R) 8-4-13 to 11-4-13, Interior (1) 11-4-13 to 16-9-5 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Gable requires continuous bottom chord bearing.