

LEGEND

| LANDSCAPE POSITION | SOIL GROUP | SOIL TEXTURE | CONVENTIONAL LTAR (gpd/ft ²) | SAPROLITE LTAR (gpd/ft ²) | LPP LTAR (gpd/ft ²) | MINERALOGY/ CONSISTENCE | | STRUCTURE | |
|--------------------|------------|------------------------|--|---------------------------------------|---------------------------------|-------------------------|----------------------|-------------------------|------------|
| | | | | | | MOIST | WET | | |
| CC (Concave slope) | I | S (Sand) | 0.8 - 1.2 | 0.6 - 0.8 | 0.4 - 0.6 | MOIST | WET | SG (Single grain) | |
| CV (Convex Slope) | | LS (Loamy sand) | | 0.5 - 0.7 | | Lo (Loose) | NS (Non-sticky) | M (Massive) | |
| D (Drainage way) | II | SL (Sandy loam) | 0.6 - 0.8 | 0.4 - 0.6 | 0.3 - 0.4 | VFR (Very friable) | SS (Slightly sticky) | GR (Granular) | |
| FP (Flood plain) | | L (Loam) | | 0.2 - 0.4 | | FR (Friable) | S (Sticky) | SBK (Subangular blocky) | |
| FS (Foot slope) | III | SiL (Silt loam) | 0.3 - 0.6 | 0.1 - 0.3 | 0.15 - 0.3 | FI (Firm) | VS (Very sticky) | ABK (Angular blocky) | |
| H (Head slope) | | SCL (Sandy clay loam) | | 0.05 - 0.15** | | VFI (Very firm) | NP (Non-plastic) | PR (Prismatic) | |
| L (Linear Slope) | | CL (Clay loam) | | None | | 0.05 - 0.2 | EFI (Extremely firm) | SP (Slightly plastic) | PL (Platy) |
| N (Nose slope) | | SiCL (Silty clay loam) | | | | | P (Plastic) | VP (Very plastic) | |
| R (Ridge/summit) | | Si (Silt) | | | | | | | |
| S (Shoulder slope) | IV | SC (Sandy clay) | 0.1 - 0.4 | 0.05 - 0.2 | SEXP (Slightly expansive) | | | | |
| T (Terrace) | | SiC (Silty clay) | | | EXP (Expansive) | | | | |
| TS (Toe Slope) | | C (Clay) | | | | | | | |
| | | O (Organic) | None | | | | | | |

* Adjust LTAR due to depth, consistence, structure, soil wetness, landscape, position, wastewater flow and quality.

**Sandy clay loam saprolite can only be used with advanced pretreatment in accordance with 15A NCAC 18E .1200.

HORIZON DEPTH

In inches below natural soil surface

DEPTH OF FILL

In inches from land surface

RESTRICTIVE HORIZON

Thickness and depth from land surface

SAPROLITE

S(suitable) or U(unsuitable); Evaluation of saprolite shall be by pits.

SOIL WETNESS

Inches from land surface to free water or inches from land surface to soil colors with chroma 2 or less - record Munsell color chip designation

CLASSIFICATION

S (Suitable) or U (Unsuitable)

Show profile locations and other site features (dimensions, reference or benchmark, and North).

