

Trenco

818 Soundside Rd
Edenton, NC 27932

Re: 4129350
4129350 Traverse Builders LLC Joiner

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Builders FirstSource (Apex,NC).

Pages or sheets covered by this seal: I68834106 thru I68834108

My license renewal date for the state of North Carolina is December 31, 2024.

North Carolina COA: C-0844



October 10,2024

Gilbert, Eric


IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job 4129350	Truss A05	Truss Type Piggyback Base	Qty 4	Ply 1	4129350 Traverse Builders LLC Joiner Job Reference (optional)	168834106
----------------	--------------	------------------------------	----------	----------	--	-----------

Builders FirstSource (Apex, NC), Apex, NC - 27523,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Thu Oct 10 13:42:58
ID:hxxclVmpC_201MLHwcaSy6yjp_-rFC?PsB70Hq3NSgPqnL8w3tUXbGKWrCDoi7J4zJC?F

Page: 1



Scale = 1:87.3

Plate Offsets (X, Y): [3:0-3-12,0-1-12], [5:0-3-12,0-1-12], [11:0-3-8,Edge], [13:0-3-0,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.54	Vert(LL)	-0.27	16-18	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.77	Vert(CT)	-0.37	16-18	>980	240		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.48	Horz(CT)	0.03	15	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS		Wind(LL)	0.03	16-18	>999	240	Weight: 338 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.1

BOT CHORD 2x4 SP No.1 *Except* 8-15:2x4 SP No.3

WEBS 2x4 SP No.3 *Except* 18-3,20-3,18-5,16-5:2x4 SP No.2

SLIDER Right 2x4 SP No.3 -- 1-4-12

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-10-7 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-5.

BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

WEBS 1 Row at midpt 4-18, 3-20, 2-22, 5-18, 7-15, 2-21

REACTIONS (size) 12=0-3-0, 15=0-3-8, 21=0-3-8, 22= Mechanical

Max Horiz 22=247 (LC 10)

Max Uplift 12=66 (LC 9), 15=131 (LC 13), 21=88 (LC 12), 22=-13 (LC 13)

Max Grav 12=221 (LC 24), 15=1834 (LC 1), 21=1420 (LC 19), 22=463 (LC 23)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-3=-617/185, 3-4=-810/193, 4-5=-810/193, 5-6=-1261/224, 6-7=-1264/104, 7-8=-96/503, 8-9=-36/394, 9-10=-39/48, 10-11=-3/69, 1-22=-321/143

BOT CHORD 21-22=-45/340, 20-21=-41/240, 18-20=-6/674, 16-18=-17/807, 15-16=-77/743, 13-15=-472/129, 12-13=-147/27, 11-12=-13/33, 8-15=-503/166

WEBS 4-18=-297/121, 3-18=-61/646, 3-20=-572/40, 2-20=0/784, 2-22=-246/118, 5-18=-112/186, 5-16=-135/435, 6-16=-375/230, 10-12=-107/107, 8-13=-54/271, 7-16=-20/366, 7-15=-1715/159, 9-13=-292/107, 9-12=0/169, 2-21=-1254/184

- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCCL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) 0-4-12 to 5-2-4, Interior (1) 5-2-4 to 14-10-13, Exterior (2) 14-10-13 to 19-7-0, Interior (1) 19-7-0 to 24-3-3, Exterior (2) 24-3-3 to 29-0-11, Interior (1) 29-0-11 to 48-2-0 zone; cantilever left and right exposed; end vertical left and right exposed; porch right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Bearings are assumed to be: Joint 12 SP No.1 crushing capacity of 565 psi, Joint 15 User Defined crushing capacity of 565 psi, Joint 21 User Defined crushing capacity of 565 psi, Joint 21 SP No.1 crushing capacity of 565 psi.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate at joint(s) 12.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 13 lb uplift at joint 22, 66 lb uplift at joint 12, 131 lb uplift at joint 15 and 88 lb uplift at joint 21.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- LOAD CASE(S)** Standard

NOTES



October 10, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
Edenton, NC 27932

Job 4129350	Truss A06	Truss Type Piggyback Base	Qty 1	Ply 1	4129350 Traverse Builders LLC Joiner Job Reference (optional)	168834107
----------------	--------------	------------------------------	----------	----------	--	-----------

Builders FirstSource (Apex, NC), Apex, NC - 27523,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Thu Oct 10 13:43:00
ID:gKkAtGShXhtH2maPTsqvdyvYw1-RfC?PsB70Hq3NSgPqnL8w3uITXbGkWrCDoi7J4zJC?F

Page: 1



Scale = 1:82.5

Plate Offsets (X, Y): [3:0-3-12,0-1-12], [5:0-3-12,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.54	Vert(LL)	-0.24	11-13	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.76	Vert(CT)	-0.37	11-13	>889	240	MT20HS	187/143
BCLL	0.0*	Rep Stress Incr	YES	WB	0.92	Horz(CT)	0.02	9	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS		Wind(LL)	0.02	11-13	>999	240	Weight: 294 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.1
BOT CHORD 2x4 SP No.1
WEBS 2x4 SP No.3 *Except*
15-3,13-5,11-5,13-3:2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-6-9 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 4-13, 3-15, 2-17, 5-11


REACTIONS (size) 9= Mechanical, 10=0-3-8, 16=0-3-8, 17= Mechanical
Max Horiz 17=281 (LC 10)
Max Uplift 9=-144 (LC 20), 10=-104 (LC 13), 16=-95 (LC 12)
Max Grav 9=35 (LC 13), 10=1520 (LC 2), 16=1271 (LC 19), 17=502 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-3=-633/222, 3-4=-723/204, 4-5=-723/204, 5-6=-928/226, 6-7=-933/118, 7-8=-56/221, 1-17=-322/143, 8-9=-25/171
BOT CHORD 16-17=-112/396, 15-16=-108/298, 13-15=-64/596, 11-13=-1/647, 10-11=-22/131, 9-10=-38/39
WEBS 4-13=-297/121, 3-15=-431/39, 2-15=0/650, 2-17=-301/127, 5-13=-89/295, 5-11=-107/160, 6-11=-367/229, 3-13=-66/514, 7-11=-44/815, 2-16=-1107/161, 8-10=-271/81, 7-10=-1296/146

NOTES
1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TC DL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) 0-4-12 to 4-3-2, Interior (1) 4-3-2 to 14-10-13, Exterior (2) 14-10-13 to 18-9-4, Interior (1) 18-9-4 to 24-3-3, Exterior (2) 24-3-3 to 28-1-9, Interior (1) 28-1-9 to 38-9-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) All plates are MT20 plates unless otherwise indicated.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 7) Bearings are assumed to be: Joint 10 User Defined crushing capacity of 565 psi, Joint 10 SP No.1 crushing capacity of 565 psi, Joint 16 User Defined crushing capacity of 565 psi, Joint 16 SP No.1 crushing capacity of 565 psi.
- 8) Refer to girder(s) for truss to truss connections.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 144 lb uplift at joint 9, 95 lb uplift at joint 16 and 104 lb uplift at joint 10.
- 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



October 10, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job 4129350	Truss A07	Truss Type Piggyback Base	Qty 3	Ply 1	4129350 Traverse Builders LLC Joiner Job Reference (optional)	168834108
----------------	--------------	------------------------------	----------	----------	--	-----------

Builders FirstSource (Apex, NC), Apex, NC - 27523,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Thu Oct 10 13:43:00
ID:T1Rc6WB0dx0sKva4v6QgSGyylTn-RFC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1




Plate Offsets (X, Y): [3:0-3-12,0-1-12], [5:0-3-12,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.54	Vert(LL)	-0.20	10-12	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.74	Vert(CT)	-0.33	12-14	>999	240	MT20HS	187/143
BCLL	0.0*	Rep Stress Incr	YES	WB	0.96	Horz(CT)	0.03	8	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS		Wind(LL)	0.02	10-12	>999	240	Weight: 295 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.1
BOT CHORD 2x4 SP No.1
WEBS 2x4 SP No.3 *Except*
14-3,12-5,10-5,12-3:2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-2-11 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 4-12, 3-14, 2-16, 6-8, 6-9


REACTIONS (size) 8= Mechanical, 9=0-3-8, 15=0-3-8, 16= Mechanical
Max Horiz 16=278 (LC 9)
Max Uplift 8=-87 (LC 13), 9=-4 (LC 13), 15=-127 (LC 12), 16=-19 (LC 13)
Max Grav 8=367 (LC 1), 9=1099 (LC 2), 15=1312 (LC 19), 16=524 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-3=-670/239, 3-4=-790/228, 4-5=-790/228, 5-7=-1168/294, 1-16=-323/143, 7-8=-280/162
BOT CHORD 15-16=-132/410, 14-15=-128/308, 12-14=-81/632, 10-12=-9/739, 9-10=-43/787, 8-9=-7/190
WEBS 4-12=-299/120, 3-14=-466/40, 2-14=0/686, 2-16=-326/133, 5-12=-102/238, 5-10=-160/355, 6-10=-135/266, 3-12=-70/578, 6-8=-190/14, 2-15=-1151/186, 6-9=-1140/75

NOTES
1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TC DL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) 0-4-12 to 4-3-2, Interior (1) 4-3-2 to 14-10-13, Exterior (2) 14-10-13 to 20-4-7, Interior (1) 20-4-7 to 24-3-3, Exterior (2) 24-3-3 to 29-8-13, Interior (1) 29-8-13 to 38-9-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) All plates are MT20 plates unless otherwise indicated.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 7) Bearings are assumed to be: Joint 9 User Defined crushing capacity of 565 psi, Joint 9 SP No.1 crushing capacity of 565 psi, Joint 15 User Defined crushing capacity of 565 psi, Joint 15 SP No.1 crushing capacity of 565 psi.
- 8) Refer to girder(s) for truss to truss connections.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 16, 87 lb uplift at joint 8, 127 lb uplift at joint 15 and 4 lb uplift at joint 9.
- 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANS/ITPI Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in MITek software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 section 6.3. These truss designs rely on lumber values established by others.

© 2023 MITek® All Rights Reserved

MITek

ENGINEERING BY
TRENCO
A MITek Affiliate

MITek Engineering Reference Sheet: MIL-7473 rev. 1/2/2023

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.