



LOT 10 WEST POINTE III
206 HILLWOOD DR.
SANFORD, NC 27332

NOTE:
MONO SLAB - STONE TO RUN TO THE BOTTOM OF WINDOW
STEM WALL - STONE TO FOUNDATION HEIGHT ONLY


NOTICE TO CONTRACTOR
All construction must comply with current NC Building Codes and is subject to field inspection and verification.

APPROVED
Limited liability only unless
Permit holder responsible for
full compliance with the code.


03/06/2024



FRONT ELEVATION
SCALE 1/4" = 1'-0"




REAR ELEVATION
SCALE 1/4" = 1'-0"



SQUARE FOOTAGE

| HEATED | |
|--------------|-------------|
| FIRST FLOOR | 776 SQ.FT. |
| SECOND FLOOR | 764 SQ.FT. |
| PLAYROOM | 280 SQ.FT. |
| TOTAL | 1820 SQ.FT. |
| UNHEATED | |
| FRONT PORCH | 101 SQ.FT. |
| GARAGE | 466 SQ.FT. |
| REAR PORCH | 152 SQ.FT. |
| TOTAL | 719 SQ.FT. |



**PLANS DESIGNED TO THE
2018 NORTH CAROLINA STATE
RESIDENTIAL BUILDING CODE**

| | MEAN ROOF HEIGHT 25'-8" | | HEIGHT TO RIDGE 30'-0" | |
|----------------------------|-------------------------|------------|------------------------|--|
| CLIMATE ZONE | ZONE 3A | ZONE 4A | ZONE 5A | |
| FENESTRATION U-FACTOR | 0.35 | 0.35 | 0.35 | |
| SKYLIGHT U-FACTOR | 0.55 | 0.55 | 0.55 | |
| GLAZED FENESTRATION SHGC | 0.30 | 0.30 | 0.30 | |
| CEILING R-VALUE | 38 or 30ci | 38 or 30ci | 38 or 30ci | |
| WALL R-VALUE | 15 | 15 | 19 | |
| FLOOR R-VALUE | 19 | 19 | 30 | |
| * BASEMENT WALL R-VALUE | 5/13 | 10/15 | 10/15 | |
| ** SLAB R-VALUE | 0 | 10 | 10 | |
| * CRAWL SPACE WALL R-VALUE | 5/13 | 10/15 | 10/19 | |

**10/13" MEANS R-10 SHEATHING INSULATION OR R-13 CAVITY INSULATION
** INSULATION DEPTH WITH MONOLITHIC SLAB 24" OR FROM INSPECTION GAP TO BOTTOM OF FOOTING; INSULATION DEPTH WITH STEM WALL SLAB 24" OR TO BOTTOM OF FOUNDATION WALL

DESIGNED FOR WIND SPEED OF 120 MPH, 3 SECOND GUST (93 FASTEST MILE) EXPOSURE 'B'

| COMPONENT & CLADDING DESIGNED FOR THE FOLLOWING LOADS | |
|---|---|
| MEAN ROOF | UP TO 30' 30'-1" TO 35' 35'-1" TO 40' 40'-1" TO 45' |
| ZONE 1 | 14.2 -15.0 14.9 -15.8 15.5 -16.4 15.9 -16.8 |
| ZONE 2 | 14.2 -18.0 14.9 -18.9 15.5 -19.6 15.9 -20.2 |
| ZONE 3 | 14.2 -18.0 14.9 -18.9 15.5 -19.6 15.9 -20.2 |
| ZONE 4 | 15.5 -16.0 16.3 -16.8 16.9 -17.4 17.4 -17.9 |
| ZONE 5 | 15.5 -20.0 16.3 -21.0 16.9 -21.8 17.4 -22.4 |

DESIGNED FOR WIND SPEED OF 130 MPH, 3 SECOND GUST (101 FASTEST MILE) EXPOSURE 'B'

| COMPONENT & CLADDING DESIGNED FOR THE FOLLOWING LOADS | |
|---|---|
| MEAN ROOF | UP TO 30' 30'-1" TO 35' 35'-1" TO 40' 40'-1" TO 45' |
| ZONE 1 | 16.7 -18.0 17.5 -18.9 18.2 -19.6 18.7 -20.2 |
| ZONE 2 | 16.7 -21.0 17.5 -22.1 18.2 -22.9 18.7 -23.5 |
| ZONE 3 | 16.7 -21.0 17.5 -22.1 18.2 -22.9 18.7 -23.5 |
| ZONE 4 | 18.2 -19.0 19.1 -20.0 19.8 -20.7 20.4 -21.3 |
| ZONE 5 | 18.2 -24.0 19.1 -25.2 19.8 -26.2 20.4 -26.9 |

ROOF VENTILATION

SECTION R806
R806.1 Ventilation required. Enclosed attics and enclosed rafter spaces formed where ceilings are applied directly to the underside of roof rafters shall have cross ventilation for each separate space by ventilating openings protected against the entrance of rain or snow. Ventilation openings shall have a least dimension of 1/16 inch (1.6 mm) minimum and 1/4 inch (6.4 mm) maximum. Ventilation openings having a least dimension larger than 1/4 inch (6.4 mm) shall be provided with corrosion-resistant wire cloth screening, hardware cloth, or similar material with openings having a least dimension of 1/16 inch (1.6 mm) minimum and 1/4 inch (6.4 mm) maximum. Openings in roof framing members shall conform to the requirements of Section R802.7.

R806.2 Minimum area. The total net free ventilating area shall not be less than 1/150 of the area of the space ventilated except that reduction of the total area to 1/300 is permitted provided that at least 50 percent and not more than 80 percent of the required ventilating area is provided by ventilators located in the upper portion of the space to be ventilated at least 3 feet (914 mm) above the eave or cornice vents with the balance of the required ventilation provided by eave or cornice vents. As an alternative, the net free cross-ventilation area may be reduced to 1/300 when a Class I or II vapor retarder is installed on the warm-in-winter side of the ceiling.

Exceptions:
1. Enclosed attic/rafter spaces requiring less than 1 square foot (0.0929 m²) of ventilation may be vented with continuous soffit ventilation only.
2. Enclosed attic/rafter spaces over unconditioned space may be vented with continuous soffit vent only.

SQUARE FOOTAGE OF ROOF TO BE VENTED = 1558 SQ.FT.
NET FREE CROSS VENTILATION NEEDED:
WITHOUT 50% TO 80% OF VENTING 3'-0" ABOVE EAVE = 10.39 SQ.FT.
WITH 50% TO 80% OF VENTING 3'-0" ABOVE EAVE; OR WITH CLASS I OR II VAPOR RETARDER ON WARM-IN-WINTER SIDE OF CEILING = 5.16 SQ.FT.

GUARD RAIL NOTES

SECTION R312
R312.1 Where required, Guards shall be located along open-sided walking surfaces, including stairs, ramps and landings, that are located more than 30 inches (762 mm) measured vertically to the floor or grade below at any point within 36 inches (914 mm) horizontally to the edge of the open side. Insect screening shall not be considered as a guard.

R312.2 Height. Required guards at open-sided walking surfaces, including stairs, porches, balconies or landings, shall be not less than 36 inches (914 mm) high measured vertically above the adjacent walking surface, adjacent fixed seating or the line connecting the leading edges of the treads.

Exceptions:
1. Guards on the open sides of stairs shall have a height not less than 34 inches (864 mm) measured vertically from a line connecting the leading edges of the treads.
2. Where the top of the guard also serves as a handrail on the open sides of stairs, the top of the guard shall not be not less than 34 inches (864 mm) and not more than 38 inches (965 mm) measured vertically from a line connecting the leading edges of the treads.

R312.3 Opening limitations. Required guards shall not have openings from the walking surface to the required guard height which allow passage of a sphere 4 inches (102 mm) in diameter.

Exceptions:
1. The triangular openings at the open side of a stair, formed by the riser, tread and bottom rail of a guard, shall not allow passage of a sphere 6 inches (153 mm) in diameter.
2. Guards on the open sides of stairs shall not have openings which allow passage of a sphere 4 3/8 inches (111 mm) in diameter.

AIR LEAKAGE

Section N1102.4
N1102.4.1 Building thermal envelope. The building thermal envelope shall be durably sealed with an air barrier system to limit infiltration. The sealing methods between dissimilar materials shall allow for differential expansion and contraction. For all homes, where present, the following shall be caulked, gasketed, weather stripped or otherwise sealed with an air barrier material or solid material consistent with Appendix E-2.4 of this code:
1. Blocking and sealing floor/ceiling systems and under knee walls open to unconditioned or exterior space.
2. Capping and sealing shafts or chases, including flue shafts.
3. Capping and sealing soffit or dropped ceiling areas.

PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTORS PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION, A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWINGS ARE INSTRUMENTS OF SERVICE AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.

FRONT & REAR ELEVATIONS
THE GASTON II

HAYNES WEAVER HOMES
910.630.2100 • 919.606.4696
350 Wagener Drive, Fayetteville, NC 28303

HAYNES HOME PLANS, INC.
P.O. Box 402, Wake Forest, NC 27386 919-435-6160 Fax 1-866-491-0336

SQUARE FOOTAGE

| HEATED | |
|--------------|-------------|
| FIRST FLOOR | 776 SQ.FT. |
| SECOND FLOOR | 764 SQ.FT. |
| PLAYROOM | 280 SQ.FT. |
| TOTAL | 1820 SQ.FT. |
| UNHEATED | |
| FRONT PORCH | 101 SQ.FT. |
| GARAGE | 466 SQ.FT. |
| REAR PORCH | 152 SQ.FT. |
| TOTAL | 719 SQ.FT. |

© Copyright 2016
Haynes Home Plans, Inc.
5/19/2020
181035B
PAGE 1 OF 8


PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS.
 HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTORS PRACTICES AND PROCEDURES.
 CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION.
 THESE DRAWING ARE INSTRUMENTS OF SERVICE AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.

LEFT & RIGHT ELEVATIONS
THE GASTON II

HAYNES WEAVER HOMES
 HOME PLANS, INC.
 910.630.2100 • 919.606.4696
350 Waggoner Drive, Fayetteville, NC 28303

| SQUARE FOOTAGE | |
|-----------------|--------------|
| HEATED | |
| FIRST FLOOR | 776 SQ. FT. |
| SECOND FLOOR | 764 SQ. FT. |
| PLAN ROOM | 280 SQ. FT. |
| TOTAL | 1820 SQ. FT. |
| UNHEATED | |
| FRONT PORCH | 101 SQ. FT. |
| GARAGE | 466 SQ. FT. |
| REAR PORCH | 132 SQ. FT. |
| TOTAL | 719 SQ. FT. |

COVERED PORCH




LEFT SIDE ELEVATION

SCALE 1/4" = 1'-0"

RAIL AS NEEDED PER CODE

PARGE



RIGHT SIDE ELEVATION

SCALE 1/4" = 1'-0"

PARGE

COVERED PORCH

Z:\Builder\Weaver Development Company, Inc\2001288 Gaston II\2001288 Gaston II.aec

ATTIC ACCESS

SECTION R807

R807.1 Attic access. An attic access opening shall be provided to attic areas that exceed 400 square feet (37.16 m²) and have a vertical height of 60 inches (1524 mm) or greater. The net clear opening shall not be less than 20 inches by 30 inches (508 mm by 762 mm) and shall be located in a hallway or other readily accessible location. A 30-inch (762 mm) minimum unobstructed headroom in the attic space shall be provided at some point above the access opening. See Section M1305.1.3 for access requirements where mechanical equipment is located in attics.

Exceptions:

1. Concealed areas not located over the main structure including porches, areas behind knee walls, dormers, bay windows, etc. are not required to have access.
2. Pull down stair treads, stringers, handrails, and hardware may protrude into the net clear opening.

WALL THICKNESSES

Exterior walls and walls adjacent to a garage area are drawn as 4" or as noted 2 X 6 are drawn as 6" to include 1/2" sheathing or gypsum. Subtract 1/2" for stud face.

Interior walls are drawn as 3 1/2" or as noted 2 X 6 are drawn as 5 1/2", and do not include gypsum.

DWELLING / GARAGE SEPARATION

REFER TO SECTIONS R302.5, R302.6, AND R302.7

WALLS. A minimum 1/2" gypsum board must be installed on all walls supporting floor/ceiling assemblies used for separation required by this section.

STAIRS. A minimum of 1/2" gypsum board must be installed on the underside and exposed sides of all stairways.

CEILINGS. A minimum of 1/2" gypsum must be installed on the garage ceiling if there are no habitable room above the garage. If there are habitable room above the garage a minimum of 5/8" type X gypsum board must be installed on the garage ceiling.

OPENING PENETRATIONS. Openings between the garage and residence shall be equipped with solid wood doors not less than 1 3/8 inches (35 mm) in thickness, solid or honeycomb core steel doors not less than 1 3/8 inches (35 mm) thick, or 20-minute fire-rated doors.

DUCT PENETRATIONS. Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel or other approved material and shall have no openings into the garage.

OTHER PENETRATIONS. Penetrations through the separation required in Section R302.6 shall be protected as required by Section R302.11, Item 4.

EXTERIOR WINDOWS AND DOORS

SECTION R612

R612.1 General. This section prescribes performance and construction requirements for exterior windows and doors installed in walls. Windows and doors shall be installed and flashed in accordance with the fenestration manufacturer's written installation instructions. Window and door openings shall be flashed in accordance with Section R703.8. Written installation instructions shall be provided by the fenestration manufacturer for each window or door.

R612.2 Window sills. In dwelling units, where the opening of an operable window is located more than 72 inches (1829 mm) above the finished grade or surface below, the lowest part of the clear opening of the window shall be a minimum of 24 inches (610 mm) above the finished floor of the room in which the window is located. Operable sections of windows shall not permit openings that allow passage of a 4 inch (102 mm) diameter sphere where such openings are located within 24 inches (610 mm) of the finished floor.

Exceptions:

1. Windows whose openings will not allow a 4-inch diameter (102 mm) sphere to pass through the opening when the opening is in its largest opened position.
2. Openings that are provided with window fall prevention devices that comply with Section R612.3.
3. Openings that are provided with fall prevention devices that comply with ASTM F 2090.
4. Windows that are provided with opening limiting devices that comply with Section R612.4.


R612.3 Window fall prevention devices. Window fall prevention devices and window guards, where provided, shall comply with the requirements of ASTM F 2090.

SQUARE FOOTAGE

| HEATED | |
|--------------|-------------|
| FIRST FLOOR | 776 SQ.FT. |
| SECOND FLOOR | 764 SQ.FT. |
| PLAYROOM | 280 SQ.FT. |
| TOTAL | 1820 SQ.FT. |
| UNHEATED | |
| FRONT PORCH | 101 SQ.FT. |
| GARAGE | 466 SQ.FT. |
| REAR PORCH | 152 SQ.FT. |
| TOTAL | 719 SQ.FT. |

FIRST FLOOR PLAN

SCALE 1/4" = 1'-0"




PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTORS PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWINGS ARE INSTRUMENTS OF SERVICE AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.

FIRST FLOOR PLAN
THE GASTON II


HAYNES WEAVER HOMES
HOME PLANS, INC.
P.O. Box 702, White Forest, NC 27388 919-485-8180 FAX 919-485-1496
910.630.2100 • 919.606.4696
309 Wiggins Drive, Fayetteville, NC 28403

| SQUARE FOOTAGE | |
|----------------|-------------|
| HEATED | |
| FIRST FLOOR | 776 SQ.FT. |
| SECOND FLOOR | 764 SQ.FT. |
| PLAYROOM | 280 SQ.FT. |
| TOTAL | 1820 SQ.FT. |
| UNHEATED | |
| FRONT PORCH | 101 SQ.FT. |
| GARAGE | 466 SQ.FT. |
| REAR PORCH | 152 SQ.FT. |
| TOTAL | 719 SQ.FT. |


© Copyright 2016
Haynes Home Plans, Inc.
5/19/2020
181035B
PAGE 4 OF 8




A MONOLITHIC SECTION
SCALE 1/2" = 1'-0"



B LUG FOOTING SECTION
SCALE 1/2" = 1'-0"



C MONOLITHIC AT STEP
SCALE 1/2" = 1'-0"




D MONOLITHIC AT GARAGE
SCALE 1/2" = 1'-0"

FOUNDATION STRUCTURAL

115 to 130 mph wind zone (1 1/2 to 2 1/2 story)
CONTINUOUS FOOTING: 16" wide and 8" thick minimum, 20" wide minimum at brick veneer. Must extend 2" to either side of supported wall.
GIRDERS: (3) 2 X 10 girder unless noted otherwise.
PIERS: 16" X 16" piers with 8" solid masonry cap on 30" X 30" X 10" concrete footing with maximum pier height of 64" with hollow masonry and 160" with solid masonry.
POINT LOADS: ■ designates significant point load and should have solid blocking to pier, girder or foundation wall.
115 and 120 MPH ANCHORS BOLTS: 1/2" diameter anchor bolts embedded minimum 7", maximum 6'-0" on center, within 12" of plate ends, and minimum two anchor bolts per plate.
130 MPH ANCHORS BOLTS: 1/2" diameter anchor bolts embedded minimum 15", maximum 4'-0" on center, within 12" of plate ends, and minimum two anchor bolts per plate.
CONCRETE: Concrete shall have a minimum 28 day strength of 3000 psi and a maximum 5" slump. Air entrained per table 402.2. All concrete shall be in accordance with ACI standards. All samples for pumping shall be taken from the exit end of the pump.
SOILS: Allowable soil bearing pressure assumed to be 2000 PSF. The contractor must contact a geotechnical engineer and a structural engineer if unsatisfactory subsurface conditions are encountered. The surface area adjacent to the foundation wall shall be provided with adequate drainage, and shall be graded so as to drain surface water away from foundation walls.

MONOLITHIC SLAB PLAN

SCALE 1/4" = 1'-0"



PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTORS PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWINGS ARE INSTRUMENTS OF SERVICE AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.

MONOLITHIC SLAB PLAN
THE GASTON II

HAYNES WEAVER HOMES
 HOME PLANS, INC.
 910.630.2100 • 919.606.4696
 350 Waggoner Drive, Fayetteville, NC 28303
 P.O. Box 702, Wake Forest, NC 27588 919-485-6180 FAX 919-866-4911-0396

| SQUARE FOOTAGE | |
|-----------------|--------------|
| HEATED | |
| FIRST FLOOR | 776 SQ. FT. |
| PLAYROOM | 764 SQ. FT. |
| TOTAL | 1540 SQ. FT. |
| UNHEATED | |
| FRONT PORCH | 101 SQ. FT. |
| GARAGE | 466 SQ. FT. |
| REAR PORCH | 132 SQ. FT. |
| TOTAL | 719 SQ. FT. |

STRUCTURAL NOTES

All construction shall conform to the latest requirements of the 2018 North Carolina Residential Building Code, plus all local codes and regulations. This document in no way shall be construed to supersede the code.
JOB SITE PRACTICES AND SAFETY: Haynes Home Plans, Inc. assumes no liability for contractor practices and procedures or safety program. Haynes Home Plans, Inc. takes no responsibility for the contractor's failure to carry out the construction work in accordance with the contract documents. All members shall be framed, anchored, and braced in accordance with good construction practice and the building code.

| DESIGN LOADS | LIVE LOAD (PSF) | DEAD LOAD (PSF) | DEFLECTION (LL) |
|------------------------------|-----------------|-----------------|-----------------|
| Attics without storage | 10 | | L/240 |
| Attics with limited storage | 20 | 10 | L/360 |
| Attics with fixed stairs | 40 | 10 | L/360 |
| Balconies and decks | 40 | 10 | L/360 |
| Fire escapes | 40 | 10 | L/360 |
| Guardrails and handrails | 200 | -- | -- |
| Guardrail in-fill components | 50 | -- | -- |
| Passenger vehicle garages | 50 | 10 | L/360 |
| Rooms other than sleeping | 40 | 10 | L/360 |
| Sleeping rooms | 30 | 10 | L/360 |
| Stairs | 40 | -- | L/360 |
| Snow | 20 | -- | -- |

FRAMING LUMBER: All non treated framing lumber shall be SPF #2 (Fb = 875 PSI) or SYP #2 (Fb = 750 PSI) and all treated lumber shall be SYP #2 (Fb = 750 PSI) unless noted otherwise.

ENGINEERED WOOD BEAMS:

Laminated veneer lumber (LVL) = Fb=2600 PSI, Fv=285 PSI, E=1.9x10⁶ PSI
 Parallel strand lumber (PSL) = Fb=2900 PSI, Fv=290 PSI, E=2.0x10⁶ PSI
 Laminated strand lumber (LSL) = Fb=2250 PSI, Fv=400 PSI, E=1.55x10⁶ PSI
 Install all connections per manufacturer's instructions.

TRUSS AND I-JOIST MEMBERS: All roof truss and I-joist layouts shall be prepared in accordance with this document. Trusses and I-joists shall be installed according to the manufacturer's specifications. Any change in truss or I-joist layout shall be coordinated with Haynes Home Plans, Inc.

LINTELS: Brick lintels shall be 3 1/2" x 3 1/2" x 1/4" steel angle for up to 6'-0" span, 6" x 4" x 5/16" steel angle with 6" leg vertical for spans up to 9'-0" unless noted otherwise, 3 1/2" x 3 1/2" x 1/4" steel angle with 1/2" bolts at 2'-0" on center for spans up to 18'-0" unless noted otherwise.

FLOOR SHEATHING: OSB or CDX floor sheathing minimum 1/2" thick for 16" on center joist spacing, minimum 5/8" thick for 19.2" on center joist spacing, and minimum 3/4" thick for 24" on center joist spacing.

ROOF SHEATHING: OSB or CDX roof sheathing minimum 3/8" thick.
CONCRETE AND SOILS: See foundation notes.

BRACE WALL PANEL NOTES

EXTERIOR WALLS: All exterior walls to be sheathed with CS-WSP or CS-SFB in accordance with section R602.10.3 unless noted otherwise.

GYPSPUM: All interior sides of exterior walls and both sides interior walls to have 1/2" gypsum installed. When not using method GB gypsum to be fastened per table R702.3.5. Method GB to be fastened per table R602.10.1.

REQUIRED LENGTH OF BRACING: Required brace wall length for each side of the circumscribed rectangle are interpolated per table R602.10.3. Methods CS-WSP and CS-SFB contribute their actual length. Method GB contributes 0.5 its actual length. Method PF contributes 1.5 times its actual length.

HD: 800 lbs hold down hold down device fastened to the edge of the brace wall panel closest to the corner.

Methods Per Table R602.10.1

CS-WSP: Shall be minimum 3/8" OSB or CDX nailed at 6" on center at edges and 12" on center at intermediate supports with 6d common nails or 8d(2 1/2" long x 0.113" diameter).

CS-SFB: Shall be minimum 1/2" structural fiber board nailed at 3" on center at edges and 3" on center at intermediate supports with 1 1/2" long x 0.12" diameter galvanized roofing nails.

GB: Interior walls show as GB are to have minimum 1/2" gypsum board on both sides of the wall fastened at 7" on center at edges and 7" on center at intermediate supports with minimum 5d cooler nails or #6 screws.

PF: Portal frame per figure R602.10.1

ROOF TRUSS REQUIREMENTS

TRUSS DESIGN. Trusses to be designed and engineered in accordance with these drawings. Any variation with these drawings must be brought to Haynes Home Plans, Inc. attention before construction begins.

KNEE WALL AND CEILING HEIGHTS. All finished knee wall heights and ceiling heights are shown furled down 10" from roof decking for insulation. If for any reason the truss manufacturer fails to meet or exceed designated rafter heights, finished knee wall heights, or finished ceiling heights shown on these drawings the finished square footage may vary. Any discrepancy must be brought to Haynes Home Plans, Inc. attention, so a suitable solution can be reached before construction begins. Any variation due to these conditions not being met is the responsibility of the truss manufacturer.

ANCHORAGE. All required anchors for trusses due to uplift or bearing shall meet the requirements as specified on the truss schematics.

BEARING. All trusses shall be designed for bearing on SPF #2 plates or ledgers unless noted otherwise.

Plate Heights & Floor Systems. See elevation page(s) for plate heights and floor system thicknesses.

EXTERIOR HEADERS

(2) 2 X 6 WITH 1 JACK STUD EACH END UNLESS NOTED OTHERWISE


- KING STUDS EACH END PER TABLE BELOW

| HEADER SPAN | < 3' | 3'-4' | 4'-8' | 8'-12' | 12'-16' |
|--------------|------|-------|-------|--------|---------|
| KING STUD(S) | 1 | 2 | 3 | 5 | 6 |

INTERIOR HEADERS


- LOAD BEARING HEADERS (2) 2 X 6 WITH 1 JACK STUD AND 1 KING STUD EACH END UNLESS NOTED OTHERWISE

- NON LOAD BEARING HEADERS TO BE LADDER FRAMED



PF PORTAL FRAME AT OPENING

(METHOD PF PER FIGURE AND SECTION R602.10.1)
 SCALE 1/4" = 1'-0"



FIRST FLOOR STRUCTURAL

SCALE 1/4" = 1'-0"

PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTOR PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWINGS ARE INSTRUMENTS OF SERVICE AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.

FIRST FLOOR STRUCTURAL
THE GASTON II

HAYNES WEAVER HOMES
 HOME PLANS, INC.
 P.O. BOX 702, WAIVE FOREST, NC 27688 919-485-8180 FAX 919-485-4396
 910.630.2100 • 919.606.4696
309 Wiggins Drive, Fayetteville, NC 28403

SQUARE FOOTAGE

| HEATED | 776 SQ. FT. |
|--------------|--------------|
| FIRST FLOOR | 764 SQ. FT. |
| SECOND FLOOR | 286 SQ. FT. |
| PLANETARIUM | 1800 SQ. FT. |
| TOTAL | 1800 SQ. FT. |
| UNHEATED | 101 SQ. FT. |
| FRONT PORCH | 466 SQ. FT. |
| GARAGE | 152 SQ. FT. |
| REAR PORCH | 719 SQ. FT. |
| TOTAL | 719 SQ. FT. |

© Copyright 2016 Haynes Home Plans, Inc.
 5/19/2020
 181035B
 PAGE 5 OF 8

STRUCTURAL NOTES

All construction shall conform to the latest requirements of the 2018 North Carolina Residential Building Code, plus all local codes and regulations. This document in no way shall be construed to supersede the code.

JOB SITE PRACTICES AND SAFETY: Haynes Home Plans, Inc. assumes no liability for contractor practices and procedures or safety program. Haynes Home Plans, Inc. takes no responsibility for the contractor's failure to carry out the construction work in accordance with the contract documents. All members shall be framed, anchored, and braced in accordance with good construction practices and the building code.

| DESIGN LOADS | LIVE LOAD (PSF) | DEAD LOAD (PSF) | DEFLECTION (LL) |
|------------------------------|-----------------|-----------------|-----------------|
| Attics without storage | 10 | 10 | L/240 |
| Attics with limited storage | 20 | 10 | L/360 |
| Attics with fixed stairs | 40 | 10 | L/360 |
| Balconies and decks | 40 | 10 | L/360 |
| Fire escapes | 40 | 10 | L/360 |
| Guardrails and handrails | 200 | - | - |
| Guardrail in-fill components | 50 | - | - |
| Passenger vehicle garages | 50 | 10 | L/360 |
| Rooms other than sleeping | 40 | 10 | L/360 |
| Sleeping rooms | 30 | 10 | L/360 |
| Stairs | 40 | - | - |
| Show | 20 | - | - |

FRAMING LUMBER: All non treated framing lumber shall be SPF #2 (Fb = 875 PSI) or SYP #2 (Fb = 750 PSI) and all treated lumber shall be SYP #2 (Fb = 750 PSI) unless noted otherwise.

ENGINEERED WOOD BEAMS:
Laminated veneer lumber (LVL) = Fb=2600 PSI, Fv=285 PSI, E=1.8x10⁶ PSI
Parallel strand lumber (PSL) = Fb=2900 PSI, Fv=290 PSI, E=2.0x10⁶ PSI
Laminated strand lumber (LSL) = Fb=2250 PSI, Fv=400 PSI, E=1.55x10⁶ PSI
Install all connections per manufacturer's instructions.

TRUSS AND I-JOIST MEMBERS: All roof truss and I-joist layouts shall be prepared in accordance with this document. Trusses and I-joists shall be installed according to the manufacturer's specifications. Any change in truss or I-joist layout shall be coordinated with Haynes Homes Plans, Inc.
LINTELS: Brick lintels shall be 3 1/2" x 3 1/2" x 1/4" steel angle for up to 6'-0" span, 6" x 4" x 5/16" steel angle with 6" leg vertical for spans up to 9'-0" unless noted otherwise. 3 1/2" x 3 1/2" x 1/4" steel angle with 1/2" bolts at 2'-0" on center for spans up to 18'-0" unless noted otherwise.

FLOOR SHEATHING: OSB or CDX floor sheathing minimum 1/2" thick for 16" on center joist spacing, minimum 5/8" thick for 19.2" on center joist spacing, and minimum 3/4" thick for 24" on center joist spacing.

ROOF SHEATHING: OSB or CDX roof sheathing minimum 3/8" thick.

CONCRETE AND SOILS: See foundation notes.

ATTIC ACCESS

SECTION R807

R807.1 Attic access. An attic access opening shall be provided to attic areas that exceed 400 square feet (37.16 m²) and have a vertical height of 60 inches (1524 mm) or greater. The net clear opening shall not be less than 20 inches by 30 inches (508 mm by 762 mm) and shall be located in a hallway or other readily accessible location. A 30-inch (762 mm) minimum unobstructed headroom in the attic space shall be provided at some point above the access opening. See Section M1305.1.3 for access requirements where mechanical equipment is located in attics.

Exceptions:

1. Concealed areas not located over the main structure including porches, areas behind knee walls, dormers, bay windows, etc. are not required to have access.
2. Pull down stair treads, stringers, handrails, and hardware may protrude into the net clear opening.

EXTERIOR WINDOWS AND DOORS

SECTION R612

R612.1 General. This section prescribes performance and construction requirements for exterior windows and doors installed in walls. Windows and doors shall be installed and flashed in accordance with the fenestration manufacturer's written installation instructions. Window and door openings shall be flashed in accordance with Section R703.8. Written installation instructions shall be provided by the fenestration manufacturer for each window or door.

R612.2 Window sills. In *dwelling* units, where the opening of an operable window is located more than 72 inches (1829 mm) above the finished grade or surface below, the lowest part of the clear opening of the window shall be a minimum of 24 inches (610 mm) above the finished floor of the room in which the window is located. Operable sections of windows shall not permit openings that allow passage of a 4 inch (102 mm) diameter sphere where such openings are located within 24 inches (610 mm) of the finished floor.

Exceptions:

1. Windows whose openings will not allow a 4-inch diameter (102 mm) sphere to pass through the opening when the opening is in its largest opened position.
 2. Openings that are provided with window fall prevention devices that comply with Section R612.3.
 3. Openings that are provided with fall prevention devices that comply with ASTM F 2090.
 4. Windows that are provided with opening limiting devices that comply with Section R612.4.
- R612.3 Window fall prevention devices.** Window fall prevention devices and window guards, where provided, shall comply with the requirements of ASTM F 2090.

EXTERIOR HEADERS

- (2) 2 X 6 WITH 1 JACK STUD EACH END UNLESS NOTED OTHERWISE

| HEADER SPAN | < 3' | 3'-4' | 4'-8' | 8'-12' | 12'-16' |
|--------------|------|-------|-------|--------|---------|
| KING STUD(S) | 1 | 2 | 3 | 5 | 6 |

INTERIOR HEADERS

- LOAD BEARING HEADERS (2) 2 X 6 WITH 1 JACK STUD AND 1 KING STUD EACH END UNLESS NOTED OTHERWISE

- NON LOAD BEARING HEADERS TO BE LADDER FRAMED

ROOF TRUSS REQUIREMENTS

TRUSS DESIGN. Trusses to be designed and engineered in accordance with these drawings. Any variation with these drawings must be brought to Haynes Home Plan, Inc. attention before construction begins.

KNEE WALL AND CEILING HEIGHTS. All finished knee wall heights and ceiling heights are shown furred down 10" from roof decking for insulation. If for any reason the truss manufacturer fails to meet or exceed designated heel heights, finished knee wall heights, or finished ceiling heights shown on these drawings the finished square footage may vary. Any discrepancy must be brought to Haynes Home Plans, Inc. attention, so a suitable solution can be reached before construction begins. Any variation due to these conditions not being met is the responsibility of the truss manufacturer.

ANCHORAGE. All required anchors for trusses due to uplift, or bearing shall meet the requirements as specified on the truss schematics.

BEARING. All trusses shall be designed for bearing on SPF #2 plates or ledgers unless noted otherwise.


Plate Heights & Floor Systems. See elevation page(s) for plate heights and floor system thicknesses.

WALL THICKNESSES

Exterior walls and walls adjacent to a garage area are drawn as 4" or as noted 2 X 6 are drawn as 6" to include 1/2" sheathing or gypsum. Subtract 1/2" for stud face.

Interior walls are drawn as 3 1/2" or as noted 2 X 6 are drawn as 5 1/2", and do not include gypsum.

BRACING NOT SHOWN ON UPPER STORY PER R602.10.3.2 (5) & (6)



SECOND FLOOR PLAN

SCALE 1/4" = 1'-0"

PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTOR'S PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWINGS ARE INSTRUMENTS OF SERVICE AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.

SECOND FLOOR PLAN
THE GASTON II

HAYNES WEAVER HOMES
HOME PLANS, INC.
P.O. Box 102, White Forest, NC 27688 919-485-8180 FAX 919-485-4189
910.630.2100 • 919.606.4696
309 Wagoner Drive, Fayetteville, NC 28403


| SQUARE FOOTAGE | |
|----------------|--------------|
| HEATED | |
| FIRST FLOOR | 276 SQ. FT. |
| SECOND FLOOR | 764 SQ. FT. |
| PLATFLOOR | 286 SQ. FT. |
| TOTAL | 1326 SQ. FT. |
| UNHEATED | |
| FRONT PORCH | 101 SQ. FT. |
| GARAGE | 466 SQ. FT. |
| REAR PORCH | 152 SQ. FT. |
| TOTAL | 719 SQ. FT. |

© Copyright 2016 Haynes Home Plans, Inc.

5/19/2020

181035B

PAGE 6 OF 8



ROOF TRUSS REQUIREMENTS

TRUSS DESIGN. Trusses to be designed and engineered in accordance with these drawings. Any variation with these drawings must be brought to Haynes Home Plan, Inc. attention before construction begins.

KNEE WALL AND CEILING HEIGHTS. All finished knee wall heights and ceiling heights are shown furred down 10" from roof decking for insulation. If for any reason the truss manufacturer fails to meet or exceed designated heel heights, finished knee wall heights, or finished ceiling heights shown on these drawings the finished square footage may vary. Any discrepancy must be brought to Haynes Home Plans, Inc. attention, so a suitable solution can be reached before construction begins. Any variation due to these conditions not being met is the responsibility of the truss manufacturer.

ANCHORAGE. All required anchors for trusses due to uplift or bearing shall meet the requirements as specified on the truss schematics.

BEARING. All trusses shall be designed for bearing on SPF #2 plates or ledgers unless noted otherwise.

Plate Heights & Floor Systems. See elevation page(s) for plate heights and floor system thicknesses.

● HEEL HEIGHT ABOVE FIRST FLOOR PLATE ● HEEL HEIGHT ABOVE SECOND FLOOR PLATE

ROOF PLAN
SCALE 1/4" = 1'-0"


PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTORS PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWINGS ARE INSTRUMENTS OF SERVICE AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.

ROOF PLAN
THE GASTON II


HAYNES HOME PLANS, INC.
P.O. Box 702, WAIVE FOREST, NC 27688 919-435-9180 FAX 919-435-1096

| SQUARE FOOTAGE | |
|-----------------|--------------|
| HEATED | |
| FIRST FLOOR | 776 SQ. FT. |
| SECOND FLOOR | 764 SQ. FT. |
| PLAYROOM | 286 SQ. FT. |
| TOTAL | 1826 SQ. FT. |
| UNHEATED | |
| FRONT PORCH | 101 SQ. FT. |
| CARAGE | 466 SQ. FT. |
| REAR PORCH | 152 SQ. FT. |
| TOTAL | 719 SQ. FT. |


© Copyright 2016
Haynes Home Plans, Inc.
5/19/2020
181035B
PAGE 7 OF 8




A CRAWL SPACE WALL
SCALE 3/4" = 1'-0"




B DROPPED/ FLUSH PIER
SCALE 3/4" = 1'-0"




D GARAGE STEM WALL
SCALE 3/4" = 1'-0"




E <48\"/>



C CRAWL SPACE AT GARAGE
SCALE 3/4" = 1'-0"



F FILLED PORCH SECTION WITH VENT
SCALE 1/2\"/>



G DECK ATTACHMENT
SCALE 1/2\"/>

DECK STAIR NOTES
SECTION AM110
AM110.1 Stairs shall be constructed per Figure AM110. Stringer spans shall be no greater than 7 foot span between supports. Spacing between stringers shall be based upon decking material used per AM107.1. Each Stringer shall have minimum 3 1/2 inches between step out and back of stringer. If used, suspended headers shall be attached with 3/8 inch galvanized bolts with nuts and washers to securely support stringers at the top.

DECK BRACING
SECTION AM109
AM109.1 Deck bracing. Decks shall be braced to provide lateral stability. The following are acceptable means to provide lateral stability.
AM109.1.1. When the deck floor height is less than 4'-0" above finished grade per Figure AM109 and the deck is attached to the structure in accordance with Section AM104, lateral bracing is not required.
AM109.1.2. 4 x 4 wood knee braces may be provided on each column in both directions. The knee braces shall attach to each post at a point not less than 1/3 of the post length from the top of the post, and the braces shall be angled between 45 degrees and 60 degrees from the horizontal. Knee braces shall be bolted to the post and the girder/double band with 5/8 inch hot dipped galvanized bolt with nut and washer at both ends of the brace per Figure AM109.1.
AM109.1.3. For freestanding decks without knee braces or diagonal bracing, lateral stability may be provided by embedding the post in accordance with Figure AM109.2 and the following:

| POST SIZE | MAX. TRIANGULAR AREA | MAX. POST HEIGHT | EMBEDMENT DEPTH | CONCRETE DIAMETER |
|-----------|----------------------|------------------|-----------------|-------------------|
| 4 X 4 | 48 SF | 4'-0" | 2'-6" | 1'-0" |
| 5 X 6 | 120 SF | 6'-0" | 3'-6" | 1'-8" |

AM109.1.4. 2 x 6 diagonal vertical cross bracing may be provided in two perpendicular directions for freestanding decks or parallel to the structure at the exterior column line for attached decks. The 2 x 6's shall be attached to the posts with one 5/8 inch hot dipped galvanized bolt with nut and washer at each end of each bracing member per Figure AM109.3.
AM109.1.5. For embedment of piles in Coastal Regions, see Chapter 45.






FIGURE AM110
TYPICAL DECK STAIR DETAIL
SCALE 3/4" = 1'-0"



WEEP SCREED
SCALE 3/4" = 1'-0"




SECTION R315
CARBON MONOXIDE ALARMS

R315.1 Carbon monoxide alarms. In new construction, dwelling units shall be provided with an approved carbon monoxide alarm installed outside of each separate sleeping area in the immediate vicinity of the bedroom(s) as directed by the alarm manufacturer.
R315.2 Where required in existing dwellings. In existing dwellings, where interior alterations, repairs, fuel-fired appliance replacements, or additions requiring a permit occurs, or where one or more sleeping rooms are added or created, carbon monoxide alarms shall be provided in accordance with Section 315.1.
R315.3 Alarm requirements. The required carbon monoxide alarms shall be audible in all bedrooms over background noise levels with all intervening doors closed. Single station carbon monoxide alarms shall be listed as complying with UL 2034 and shall be installed in accordance with this code and the manufacturer's installation instructions.


STAIRWAY NOTES
R311.7
R311.7.2 Headroom. The minimum headroom in all parts of the stairway shall not be less than 6 feet 8 inches (2032 mm) measured vertically from the sloped line adjoining the tread nosing or from the floor surface of the landing or platform on that portion of the stairway.
R311.7.4 Stair treads and risers. Stair treads and risers shall meet the requirements of this section. For the purposes of this section all dimensions and dimensional surfaces shall be exclusive of carpets, rugs or runners.
R311.7.4.1 Riser height. The maximum riser height shall be 8 1/4 inches (210 mm). The riser shall be measured vertically between leading edges of the adjacent treads.
R311.7.4.2 Tread depth. The minimum tread depth shall be 9 inches (229 mm). The tread depth shall be measured horizontally between the vertical planes of the foremost projection of adjacent treads and at a right angle to the tread's leading edge. Winder treads shall have a minimum tread depth of 9 inches (229 mm) measured as above at a point 12 inches (305 mm) from the side where the treads are narrower. Winder treads shall have a minimum tread depth of 4 inches (102 mm) at any point.
R311.7.4.3 Profile. The radius of curvature at the nosing shall be no greater than 9/16 inch (14 mm). A nosing not less than 3/4 inch (19 mm) but not more than 1 1/4 inches (32 mm) shall be provided on stairways with solid risers.
R311.7.7 Handrails. Handrails shall be provided on at least one side of each continuous run of treads or flight with four or more risers.
R311.7.7.1 Height. Handrail height, measured vertically from the sloped planes adjoining the tread nosing, or finish surface of ramp slope, shall be not less than 34 inches (864 mm) and not more than 38 inches (965 mm).
Exceptions:
1. The use of a volute, turnout or starting easing shall be allowed over the lowest tread.
2. When handrail fittings or bendings are used to provide continuous transition between flights, the transition from handrail to guardrail, or used at the start of a flight, the handrail height at the fittings or bendings shall be permitted to exceed the maximum height.
R311.7.7.2 Continuity. Handrails for stairways shall be continuous for the full length of the flight, from a point directly above the top riser of the flight to a point directly above the lowest riser of the flight. Handrail ends shall be returned or shall terminate in newel posts or safety terminals. Handrails adjacent to a wall shall have a space of not less than 1 1/2 inch (38 mm) between the wall and the handrails.
Exceptions:
1. Handrails shall be permitted to be interrupted by a newel post.
2. The use of a volute, turnout, starting easing or starting newel shall be allowed over the lowest tread.
3. Two or more separate rails shall be considered continuous if the termination of the rails occurs within 6 inches (152 mm) of each other. If transitioning between a wall-mounted handrail and a guardrail/handrail, the wall-mounted rail must return into the wall.

SMOKE ALARMS
SECTION R314
R314.1 Smoke detection and notification. All smoke alarms shall be listed in accordance with UL 217 and installed in accordance with the provisions of this code and the household fire warning equipment provisions of NFPA 72.
R314.2 Smoke detection systems. Household fire alarm systems installed in accordance with NFPA 72 that include smoke alarms, or a combination of smoke detector and audible notification device installed as required by this section for smoke alarms, shall be permitted. The household fire alarm system shall provide the same level of smoke detection and alarm as required by this section for smoke alarms. Where a household fire warning system is installed using a combination of smoke detector and audible notification device(s), it shall become a permanent fixture of the occupancy and owned by the homeowner. The system shall be monitored by an approved supervising station and be maintained in accordance with NFPA 72.
Exception: Where smoke alarms are provided meeting the requirements of Section R314.4.
R314.3 Location. Smoke alarms shall be installed in the following locations:
1. In each sleeping room.
2. Outside each separate sleeping area in the immediate vicinity of the bedrooms.
3. On each additional story of the dwelling, including basements and habitable attics (finished) but not including crawl spaces, uninhabitable (unfinished) attics and uninhabitable (unfinished) attic-stories. In dwellings or dwelling units with split levels and without an intervening door between the adjacent levels, a smoke alarm installed on the upper level shall suffice for the adjacent lower level provided that the lower level is less than one full story below the upper level.
When more than one smoke alarm is required to be installed within an individual dwelling unit the alarm devices shall be interconnected in such a manner that the actuation of one alarm will activate all of the alarms in the individual unit.
R314.4 Power source. Smoke alarms shall receive their primary power from the building wiring when such wiring is served from a commercial source, and when primary power is interrupted, shall receive power from a battery. Wiring shall be permanent and without a disconnecting switch other than those required for overcurrent protection. Smoke alarms shall be interconnected.


WEEP SCREEDS
All weep screeds and stone veneer to be installed per manufacturers instructions and per the 2012 North Carolina Residential Building code.
R703.6.2.1 - A minimum 0.019-inch (0.5 mm) (No. 26 galvanized sheet gage), corrosion-resistant weep screed or plastic weep screed, with a minimum vertical attachment flange of 31/2 inches (89 mm) shall be provided at or below the foundation plate line on exterior stud walls in accordance with ASTM C 926. The weep screed shall be placed a minimum of 4 inches (102 mm) above the earth or 2 inches (51 mm) above paved areas and shall be of a type that will allow trapped water to drain to the exterior of the building. The weather-resistant barrier shall lap the attachment flange. The exterior lath shall cover and terminate on the attachment flange of the weep screed.



PORCH HEADER WITH TAPERED COLUMN
SCALE 3/4" = 1'-0"



TYPICAL WALL DETAIL
SCALE 3/4" = 1'-0"



TYPICAL STAIR DETAIL
SCALE 1/4" = 1'-0"

PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES HOME PLANS, INC. ASSUMES LIABILITY FOR CONTRACTORS PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWINGS ARE INSTRUMENTS OF SERVICE AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.

TYPICAL DETAILS
THE GASTON II

HAYNES WEAVER HOMES
910.630.2100 • 919.606.4696
309 Wagoner Drive, Fayetteville, NC 28403


HAYNES HOME PLANS, INC.
P.O. Box 702, White Forest, NC 27388 919-455-1180 Fax: 986-91-0396

SQUARE FOOTAGE

| AREA | AREA |
|----------------------|--------------|
| HEATED FIRST FLOOR | 276 SQ. FT. |
| HEATED SECOND FLOOR | 764 SQ. FT. |
| REAR PORCH | 286 SQ. FT. |
| TOTAL | 1326 SQ. FT. |
| UNHEATED FRONT PORCH | 101 SQ. FT. |
| GARAGE | 466 SQ. FT. |
| REAR PORCH | 152 SQ. FT. |
| TOTAL | 719 SQ. FT. |

© Copyright 2016 Haynes Home Plans, Inc.
5/19/2020
181035B
PAGE 8 OF 8

Z:\Builder\Weaver Development Company, Inc\2001288 Gaston II\2001288 Gaston II.aec




SIDE ELEVATION

SCALE 1/8" = 1'-0"




FRONT ELEVATION

SCALE 1/8" = 1'-0"




REAR ELEVATION

SCALE 1/8" = 1'-0"




ROOF PLAN

SCALE 1/4" = 1'-0"




MONOLITHIC SLAB PLAN

SCALE 1/4" = 1'-0"



CRAWL SPACE / STEM WALL

SCALE 1/4" = 1'-0"



FIRST FLOOR PLAN

SCALE 1/4" = 1'-0"


PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTORS PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWING ARE INSTRUMENTS OF SERVICE AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.

FRONT LOAD THIRD CAR
THE GASTON II

HAYNES WEAVER HOMES
HOME PLANS, INC.
P.O. BOX 702, WAKE FOREST, NC 27588 919-485-6180 FAX 1-866-491-0396
350 Waggoner Drive, Fayetteville, NC 28303
910.630.2100 • 919.606.4696

| SQUARE FOOTAGE HEATED | |
|-----------------------|--------------|
| FIRST FLOOR | 776 SQ. FT. |
| SECOND FLOOR | 764 SQ. FT. |
| PLAN ROOM | 288 SQ. FT. |
| TOTAL | 1828 SQ. FT. |
| UNHEATED | |
| FRONT PORCH | 101 SQ. FT. |
| GARAGE | 466 SQ. FT. |
| REAR PORCH | 132 SQ. FT. |
| TOTAL | 719 SQ. FT. |

© Copyright 2016 Haynes Home Plans, Inc.
5/19/2020
181035B
ADDENDUM



| | | | | | | |
|---|--------|-----|----|--------|------------|------------|
| ● | HUS410 | USP | 10 | NA | 16d/3-1/2" | 16d/3-1/2" |
| ● | MSH422 | USP | 9 | Varies | 10d/3" | 10d/3" |

| Products | | | | | | |
|----------------------|----------|-----------------------------|-------|---------|----------|--|
| PlotID | Length | Product | Plies | Net Qty | Fab Type | |
| 6/0 Sliding Door HDR | 7-00-00 | 1-3/4"x 9-1/4" LVL Kerto-S | 2 | 2 | FF | |
| GDH | 23-00-00 | 1-3/4"x 14" LVL Kerto-S | 2 | 2 | FF | |
| GCO | 14-00-00 | 1-3/4"x 14" LVL Kerto-S | 2 | 2 | FF | |
| FB1 | 12-00-00 | 1-3/4"x 14" LVL Kerto-S | 2 | 2 | FF | |
| DB1 | 7-00-00 | 1-3/4"x 14" LVL Kerto-S | 2 | 2 | FF | |
| FB2 | 23-00-00 | 1-3/4"x 23-7/8" LVL Kerto-S | 3 | 3 | FF | |

All Truss Reactions are Less than 3,000 lbs. Unless Noted Otherwise.

○ -- Denotes Reaction Greater than 3,000 lbs. Reaction / # of Studs

Truss Placement Plan
SCALE: 1/4"=1'

△ = Indicates Left End of Truss
(Reference Engineered Truss Drawing)
Do NOT Erect Truss Backwards

| LOAD CHART FOR JACK STUDS (BASED ON TABLES B502.5(1) & (2)) NUMBER OF JACK STUDS REQUIRED @ EA END OF HEADERS | | | |
|---|------------------------------|------------------------------|-------------------------------|
| END REACTION (UP TO) 2550 #s | END REACTION (UP TO) 5100 #s | END REACTION (UP TO) 7650 #s | END REACTION (UP TO) 10200 #s |
| 1700 | 2550 | 3400 | 4250 |
| 3400 | 5100 | 6900 | 8700 |
| 5100 | 7650 | 10200 | 12750 |
| 6800 | 10200 | 13600 | 17000 |
| 8500 | 12750 | 17000 | |
| 10200 | 15300 | | |
| 11900 | | | |
| 13600 | | | |
| 15300 | | | |

| | | | |
|------------------|---------------------------|------------------|------------------|
| BUILDER | Weaver Homes, Inc. | COUNTY | Harnett |
| JOB NAME | Lot 10 West Pointe III | ADDRESS | 206 Hillwood Dr. |
| PLAN | Gaston II (181035B) 3 Car | MODEL | Floor |
| SEAL DATE | N/A | DATE REV. | 02/19/24 |
| QUOTE # | Quote # | DRAWN BY | Marshall Naylor |
| JOB # | J0124-0290 | SALESMAN | Lenny Norris |

THIS IS A TRUSS PLACEMENT DIAGRAM ONLY.
These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designer is responsible for temporary and permanent bracing of the roof and floor system and for the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer. For general guidance regarding bracing, consult BCSH-B1 and BCSH-B3 provided with the truss delivery package or online @ sbcindustry.com


Bearing reactions less than or equal to 3000# are deemed to comply with the prescriptive Code requirements. The contractor shall refer to the attached Tables (derived from the prescriptive Code requirements) to determine the minimum foundation size and number of wood studs required to support reactions greater than 3000# but not greater than 15000#. A registered design professional shall be retained to design the support system for any reaction that exceeds those specified in the attached Tables. A registered design professional shall be retained to design the support system for all reactions that exceed 15000#.

Signature: Marshall Naylor

comTECH

ROOF & FLOOR TRUSSES & BEAMS

Reilly Road Industrial Park
Fayetteville, N.C. 28309
Phone: (910) 864-8787
Fax: (910) 864-4444



| | | | | | | |
|---|--------|-----|----|--------|------------|------------|
| ● | HUS410 | USP | 10 | NA | 16d/3-1/2" | 16d/3-1/2" |
| ● | MSH422 | USP | 9 | Varies | 10d/3" | 10d/3" |

| Products | | | | | | |
|----------------------|--------|-----------------------------|-------|---------|----------|--|
| PlotID | Length | Product | Plies | Net Qty | Fab Type | |
| 6/0 Sliding Door HDR | 7-0-0 | 1-3/4"x 9-1/4" LVL Kerto-S | 2 | 2 | FF | |
| GDH | 23-0-0 | 1-3/4"x 14" LVL Kerto-S | 2 | 2 | FF | |
| GCO | 14-0-0 | 1-3/4"x 14" LVL Kerto-S | 2 | 2 | FF | |
| FB1 | 12-0-0 | 1-3/4"x 14" LVL Kerto-S | 2 | 2 | FF | |
| DB1 | 7-0-0 | 1-3/4"x 14" LVL Kerto-S | 2 | 2 | FF | |
| FB2 | 23-0-0 | 1-3/4"x 23-7/8" LVL Kerto-S | 3 | 3 | FF | |

All Truss Reactions are Less than 3,000 lbs. Unless Noted Otherwise.

○ -- Denotes Reaction Greater than 3,000 lbs. Reaction / # of Studs

Truss Placement Plan
SCALE: 1/4"=1'


△ = Indicates Left End of Truss
(Reference Engineered Truss Drawing)
Do NOT Erect Truss Backwards

| LOAD CHART FOR JACK STUDS (BASED ON TABLES R502.5(1) & (2)) NUMBER OF JACK STUDS REQUIRED @ EA END OF HEADERS | | | |
|---|---------------------------------------|---------------------------------------|---------------------------------------|
| END REACTION (UP TO) @ END OF HEADERS | END REACTION (UP TO) @ END OF HEADERS | END REACTION (UP TO) @ END OF HEADERS | END REACTION (UP TO) @ END OF HEADERS |
| 1700 | 2550 | 3400 | |
| 3400 | 5100 | 6800 | |
| 5100 | 7650 | 10200 | |
| 6800 | 10200 | 13600 | |
| 8500 | 12750 | 17000 | |
| 10200 | 15300 | | |
| 11900 | | | |
| 13600 | | | |
| 15300 | | | |

| | | | |
|------------------|---------------------------|------------------|------------------|
| BUILDER | Weaver Homes, Inc. | COUNTY | Harnett |
| JOB NAME | Lot 10 West Pointe III | ADDRESS | 206 Hillwood Dr. |
| PLAN | Gaston II (181035B) 3 Car | MODEL | Floor |
| SEAL DATE | N/A | DATE REV. | 02/19/24 |
| QUOTE # | Quote # | DRAWN BY | Marshall Naylor |
| JOB # | J0124-0290 | SALESMAN | Lenny Norris |

| | | | |
|--|--|--|--|
| THIS IS A TRUSS PLACEMENT DIAGRAM ONLY. These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designer is responsible for temporary and permanent bracing of the roof and floor system and for the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer. For general guidance regarding bracing, consult BCS-B1 and BCS-B3 provided with the truss delivery package or online @ sbcindustry.com | | | |
| Bearing reactions less than or equal to 3000# are deemed to comply with the prescriptive Code requirements. The contractor shall refer to the attached Tables (derived from the prescriptive Code requirements) to determine the minimum foundation size and number of wood studs required to support reactions greater than 3000# but not greater than 15000#. A registered design professional shall be retained to design the support system for any reaction that exceeds those specified in the attached Tables. A registered design professional shall be retained to design the support system for all reactions that exceed 15000#. | | | |
| Signature: <u>Marshall Naylor</u> | | | |

| | |
|---|---------|
| PRODUCT | comTECH |
| ROOF & FLOOR TRUSSES & BEAMS | |
| Reilly Road Industrial Park Fayetteville, N.C. 28309 Phone: (910) 864-8787 Fax: (910) 864-4444 | |



| | | | | | | |
|--|-------|-----|----|----|------------|------------|
| | HUS26 | USP | 18 | NA | 16d/3-1/2" | 16d/3-1/2" |
|--|-------|-----|----|----|------------|------------|

= 1st Level Wall

= 2nd Level Wall

| LVL | | | | | | |
|--------|----------|------------------------------|-------|---------|----------|--|
| PlotID | Length | Product | Plies | Net Qty | Fab Type | |
| GDH-3 | 13-00-00 | 1-3/4" x 11-7/8" LVL Kerto-S | 2 | 2 | FF | |

All Truss Reactions are Less than 3,000 lbs. Unless Noted Otherwise.

○ -- Denotes Reaction Greater than 3,000 lbs. Reaction / # of Studs

Truss Placement Plan
SCALE: 1/4"=1'

△ = Indicates Left End of Truss
(Reference Engineered Truss Drawing)
Do NOT Erect Truss Backwards

LOAD CHART FOR JACK STUDS

(BASED ON TABLES B502.5(1) & (2))

NUMBER OF JACK STUDS REQUIRED @ EA END OF HEADERS/BOARDS

| END REACTION (UP TO) (DOWN TO) | NUMBER OF JACK STUDS REQUIRED @ EA END OF HEADERS/BOARDS | END REACTION (UP TO) (DOWN TO) | NUMBER OF JACK STUDS REQUIRED @ EA END OF HEADERS/BOARDS | END REACTION (UP TO) (DOWN TO) | NUMBER OF JACK STUDS REQUIRED @ EA END OF HEADERS/BOARDS |
|--------------------------------|--|--------------------------------|--|--------------------------------|--|
| 1700 | 2 | 2550 | 2 | 3400 | 2 |
| 3400 | 2 | 5100 | 2 | 6800 | 2 |
| 5100 | 3 | 7650 | 3 | 10200 | 3 |
| 6800 | 4 | 10200 | 4 | 13600 | 4 |
| 8500 | 5 | 12750 | 5 | 17000 | 5 |
| 10200 | 6 | 15300 | 6 | | |
| 11900 | 7 | | | | |
| 13600 | 8 | | | | |
| 15300 | 9 | | | | |

| | | | |
|------------------|-------------------------------|------------------|------------------|
| BUILDER | Weaver Homes, Inc. | COUNTY | Harnett |
| JOB NAME | Lot 10 West Pointe III | ADDRESS | 206 Hillwood Dr. |
| PLAN | Gaston II (181035B) w/3rd Car | MODEL | Roof |
| SEAL DATE | N/A | DATE REV. | 02/19/24 |
| QUOTE # | | DRAWN BY | Marshall Naylor |
| JOB # | J0124-0289 | SALESMAN | Lenny Norris |

THIS IS A TRUSS PLACEMENT DIAGRAM ONLY.
These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designer is responsible for temporary and permanent bracing of the roof and floor system and for the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer. For general guidance regarding bracing, consult BCSI-B1 and BCSI-B3 provided with the truss delivery package or online @ sbcindustry.com


Bearing reactions less than or equal to 3000# are deemed to comply with the prescriptive Code requirements. The contractor shall refer to the attached Tables (derived from the prescriptive Code requirements) to determine the minimum foundation size and number of wood studs required to support reactions greater than 3000# but not greater than 15000#. A registered design professional shall be retained to design the support system for any reaction that exceeds those specified in the attached Tables. A registered design professional shall be retained to design the support system for all reactions that exceed 15000#.

Signature: Marshall Naylor

comtech

ROOF & FLOOR TRUSSES & BEAMS

Reilly Road Industrial Park
Fayetteville, N.C. 28309
Phone: (910) 864-8787
Fax: (910) 864-4444



| | | | | | | |
|---|-------|-----|----|----|------------|------------|
| ■ | HUS26 | USP | 18 | NA | 16d/3-1/2" | 16d/3-1/2" |
|---|-------|-----|----|----|------------|------------|

■ = 1st Level Wall

■ = 2nd Level Wall

| LVL | | | | | |
|--------|--------|-----------------------------|-------|---------|----------|
| PlotID | Length | Product | Plies | Net Qty | Fab Type |
| GDH-3 | 13-0-0 | 1-3/4"x 11-7/8" LVL Kerto-S | 2 | 2 | FF |

All Truss Reactions are Less than 3,000 lbs. Unless Noted Otherwise.

○ -- Denotes Reaction Greater than 3,000 lbs. Reaction / # of Studs

Truss Placement Plan
SCALE: 1/4"=1'

△ = Indicates Left End of Truss
(Reference Engineered Truss Drawing)
Do NOT Erect Truss Backwards

LOAD CHART FOR JACK STUDS

(BASED ON TABLES B502.5(1) & (2))
NUMBER OF JACK STUDS REQUIRED @ EA END OF HEADQUADRE

| END REACTION (UP TO) (DOWN TO) | END REACTION (UP TO) (DOWN TO) | END REACTION (UP TO) (DOWN TO) | END REACTION (UP TO) (DOWN TO) |
|--------------------------------|--------------------------------|--------------------------------|--------------------------------|
| NO. OF JACK STUDS | NO. OF JACK STUDS | NO. OF JACK STUDS | NO. OF JACK STUDS |
| 1700 | 2550 | 3400 | 4250 |
| 3400 | 5100 | 6800 | 8500 |
| 5100 | 7650 | 10200 | 11900 |
| 6800 | 10200 | 13600 | 15300 |
| 8500 | 12750 | 17000 | |
| 10200 | 15300 | | |
| 11900 | | | |
| 13600 | | | |
| 15300 | | | |

| | | | |
|------------------|-------------------------------|------------------|------------------|
| BUILDER | Weaver Homes, Inc. | COUNTY | Harnett |
| JOB NAME | Lot 10 West Pointe III | ADDRESS | 206 Hillwood Dr. |
| PLAN | Gaston II (181035B) w/3rd Car | MODEL | Roof |
| SEAL DATE | N/A | DATE REV. | 02/19/24 |
| QUOTE # | | DRAWN BY | Marshall Naylor |
| JOB # | J0124-0289 | SALESMAN | Lenny Norris |

THIS IS A TRUSS PLACEMENT DIAGRAM ONLY.
These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designer is responsible for temporary and permanent bracing of the roof and floor system and for the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer. For general guidance regarding bracing, consult BCSH-B1 and BCSH-B3 provided with the truss delivery package or online @ sbcindustry.com

Bearing reactions less than or equal to 3000# are deemed to comply with the prescriptive Code requirements. The contractor shall refer to the attached Tables (derived from the prescriptive Code requirements) to determine the minimum foundation size and number of wood studs required to support reactions greater than 3000# but not greater than 15000#. A registered design professional shall be retained to design the support system for any reaction that exceeds those specified in the attached Tables. A registered design professional shall be retained to design the support system for all reactions that exceed 15000#.

Signature: Marshall Naylor

ROOF & FLOOR TRUSSES & BEAMS

Reilly Road Industrial Park
Fayetteville, N.C. 28309
Phone: (910) 864-8787
Fax: (910) 864-4444




Client: Weaver Homes
 Project:
 Address: Gaston II (181035B)

Date: 9/18/2023
 Input by: Marshall Naylor
 Job Name: Gaston II (181035B) 3 Car
 Project #:

FB1 Kerto-S LVL 1.750" X 14.000" 2-Ply - PASSED

Level: Level



Member Information

| | | | |
|---------------------|---------------|----------------|-------------|
| Type: | Girder | Application: | Floor |
| Plies: | 2 | Design Method: | ASD |
| Moisture Condition: | Dry | Building Code: | IBC 2012 |
| Deflection LL: | 480 | Load Sharing: | No |
| Deflection TL: | 360 | Deck: | Not Checked |
| Importance: | Normal - II | | |
| Temperature: | Temp <= 100°F | | |

Reactions UNPATTERNED lb (Uplift)

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1 | Vertical | 2129 | 771 | 0 | 0 | 0 |
| 2 | Vertical | 2523 | 904 | 0 | 0 | 0 |

Bearings

| Bearing | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb. |
|---------|--------|------|------|--------------|-------|----------|-----------|
| 1 - SPF | 4.500" | Vert | 43% | 771 / 2129 | 2899 | L | D+L |
| 2 - SPF | 6.000" | Vert | 38% | 904 / 2523 | 3426 | L | D+L |

Analysis Results

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|----------------|-----------|---------------|-------------|-------|------|
| Moment | 8168 ft-lb | 5'9 3/16" | 26999 ft-lb | 0.303 (30%) | D+L | L |
| Unbraced | 8168 ft-lb | 5'9 3/16" | 10268 ft-lb | 0.795 (80%) | D+L | L |
| Shear | 2421 lb | 9'8 1/2" | 10453 lb | 0.232 (23%) | D+L | L |
| LL Defl inch | 0.090 (L/1419) | 5'8 3/16" | 0.266 (L/480) | 0.338 (34%) | L | L |
| TL Defl inch | 0.122 (L/1044) | 5'8 3/16" | 0.354 (L/360) | 0.345 (34%) | D+L | L |

Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Girders are designed to be supported on the bottom edge only.
- 3 Multiple plies must be fastened together as per manufacturer's details.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at end bearings.
- 6 Bottom must be laterally braced at end bearings.
- 7 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|---------------|-----------------|------------|------|----------|---------|-----------|----------|-------------|----------|
| 1 | Uniform | | | Top | 106 PLF | 318 PLF | 0 PLF | 0 PLF | 0 PLF | F5 |
| 2 | Part. Uniform | 3-6-8 to 11-4-8 | | Top | 44 PLF | 132 PLF | 0 PLF | 0 PLF | 0 PLF | F9 |
| | Self Weight | | | | 11 PLF | | | | | |

Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

chemicals

Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

Manufacturer Info

Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS







Client: Weaver Homes
 Project:
 Address: Gaston II (181035B)

Date: 9/18/2023
 Input by: Marshall Naylor
 Job Name: Gaston II (181035B) 3 Car
 Project #:

FB2 Kerto-S LVL 1.750" X 24.000" 3-Ply - PASSED

Level: Level



Member Information

| | | | |
|---------------------|---------------|----------------|-------------|
| Type: | Girder | Application: | Floor |
| Plies: | 3 | Design Method: | ASD |
| Moisture Condition: | Dry | Building Code: | IBC 2012 |
| Deflection LL: | 480 | Load Sharing: | Yes |
| Deflection TL: | 360 | Deck: | Not Checked |
| Importance: | Normal - II | | |
| Temperature: | Temp <= 100°F | | |

Reactions UNPATTERNED lb (Uplift)

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1 | Vertical | 225 | 6536 | 5095 | 0 | 0 |
| 2 | Vertical | 225 | 4429 | 3676 | 0 | 0 |

Bearings

| Bearing | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb. |
|-------------------|--------|------|------|--------------|-------|----------|-----------|
| 1 - SPF End Grain | 3.500" | Vert | 75% | 6536 / 5095 | 11631 | L | D+S |
| 2 - SPF End Grain | 3.500" | Vert | 53% | 4429 / 3676 | 8104 | L | D+S |

Analysis Results

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|----------------|-------------|---------------|--------------|-------|------|
| Moment | 65477 ft-lb | 11'5 3/4" | 131295 ft-lb | 0.499 (50%) | D+S | L |
| Unbraced | 65477 ft-lb | 11'5 3/4" | 65512 ft-lb | 0.999 (100%) | D+S | L |
| Shear | 10076 lb | 2'3 1/2" | 30912 lb | 0.326 (33%) | D+S | L |
| LL Defl inch | 0.226 (L/1171) | 11'1 11/16" | 0.552 (L/480) | 0.410 (41%) | S | L |
| TL Defl inch | 0.501 (L/528) | 11' 7/8" | 0.735 (L/360) | 0.682 (68%) | D+S | L |

Design Notes

- Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- Refer to last page of calculations for fasteners required for specified loads.
- Girders are designed to be supported on the bottom edge only.
- Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at a maximum of 4' 3/8" o.c.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|---------------|-----------------|------------|-----------|----------|--------|-----------|----------|-------------|----------|
| 1 | Tie-In | 0-0-0 to 22-6-0 | 0-6-0 | Far Face | 15 PSF | 40 PSF | 0 PSF | 0 PSF | 0 PSF | 1' Floor |
| 2 | Part. Uniform | 0-0-0 to 11-7-8 | | Top | 120 PLF | 0 PLF | 0 PLF | 0 PLF | 0 PLF | Wall |
| 3 | Part. Uniform | 0-0-0 to 11-4-0 | | Near Face | 79 PLF | 0 PLF | 79 PLF | 0 PLF | 0 PLF | M2 |
| 4 | Part. Uniform | 0-0-0 to 11-0-0 | | Top | 341 PLF | 0 PLF | 341 PLF | 0 PLF | 0 PLF | A2 |

Continued on page 2...

Notes

Calculated Structural Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

- Dry service conditions, unless noted otherwise
- LVL not to be treated with fire retardant or corrosive chemicals

Handling & Installation

- LVL beams must not be cut or drilled
- Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
- Damaged Beams must not be used
- Design assumes top edge is laterally restrained
- Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

Manufacturer Info

Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us


Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS



This design is valid until 11/3/2024

FB2 Kerto-S LVL 1.750" X 24.000" 3-Ply - PASSED

Level: Level



...Continued from page 1

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|----------------|------------------|------------|-----------|----------|--------|-----------|----------|-------------|----------|
| 5 | Part. Uniform | 11-4-0 to 22-6-0 | | Near Face | 164 PLF | 0 PLF | 164 PLF | 0 PLF | 0 PLF | M3 |
| 6 | Point | 11-5-12 | | Top | 2293 lb | 0 lb | 2293 lb | 0 lb | 0 lb | B2 |
| | Bearing Length | 0-3-8 | | | | | | | | |
| | Self Weight | | | | 28 PLF | | | | | |

Notes
 Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber
 1. Dry service conditions, unless noted otherwise
 2. LVL not to be treated with fire retardant or corrosive chemicals

Handling & Installation

- LVL beams must not be cut or drilled
- Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
- Damaged Beams must not be used
- Design assumes top edge is laterally restrained
- Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

Manufacturer Info


Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS



Front GDH Kerto-S LVL 1.750" X 14.000" 2-Ply - PASSED

Level: Level



Member Information

| | | | |
|---------------------|---------------|----------------|-------------|
| Type: | Girder | Application: | Floor |
| Plies: | 2 | Design Method: | ASD |
| Moisture Condition: | Dry | Building Code: | IBC 2012 |
| Deflection LL: | 480 | Load Sharing: | No |
| Deflection TL: | 360 | Deck: | Not Checked |
| Importance: | Normal - II | | |
| Temperature: | Temp <= 100°F | | |

Reactions UNPATTERNED lb (Uplift)

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1 | Vertical | 0 | 1619 | 952 | 0 | 0 |
| 2 | Vertical | 0 | 1720 | 1052 | 0 | 0 |

Bearings

| Bearing | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb. |
|-------------------|--------|------|------|--------------|-------|----------|-----------|
| 1 - SPF End Grain | 3.000" | Vert | 29% | 1619 / 952 | 2571 | L | D+S |
| 2 - SPF End Grain | 3.000" | Vert | 31% | 1720 / 1052 | 2772 | L | D+S |

Analysis Results

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|----------------|------------|---------------|--------------|-------|------|
| Moment | 12090 ft-lb | 9'8 7/8" | 31049 ft-lb | 0.389 (39%) | D+S | L |
| Unbraced | 12090 ft-lb | 9'8 7/8" | 12128 ft-lb | 0.997 (100%) | D+S | L |
| Shear | 2353 lb | 17'5" | 12021 lb | 0.196 (20%) | D+S | L |
| LL Defl inch | 0.184 (L/1202) | 9'6 3/16" | 0.461 (L/480) | 0.399 (40%) | S | L |
| TL Defl inch | 0.491 (L/451) | 9'5 13/16" | 0.615 (L/360) | 0.798 (80%) | D+S | L |

Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Girders are designed to be supported on the bottom edge only.
- 3 Multiple plies must be fastened together as per manufacturer's details.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at a maximum of 8'7 13/16" o.c.
- 6 Bottom must be laterally braced at end bearings.
- 7 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|---------------|------------------|------------|------|----------|--------|-----------|----------|-------------|----------|
| 1 | Uniform | | | Top | 60 PLF | 0 PLF | 0 PLF | 0 PLF | 0 PLF | wall |
| 2 | Part. Uniform | 0-0-0 to 9-6-0 | | Top | 96 PLF | 0 PLF | 96 PLF | 0 PLF | 0 PLF | M2 |
| 3 | Part. Uniform | 9-6-0 to 18-10-0 | | Top | 117 PLF | 0 PLF | 117 PLF | 0 PLF | 0 PLF | M3 |
| | Self Weight | | | | 11 PLF | | | | | |

Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

Manufacturer Info

Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS







Client: Weaver Homes
 Project:
 Address: Gaston II (181035B)

Date: 9/18/2023
 Input by: Marshall Naylor
 Job Name: Gaston II (181035B) 3 Car
 Project #:

GDH-2 Kerto-S LVL 1.750" X 11.875" 2-Ply - PASSED

Level: Level



Member Information

| | | | |
|---------------------|---------------|----------------|-------------|
| Type: | Girder | Application: | Floor |
| Plies: | 2 | Design Method: | ASD |
| Moisture Condition: | Dry | Building Code: | IBC 2012 |
| Deflection LL: | 480 | Load Sharing: | No |
| Deflection TL: | 360 | Deck: | Not Checked |
| Importance: | Normal - II | | |
| Temperature: | Temp <= 100°F | | |

Reactions UNPATTERNED lb (Uplift)

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1 | Vertical | 0 | 1145 | 1104 | 0 | 0 |
| 2 | Vertical | 0 | 1145 | 1104 | 0 | 0 |

Bearings

| Bearing | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb. |
|-------------------|--------|------|------|--------------|-------|----------|-----------|
| 1 - SPF End Grain | 3.000" | Vert | 26% | 1145 / 1104 | 2249 | L | D+S |
| 2 - SPF End Grain | 3.000" | Vert | 26% | 1145 / 1104 | 2249 | L | D+S |

Analysis Results

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|----------------|-----------|---------------|-------------|-------|------|
| Moment | 4554 ft-lb | 4'5" | 22897 ft-lb | 0.199 (20%) | D+S | L |
| Unbraced | 4554 ft-lb | 4'5" | 10675 ft-lb | 0.427 (43%) | D+S | L |
| Shear | 1627 lb | 1'2 7/8" | 10197 lb | 0.160 (16%) | D+S | L |
| LL Defl inch | 0.036 (L/2845) | 4'5 1/16" | 0.211 (L/480) | 0.169 (17%) | S | L |
| TL Defl inch | 0.073 (L/1397) | 4'5 1/16" | 0.282 (L/360) | 0.258 (26%) | D+S | L |

Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Girders are designed to be supported on the bottom edge only.
- 3 Multiple plies must be fastened together as per manufacturer's details.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at end bearings.
- 6 Bottom must be laterally braced at end bearings.
- 7 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|-------------|----------|------------|------|----------|--------|-----------|----------|-------------|----------|
| 1 | Uniform | | | Top | 250 PLF | 0 PLF | 250 PLF | 0 PLF | 0 PLF | G2 |
| | Self Weight | | | | 9 PLF | | | | | |

Notes

Calculated Structural Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

Manufacturer Info


Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS



GCO Kerto-S LVL 1.750" X 14.000" 2-Ply - PASSED

Level: Level



Member Information

| | | | |
|---------------------|---------------|----------------|-------------|
| Type: | Girder | Application: | Floor |
| Plies: | 2 | Design Method: | ASD |
| Moisture Condition: | Dry | Building Code: | IBC 2012 |
| Deflection LL: | 480 | Load Sharing: | No |
| Deflection TL: | 240 | Deck: | Not Checked |
| Importance: | Normal - II | | |
| Temperature: | Temp <= 100°F | | |

Reactions UNPATTERNED lb (Uplift)

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1 | Vertical | 2374 | 3468 | 0 | 0 | 0 |
| 2 | Vertical | 2374 | 3468 | 0 | 0 | 0 |

Bearings

| Bearing | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb. |
|---------|--------|------|------|--------------|-------|----------|-----------|
| 1 - SPF | 4.000" | Vert | 98% | 3468 / 2374 | 5842 | L | D+L |
| 2 - SPF | 4.000" | Vert | 98% | 3468 / 2374 | 5842 | L | D+L |

Analysis Results

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|----------------|----------|---------------|--------------|-------|------|
| Moment | 17498 ft-lb | 6'6 1/4" | 26999 ft-lb | 0.648 (65%) | D+L | L |
| Unbraced | 17498 ft-lb | 6'6 1/4" | 17512 ft-lb | 0.999 (100%) | D+L | L |
| Shear | 4511 lb | 1'6" | 10453 lb | 0.432 (43%) | D+L | L |
| LL Defl inch | 0.142 (L/1059) | 6'6 1/4" | 0.312 (L/480) | 0.453 (45%) | L | L |
| TL Defl inch | 0.349 (L/430) | 6'6 1/4" | 0.625 (L/240) | 0.558 (56%) | D+L | L |

Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Girders are designed to be supported on the bottom edge only.
- 3 Multiple plies must be fastened together as per manufacturer's details.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at a maximum of 5'7 3/8" o.c.
- 6 Bottom must be laterally braced at end bearings.
- 7 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|-------------|----------|------------|------|----------|---------|-----------|----------|-------------|----------|
| 1 | Uniform | | | Top | 122 PLF | 364 PLF | 0 PLF | 0 PLF | 0 PLF | F01 |
| 2 | Uniform | | | Top | 125 PLF | 0 PLF | 0 PLF | 0 PLF | 0 PLF | Wall |
| 3 | Uniform | | | Top | 274 PLF | 0 PLF | 0 PLF | 0 PLF | 0 PLF | A1 |
| | Self Weight | | | | 11 PLF | | | | | |

Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

Manufacturer Info


Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS



6/0 SLIDER Kerto-S LVL 1.750" X 9.250" 2-Ply - PASSED

Level: Level



Member Information

| | | | |
|---------------------|---------------|----------------|-------------|
| Type: | Girder | Application: | Floor |
| Plies: | 2 | Design Method: | ASD |
| Moisture Condition: | Dry | Building Code: | IBC 2012 |
| Deflection LL: | 480 | Load Sharing: | No |
| Deflection TL: | 360 | Deck: | Not Checked |
| Importance: | Normal - II | | |
| Temperature: | Temp <= 100°F | | |

Reactions UNPATTERNED lb (Uplift)

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1 | Vertical | 1060 | 1887 | 1113 | 0 | 0 |
| 2 | Vertical | 1060 | 1887 | 1113 | 0 | 0 |

Bearings

| Bearing | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb. |
|-------------------|--------|------|------|--------------|-------|----------|-------------|
| 1 - SPF End Grain | 3.500" | Vert | 34% | 1887 / 1629 | 3516 | L | D+0.75(L+S) |
| 2 - SPF End Grain | 3.500" | Vert | 34% | 1887 / 1629 | 3516 | L | D+0.75(L+S) |

Analysis Results

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|----------------|----------|---------------|-------------|-------------|------|
| Moment | 5009 ft-lb | 3'3 1/2" | 14423 ft-lb | 0.347 (35%) | D+0.75(L+S) | L |
| Unbraced | 5009 ft-lb | 3'3 1/2" | 10451 ft-lb | 0.479 (48%) | D+0.75(L+S) | L |
| Shear | 2387 lb | 1' 3/4" | 7943 lb | 0.300 (30%) | D+0.75(L+S) | L |
| LL Defl inch | 0.042 (L/1741) | 3'3 1/2" | 0.153 (L/480) | 0.276 (28%) | 0.75(L+S) | L |
| TL Defl inch | 0.091 (L/807) | 3'3 1/2" | 0.204 (L/360) | 0.446 (45%) | D+0.75(L+S) | L |

Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Girders are designed to be supported on the bottom edge only.
- 3 Multiple plies must be fastened together as per manufacturer's details.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at end bearings.
- 6 Bottom must be laterally braced at end bearings.
- 7 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|-------------|----------|------------|------|----------|---------|-----------|----------|-------------|----------|
| 1 | Uniform | | | Top | 108 PLF | 322 PLF | 0 PLF | 0 PLF | 0 PLF | F4 |
| 2 | Uniform | | | Top | 120 PLF | 0 PLF | 0 PLF | 0 PLF | 0 PLF | WALL |
| 3 | Uniform | | | Top | 338 PLF | 0 PLF | 338 PLF | 0 PLF | 0 PLF | A4 |
| | Self Weight | | | | 7 PLF | | | | | |

Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

Manufacturer Info



Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS



Window Hdr. Kerto-S LVL 1.750" X 14.000" 2-Ply - PASSED

Level: Level



Member Information

| | | | |
|---------------------|---------------|----------------|-------------|
| Type: | Girder | Application: | Floor |
| Plies: | 2 | Design Method: | ASD |
| Moisture Condition: | Dry | Building Code: | IBC 2012 |
| Deflection LL: | 480 | Load Sharing: | No |
| Deflection TL: | 360 | Deck: | Not Checked |
| Importance: | Normal - II | | |
| Temperature: | Temp <= 100°F | | |

Reactions UNPATTERNED lb (Uplift)

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1 | Vertical | 2861 | 3387 | 1990 | 0 | 0 |
| 2 | Vertical | 873 | 1906 | 1168 | 0 | 0 |

Bearings

| Bearing | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb. |
|-------------------|--------|------|------|--------------|-------|----------|-------------|
| 1 - SPF End Grain | 3.000" | Vert | 80% | 3387 / 3638 | 7025 | L | D+0.75(L+S) |
| 2 - SPF End Grain | 3.000" | Vert | 39% | 1906 / 1531 | 3437 | L | D+0.75(L+S) |

Analysis Results

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|----------------|----------|---------------|-------------|-------------|------|
| Moment | 11172 ft-lb | 2' | 31049 ft-lb | 0.360 (36%) | D+0.75(L+S) | L |
| Unbraced | 11172 ft-lb | 2' | 15767 ft-lb | 0.709 (71%) | D+0.75(L+S) | L |
| Shear | 6407 lb | 1'5" | 12021 lb | 0.533 (53%) | D+0.75(L+S) | L |
| LL Defl inch | 0.033 (L/2343) | 2'7 5/8" | 0.161 (L/480) | 0.205 (20%) | 0.75(L+S) | L |
| TL Defl inch | 0.067 (L/1165) | 2'8 7/8" | 0.215 (L/360) | 0.309 (31%) | D+0.75(L+S) | L |

Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Girders are designed to be supported on the bottom edge only.
- 3 Multiple plies must be fastened together as per manufacturer's details.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at end bearings.
- 6 Bottom must be laterally braced at end bearings.
- 7 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|----------------|----------------|------------|------|----------|---------|-----------|----------|-------------|----------|
| 1 | Uniform | | | Top | 120 PLF | 0 PLF | 0 PLF | 0 PLF | 0 PLF | WALL |
| 2 | Tie-In | 0-0-0 to 2-0-0 | 1-0-0 | Top | 20 PSF | 0 PSF | 20 PSF | 0 PSF | 0 PSF | 2' ROOF |
| 3 | Point | 1-9-8 | | Top | 1040 lb | 3115 lb | 0 lb | 0 lb | 0 lb | F08 |
| 4 | Bearing Length | 0-3-8 | | | | | | | | |
| 4 | Point | 2-0-0 | | Top | 2385 lb | 0 lb | 2385 lb | 0 lb | 0 lb | C3 |
| | Bearing Length | 0-3-8 | | | | | | | | |

Continued on page 2...

Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

Manufacturer Info



Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS



Window Hdr. Kerto-S LVL 1.750" X 14.000" 2-Ply - PASSED

Level: Level



...Continued from page 1

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|------------------------------|-----------------|------------|------|------------------|---------|-----------|----------|-------------|----------|
| 5 | Part. Uniform | 2-3-0 to 6-10-0 | | Top | 160 PLF | 0 PLF | 160 PLF | 0 PLF | 0 PLF | C2 |
| 6 | Part. Uniform Self Weight | 2-3-0 to 0-0-0 | | Top | 97 PLF 11 PLF | 300 PLF | 0 PLF | 0 PLF | 0 PLF | F07 |

Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

Manufacturer Info

Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS

