



- \*Keep tanks and drain lines 10' from property lines.
- \*Not a survey.
- \*Not a guarantee of a septic permit.
- \*Keep supply lines >5' from property lines.
- \*Some lines are flagged longer in the field than lengths indicate.
- \*No grading septic area.

System: Pump to D-Box Lines: 6-10, (375') Accepted Status System 0.35 Soil LTAR 22" Trench Bottom
Repair: Pressure Manifold Lines: 1-5, (310') T&J Panel 50% Reduction 0.35 Soil LTAR 22" Trench Bottom

GRAPHIC SCALE  
1" = 50'



Central Carolina Soil Consulting, PLLC  
 1900 South Main Street, Suite 110  
 Wake Forest, North Carolina 27587  
 Phone (919)569-6704 Fax (919)569-6703

4-Bedroom Septic Layout  
 Lot 161, Birchwood Subdivision  
 Harnette County, North Carolina

Job# : 3753
Drawn By : LW
Date : 04/12/2023
Revision: