North Carolina 2018 - R402.1.5 Total UA

Property 15 Red Bird Dr Cameron, NC 28326 Model: Hazel

Organization

Southern Energy Manageme Justin Smith

Inspection Status Results are projected



Builder

Template - Hunters Dream Homes - Hazel Hunters Dream Homes

Hazel plan slab

This report is based on a proposed design and does not confirm field enforcement of design elements.

Building UA

| Elements | NC Reference | As Designed |
|---|--------------|-------------|
| Ceilings | 28.9 | 25.2 |
| Above-Grade Walls | 143.2 | 141.3 |
| Windows, Doors and Skylights | 66.1 | 57.2 |
| Slab Floor: | 59.0 | 75.5 |
| Framed Floors | 14.7 | 8.8 |
| Foundation Walls | 0.0 | 0.0 |
| Rim Joists | 7.3 | 7.2 |
| Overall UA (Design must be equal or lower): | 319.2 | 315.2 |

Requirements

| R402.1.5 | Total UA alternative compliance passes by 1.3%. | The proposed home meets the UA requirement by 1.3% |
|---------------------|---|---|
| R402.3.2 | Average SHGC: 0.26 Max SHGC: 0.30 | Average SHGC of 0.26 is greater than the maximum of 0.30. |
| R402.4.2.2 | Air Leakage Testing | Air sealing is 0.26 CFM50 / ft^2 Shell Area. It must not exceed 0.30 CFM50 / ft^2 Shell Area. |
| R402.5 | Area-weighted average fenestration SHGC | Area-weighted average fenestration SHGC is 0.26. The maximum allowed value is [No Limit]. |
| R402.5 | Area-weighted average fenestration U-Factor | |
| R404.1 | Lighting Equipment | At least 75.0% of fixtures shall be high-efficacy lamps, currently 100.0% are high-efficacy. |
| Mandatory Checklist | Mandatory code requirements that are not checked by Ekotrope must be met. | 2015 IECC Mandatory Checklist must be checked as complete. |
| R403.3.1 | Duct Insulation | Duct insulation meets the requirements specified in North Carolina 2018 Code Section 403.3.1. |
| 403.3.3 | Duct Testing | |

Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 1.3%.

| Name: | Justin Smith | Signature: | Justin Smith |
|---------------|----------------------------|-------------------|---------------------|
| Organization: | Southern Energy Management | Digitally signed: | 4/16/24 at 10:49 AM |

Property 15 Red Bird Dr Cameron, NC 28326 Model: Hazel **Organization**Southern Energy Management
Justin Smith

Inspection Status Results are projected



Template - Hunters Dream Homes - Hazel plan slab - HERS Hazel plan slab

Builder Hunters Dream Homes

| General Building Informatio | n |
|------------------------------------|------------------------|
| Number Of Bedrooms | 3 |
| Number Of Floors | 2 |
| Conditioned Floor Area [sq. ft.] | 1,494 |
| Has Electric Vehicle Ready Space | No |
| Unconditioned, attached garage? | Yes |
| Conditioned Volume [cu. ft.] | 13,578 |
| Total Units in Building | 1 |
| Residence Type | Single family detached |
| Number of Floors in Building | - 1 |
| Floor Number | - |
| Model | Hazel |
| Community | |
| RESNET/IECC 2006-2018 Climate Zone | 4A |
| IECC 2021 Climate Zone | 3A |

Foundation Wall

None Present

Foundation Wall Library List

None Present

| Slab | | | | | | | | | |
|------|------|--------------|-----------|-------------|------------|---------------------------|-----------|------------------|-------------------|
| | Name | Library Type | Perimeter | Floor Grade | e Carpet F | R Exposed Masonry Area | | Location | Enclosing |
| | slab | Uninsulated | 130 | On Grade | 1 | 0 | 650.0 ft² | Exposed Exterior | Conditioned Space |

| Slab Library L | ist | | | | | | | |
|----------------|---------------------------|-------------------------------|---------------------------------------|---|---------------------------------|----|---------------|-------------------|
| Name | Wall Construction Type | Slab Completely Insulated? | Underslab Insulation Width [ft] | | Perimeter Insulation R Value | | Thermal Break | Effective R-value |
| Uninsulated | Wood Frame / Other | No | 0 | 0 | 0 | No | No | 0.00 |

Property 15 Red Bird Dr Cameron, NC 28326 Model: Hazel

Organization

Southern Energy Management Justin Smith **Inspection Status** Results are projected



Builder

Template - Hunters Dream Homes - Hazel plan slab - HERS

Hunters Dream Homes

| Framed Floor | | | | | |
|--------------|------------------------|----------|-------------|--------------|-------------------------|
| Name | Library Type | Carpet R | Floor Grade | Surface Area | Location |
| | | | | | |
| over garage | R 38, 16" OC G1 Carpet | 0 | Above Grade | 313.0 ft² | Unconditioned, attached |
| | | | | | garage |

| Framed Floor Librar | ry List |
|------------------------|---------------------|
| Name | e Effective R-value |
| R 38, 16" OC G1 Carpet | 35.384 |

| Rim Joist | | | |
|-------------------|----------------|--------------|--------------------------------|
| Name | Library Type | Surface Area | Location |
| 1st floor ambient | R 15 G1, 16"OC | 95.0 ft² | Exposed Exterior |
| 1st floor garage | R 15 G1, 16"OC | 36.0 ft² | Unconditioned, attached garage |

| Rim Joist Library Lis | t |
|-----------------------|------------------------------|
| Name | Effective Insulation R-value |
| R 15 G1, 16"OC | 13.30 |

| Wall | | | | |
|-------------------|--------------------|---------------|--------------|--------------------------------|
| Name | Library Type | Surface Color | Surface Area | Location |
| 1st floor ambient | R 15 FG G1 16" O.C | Medium | 756.0 ft² | Exposed Exterior |
| 1st floor garage | R 15 FG G1 16" O.C | Medium | 284.0 ft² | Unconditioned, attached garage |
| 2nd floor ambient | R 15 FG G1 16" O.C | Medium | 930.0 ft² | Exposed Exterior |
| 2nd floor attic | R 15 FG G1 16" O.C | Medium | 78.0 ft² | Attic |

Property 15 Red Bird Dr Cameron, NC 28326 Model: Hazel **Organization** Southern Energy Management Justin Smith **Inspection Status** Results are projected



Builder

Template - Hunters Dream Homes - Hazel plan slab - HERS

Hunters Dream Homes

| Wall Library List | | |
|-------------------|-----|-------------------|
| N: | me | Effective R-value |
| R 15 FG G1 16" | D.C | 13.156 |

| Glazing | | | | | | | | | |
|--------------------|--------------|----------------------|-------------------------------|-------------|-------------------|-----------------------|--------------------------|-------------|--------------|
| Name | Library Type | Wall Assignment | Foundation Wall Assignment | Is Operable | Overhang Depth | Overhang Ft To Top | Overhang Ft To Bottom | Orientation | Surface Area |
| front 2nd unshaded | 33/26 | 2nd floor ambient | | Yes | 0 | 0 | 0 | Southeast | 24.3 ft² |
| left 2nd unshaded | 33/26 | 2nd floor ambient | | Yes | 0 | 0 | 0 | Southwest | 10.4 ft² |
| rear 2nd unshaded | 33/26 | 2nd floor ambient | | Yes | 0 | 0 | 0 | Northwest | 24.3 ft² |
| rear unshaded | 33/26 | 1st floor ambient | | Yes | 0 | 0 | 0 | Northwest | 54.0 ft² |
| right 2nd unshaded | 33/26 | 2nd floor ambient | | Yes | 0 | 0 | 0 | Northeast | 22.2 ft² |
| right unshaded | 33/26 | 1st floor ambient | | Yes | 0 | 0 | 0 | Northeast | 14.6 ft² |

| Glazing Library List |
|----------------------|
| Name Shgc U-factor |
| 33/26 0.26 0.330 |

| Skylight | | |
|----------|--------------|--|
| | None Present | |

Skylight Library List

None Present

Property 15 Red Bird Dr Cameron, NC 28326 Model: Hazel

OrganizationSouthern Energy Management

Inspection Status Results are projected



Builder

Justin Smith

Template - Hunters Dream Homes - Hazel plan slab - HERS Hazel plan slab

Hunters Dream Homes

| Opaque Door | | | | | | | | |
|--------------|----------------|-------------------|-------------------------------|-----|-------------------|---------------|--------------|-----------------------------------|
| Name | Library Type | Wall Assignment | Foundation Wall Assignment | | Solar Absorptance | Surface Color | Surface Area | Location |
| front entry | Fiberglass R-5 | 1st floor ambient | | 0.9 | 0.75 | Medium | 21.0 ft² | Exposed Exterior |
| garage entry | Fiberglass R-5 | 1st floor garage | | 0.9 | 0.75 | Medium | 18.0 ft² | Unconditioned, attached garage |

| Opaque Door Library List | | |
|--------------------------|----------------------|--|
| Nam | ne Effective U-facto | |
| Fiberglass R- | 5 0.200 | |

| Roof Insulatio | n | | | | | |
|----------------|--|---------------------------|--------------------------------|------|----------------|----------|
| Name | Library Type | Attic Exterior Area [ft²] | Clay or Concrete Roof Tiles | | r Surface Area | Location |
| attic | R 38 Attic BLOWN FG G1 2x6 24"OC NO Radiant | 1,415.61 | No | Dark | 963.0 ft² | Attic |

| Roof Insulation | Roof Insulation Library List | | | | | |
|--|------------------------------|------------------------|--|--|--|--|
| Name | Has Radiant Bar | rier Effective R-value | | | | |
| R 38 Attic BLOWN FG G1 2x6 24"OC NO Radiant | | No 38.193 | | | | |

| Whole House | Infiltration | |
|-------------------|--------------------|---------------|
| Infiltration | Measurement Type | Shelter Class |
| 1086 CFM at 50 Pa | Blower-door tested | 4 |

| ı | Mechanical Ventilation |
|---|------------------------|
| ı | None Present |

Template - Hunters Dream Homes - Hazel plan slab - HERS

Property 15 Red Bird Dr Cameron, NC 28326 Model: Hazel

Organization

Southern Energy Management Justin Smith

Inspection Status Results are projected



Builder

Hunters Dream Homes

| Lighting | | | | | |
|------------------------------------|-----------------|------------------------------------|-----|----------------------------------|-----------------------|
| % Interior Fluorescent Lighting | or LED Lighting | % Exterior Fluorescent Lighting | | % Garage Fluorescent Lighting | % Garage LED Lighting |
| o | 100 | 0 | 100 | 0 | 100 |

| ı | Lighting | | Lighting | | Lighting | ļ |
|---|---------------|--------------------|--------------|-----|----------|-----|
| | o | 100 | 0 | 100 | 0 | 100 |
| | | | | | | |
| ı | Onsite Genera | ntion | | | | |
| | | | None Present | | | |
| ı | Onsite Genera | ntion Library List | | | | |
| | | | None Present | | | |
| | Solar Generat | ion | | | | |
| | | | None Present | | | |
| ı | Dehumidifier | | | | | |
| | | | None Present | | | |
| | Dehumidifier | Library List | | | | |
| | | | None Present | | | |

| Whole House Fan | |
|-----------------|--------------|
| | None Present |

Property 15 Red Bird Dr

Hazel plan slab

Cameron, NC 28326 Model: Hazel

Organization

Southern Energy Management Justin Smith

Builder

Hunters Dream Homes



Whole House Fan Library List

Template - Hunters Dream Homes - Hazel plan slab - HERS

None Present

| Conditioning | Equipment | | | | | |
|-----------------------|---------------------------|--------------|------------------------|----------------------|------------------------|-------------|
| Name | Library Type | Serial Numbe | r Heating Percent Load | Cooling Percent Load | Hot Water Percent Load | Location |
| | | | | | | |
| Water Heater | z 50 gal. 0.93 EF Elec | | 0% | 0% | 100% | Unspecified |
| whole house heat pump | z 30K 14.3 SEER2 7.5hspf2 | | 100% | 100% | 0% | Unspecified |
| | | | | | | |

Inspection Status

Results are projected

| Equipment Type: z 30K 14.3 SEER2 7.5hspf2 | | |
|---|----------------------|--|
| Equipment Type | Air Source Heat Pump | |
| Fuel Type | Electric | |
| Distribution Type | Forced Air | |
| Motor Type | PSC (Single Speed) | |
| Heat Pump System Type | Unspecified | |
| Heating Efficiency | 7.5 HSPF2 | |
| Heating Capacity [kBtu/h] | 30 | |
| Backup Fuel Type | Electric | |
| Switchover Temperature [°F] | 0 | |
| Backup Heating Efficiency | 1 COP | |
| Use default Supplemental Heat | Yes | |
| Cooling Efficiency | 14.3 SEER2 | |
| Cooling Capacity [kBtu/h] | 30 | |

| Equipment Type: z 50 gal. 0.93 EF Elec | | |
|--|-----------------------------|--|
| Equipment Type | Residential Water Heater | |
| Fuel Type | Electric | |
| Distribution Type | Hydronic Delivery (Radiant) | |
| Hot Water Efficiency | 0.93 Energy Factor | |
| Tank Capacity (gal.) | 50 | |
| Hot Water Capacity [kBtu/h] | 40 | |
| Recovery Efficiency | 0.98 | |

Property 15 Red Bird Dr Cameron, NC 28326 Model: Hazel

Template - Hunters Dream Homes - Hazel plan slab - HERS Hazel plan slab

Organization

Southern Energy Management Justin Smith

Builder

Hunters Dream Homes





| Distribution Type | Forced Air |
|--|---|
| Heating Equipment | whole house heat pump |
| Cooling Equipment | whole house heat pump |
| Sa. Feet Served | 1,494 |
| # Return Grilles | 2 |
| Supply Duct R Value | 8 |
| Return Duct R Value | 8 |
| Supply Duct Area [ft²] | 403.38 |
| Return Duct Area [ft²] | 149.4 |
| Leakage to Outdoors | 59 CFM @ 25Pa (3.95 / 100 ft ²) |
| Total Leakage | 59 CFM @ 25F8 (5.95 / 100 ft) |
| Total Leakage Duct Test Conditions | Post-Construction |
| Use Default Flow Rate | Yes |
| Duct 1 | ies |
| Duct Location | Attic (well vented) |
| Percent Supply Area | 60 |
| Percent Return Area | 60 |
| Duct 2 | 00 |
| Duct 2 Duct Location | Conditioned Space |
| Percent Supply Area | 40 |
| Percent Supply Area Percent Return Area | 40 |
| Duct 3 | 40 |
| Duct S Duct Location | Conditioned Space |
| Percent Supply Area | 0 |
| Percent Supply Area Percent Return Area | 0 |
| Duct 4 | 0 |
| Duct I ocation | Canditioned Cases |
| Percent Supply Area | Conditioned Space |
| Percent Supply Area Percent Return Area | 0 |
| Duct 5 | 0 |
| Duct 5 Duct Location | Conditioned Space |
| | Conditioned Space |
| Percent Supply Area | 0 |
| Percent Return Area | 0 |
| Duct 6 | Can disian ad Susas |
| Duct Location | Conditioned Space |
| Percent Supply Area | 0 |

| $HV\Delta C$ | Grading |
|--------------|---------|
| HVAC | Grading |

HVAC Grading Not Conducted

| Ceiling Fan | |
|-----------------|----|
| Has Ceiling Fan | No |

Property 15 Red Bird Dr Cameron, NC 28326 Model: Hazel

Organization

Southern Energy Management Justin Smith **Inspection Status** Results are projected





Template - Hunters Dream Homes - Hazel plan slab - HERS

Builder Hunters Dream Homes

| Water Distribution | |
|-----------------------------------|----------|
| Water Fixture Type | Standard |
| Use Default Hot Water Pipe Length | No |
| Hot Water Pipe Length [ft] | 75 |
| At Least R3 Pipe Insulation? | No |
| Hot Water Recirculation System? | No |
| Drain Water Heat Recovery? | No |

| Clothes Dryer | |
|------------------------------|----------------|
| Cef | 3.01 |
| Fuel Type | Electric |
| Field Utilization | Timer Controls |
| Is Outside Conditioned Space | No |
| Clothes Dryer Available | Yes |
| Defaults Type | HERS Reference |

| Clothes Washer | |
|------------------------------|-----------------|
| Label Energy Rating | 151 kWh/Year |
| Annual Gas Cost | \$12.00 |
| Electric Rate | \$0.11/kWh |
| Gas Rate | \$1.22/Therm |
| Capacity | 3.31 |
| Imef | 2.15473684 |
| Defaults Type | High Efficiency |
| Load Type | Front-load |
| Loads Per Week | 6 |
| Is Outside Conditioned Space | No |
| Clothes Washer Available | Yes |

| Dishwasher | |
|------------------------------|--------------|
| Dishwasher Defaults Type | Custom |
| Dishwasher Size | Standard |
| Dishwasher Efficiency | 270 kWh |
| Annual Gas Cost | \$33.12 |
| Electric Rate | \$0.12/kWh |
| Gas Rate | \$1.09/Therm |
| Is Outside Conditioned Space | No |
| Dishwasher Available | Yes |

Template - Hunters Dream Homes - Hazel plan slab - HERS

Property 15 Red Bird Dr Cameron, NC 28326 Model: Hazel

Organization Southern Energy Management Justin Smith

Inspection Status Results are projected



Hunters Dream Homes

| Appliances and Controls | |
|---|--------------|
| Programmable thermostat? | Yes |
| Range/Oven Fuel | Electric |
| Convection Oven? | No |
| Induction Range? | No |
| Range/Oven Outside Conditioned Space? | No |
| Refrigerator Consumption | 538 kWh/Year |
| Refrigerator Outside Conditioned Space? | No |
| | |

Notes

Initial inputs by __JS 04/16/2024__

- -confirm HVAC specs
- -confirm cfl lighting
- -modeled to worse case orientation