



HARNETT COUNTY ENVIROMENTAL HEALTH

File/Permit #: SFD2403-0007

CDP #:

IMPROVEMENT PERMIT (IP)

☒ New ☐ Expansion ☐ Repair ☐ System Relocation ☐ Change of Use

Owner: GARCIA SAMUEL VELAZQUEZ Applicant: GARCIA SAMUEL VELAZQUEZ

Property Location: 3866 BENSON RD ANGIER, NC 27501 PIN/Lot Identifier: 0693-62-4219.000

Subdivision: _____ Lot #: 2 Block: _____ Section: _____

Facility Type: SFD 70' x 41' Number of bedrooms: 3 Number of Occupants: 6 Other: _____

Design Daily Flow: 360 GPD LTAR (Initial): .3 gpd/ft² LTAR (Repair): .3 gpd/ft²

Wastewater System Type: 25% Reduction System (Initial)

Pump Required: ☒ Yes ☐ No ☐ May be required Usable Depth to Limiting Condition (Initial): 27"

Wastewater System Type: 50% Reduction System (Repair)

Pump Required: ☒ Yes ☐ No ☐ May be required Usable Depth to Limiting Condition (Repair): 27"

Effluent Standard: ☒ DSE ☐ HSE ☐ Other: _____ Type of Water Supply: ☐ Private well ☒ Municipal Supply ☐ Other: _____

Permit conditions:

No Foundation or Gutter Drains to be Directed Towards Septic System.
No Cutting or Grading of Soil in Septic or Septic Repair Area.
Route Water Line as Shown on Site Plan.

The issuance of this permit in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This permit is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of 15A NCAC 18E and to the conditions of this permit.

Authorized Agent's Printed Name: Ren LevoczDate: 10/01/2025Authorized Agent's Signature: [Signature]Expiration Date: 10/01/2030

CONSTRUCTION AUTHORIZATION (CA)

☒ New ☐ Expansion ☐ Repair ☐ System Relocation ☐ Change of Use

Owner: GARCIA SAMUEL VELAZQUEZ Applicant: GARCIA SAMUEL VELAZQUEZ

Property Location: 3866 BENSON RD ANGIER, NC 27501 PIN/Lot Identifier: 0693-62-4219.000

Subdivision: _____ Lot #: 2 Block: _____ Section: _____

Facility Type: SFD 70' x 41' Number of bedrooms: 3 Number of Occupants: 6 Other: _____

Design Daily Flow: 360 GPD LTAR: .3 gpd/ft²

Effluent Standard: ☒ DSE ☐ HSE ☐ Other: _____ Type of Water Supply: ☐ Private well ☒ Municipal Supply ☐ Other: _____

Installation Requirements/Conditions

Wastewater System Type: 25% Reduction System Pump Required: ☐ Yes ☒ No ☐ May be required

Septic Tank Size: 1,000 gallons Total Trench Length: 300' feet Trench Spacing: 9' feet on center

Pump Tank Size: 1,000 gallons Maximum Trench Depth: See Site plan inches Soil Cover: 6" inches

Trench Width: 36" inches Distribution Method: ☒ Serial ☐ D-Box or Parallel ☐ Pressure Manifold ☐ Other: _____

Artificial Drainage Required: Yes ☐ No ☒ If yes, please specify details: _____

Management Entity Required: ☐ Yes ☒ No Minimum O&M Requirements: _____

Permit conditions:

No Foundation or Gutter Drains to be Directed Towards Septic System.
No Cutting or Grading of Soil in Septic or Septic Repair Area.
No Driving on on Septic Area. Recommended to put up a fence along drive way.

The requirements of 15A NCAC 18E are incorporated by reference into this permit and shall be met. Systems shall be installed in accordance with the attached site sketch. This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of 15A NCAC 18E, or 15A NCAC 18A .1900, as applicable, and to the conditions of this permit.

Authorized Agent's Printed Name: Ren LevoczDate: 10/01/25Authorized Agent's Signature: [Signature]Expiration Date: 10/01/2030

Owner/Legal Representative Signature: _____

Date: _____

***See attached site sketch**

Harnett County Environmental Health

SITE SKETCH

PIN 0693-62-4219.000

Permit Number SFD2403-0007

GARCIA SAMUEL VELAZQUEZ

Lot 2

Applicant's Name

Subdivision/Section/Lot Number

Ren Levocz

10/01/2025

Authorized State Agent

Date

System components represent approximate contours only. The contractor must flag the system prior to beginning the installation to ensure that the proper grade is maintained.

Scale = NTS

*** More Line is Flagged Than Needed, Only Need a Total of 300'**

