EACH EGRESS WINDOW FROM SLEEPING ROOMS MUST HAVE A SILL HIGHT OF NO MORE THAN 44" FROM THE FLOOR, ALL WINDOW SIZES ARE NOMINAL AND ARE TO BE VERIFIED WITH MANUFACTURER FOR AVAILABILITY AND CONFORMITY TO STATE AND LOCAL CODE REQUIREMENTS.

PORCHES, BALCONIES, OR RAISED FLOOR SURFACES LOCATED MORE THAN 30" ABOYE THE FLOOR OR GRADE BELOW SHALL HAVE GUARDRAILS NOT LESS THAN 32" IN HEIGHT.

I ASSUME NO RESPONSIBILITY FOR ANY DISTANCES AFTER START OF CONSTRUCTION. CONTRACTOR/BUILDER SHALL CONSULT WITH HOME OWNER ON ALL INTERIOR AND EXTERIOR MOLDINGS, TRIMS, COLORS, FINISHES, CABINET LAYOUTS, AND MANUFACTORS BEFORE CONSTRUCTION BEGINS.
ALL BEAMS AND FRAMING MEMBERS ARE SIZED BY OTHERS.

1.1 This plan has been drawn to comply with the 2018 NC Building Code

1.2 Minimum Design Loads for Building and Other Structures ASCE 7-9B

2 Roof Dead Load 115 PSF

3 Roof Live Load 20 PSF

4 Typical Floor Dead Load 10 PSF

5 Floor Live Loads 5.1 Rooms other than sleeping rooms 40 PSF

5.2 Sleeping Rooms 30 PSF

5.3 Stairs 40 PSF

5.4 Decks 40 PSF

5.5 Exterior Balconies 60 PSF Wind Loads


6.1 Ultimate Design Wind Speeds 15 MPH

6.2 Wind Importance Factor, IW 1.00


6.3 Exposure B

6.4 Walls (Component and Cladding) 25 PSF 6.5 Roofs (Component and Cladding) 6.5.1 Roof Slopes 2.25/12 to 7/12 34.8 PSF 6.5.2 Roof Slopes 7/12 to 12/12 21 PSF

It is the sole responsibility of the Contractor and/or Builder to conform to all standards, provisions, requirements, methods of construction and uses of materials provided in buildings and/or structures as required by NC Uniform Building Code, Local Agencies and in accordance with good engineering practices. Verify all dimensions prior to construction.




LEFT ELEVATION SCALE: 1'= 1/4"










REAR ELEVATION SCALE: 1'= 1/4"


SHINGLE ROOF

1 × 5 FASICA

EVATIONS.





Termite Soil Treatment: Treat entire slab area soil or crawl space surface before vapor barrier is installed and slab is poured with a state approved termiticide. Termiticide should be applied by a licensed and certified pest control professional by the state of North Carolina.




STEM WALL FOUNDATION Detail


not to scale





TYPICAL THICKENED SLAB





FOUNDATION PLAN

SCALE: 1'= 1/4"

GENERAL FRAMING NOTES:

ALL LUMBER IN CONTACT WITH CONCRETE OR MASONRY SHALL BE PRESSURE TREATED

FRAMING LUMBER SHALL BE SYP *2 GRADE AND/OR

SPRUCE PINE FIR #1 AND/OR #2, KILN DRIED.

WHERE PRE-ENGINEERED JOISTS ARE USED, JOIST MANUFACTURER SHALL PROVIDE SHOP DRAWINGS, WHICH BEAR SEAL OF A N.C. ENGINEER.

STUDS AND JOISTS SHALL NOT BE CUT TO INSTALL PLUMBING OR WIRING WITHOUT ADDING METAL OR WOOD SIDE PANELS TO STRENGTHEN THE MEMBER TO ITS ORIGINAL CAPACITY.

NAIL MULTIPLE MEMBERS WITH 2 ROWS OF 16d NAILS STAGGERED 32" OC AN USE 3-16d NAILS 2" IN AT EACH END. DOUBLE ALL STUDS UNDER ROOF POST DOWNS UNO.

NAIL FLOOR JOISTS TO SILL PLATE WITH 8d TOE NAILS.

ALL EXPOSED FRAMING ON PORCHES AND DECKS SHALL BE PRESSURE TREATED.


PROVIDE WATERPROOFING AND DRAINS AS REQUIRED.

ALL FRAMING TO BE 16" OC UNO. WALL FRAMING DIMENSIONS ARE BASED ON 2 \times 4 STUDS UNO. DOUBLE STUDS UNDER ALL HEADERS.


LVL'S AND TJI'S TO BE SIZED BY OTHERS

EXTERIOR WALLS IN LIVING AREAS ARE 2 × 4

	WINDOW SCHEDULE			
SIZE	COUNT	LIBRARY NAME	R.O. WIDTH	R.O. HEIGHT
2'-0" x 2'-0"	3	Window\Casement	24"	24"
2'-0" x 3'-0"	3	Window\Single Hung	24"	36"
2'-8" x 5'-0"	4	Window\Single Hung	32"	60-1/2"
4'-8" x 3'-0" Twin	1	Window\Single Hung	56"	36"
2'-8" x 5'-0" Twin	3	Window\Single Hung	64"	60-1/2"




AREA SCHEDULE			
NAME	AREA		
Heated	1338 sq ft.		
Covered Rear Porch	98 sq ft.		
Covered Front Porch	138 sq ft.		
Garage	394 sq ft.		




Diane Rives	6205 Mockin DDD Sanford, N.C.	golfwoman@ch
30AEE. 1 = 1/4	DRAWN BY:	DATE: 8/18/2023
		######################################
	OR FLAN	

TOP OF PLATE

TOP OF FOOTING





ROOF NOTES: TRUSSES, BRACINGS, BRIDGING AND CONNECTORS ARE TO BE DESIGNED BY THE TRUSS MANUFACTURER. IDENTIFY LUMBER BY OFFICIAL GRADE MARKINGS. DO NOT CUT OR REMOVE CHORDS OR OTHER TRUSS MEMBERS. DO NOT NOTCH OR DRILL TRUSS MEMBERS.

SECTION A

SCALE: 1'= 1/4"

TYPICAL 2x4 SIDING EXTERIOR WALL: TYPICAL TRUSS ROOF:

SHINGLES

'H' CLIPS

7/16" ROOFING PLYWOOD c/w

2×4 TRUSS BRACING R38 BLOWN INSULATION

1/2" CEILING BOARD TAPED & SANDED

BLOCK & BRACE PER TRUSS MGR.

PRE-ENGINEERED TRUSSES @ 24" o.c.

HORIZONTAL SIDING

2x4 STUDS @ 16" o.c.

TAPED & SANDED

1/2" DRYWALL

RIS BATT INSULATION

7/16" PLYWOOD SHEATHING

TYPICAL 2x4 WALL:

TAPED & SANDED

TAPED & SANDED


2x4 STUDS @ 16" o.c.


1/2" DRYWALL

1/2" DRYWALL

WHERE PRE-ENGINEERED ROOF TRUSSES ARE USED, TRUSS MANUFACTURER SHALL PROVIDE SHOP DRAWINGS, WHICH BEAR SEAL OF A N. C. REGISTERED ENGINEER.

ELECTRICAL LEGEND				
ELECTRICAL	COUNT	SYMBOL		
ceiling fan	2			
10" led	6	\odot		
7" led	10			
foyer light	1			
dinning room light	1	0.0		
coach light	2			
exterior over head light	3			
flood light	2	QP		
vanity bar light	3	000		
wall sconce		00		
oendant light				





/4"

Diane Rives Designs
6205 Mockingbird Lans
6205 Mockingbird Land
6205 Mockingbird La

DRAWN BY:

CRH HOMES

THE KRIB HT GARAGE

TRICAL LAYOUT