

**General Notes:** \*\* CUTTING OR DRILLING OF COMPONENTS SHOULD NOT BE DONE WITHOUT CONTACTING COMPONENT SUPPLIER FIRST. CUSTOMER TAKES FULL RESPONSIBILITY FOR COMPONENTS IF CUT BEFORE AUTHORIZATION. \*\* ALL BEARING POINTS MUST BE INSTALLED PRIOR TO SETTING ANY COMPONENTS.


| Revisions |      |
|-----------|------|
| 00/00/00  | Name |
| 00/00/00  | Name |
| 00/00/00  | Name |
| 00/00/00  | Name |
| 00/00/00  | Name |

**THIS IS A TRUSS PLACEMENT DIAGRAM ONLY.** These trusses are designed as individual components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designer is responsible for temporary and permanent bracing of the roof and floor systems and for the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer. For general guidance regarding the bracing, consult "Bracing of Wood Truss" available from the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53179.



Lamco Custom Builders LLC  
 Kristie Bonus Rm SL Garage  
**COMPONENT PLAN**

|                 |           |
|-----------------|-----------|
| Scale:          | NTS       |
| Date:           | 5/11/2023 |
| Designer:       | M. Finch  |
| Project Number: | 23050075  |
| Sheet Number:   | 1/1       |



| Products |          |                                    |        |         |          |
|----------|----------|------------------------------------|--------|---------|----------|
| PlotID   | Length   | Product                            | Pieces | Net Qty | Fab Type |
| BM2      | 6-00-00  | 2.0 RigidLam DF LVL 1-3/4 x 9-1/4  | 1      | 1       | FF       |
| BM3      | 6-00-00  | 2.0 RigidLam DF LVL 1-3/4 x 9-1/4  | 1      | 1       | FF       |
| GDH      | 24-00-00 | 2.0 RigidLam DF LVL 1-3/4 x 11-7/8 | 2      | 2       | FF       |


| Truss Connector Total List |           |     |
|----------------------------|-----------|-----|
| Manuf                      | Product   | Qty |
| Simpson                    | One H2.5A | 73  |
| Simpson                    | HTU26"    | 4   |

| Connector Summary |         |           |
|-------------------|---------|-----------|
| Qty               | Manuf   | Product   |
| 2                 | Simpson | HUS181/10 |

\*\* DAMAGED COMPONENTS SHOULD NOT BE INSTALLED UNLESS TOLD TO BY THE COMPONENT PLANT.

\*\* FRAMER MUST REFER TO PLANS WHILE SETTING COMPONENTS.



\*\* TRIANGULAR SYMBOL NEAR END OF TRUSS INDICATES LEFT END OF TRUSS AS SHOWN ON INDIVIDUAL TRUSS DRAWINGS. \*\* PLUMBING DROPS NOTED ARE IN THE APPROXIMATE LOCATIONS PER PLAN. BUILDER TO VERIFY LOCATIONS BEFORE SETTING TRUSSES. \*\* REFER TO FINAL TRUSS ENGINEERING SHEETS FOR PLY TO PLY CONNECTIONS.

\*\* TRUSS TO TRUSS CONNECTIONS ARE TOE-NAILED, UNLESS NOTED OTHERWISE. \*\* DIMENSIONS ARE READ AS: FOOT-INCH-SIXTEENTH. \*\* GIRDERS MUST BE FULLY CONNECTED TOGETHER PRIOR TO ADDING ANY LOADS.