

# Reaction Summary of Order



REQ. QUOTE DATE	/ /	ORDER #	J1123-6516
ORDER DATE	11/17/23	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	0000007216
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	Shaun Garderner	INVOICE #	
COUNTY	Harnett	TERMS	
SUPERINTENDANT	Shaun Garderner	SALES REP	Neil Baggett
JOBSITE PHONE #	(910) 988-8172	SALES AREA	David Landry

SPECIAL TO	<b>Precision Custom Homes</b> 206 Shoreline Drive Raeford, NC 28376 (910) 988-8172	<b>JOB NAME:</b> Lot 73 Liberty Meadow <b>MODEL:</b> Roof <b>TAG:</b> Liberty 2.0 <b>DELIVERY INSTRUCTIONS:</b> 52 miles round trip	<b>LOT #</b> 73 <b>SUBDIV:</b> Liberty Meadow <b>JOB CATEGORY:</b> _
	<b>Precision Custom Homes and</b> Cameron, NC	<b>SPECIAL INSTRUCTIONS:</b>  <b>PLAN SEAL DATE:</b>	

<b>BUILDING DEPARTMENT</b>	<b>OVERHANG INFO</b>	<b>HEEL HEIGHT</b>	00-06-08	<b>REQ. LAYOUTS</b>	<b>REQ. ENGINEERING</b>	<b>QUOTE</b>	<b>DTL</b>	04/02/24
Roof Order	END CUT	RETURN						
	<b>GABLE STUDS</b>	24 IN. OC		JOBSITE	1	JOBSITE	1	<b>CUTTING</b>
								<b>DTL</b>
								04/02/24

**ROOF TRUSSES**      **LOADING INFORMATION**      TOLL-TCDL-BCLL-BCDL      STRESS INCR.      **ROOF TRUSS SPACING:** 24.0 IN. O.C. (TYP.)  
 20.0,10.0,0.0,10.0      1.15

PROFILE	QTY	PITCH		TYPE ID	BASE O/A	LUMBER		OVERHANG		REACTIONS
		TOP	BOT			TOP	BOT	LEFT	RIGHT	
	6	7.00	0.00	COMMON A1	33-00-00 33-00-00	2 X 6	2 X 6	01-02-08	01-02-08	Joint 2      Joint 8 1525.2 lbs.      1525.2 lbs. -90.9 lbs.      -90.9 lbs.
	1	7.00	0.00	GABLE A1GE	33-00-00 33-00-00	2 X 6	2 X 6	01-02-08	01-02-08	Joint 2      Joint 20      Joint 22      Joint 23      Joint 24 198.3 lbs.      172.7 lbs.      209.1 lbs.      164.5 lbs.      175.8 lbs. -61.9 lbs.      -4.6 lbs.      -93.2 lbs.      -75.0 lbs.      -77.8 lbs.
	4	7.00	0.00	COMMON A2	33-00-00 33-00-00	2 X 6	2 X 6	01-02-08	01-02-08	Joint 1      Joint 2      Joint 5      Joint 8 1109.6 lbs.      1525.2 lbs.      1109.6 lbs.      1525.2 lbs. -84.9 lbs.      -90.9 lbs.      -84.9 lbs.      -90.9 lbs.
	9	7.00	0.00	COMMON A3	33-00-00 33-00-00	2 X 6	2 X 6	01-02-08		Joint 2      Joint 8 1529.4 lbs.      1461.3 lbs. -91.0 lbs.      -74.7 lbs.
	1	7.00	0.00	GABLE A3GE	33-00-00 33-00-00	2 X 6	2 X 6	01-02-08		Joint 2      Joint 4      Joint 20      Joint 21      Joint 22 723.5 lbs.      723.5 lbs.      117.2 lbs.      230.5 lbs.      158.3 lbs. -77.5 lbs.      -77.5 lbs.      -2.3 lbs.      -107.2 lbs.      -71.1 lbs.
	1	6.00	0.00	GABLE B1GE	12-00-00 12-00-00	2 X 4	2 X 6	01-02-08	01-02-08	Joint 2      Joint 8 550.0 lbs.      550.0 lbs. -142.9 lbs.      -142.9 lbs.
	4	6.00	0.00	COMMON B2	12-00-00 12-00-00	2 X 4	2 X 6	01-02-08	01-02-08	Joint 2      Joint 4 550.0 lbs.      550.0 lbs. -108.9 lbs.      -108.9 lbs.
	5	10.00	0.00	COMMON C1	20-00-00 20-00-00	2 X 6	2 X 6	01-02-08	01-02-08	Joint 2      Joint 4 1043.7 lbs.      1043.7 lbs. -48.5 lbs.      -48.5 lbs.
	1 2 Ply	10.00	0.00	COMMON C1-GR	20-00-00 20-00-00	2 X 6	2 X 8	01-02-08		Joint 2      Joint 6 6838.3 lbs.      6844.2 lbs. -436.9 lbs.      -424.1 lbs.
	1	10.00	0.00	GABLE C1GE	20-00-00 20-00-00	2 X 6	2 X 6	01-02-08	01-02-08	Joint 2      Joint 12 859.7 lbs.      859.7 lbs. -169.5 lbs.      -169.5 lbs.
	6	6.00	0.00	COMMON G1	46-00-00 46-00-00	2 X 6	2 X 8	01-02-08	01-02-08	Joint 2      Joint 12      Joint 18 1250.3 lbs.      1365.2 lbs.      1447.0 lbs. -65.6 lbs.      -168.3 lbs.      -119.5 lbs.

# Reaction Summary of Order



REQ. QUOTE DATE	/ /	ORDER #	J1123-6516
ORDER DATE	11/17/23	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	0000007216
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	Shaun Garderner	INVOICE #	
COUNTY	Harnett	TERMS	
SUPERINTENDANT	Shaun Garderner	SALES REP	Neil Baggett
JOBSITE PHONE #	(910) 988-8172	SALES AREA	David Landry

SOLD TO	<b>Precision Custom Homes</b> 206 Shoreline Drive Raeford, NC 28376 (910) 988-8172	<b>JOB NAME:</b> Lot 73 Liberty Meadow <b>MODEL:</b> Roof <b>TAG:</b> Liberty 2.0 <b>DELIVERY INSTRUCTIONS:</b> 52 miles round trip	<b>LOT #</b> 73 <b>SUBDIV:</b> Liberty Meadow <b>JOB CATEGORY:</b> _
	<b>Precision Custom Homes and</b> Cameron, NC	<b>SPECIAL INSTRUCTIONS:</b>  <b>PLAN SEAL DATE:</b>	

<b>BUILDING DEPARTMENT</b>	<b>OVERHANG INFO</b>	<b>HEEL HEIGHT</b>	00-06-08	<b>REQ. LAYOUTS</b>	<b>REQ. ENGINEERING</b>	<b>QUOTE</b>	<b>DTL</b>	04/02/24
Roof Order	END CUT	RETURN				<b>LAYOUT</b>	<b>DTL</b>	04/02/24
	<b>GABLE STUDS</b>	24 IN. OC		JOBSITE	1	JOBSITE	1	<b>CUTTING</b> DTL 04/02/24

<b>ROOF TRUSSES</b>	<b>LOADING INFORMATION</b>	TCLL-TCDL-BCLL-BCDL	STRESS INCR.	<b>ROOF TRUSS SPACING:</b> 24.0 IN. O.C. (TYP.)
		20.0,10.0,0.0,10.0	1.15	

PROFILE	QTY	PITCH		TYPE ID	BASE O/A	LUMBER		OVERHANG		REACTIONS				
		TOP	BOT			TOP	BOT	LEFT	RIGHT	Joint 2	Joint 26	Joint 28	Joint 29	Joint 30
	1	6.00	0.00	COMMON G1GE	46-00-00 46-00-00	2 X 4	2 X 6	01-02-08	01-02-08	196.2 lbs. -27.2 lbs.	196.2 lbs. -3.2 lbs.	219.1 lbs. -94.9 lbs.	139.7 lbs. -62.0 lbs.	165.1 lbs. -70.6 lbs.
	4	4.00	0.00	MONO TRUSS J1	06-00-00 06-00-00	2 X 4	2 X 6	01-02-08	-00-01-08	316.0 lbs. -132.3 lbs.	215.2 lbs. -90.3 lbs.			
	6	4.00	0.00	MONOPITCH J2	05-00-00 05-00-00	2 X 4	2 X 6	01-02-08	-00-01-08	277.3 lbs. -119.5 lbs.	174.4 lbs. -72.2 lbs.			
	1	4.00	0.00	MONOPITCH J2GE	05-00-00 05-00-00	2 X 4	2 X 6	01-02-08		189.3 lbs. -89.3 lbs.	3.5 lbs. -3.4 lbs.	52.4 lbs. -34.0 lbs.	222.4 lbs. -70.5 lbs.	
	9	4.00	0.00	MONOPITCH J3	03-04-08 03-04-08	2 X 4	2 X 6	01-02-08		223.8 lbs. -68.8 lbs.	107.4 lbs. -14.2 lbs.			
	2	4.00	0.00	MONOPITCH J3GE	03-06-00 03-06-00	2 X 4	2 X 4	01-02-08		164.5 lbs. -91.1 lbs.	52.0 lbs. -26.0 lbs.	125.2 lbs. -37.7 lbs.		
	1	10.00	0.00	VALLEY V1	18-05-05 18-05-05	2 X 4	2 X 4			193.5 lbs. -7.5 lbs.	182.2 lbs. 22.4 lbs.	560.1 lbs. -171.8 lbs.	410.9 lbs. 55.3 lbs.	560.3 lbs. -171.9 lbs.
	1	10.00	0.00	VALLEY V2	15-07-11 15-07-11	2 X 4	2 X 4			150.3 lbs. -16.8 lbs.	134.9 lbs. 10.7 lbs.	428.5 lbs. -142.4 lbs.	410.8 lbs. 56.2 lbs.	428.9 lbs. -142.5 lbs.
	1	10.00	0.00	VALLEY V3	12-10-02 12-10-02	2 X 4	2 X 4			101.5 lbs. -31.1 lbs.	84.7 lbs. -8.6 lbs.	329.9 lbs. -123.9 lbs.	242.2 lbs. 54.2 lbs.	330.1 lbs. -124.1 lbs.
	1	10.00	0.00	VALLEY V4	10-00-08 10-00-08	2 X 4	2 X 4			198.9 lbs. -21.8 lbs.	198.9 lbs. -30.4 lbs.	346.9 lbs. 10.9 lbs.		
	1	10.00	0.00	VALLEY V5	07-02-15 07-02-15	2 X 4	2 X 4			150.6 lbs. -22.7 lbs.	150.7 lbs. -28.7 lbs.	219.7 lbs. 22.5 lbs.		

# Reaction Summary of Order




**ROOF & FLOOR TRUSSES & BEAMS**  
 Reilly Road Industrial Park P.O. Box 40408  
 Fayetteville, N.C. 28309 (910) 864-TRUS

REQ. QUOTE DATE	/ /	ORDER #	J1123-6516
ORDER DATE	11/17/23	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	0000007216
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	Shaun Garderner	INVOICE #	
COUNTY	Harnett	TERMS	
SUPERINTENDANT	Shaun Garderner	SALES REP	Neil Baggett
JOBSITE PHONE #	(910) 988-8172	SALES AREA	David Landry

S O F T W A R E	<b>Precision Custom Homes</b> 206 Shoreline Drive Raeford, NC 28376 (910) 988-8172	<b>JOB NAME:</b> Lot 73 Liberty Meadow <b>MODEL:</b> Roof <b>TAG:</b> Liberty 2.0 <b>DELIVERY INSTRUCTIONS:</b> 52 miles round trip	<b>LOT #</b> 73 <b>SUBDIV:</b> Liberty Meadow <b>JOB CATEGORY:</b> _
	<b>Precision Custom Homes and</b> Cameron, NC	<b>SPECIAL INSTRUCTIONS:</b>  <p style="text-align: right;"><b>PLAN SEAL DATE:</b></p>	<p style="text-align: right;"><b>BY</b>      <b>DATE</b></p>

BUILDING DEPARTMENT Roof Order	OVERHANG INFO	HEEL HEIGHT	00-06-08	REQ. LAYOUTS	REQ. ENGINEERING	QUOTE	DTL	04/02/24
	END CUT	RETURN				LAYOUT	DTL	04/02/24
	GABLE STUDS		24 IN. OC		JOBSITE 1	JOBSITE 1	CUTTING	DTL

<b>ROOF TRUSSES</b>		<b>LOADING INFORMATION</b>		TCLL-TCDL-BCLL-BCDL	STRESS INCR.	<b>ROOF TRUSS SPACING:</b> 24.0 IN. O.C. (TYP.)					
				20.0,10.0,0.0,10.0	1.15						
PROFILE	QTY	PITCH		TYPE ID	BASE O/A	LUMBER		OVERHANG	REACTIONS		
	1	TOP	BOT	VALLEY V6	04-05-05	2 X 4	2 X 4		Joint 1	Joint 3	Joint 4
		10.00	0.00		04-05-05				85.8 lbs.	85.8 lbs.	125.2 lbs.
									-12.9 lbs.	-16.3 lbs.	12.8 lbs.

<b>ITEMS</b>									
QTY	ITEM TYPE	SIZE	LENGTH FT-IN-16	PART NUMBER	NOTES				
9	Hangers, USP	HUS 26			SIMPSON (HUS26)				

# Job Estimate



**ROOF & FLOOR  
TRUSSES & BEAMS**

Reilly Road Industrial Park P.O. Box 40408  
Fayetteville, N.C. 28309 (910) 864-TRUS

REQ. QUOTE DATE	/ /	ORDER #	J1123-6517
ORDER DATE	11/17/23	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	0000007216
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	Shaun Garderner	INVOICE #	
SUPERINTENDANT	Shaun Garderner	SALES REP	Neil Baggett
JOBSITE PHONE #	(910) 988-8172		
DESIGNER	DTL	TRACKING	David Landry

SOLD TO	<b>Precision Custom Homes</b> 206 Shoreline Drive Raeford, NC 28376 (910) 988-8172	<b>JOB NAME:</b> Lot 73 Liberty Meadow <b>MODEL:</b> Floor <b>TAG:</b> Liberty 2.0 <b>DELIVERY INSTRUCTIONS:</b> 52 MILES ROUND TRIP	<b>LOT #</b> 73 <b>SUBDIV:</b> Liberty Meadow <b>JOB CATEGORY:</b> _
	<b>SHIPPED TO</b> Precision Custom Homes and Cameron, NC	<b>SPECIAL INSTRUCTIONS:</b>	<b>PLAN SEAL DATE:</b>

## FLOOR TRUSSES

FLOOR PROFILE	QTY PLY	DEPTH ID	SPAN FT-IN-16	END TYPE		INT BEARING		CANTILEVER		NOTES
				LEFT	RIGHT	SIZE	LOCATION	LEFT	RIGHT	
	1	01-04-00 ET1	32-11-00							
	1	01-04-00 ET2	18-04-00							
	1	01-04-00 ET3	19-04-08							
	7	01-04-00 F1	32-11-00							
	3	01-04-00 F2	31-11-00							
	9	01-04-00 F3	19-11-00							
	10	01-04-00 F4	19-08-00							
	1	01-04-00 F4A	19-08-00							
	1	01-04-00 F5	05-10-08							
	1	01-01-00 FG1	05-06-00							
	1	Truss Drawings With B-1 and B-3 Bracing And Handling Instructions (Included in truss price)								

**FLOOR SUB-TOTAL: \$ 4,610.06**

## ITEMS

QTY	ITEM TYPE	SIZE	LENGTH FT-IN-16	PART NUMBER	NOTES
8	Hangers, USP	HUS 410			SIMPSON (HUS410)
2	LVL Beams (Sized)	LVL, 1-3/4" x 9-1/4" (S)	07-00-00		BM4
2	LVL Beams (Sized)	LVL, 1-3/4" x 11-7/8" (S)	09-00-00		BM5
2	LVL Beams (Sized)	LVL, 1-3/4" x 11-7/8" (S)	20-00-00		GDH
2	LVL Beams (Sized)	LVL, 1-3/4" x 16" (S)	17-00-00		BM1
2	LVL Beams (Sized)	LVL, 1-3/4" x 16" (S)	20-00-00		BM2

**ITEMS SUB-TOTAL: \$ 1,415.14**

Please examine this quote, as we agree to furnish at the price herein specified only the articles named and described herein. Prices quoted are valid for jobs released for production within thirty days of date of estimate unless otherwise specified. Additional design time made necessary by incorrect foundation installation or plan changes may require additional charges. This estimate includes sealed engineering of individual truss drawings only. Any requirement for additional engineering services will be billed in quarter hour increments as costs are incurred.

<b>SUB-TOTAL</b>	<b>\$6,025.20</b>
<b>SALES TAX 7.00%</b>	<b>\$421.76</b>
<b>GRAND TOTAL</b>	<b>\$6446.96</b>

**ACCEPTED BY SELLER**

BY: \_\_\_\_\_

TITLE: \_\_\_\_\_

DATE OF ACCEPTANCE: \_\_\_\_\_

**ACCEPTED BY BUYER**

PURCHASER: \_\_\_\_\_

BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

\_\_\_\_\_

PHONE: \_\_\_\_\_ DATE: \_\_\_\_\_

**WARNING:**As part of this proposal, we warn that trusses can be dangerous and cause property damage or personal injury if improperly installed and / or braced. Customer acceptance hereof shall constitute his affirmative representation to us that he is trained in the proper and safe methods of truss installation and bracing, and will use such methods. Customer acknowledges receipt of instructional pamphlet entitle: 'Bracing Wood Trusses: Commentary and recommendations', HIB-91, as published by the Truss Plate Institute, Inc., and also the engineering drawings showing the required lateral bracing. By his acceptance, Customer agrees, for himself, his agents and employees, to hold Comtech Inc. harmless from any and all actions for property damage, personal injury, or wrongful death resulting from improper installation and / or bracing during erection of the trusses comprehended hereby.