North Carolina 2018 - R402.1.5 Total UA

Property , NC 27546 Model: Berton Organization
Southern Energy Manager
Justin Smith

Inspection StatusResults are projected



Template - OnSite Homes - Berton 2452 plan slab - CZ 4 - ecoSelect Berton 2452 plan slab Builder OnSite Homes

This report is based on a proposed design and does not confirm field enforcement of design elements.

Building UA

Elements	NC Reference	As Designed
Ceilings	57.4	53.1
Above-Grade Walls	201.9	171.2
Windows, Doors and Skylights	94.5	87.3
Slab Floor:	78.6	102.5
Framed Floors	15.4	15.0
Foundation Walls	0.0	0.0
Rim Joists	7.9	7.9
Overall UA (Design must be equal or lower):	455.7	437.0

Requirements

402.1.5	Total UA alternative compliance passes by 4.1%.	
402.3.2 Glazed Fenestration SHGC	Average SHGC: 0.27 Max SHGC: 0.30	
R402.4.2.2	Air Leakage Testing	Air sealing is 0.28 CFM50 / ft² Shell Area. It must not exceed 0.30 CFM50 / ft² Shell Area.
R402.5	Area-weighted average fenestration SHGC	
R402.5	Area-weighted average fenestration U-Factor	
R404.1	Lighting Equipment Efficiency	
Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.	
R403.3.1	Duct Insulation	
403.3.3	Duct Testing	

Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 4.1%.

Name:	Justin Smith	Signature:	Justin Smith
Organization:	Southern Energy Management	Digitally signed:	6/25/21 at 10:02 AM

Property , NC 27546 Model: Berton

Justin Smith Builder

Template - OnSite Homes - Berton 2452 plan slab - CZ 4 - ecoSelect Berton 2452 plan slab

Organization Southern Energy Manager

OnSite Homes

Results are projected

Inspection Status



General Building Information

Conditioned Area (sq ft) 2,452 Conditioned Volume (cubic ft) 23,460 Insulated Shell Area (sq ft) 6,636.72

The building energy model in Ekotrope reflects the building assemblies and energy features listed below. Sometimes energy deled. The inspection process should identify any changes and ensure

	res will change in the field from what has been model ne home continues to meet the applicable energy coo
Slab	
	Name: slab(1,362 s.f., 162 ft. exterior perimeter) R-0 perimeter insulation, R-0 under slab insulation.
Fran	ned Floor
	Name: over garage (327 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: I
Fou	ndation Wall
	None Present
Abo	ve Grade Wall
	Name: 1st floor ambient (1,155 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: III
	Name: 1st floor garage (303 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: III
	Name: 2nd floor ambient (953 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: III

Property , NC 27546 Model: Berton Organization
Southern Energy Manager
Justin Smith

Inspection StatusResults are projected



Model	. Derton	Justin O	111101			
2452	ate - OnSite Homes - Berton blan slab - CZ 4 - ecoSelect n 2452 plan slab	Builder OnSite I				
	Name: 2nd floor attic (481 s.f.) R-0 continuous insulation, R-19 c Insulation Grade: III	avity insu	ulation			
Rim	Joist					
	Name: 1st floor ambient (109 s.f.) R: 13.20)				
П	Name: 1st floor garage (34 s.f.) R: 13.20					
Ceili	ng / Roof					
	Name: Attic (1,213 s.f.) R-13 continuous insulation, R-25 Insulation Grade: I	cavity ins	sulation			
	Name: Attic vaulted (699.72 s.f.) R-0 continuous insulation, R-38 c Insulation Grade: I	avity insu	ulation			
Opad	que Door					
	Name: front entry (20 s.f.) U: 0.200					
	Name: garage entry (18 s.f.) U: 0.200					
	Name: attic door (10 s.f.) U: 0.200					
Glazi	ing					
	Name: front shaded (39 s.f.), U	: 0.350,	SHGC: 0.27,	Orientation: SOUTH_E	AST	

Name: front 2nd unshaded (36.9 s.f.), U: 0.350, SHGC: 0.27, Orientation: SOUTH_EAST

Property , NC 27546 Model: Berton Organization Southern Energy Manager Justin Smith Inspection Status
Results are projected



Template - OnSite Homes - Berton Builder 2452 plan slab - CZ 4 - ecoSelect OnSite Homes Berton 2452 plan slab Name: left unshaded (8 s.f.), U: 0.350, SHGC: 0.27, Orientation: SOUTH WEST Name: left 2nd unshaded (30 s.f.), U: 0.350, SHGC: 0.27, Orientation: SOUTH WEST Name: right unshaded (15 s.f.), U: 0.350, SHGC: 0.27, Orientation: NORTH EAST Name: right 2nd unshaded (30 s.f.), U: 0.350, SHGC: 0.27, Orientation: NORTH EAST Name: rear unshaded (63 s.f.), U: 0.350, SHGC: 0.27, Orientation: NORTH WEST Skylight None Present **Mechanical Ventilation** None Present Mechanical Equipment whole house heat pump • Electric • 100% Heating Load @ 8.2 HSPF, 100% Cooling Load @ 14 SEER Water Heating • Natural Gas • 100% Hot Water Load @ 0.59 Energy Factor

Air Leakage Control

Test Status: Blower-door tested

House is air-sealed as to achieve 1,876 CFM50 (4.80 ACH50) or less at final blower-door test.

Infiltration Requirements for IECC in Climate Zone 4

2009 IECC Infiltration limit for the design home is 7 ACH50.

2012 IECC Infiltration limit for the design home is 3 ACH50.

2015 IECC Infiltration limit for the design home is 3 ACH50.

2018 IECC Infiltration limit for the design home is 3 ACH50.

Property , NC 27546 Model: Berton

Template - OnSite Homes - Berton

Organization Southern Energy Manager Justin Smith **Inspection Status**Results are projected



Template - OnSite Homes - Berton 2452 plan slab - CZ 4 - ecoSelect Berton 2452 plan slab Builder OnSite Homes

Duct Leakage

Duct System 1

NOT entirely within conditioned space, testing required Leakage to Outside specified as: 98 CFM @ 25Pa (4 / 100 ft²) Total Leakage specified as: 98 CFM @ 25Pa (Post-Construction)

Duct Leakage Code Requirements for IECC

2009 IECC:

Postconstruction Leakage Test: Duct Leakage to Outdoors <= 8 CFM25 / 100 sq ft CFA. Rough in Test with AHU: Total Duct Leakage <= 6 CFM25 / 100 sq ft CFA. Rough in Test without AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

2012 IECC Mandatory, 2015 and 2018 IECC Prescriptive Paths:

Postconstruction Leakage Test: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA. Rough in Test with AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA. Rough in Test without AHU: Total Duct Leakage <= 3 CFM25 / 100 sq ft CFA.

2015 and 2018 IECC Performance Paths (Cost Compliance):

Leakage testing is required UNLESS all ducts and air handlers are located entirely within the thermal envelope. There is no pass/fail threshold for duct leakage on the performance path.

Project Notes

- -updated JS 06/25/21
- -confirm attic insulation and hyac specs
- -ventilation modeled as none
- -confirm cfl lighting %
- -modeled to worst case orientation