

3

REQUIRED VENTS ARE TO BE PLACED SO AS TO
PROVIDE CROSS-VENTILATION OF THE CRAWL SPACE.

USE 2 X 6 MUD SILL W/ SGL. 2X8 BANDS ON 8" WALLS.
PROVIDE ANCHOR BOLTS PER NC STATE CODE
USE DOUBLE 2X10 GIRDERS W/ 2X2 LEDGERS
USE 2X8 JOISTS AT 16" AND 12" O.C., ADD SGL. JOIST
PARALLEL INTERIOR WALLS AS REQ'D.
PROVIDE 24 X 36 ACCESS OPENING IN FND. WALL.
PROVIDE STEPS TO BELOW (MAX. 8")
HOLD ALL PIERS 1/2" GROUND FND. WALLS.