



April 23, 2025

C & C Services  
Chad Tyndall  
3782 Tyndall Bridge Road  
Salemberg, NC 28385

Reference: Engineering Services  
122 Jones Creek Lane  
Lillington, NC 27546  
Project No.: 2501-020310

To Whom It May Concern:

As requested, the undersigned representative of Tyndall Engineering and Design, PA (TE&D) has provided the following engineering services:

- 1) Overexcavated footing at front left corner of front porch due to tree stump.

The following conclusions and recommendations were noted:

- 1) The existing footing at the front left corner of the front porch had been overexcavated due to a tree stump. The footing in this area was reinforced with (2) #4 rebar at the bottom of the specified footing depth and filled solid with concrete. Based on our analysis, the completed repair is adequate to support the anticipated loading conditions.

We appreciate being able to assist you during this phase of the project. If you need further assistance or require additional information, please do not hesitate to contact us.

Sincerely,  
Tyndall Engineering & Design

Prentice A. Tyndall Jr., PE  
PT III | 2501-020310



