

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: BLAKE POND

LOT 92

INITIAL SYSTEM: APPROVED 25% REDUCTION

REPAIR: APPROVED 25% REDUCTION

DISTRIBUTION: D-BOX

DISTRIBUTION D-BOX

BENCHMARK: 100.0

LOCATION FL 91/92

NO. BEDROOMS: 4

LTAR 0.3 GPD/FT<sup>2</sup>

SEPTIC TANK SIZE: 1000

PUMP TANK SIZE: NA

LINE	FLAG COLOR	ELEVATION	LENGTH
INITIAL SYSTEM {	1	0	103.50
	2	W	103.34
	3	0	103.17
	4	W	102.84
			400'
5	0	102.84	100'
6	W	102.92	100'
7	0	102.34	100'
8	W	102.17	100'
			400'

BY: M EAKER

DATE 12/2022

TYPICAL PROFILE

0-8 LS (VF, wq-)

8-48 SCL (Fi, sbk)

cc 2 > 48"

INSTALL AT 18-24"

**THERE SHALL BE NO GRADING,  
CUTTING, LOGGING OR OTHER SOIL  
DISTURBANCE IN SEPTIC AREA**

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GURANTEE FUNCTIONALITY

# Southeastern Soil & Environmental Associates, Inc.

P.O. Box 9321  
Fayetteville, NC 28311  
Phone/Fax (910) 822-4540  
Email mike@southeasternsoil.com

