

# North Carolina 2018 - R402.1.5 Total UA



SOUTHERN ENERGY  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

## Property

95 Barn Door Drive  
Lillington, NC 27546  
Model: 307 slab

## Organization

Southern Energy Management  
Justin Smith

## Inspection Status

Results are projected

## Builder

Chesapeake - 307 one story plan slab - ec  
307 plan slab Chesapeake Homes

**This report is based on a proposed design and does not confirm field enforcement of design elements.**

## Building UA

Elements	NC Reference	As Designed
Ceilings	58.1	52.3
Above-Grade Walls	125.7	118.6
Windows, Doors and Skylights	115.3	95.0
Slab Floor:	106.3	139.0
Framed Floors	0.0	0.0
Foundation Walls	0.0	0.0
Rim Joists	0.0	0.0
<b>Overall UA (Design must be equal or lower):</b>	<b>405.4</b>	<b>404.9</b>

## Requirements

✓	R402.1.5	Total UA alternative compliance passes by 0.1%.	The proposed home meets the UA requirement by 0.1%
✓	R402.3.2	Average SHGC: 0.28 Max SHGC: 0.30	Average SHGC of 0.28 is greater than the maximum of 0.30.
✓	R402.4.2.2	Air Leakage Testing	Air sealing is 0.24 CFM50 / ft <sup>2</sup> Shell Area. It must not exceed 0.30 CFM50 / ft <sup>2</sup> Shell Area.
✓	R402.5	Area-weighted average fenestration SHGC	Area-weighted average fenestration SHGC is 0.28. The maximum allowed value is [No Limit].
✓	R402.5	Area-weighted average fenestration U-Factor	
✓	R404.1	Lighting Equipment	At least 75.0% of fixtures shall be high-efficacy lamps, currently 100.0% are high-efficacy.
✓	Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.	2015 IECC Mandatory Checklist must be checked as complete.
✓	R403.3.1	Duct Insulation	Duct insulation meets the requirements specified in North Carolina 2018 Code Section 403.3.1.
✓	403.3.3	Duct Testing	

**Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 0.1%.**

Name: Justin Smith  
Organization: Southern Energy Management

Signature: Justin Smith  
Digitally signed: 4/16/24 at 11:27 AM

## Ekotrope RATER - Version 4.1.2.3380

North Carolina 2018 Prescriptive compliance results calculated using Ekotrope RATER's energy and code compliance algorithm, including appropriate amendments.  
Ekotrope RATER is a RESNET Accredited HERS Rating Tool. All results are based on data entered by Ekotrope users.  
Ekotrope disclaims all liability for the information shown on this report.

# Building Summary



**SOUTHERN ENERGY**  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
95 Barn Door Drive  
Lillington, NC 27546  
Model: 307 slab

**Organization**  
Southern Energy Management  
Justin Smith

**Inspection Status**  
Results are projected

Chesapeake - 307 one story plan slab - ecoSelect  
307 plan slab

**Builder**  
Chesapeake Homes

## General Building Information

Number Of Bedrooms	3
Number Of Floors	1
Conditioned Floor Area [sq. ft.]	1,938
Has Electric Vehicle Ready Space	No
Unconditioned, attached garage?	Yes
Conditioned Volume [cu. ft.]	17,442
Total Units in Building	1
Residence Type	Single family detached
Number of Floors in Building	-
Floor Number	-
Model	307 slab
Community	
RESNET/IECC 2006-2018 Climate Zone	4A
IECC 2021 Climate Zone	3A

## Foundation Wall

None Present

## Foundation Wall Library List

None Present

## Slab

Name	Library Type	Perimeter	Floor Grade	Carpet R	Exposed Masonry Area	Surface Area	Location	Enclosing
slab	Uninsulated	218	On Grade	1	0	1,938.0 ft <sup>2</sup>	Exposed Exterior	Conditioned Space

## Slab Library List

Name	Wall Construction Type	Slab Completely Insulated?	Underslab Insulation Width [ft]	Perimeter Insulation Depth [ft]	Perimeter Insulation R Value	Perimeter Insulation Is Exterior	Thermal Break	Effective R-value
Uninsulated	Wood Frame / Other	No	0	0	0	No	No	0.00

## Framed Floor

None Present

# Building Summary



**SOUTHERN ENERGY  
MANAGEMENT**  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
95 Barn Door Drive  
Lillington, NC 27546  
Model: 307 slab

**Organization**  
Southern Energy Management  
Justin Smith

**Inspection Status**  
Results are projected

Chesapeake - 307 one story plan slab - ecoSelect  
307 plan slab

**Builder**  
Chesapeake Homes

## Framed Floor Library List

None Present

## Rim Joist

None Present

## Rim Joist Library List

None Present

## Wall

Name	Library Type	Surface Color	Surface Area	Location
1st floor ambient	R 15 Adv. Framing G1 16" O.C	Medium	1,628.0 ft <sup>2</sup>	Exposed Exterior
1st floor garage	R 15 Adv. Framing G1 16" O.C	Medium	334.0 ft <sup>2</sup>	Unconditioned, attached garage

## Wall Library List

Name	Effective R-value
R 15 Adv. Framing G1 16" O.C	13.771

## Glazing

Name	Library Type	Wall Assignment	Foundation Wall Assignment	Is Operable	Overhang Depth	Overhang Ft To Top	Overhang Ft To Bottom	Orientation	Surface Area
front shaded	30/28	1st floor ambient		Yes	13	1	9	Southwest	17.0 ft <sup>2</sup>
front unshaded	30/28	1st floor ambient		Yes	0	0	0	Southwest	36.0 ft <sup>2</sup>
left shaded	30/28	1st floor ambient		Yes	11	1	7	Northwest	36.0 ft <sup>2</sup>
left unshaded	30/28	1st floor ambient		Yes	0	0	0	Northwest	58.0 ft <sup>2</sup>

# Building Summary



**SOUTHERN ENERGY  
MANAGEMENT**  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
95 Barn Door Drive  
Lillington, NC 27546  
Model: 307 slab

**Organization**  
Southern Energy Management  
Justin Smith

**Inspection Status**  
Results are projected

Chesapeake - 307 one story plan slab - ecoSelect  
307 plan slab

**Builder**  
Chesapeake Homes

Name	Library Type	Wall Assignment	Foundation Wall Assignment	Is Operable	Overhang Depth	Overhang Ft To Top	Overhang Ft To Bottom	Orientation	Surface Area
rear shaded	30/28	1st floor ambient		Yes	16	1	9	Northeast	41.1 ft <sup>2</sup>
rear unshaded	30/28	1st floor ambient		Yes	0	0	0	Northeast	55.2 ft <sup>2</sup>
right unshaded	30/28	1st floor ambient		Yes	0	0	0	Southeast	48.0 ft <sup>2</sup>

## Glazing Library List

Name	Shgc	U-factor
30/28	0.28	0.300

## Skylight

None Present

## Skylight Library List

None Present

## Opaque Door

Name	Library Type	Wall Assignment	Foundation Wall Assignment	Emittance	Solar Absorptance	Surface Color	Surface Area	Location
front entry	Fiberglass R-5	1st floor ambient		0.9	0.75	Medium	20.0 ft <sup>2</sup>	Exposed Exterior
garage entry	Fiberglass R-5	1st floor garage		0.9	0.75	Medium	18.0 ft <sup>2</sup>	Unconditioned, attached garage

## Opaque Door Library List

Name	Effective U-factor
Fiberglass R-5	0.200

# Building Summary



**SOUTHERN ENERGY  
MANAGEMENT**  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
95 Barn Door Drive  
Lillington, NC 27546  
Model: 307 slab

**Organization**  
Southern Energy Management  
Justin Smith

**Inspection Status**  
Results are projected

Chesapeake - 307 one story plan slab - ecoSelect  
307 plan slab

**Builder**  
Chesapeake Homes

## Roof Insulation

Name	Library Type	Attic Exterior Area [ft <sup>2</sup> ]	Clay or Concrete Roof Tiles	Surface Color	Surface Area	Location
attic	R 38 Attic BLOWN FG G1 2x10 24"OC NO Radiant	2,848.86	No	Dark	1,938.0 ft <sup>2</sup>	Attic

## Roof Insulation Library List

Name	Has Radiant Barrier	Effective R-value
R 38 Attic BLOWN FG G1 2x10 24"OC NO Radiant	No	37.074

## Whole House Infiltration

Infiltration	Measurement Type	Shelter Class
1395 CFM at 50 Pa	Blower-door tested	4

## Mechanical Ventilation

None Present

## Lighting

% Interior Fluorescent Lighting	% Interior LED Lighting	% Exterior Fluorescent Lighting	% Exterior LED Lighting	% Garage Fluorescent Lighting	% Garage LED Lighting
0	100	0	0	0	0

## Onsite Generation

None Present

# Building Summary



**SOUTHERN ENERGY**  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
95 Barn Door Drive  
Lillington, NC 27546  
Model: 307 slab

**Organization**  
Southern Energy Management  
Justin Smith

**Inspection Status**  
Results are projected

Chesapeake - 307 one story plan slab - ecoSelect  
307 plan slab

**Builder**  
Chesapeake Homes

## Onsite Generation Library List

None Present

## Solar Generation

None Present

## Dehumidifier

None Present

## Dehumidifier Library List

None Present

## Whole House Fan

None Present

## Whole House Fan Library List

None Present

## Conditioning Equipment

Name	Library Type	Serial Number	Heating Percent Load	Cooling Percent Load	Hot Water Percent Load	Location
Water Heating	z 50 gal. 0.58 EF Gas		0%	0%	100%	Unconditioned Garage
whole house a/c	z 14 SEER A/C 3 ton		0%	100%	0%	Attic
whole house furnace	z 92 AFUE Gas Furn 64k		100%	0%	0%	Attic

# Building Summary



## Property

95 Barn Door Drive  
Lillington, NC 27546  
Model: 307 slab

## Organization

Southern Energy Management  
Justin Smith

## Inspection Status

Results are projected

Chesapeake - 307 one story plan slab - ecoSelect  
307 plan slab

## Builder

Chesapeake Homes

### Equipment Type: z 14 SEER A/C 3 ton

Equipment Type	Air Conditioner
Fuel Type	Electric
Distribution Type	Forced Air
Motor Type	PSC (Single Speed)
Heat Pump System Type	Unspecified
Cooling Efficiency	14 SEER
Cooling Capacity [kBtu/h]	36

### Equipment Type: z 50 gal. 0.58 EF Gas

Equipment Type	Residential Water Heater
Fuel Type	Natural Gas
Distribution Type	Hydronic Delivery (Radiant)
Hot Water Efficiency	0.58 Energy Factor
Tank Capacity (gal.)	50
Hot Water Capacity [kBtu/h]	40
Recovery Efficiency	0.76

### Equipment Type: z 92 AFUE Gas Furn 64k

Equipment Type	Furnace
Fuel Type	Natural Gas
Distribution Type	Forced Air
Motor Type	PSC (Single Speed)
Heating Efficiency	92 AFUE
Heating Capacity [kBtu/h]	64
Use default EAE	No
EAE [kWh]	591

# Building Summary



**SOUTHERN ENERGY**  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
95 Barn Door Drive  
Lillington, NC 27546  
Model: 307 slab

**Organization**  
Southern Energy Management  
Justin Smith

**Inspection Status**  
Results are projected

Chesapeake - 307 one story plan slab - ecoSelect  
307 plan slab

**Builder**  
Chesapeake Homes

## Distribution System

Distribution Type	Forced Air
Heating Equipment	whole house furnace
Cooling Equipment	whole house a/c
Sq. Feet Served	1,938
# Return Grilles	2
Supply Duct R Value	8
Return Duct R Value	8
Supply Duct Area [ft <sup>2</sup> ]	523.26
Return Duct Area [ft <sup>2</sup> ]	193.8
Leakage to Outdoors	77 CFM @ 25Pa (3.97 / 100 ft <sup>2</sup> )
Total Leakage	77 CFM25
Total Leakage Duct Test Conditions	Post-Construction
Use Default Flow Rate	Yes
Duct 1	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 2	
Duct Location	Attic (well vented)
Percent Supply Area	100
Percent Return Area	100
Duct 3	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 4	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 5	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 6	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0

## HVAC Grading

HVAC Grading Not Conducted

## Ceiling Fan

Has Ceiling Fan No



# Building Summary



**Property**  
95 Barn Door Drive  
Lillington, NC 27546  
Model: 307 slab

**Organization**  
Southern Energy Management  
Justin Smith

**Inspection Status**  
Results are projected

Chesapeake - 307 one story plan slab - ecoSelect  
307 plan slab

**Builder**  
Chesapeake Homes

## Water Distribution

Water Fixture Type	Standard
Use Default Hot Water Pipe Length	No
Hot Water Pipe Length [ft]	72
At Least R3 Pipe Insulation?	No
Hot Water Recirculation System?	No
Drain Water Heat Recovery?	No

## Clothes Dryer

Cef	3.01
Fuel Type	Electric
Field Utilization	Timer Controls
Is Outside Conditioned Space	No
Clothes Dryer Available	Yes
Defaults Type	HERS Reference

## Clothes Washer

Label Energy Rating	153 kWh/Year
Annual Gas Cost	\$12.00
Electric Rate	\$0.11/kWh
Gas Rate	\$1.22/Therm
Capacity	3.31
Imef	2.1547
Defaults Type	Custom
Load Type	Front-load
Loads Per Week	6
Is Outside Conditioned Space	No
Clothes Washer Available	Yes

## Dishwasher

Dishwasher Defaults Type	Custom
Dishwasher Size	Standard
Dishwasher Efficiency	270 kWh
Annual Gas Cost	\$22.23
Electric Rate	\$0.12/kWh
Gas Rate	\$1.09/Therm
Is Outside Conditioned Space	No
Dishwasher Available	Yes

# Building Summary



**Property**  
95 Barn Door Drive  
Lillington, NC 27546  
Model: 307 slab

**Organization**  
Southern Energy Management  
Justin Smith

**Inspection Status**  
Results are projected

Chesapeake - 307 one story plan slab - ecoSelect  
307 plan slab

**Builder**  
Chesapeake Homes

## Appliances and Controls

Thermostat Cooling Setpoint	*** 75.0
Thermostat Heating Setpoint	*** 70.0
Range/Oven Fuel	Electric
Convection Oven?	No
Induction Range?	No
Range/Oven Outside Conditioned Space?	No
Refrigerator Consumption	538 kWh/Year
Refrigerator Outside Conditioned Space?	No

## Notes

Updated inputs\_\_\_\_AT 5/14/2021\_\_\_\_  
updated JS 09/29/23

- \*\*no slab insulation modeled\*\*
- confirm utilities
- confirm window specs
- confirm if radiant barrier installed, modeled as yes
- confirm HVAC specs
- confirm ventilation entry, modeled as none
- confirm cfl lighting %
- modeled to worst case orientation