



November 20, 2024

C & C Services
Chad Tyndall
3782 Tyndall Bridge Road
Salemberg, NC 28385

Reference: Engineering Services
244 Hazelwood Rd.
Lillington, NC
Project No.: 2401-020986

To Whom It May Concern:

As requested, the undersigned representative of Tyndall Engineering and Design, PA (TE&D) has provided the following engineering services:

- 1) 3RD party footing projection repair located along the rear foundation wall.

The following conclusions and recommendations were noted:

- 1) The existing footing projection repairs consisted of the addition of an 8” #4 rebar dowel embedded 4” into the existing concrete footing. The new rebar dowels are located within 1 foot from the corners and at 2 feet on center in the field. The existing repairs are adequate to support the anticipated loading conditions.

We appreciate being able to assist you during this phase of the project. If you need further assistance or require additional information, please do not hesitate to contact us.

Sincerely,
Tyndall Engineering & Design

Sean M. Holmes
SMH| 2401-020986

Prentice A. Tyndall Jr., PE







