

Client: Project: Address: SOUTHERN TOUCH HOMES


SOUTHERN BELLE PLAN

Date: 3/19/2021 Input by: **Bob Lewis** 

Job Name: j0321-1555 beams Project #: j0321-1555

**Kerto-S LVL** 1.750" X 14.000" 2-Ply - PASSED **GDH** 

Level: Level



### Member Information Reactions UNPATTERNED Ib (Uplift) Type: Girder Application: Floor Brg Live Snow Dead Plies: 2 Design Method: ASD 0 1386 0 1 Moisture Condition: Dry **Building Code: IBC/IRC 2015** 0 1386 O 2 Deflection LL: 480 Load Sharing: No Deflection TL: 240 Deck: Not Checked Importance: Normal Temperature: Temp <= 100°F **Bearings** Bearing Length Cap. React D/L lb 1 - SPF 3.500" 1386 / 0 End Grain

Analy	ysis	Resu	lts
-------	------	------	-----

•						
Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	6945 ft-lb	9'6"	24299 ft-lb	0.286 (29%)	D	Uniform
Unbraced	6945 ft-lb	9'6"	6949 ft-lb	0.999 (100%)	D	Uniform
Shear	1236 lb	1'4 3/4"	9408 lb	0.131 (13%)	D	Uniform
LL Defl inch	0.000 (L/999)	0	999.000 (L/0)	0.000 (0%)		
TL Defl inch	0.281 (L/792)	9'6 1/16"	0.927 (L/240)	0.300 (30%)	D	Uniform

# **Design Notes**

- 1 Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at a maximum of 16'10 1/2" o.c.
- 6 Bottom braced at bearings.

7 Lateral slend	derness ratio based on sing	le ply width.								
ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Tapered Start	0-0-0		Тор	90 PLF	0 PLF	0 PLF	0 PLF	0 PLF	
	End	9-6-0			180 PLF	0 PLF	0 PLF	0 PLF	0 PLF	
2	Tapered Start	9-6-0		Тор	180 PLF	0 PLF	0 PLF	0 PLF	0 PLF	
	End	19-0-0			90 PLF	0 PLF	0 PLF	0 PLF	0 PLF	
	Self Weight				11 PLF					

2 - SPF 3.500"

End Grain 13%

1386 / 0

### Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive
- Handling & Installation
- LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals Damaged Beams must not be used
- Design assumes top edge is laterally restrained
  Provide lateral support at bearing points to avoid
  lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS

Wind

Total Ld. Case

1386 Uniform

1386 Uniform

0

0

Const

0

0

Ld. Comb.

D



Page 1 of 2

This design is valid until 2/26/2023 CSD DESIGN



Client: Project:

Address:


SOUTHERN TOUCH HOMES SOUTHERN BELLE PLAN

Date: 3/19/2021 Input by: **Bob Lewis** 

Job Name: j0321-1555 beams Project #: j0321-1555

Page 2 of 2

**GDH Kerto-S LVL** 1.750" X 14.000" 2-Ply - PASSED Level: Level



# Multi-Ply Analysis

Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c., Maximum end distance not to exceed 6"

	, , , , , , , , , , , , , , , , , , , ,
Capacity	0.0 %
Load	0.0 PLF
Yield Limit per Foot	245.6 PLF
Yield Limit per Fastener	81.9 lb.
Yield Mode	IV
Edge Distance	1 1/2"
Min. End Distance	3"
Load Combination	
Duration Factor	1.00

## Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

# Handling & Installation

- Handling & Installation

  1. IVI beams must not be cut or drilled

  2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  3. Damaged Beams must not be used

  4. Design assumes top edge is laterally restrained

  5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



This design is valid until 2/26/2023