

Mark Morris, P.E.

#126, 1317-M, Summerville, SC 29483

843 209-5784, Fax (866)-213-4614

The truss drawing(s) listed below have been prepared by **Atlantic Building Components** under my direct supervision based on the parameters provided by the truss designers.

AST #: 46042

JOB: 24-1170-F02

JOB NAME: LOT 0.0003 HONEYCUTT HILLS

Wind Code: N/A

Wind Speed: Vult= N/A

Exposure Category: N/A

Mean Roof Height (feet): N/A

These truss designs comply with IRC 2015 as well as IRC 2018.

16 Truss Design(s)

Trusses:

F01, F02, F03, F04, F05, F06, F07, F08, F09, F10, F12, F13, F14, F15, F16, F17



3/1/2024

Mark Morris

Warning !—Verify design parameters and read notes before use.

This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to

Job 24-1170-F02	Truss F01	Truss Type Floor Supported Gable	Qty 1	Ply 1	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 46042
--------------------	--------------	-------------------------------------	----------	----------	---

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:33 2024 Page 1
ID:C6coucD2lwHaZ3sGy11mE3yowb3-4fZW5cdePgRXnv4lvkftvXFECgHbrGwb_zSjVzeGw4

0₁1-8

0₁1-8

Scale = 1:19.9




Plate Offsets (X,Y)-- [6:0-1-8,Edge], [16:0-1-8,Edge], [20:Edge,0-1-8]									
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00		TC 0.06	Vert(LL) n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL 1.00		BC 0.01	Vert(CT) n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr YES		WB 0.03	Horz(CT) 0.00	11	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH					Weight: 54 lb	FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 12-1-0.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 20, 11, 19, 18, 17, 16, 15, 14, 13, 12

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.



- NOTES-** (5)
- Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



3/1/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.23	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.44	Vert(LL) -0.07 11-12 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.32	Vert(CT) -0.09 11 >999 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.02 7 n/a n/a		
	Code IRC2021/TPI2014			Weight: 62 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 14=531/0-3-6 (min. 0-1-8), 7=531/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 14-15=-528/0, 1-15=-527/0, 7-16=-528/0, 6-16=-527/0, 1-2=-533/0, 2-3=-1304/0, 3-4=-1546/0, 4-5=-1304/0, 5-6=-533/0
BOT CHORD 12-13=0/1055, 11-12=0/1546, 10-11=0/1546, 9-10=0/1546, 8-9=0/1055
WEBS 3-12=-396/0, 2-12=0/335, 2-13=-679/0, 1-13=0/675, 4-9=-396/0, 5-9=0/335, 5-8=-679/0, 6-8=0/675

- NOTES-** (3-6)
- Unbalanced floor live loads have been considered for this design.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



3/1/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-1170-F02	Truss F03	Truss Type Floor	Qty 1	Ply 1	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC	Job Reference (optional) # 46042
--------------------	--------------	---------------------	----------	----------	---	--

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:34 2024 Page 1
ID: C6coucD2lwHaZ3sGy11mE3yowb3-Yr7uJyeGAZOP2fxTRArQi4NocwmKDM3qei0GxzeGw3





Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge], [16:Edge,0-1-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.23	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.44	Vert(LL) -0.07 13-14 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.34	Vert(CT) -0.09 13-14 >999 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.02 9 n/a n/a		
	Code IRC2021/TPI2014			Weight: 67 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 16=530/0-3-6 (min. 0-1-8), 9=574/0-3-8 (min. 0-1-8)
Max Grav 16=530(LC 3), 9=574(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 16-17=-528/0, 1-17=-527/0, 1-2=-532/0, 2-3=-1302/0, 3-4=-1543/0, 4-5=-1297/0, 5-6=-535/0
BOT CHORD 14-15=0/1053, 13-14=0/1543, 12-13=0/1543, 11-12=0/1543, 10-11=0/1046
WEBS 6-9=-615/0, 3-14=-395/0, 2-14=0/334, 2-15=-678/0, 1-15=0/674, 4-11=-400/0, 5-11=0/338, 5-10=-666/0, 6-10=0/707

- NOTES-** (4-7)
- Unbalanced floor live loads have been considered for this design.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



3/1/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC
24-1170-F02	F04	Floor	1	1	
Job Reference (optional)					# 46042

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:35 2024 Page 1
ID:C6coucD2lwHaZ3sGy11mE3yowb3-02hHWlfuxHhF1CE719h4zwcXY0Fd3gAC3ISZoOzeGw2





Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge], [17:Edge,0-1-8]	
LOADING (psf)	SPACING- 1-7-3
TCLL 40.0	Plate Grip DOL 1.00
TCDL 10.0	Lumber DOL 1.00
BCLL 0.0	Rep Stress Incr YES
BCDL 5.0	Code IRC2021/TPI2014
	CSI.
	TC 0.27
	BC 0.46
	WB 0.33
	Matrix-SH
	DEFL. in (loc) l/defl L/d
	Vert(LL) -0.07 14-15 >999 480
	Vert(CT) -0.09 14-15 >999 360
	Horz(CT) 0.02 10 n/a n/a
	PLATES MT20
	GRIP 244/190
	Weight: 75 lb FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)


BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 10-11,9-10.

REACTIONS. (lb/size) 17=517/0-3-6 (min. 0-1-8), 10=727/0-3-8 (min. 0-1-8)
Max Grav 17=527(LC 3), 10=727(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 17-18=-525/0, 1-18=-524/0, 1-2=-529/0, 2-3=-1292/0, 3-4=-1526/0, 4-5=-1275/0, 5-6=-503/0
BOT CHORD 15-16=0/1047, 14-15=0/1526, 13-14=0/1526, 12-13=0/1526, 11-12=0/1017
WEBS 6-10=-707/0, 3-15=-387/0, 2-15=0/328, 2-16=-674/0, 1-16=0/670, 4-12=-440/0, 5-12=0/366, 5-11=-672/0, 6-11=0/684

- NOTES-** (4-7)
- Unbalanced floor live loads have been considered for this design.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard




3/1/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D*Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC
24-1170-F02	F05	Floor	1	1	
					# 46042

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:36 2024 Page 1
 ID: C6coucD2lwHaZ3sGy11mE3yowb3-UEFjdfWibq6eMpJasCJV79hEPauo65MlxB7KqzeGw1



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.33	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.53	Vert(LL) -0.08 16-17 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.35	Vert(CT) -0.10 16-17 >999 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.02 12 n/a n/a		
	Code IRC2021/TPI2014			Weight: 83 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)


BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. (lb/size) 19=485/0-3-6 (min. 0-1-8), 12=900/0-3-8 (min. 0-1-8)
 Max Grav 19=519(LC 3), 12=900(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 19-20=-516/0, 1-20=-515/0, 1-2=-519/0, 2-3=-1260/0, 3-4=-1475/0, 4-5=-1204/19, 5-6=-411/328
 BOT CHORD 17-18=0/1028, 16-17=0/1475, 15-16=0/1475, 14-15=0/1475, 13-14=-165/934, 12-13=-511/0, 11-12=-509/0, 10-11=-509/0
 WEBS 6-12=-882/0, 3-17=-362/53, 2-17=0/313, 2-18=-662/0, 1-18=0/657, 4-14=-533/0, 5-14=0/425, 5-13=-711/0, 6-13=0/727,
 6-10=0/342, 7-10=-301/0

- NOTES-** (4-7)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 3) CAUTION. Do not erect truss backwards.
 - 4) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - 5) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - 6) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - 7) SEE BCSI-B3 SUMMARY SHEET - PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard




3/1/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-1170-F02	Truss F06	Truss Type Floor	Qty 3	Ply 1	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 46042
--------------------	--------------	---------------------	----------	----------	---

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:37 2024 Page 1
ID:C6coud2lwHaZ3sGy11mE3yowb3-zQp1xzg8TuyzGWOW8akY2LisspxyXZ7VWbxsGzeGwO



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.28	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.47	Vert(LL) -0.07 17-18 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.36	Vert(CT) -0.10 17-18 >999 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.01 12 n/a n/a		
	Code IRC2021/TPI2014			Weight: 84 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)


BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. (lb/size) 20=469/0-3-6 (min. 0-1-8), 12=961/0-3-8 (min. 0-1-8), 10=-22/0-3-8 (min. 0-1-8)
Max Uplift 10=-139(LC 3)
Max Grav 20=471(LC 3), 12=961(LC 1), 10=111(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 20-21=-466/0, 1-21=-465/0, 1-2=-464/0, 2-3=-1088/0, 3-4=-1195/0, 4-5=-817/0, 5-6=-115/292, 6-7=-115/292, 7-8=0/424
BOT CHORD 18-19=0/921, 17-18=0/1195, 16-17=0/1195, 15-16=0/1195, 14-15=0/480, 13-14=0/480, 12-13=-791/0, 11-12=-787/0
WEBS 7-12=-944/0, 2-19=-596/0, 1-19=0/587, 4-15=-492/0, 5-15=0/445, 5-13=-745/0, 7-13=0/757, 7-11=0/457, 8-11=-411/0, 8-10=-135/252

- NOTES-** (5-8)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 139 lb uplift at joint 10.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) CAUTION. Do not erect truss backwards.
 - 5) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - 6) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - 7) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - 8) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



3/1/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D*Onofrio Drive, Madison, WI 53719.





Plate Offsets (X,Y)-- [1:Edge,0-1-8], [7:0-1-8,Edge], [8:0-1-8,Edge], [11:0-1-8,Edge], [23:Edge,0-1-8]					
LOADING (psf)	SPACING-	CSI.	DEFL.		PLATES GRIP
TCLL 40.0	1-4-0 Plate Grip DOL 1.00	TC 0.43	in (loc) l/defl L/d		MT20 244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.99	Vert(LL) -0.32 18 >736 480		MT20HS 187/143
BCLL 0.0	Rep Stress Incr YES	WB 0.49	Vert(CT) -0.44 18-19 >535 360		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH	Horz(CT) 0.06 12 n/a n/a		Weight: 100 lb FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 2-2-0 oc bracing: 18-19,17-18.

REACTIONS. (lb/size) 23=718/0-3-8 (min. 0-1-8), 12=718/0-3-0 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 23-24=-715/0, 1-24=-714/0, 12-25=-714/0, 11-25=-713/0, 1-2=-855/0, 2-3=-2137/0, 3-4=-2137/0, 4-5=-2994/0, 5-6=-2994/0, 6-7=-3356/0, 7-8=-3344/0, 8-9=-2961/0, 9-10=-2139/0, 10-11=-854/0
 BOT CHORD 21-22=0/1614, 20-21=0/2638, 19-20=0/3277, 18-19=0/3344, 17-18=0/3344, 16-17=0/3344, 15-16=0/2637, 14-15=0/2637, 13-14=0/1614
 WEBS 1-22=0/1037, 2-22=-987/0, 2-21=0/681, 4-21=-652/0, 4-20=0/455, 6-20=-361/0, 6-19=-49/276, 8-16=-623/0, 9-16=0/468, 9-14=-648/0, 10-14=0/684, 10-13=-988/0, 11-13=0/1036, 7-19=-288/250

NOTES- (4)
 1) Unbalanced floor live loads have been considered for this design.
 2) All plates are MT20 plates unless otherwise indicated.
 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



3/1/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D*Onofrio Drive, Madison, WI 53719.

Job 24-1170-F02	Truss F08	Truss Type Floor	Qty 3	Ply 1	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 46042
--------------------	--------------	---------------------	----------	----------	---

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:40 2024 Page 1
ID:C6cocucD2lwHaZ3sGy11mE3yowb3-N?U9Z?i1lpKY7z65piHFzJKt0v4kTyCZ9KSbzeGvz





Plate Offsets (X,Y)-- [7:0-1-8,Edge], [8:0-1-8,Edge], [12:0-1-8,Edge], [23:0-1-8,Edge], [24:0-1-8,Edge], [25:Edge,0-1-8]					
LOADING (psf)	SPACING- 1-4-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.48	Vert(LL) -0.17 16-17 >999 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.70	Vert(CT) -0.22 16-17 >807 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.39	Horz(CT) 0.03 13 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH			Weight: 101 lb FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. (lb/size) 25=99/0-3-8 (min. 0-1-8), 13=530/0-3-0 (min. 0-1-8), 22=809/0-3-8 (min. 0-1-8)
Max Horz 25=26(LC 4)
Max Uplift 25=-49(LC 11), 13=-46(LC 7)
Max Grav 25=157(LC 12), 13=549(LC 18), 22=809(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 13-27=-546/48, 12-27=-545/47, 2-3=-311/289, 3-4=-435/442, 4-5=-664/364, 5-6=-1327/11, 6-7=-1403/180, 7-8=-1789/0, 8-9=-1817/0, 9-10=-1450/0, 10-11=-1450/0, 11-12=-625/44
BOT CHORD 22-23=-455/225, 21-22=-452/226, 20-21=0/1105, 19-20=0/963, 18-19=-207/1882, 17-18=0/1789, 16-17=0/1789, 15-16=0/1750, 14-15=-25/1139
WEBS 7-18=-124/260, 4-22=-839/0, 4-23=-93/440, 4-21=-77/852, 5-21=-760/90, 5-19=-105/544, 8-16=-436/441, 9-16=-249/347, 9-15=-475/144, 11-15=-135/505, 11-14=-744/119, 12-14=-93/787, 7-19=-908/379

- NOTES-** (6)
- Unbalanced floor live loads have been considered for this design.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 49 lb uplift at joint 25 and 46 lb uplift at joint 13.
 - This truss has been designed for a total drag load of 125 plf. Lumber DOL=(1.33) Plate grip DOL=(1.33) Connect truss to resist drag loads along bottom chord from 4-8-12 to 19-11-8 for 163.8 plf.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard




3/1/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-1170-F02	Truss F09	Truss Type Floor	Qty 1	Ply 1	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC	Job Reference (optional) # 46042
--------------------	--------------	---------------------	----------	----------	---	--

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:42 2024 Page 1
ID:C6coucD2lwHaZ3sGy11mE3yowb3-JOcW_hkHHRaGNHGTX7JjOPjbqe8CqNEgteRXUzeGvx



5-2-10	6-2-10	7-2-10	12-3-10	16-2-10	20-3-6
5-2-10	1-0-0	1-0-0	5-1-0	3-11-0	4-0-12
Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge], [24:Edge,0-1-8]					

LOADING (psf)	SPACING-	1-7-3	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.28	Vert(LL)	-0.07 21-22	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.47	Vert(CT)	-0.10 21-22	>999	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.36	Horz(CT)	0.01 16	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
									Weight: 105 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. All bearings 0-3-8 except (jt=length) 24=0-3-6.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 12 except 24=471(LC 5), 16=940(LC 3), 14=350(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 24-25=-466/0, 1-25=-465/0, 1-2=-464/0, 2-3=-1088/0, 3-4=-1196/0, 4-5=-818/0, 5-6=-117/290, 6-7=-117/290, 7-8=0/468
BOT CHORD 22-23=0/921, 21-22=0/1196, 20-21=0/1196, 19-20=0/1196, 18-19=0/481, 17-18=0/481, 16-17=-788/0, 15-16=-784/0, 14-15=-255/58
WEBS 7-16=-922/0, 9-14=-256/0, 2-23=-596/0, 1-23=0/587, 4-19=-491/0, 5-19=0/445, 5-17=-744/0, 7-17=0/755, 7-15=0/398, 8-15=-359/0, 8-14=-155/267

- NOTES-** (4-7)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 3) CAUTION, Do not erect truss backwards.
 - 4) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - 5) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - 6) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - 7) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard





3/1/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-1170-F02	Truss F10	Truss Type Floor	Qty 1	Ply 1	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC	# 46042
--------------------	--------------	---------------------	----------	----------	---	---------

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:43 2024 Page 1
ID: C6coucD2lwHaZ3sGy11mE3yowb3-naAIB1lv2ki7_RrgVqryHcxu_E_1xHeOvXO_3wzeGvw



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.30	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.49	Vert(LL) -0.07 21-22 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.36	Vert(CT) -0.10 21-22 >999 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.01 12 n/a n/a		
	Code IRC2021/TPI2014				Weight: 104 lb FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)


BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. (lb/size) 24=462/0-3-6 (min. 0-1-8), 12=234/0-3-8 (min. 0-1-8), 16=1055/0-3-8 (min. 0-1-8)
Max Grav 24=473(LC 3), 12=295(LC 4), 16=1055(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 24-25=-468/0, 1-25=-467/0, 12-26=-291/0, 11-26=-291/0, 1-2=-466/0, 2-3=-1096/0, 3-4=-1208/0, 4-5=-835/0,
5-6=-1/353, 6-7=-1/353, 7-8=-64/449, 8-9=-477/152, 9-10=-477/152, 10-11=-275/20
BOT CHORD 22-23=0/926, 21-22=0/1208, 20-21=0/1208, 19-20=0/1208, 18-19=-4/501, 17-18=-4/501, 16-17=-857/0, 15-16=-852/0,
14-15=-292/385, 13-14=-59/505
WEBS 7-16=-1035/0, 2-23=-599/0, 1-23=0/590, 4-19=-511/0, 5-19=0/458, 5-17=-742/0, 7-17=0/754, 7-15=0/568, 8-15=-523/0,
10-13=-299/51, 11-13=-25/331

- NOTES-** (4-7)
- Unbalanced floor live loads have been considered for this design.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard




3/1/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.


Job 24-1170-F02	Truss F12	Truss Type Floor	Qty 2	Ply 1	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 46042
--------------------	--------------	---------------------	----------	----------	---

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:44 2024 Page 1
ID:C6coucD2lwHaZ3sGy11mE3yowb3-FnkgPNmXp2qzcbQs2YMBqpU_aeDBgjKX7B7YbMzeGvv



0-1-8

Scale = 1:23.1



LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES		GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.63	Vert(LL)	-0.18	11-12	>918	L/d	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.88	Vert(CT)	-0.24	11-12	>679	L/d	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.39	Horz(CT)	0.03	8	n/a	n/a			
BCDL	5.0	Code IRC2021/TPI2014		Matrix-SH								Weight: 70 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 15=608/Mechanical, 8=603/0-3-0 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-15=-584/0, 8-16=-600/0, 7-16=-599/0, 1-2=-647/0, 2-3=-1848/0, 3-4=-1848/0, 4-5=-1966/0, 5-6=-1613/0, 6-7=-684/0
 BOT CHORD 13-14=0/1288, 12-13=0/1848, 11-12=0/1848, 10-11=0/1937, 9-10=0/1278
 WEBS 3-13=-291/0, 1-14=0/812, 2-14=-834/0, 2-13=0/782, 4-11=-129/255, 5-10=-423/0, 6-10=0/436, 6-9=-772/0, 7-9=0/828

- NOTES-** (5)
- Unbalanced floor live loads have been considered for this design.
 - Refer to girder(s) for truss to truss connections.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



3/1/2024


Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-1170-F02	Truss F13	Truss Type Floor Supported Gable	Qty 1	Ply 1	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 46042
--------------------	--------------	-------------------------------------	----------	----------	---

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:45 2024 Page 1
ID:lovufdhNr7VckecRyt1FFyBNDc-kzl2cim9aMyqEI?2cFtQM11IE1m5PGEhMrt58pzeGvu

0-1-8

Scale: 1/2"=1'



LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	13	n/a	n/a		
BCDL	5.0	Code IRC2021/TPI2014		Matrix-SH							Weight: 65 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)
OTHERS 2x4 SP No.3(flat)


BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 14-8-12.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 24, 13, 23, 22, 21, 20, 19, 18, 17, 16, 15, 14

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (6)
- Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1'-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION. Do not erect truss backwards.

LOAD CASE(S) Standard





3/1/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC
24-1170-F02	F14	Floor	1	1	# 46042

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:46 2024 Page 1
 ID:C6coucD2lwHaZ3sGy11mE3yowb3-C9sRq2noL4hruaEAzOfvEZOOR_58fXqbVcegFzeGvt



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.35	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.53	Vert(LL) -0.08 21-22 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.29	Vert(CT) -0.10 21-22 >999 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.02 13 n/a n/a		
	Code IRC2021/TPI2014			Weight: 104 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)


BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 17-19,16-17.

REACTIONS. (lb/size) 24=425/0-3-6 (min. 0-1-8), 17=979/0-5-8 (min. 0-1-8), 13=348/0-3-8 (min. 0-1-8)
 Max Grav 24=443(LC 3), 17=979(LC 1), 13=379(LC 7)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 24-25=-438/0, 1-25=-437/0, 1-2=-432/0, 2-3=-989/0, 3-4=-1037/0, 4-5=-588/25, 5-6=0/602, 6-7=-262/124,
 7-8=-262/124, 8-9=-767/0, 9-10=-767/0, 10-11=-666/0
 BOT CHORD 22-23=0/860, 21-22=0/1037, 20-21=0/1037, 19-20=0/1037, 16-17=-602/0, 15-16=0/622, 14-15=0/826, 13-14=0/479
 WEBS 6-17=-526/0, 2-23=-557/0, 1-23=0/546, 4-19=-629/0, 5-19=0/529, 5-17=-650/0, 6-16=0/599, 8-16=-551/0, 8-15=0/266,
 11-13=-584/0

- NOTES-** (4-7)
- Unbalanced floor live loads have been considered for this design.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION. Do not erect truss backwards.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard





3/1/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-1170-F02	Truss F15	Truss Type FLOOR GIRDER	Qty 1	Ply 1	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 46042
--------------------	--------------	----------------------------	----------	----------	---

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:47 2024 Page 1
ID:lovsufdhNr7VckecRyt1FFyBNDc-gMQp1OoQ6zCYT29RkgvuSS6SCrEPtzV_q9MCCzheGvs



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	2-3-0	TC 0.80	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.91	Vert(LL) -0.20 15-16 >864 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.88	Vert(CT) -0.28 15-16 >614 360		
BCDL 5.0	Rep Stress Incr NO	Matrix-SH	Horz(CT) 0.05 13 n/a n/a		
	Code IRC2021/TPI2014			Weight: 79 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD 2-0-0 oc purlins (6-0-0 max.), except end verticals (Switched from sheeted: Spacing > 2-0-0).
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 20=1152/Mechanical, 13=1274/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-20=-1145/0, 13-21=-1267/0, 12-21=-1265/0, 1-2=-1495/0, 2-22=-1495/0, 3-22=-1495/0, 3-4=-3265/0, 4-5=-3265/0, 5-6=-3863/0, 6-7=-3863/0, 7-8=-3863/0, 8-23=-3334/0, 9-23=-3334/0, 9-10=-3334/0, 10-11=-1541/0, 11-24=-1541/0, 12-24=-1541/0
BOT CHORD 18-19=0/2503, 17-18=0/3680, 16-17=0/3863, 15-16=0/3740, 14-15=0/2579
WEBS 6-17=-426/0, 1-19=0/1846, 2-19=-256/0, 3-19=-1288/0, 3-18=0/972, 4-18=-264/0, 5-18=-530/0, 12-14=0/1839, 11-14=-268/0, 10-14=-1324/0, 10-15=0/965, 8-15=-517/0, 5-17=0/588, 8-16=-8/312

NOTES- (9)
1) Unbalanced floor live loads have been considered for this design.
2) Refer to girder(s) for truss to truss connections.
3) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
5) CAUTION, Do not erect truss backwards.
6) Use Simpson Strong-Tie THA422 (Single Chord Girder) or equivalent spaced at 5-11-8 oc max. starting at 2-0-12 from the left end to 14-0-4 to connect truss(es) F16 (1 ply 2x4 SP) to front face of top chord.
7) Fill all nail holes where hanger is in contact with lumber.
8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 13-20=-11, 1-12=-113
Concentrated Loads (lb)
Vert: 4=-118(F) 10=-118(F) 22=-120(F) 23=-118(F) 24=-166(F)




3/1/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-1170-F02	Truss F16	Truss Type FLOOR	Qty 5	Ply 1	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 46042
--------------------	--------------	---------------------	----------	----------	---

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:48 2024 Page 1
ID:lovzufdhNr7VcckecRyt1FFyBNDc-8YzBFkp2tHKP5CkdHOQ7_ffOFojcdG72p5lk7zeGv
3x6 =



Scale = 1:8.5

Plate Offsets (X,Y)-- [5:Edge,0-1-8]

LOADING (psf)	SPACING-	4-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.64	Vert(LL)	-0.00	4	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	-0.00	5	>999	360		
BCLL 0.0	Rep Stress Incr	NO	WB 0.01	Horz(CT)	0.00	3	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-P							
									Weight: 16 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD 2-0-0 oc purlins, except end verticals
(Switched from sheeted: Spacing > 2-0-0).
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 5=235/0-3-8 (min. 0-1-8), 3=247/Mechanical

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (5)
- 1) Refer to girder(s) for truss to truss connections.
 - 2) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard




3/1/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-1170-F02	Truss F17	Truss Type Floor	Qty 11	Ply 1	LOT 0.0003 HONEYCUTT HILLS 53 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 46042
--------------------	--------------	---------------------	-----------	----------	---

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Mon Mar 4 15:26:49 2024 Page 1
ID:C6coucD2lwHaZ3sGy11mE3yowb3-ckXZS4pgeaSGiMlpr5xMxTBwOf?KL?KGHTTrJHazeGvq



Scale: 1/2"=1'




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [4:0-1-8,Edge], [5:0-1-8,Edge]					
LOADING (psf)	SPACING- 1-7-3	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.31	Vert(LL) -0.12 11-12 >999 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.63	Vert(CT) -0.16 11-12 >999 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.35	Horz(CT) 0.03 9 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH			Weight: 74 lb FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 16=636/Mechanical, 9=631/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1074/0, 3-4=-1888/0, 4-5=-2183/0, 5-6=-1988/0, 6-7=-1284/0
 BOT CHORD 15-16=0/517, 14-15=0/1605, 13-14=0/2183, 12-13=0/2183, 11-12=0/2183, 10-11=0/1768, 9-10=0/775
 WEBS 4-14=-493/0, 3-14=0/396, 3-15=-691/0, 2-15=0/725, 2-16=-815/0, 5-11=-405/0, 6-11=0/339, 6-10=-629/0, 7-10=0/663, 7-9=-973/0

- NOTES-** (5-8)
- Unbalanced floor live loads have been considered for this design.
 - Refer to girder(s) for truss to truss connections.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION. Do not erect truss backwards.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET - PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



3/1/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.