

Mark Morris, P.E.

#126, 1317-M, Summerville, SC 29483

843 209-5784, Fax (866)-213-4614

The truss drawing(s) listed below have been prepared by **Atlantic Building Components** under my direct supervision based on the parameters provided by the truss designers.

AST #: 47608

JOB: 24-3026-F01

JOB NAME: LOT 0.0042 HONEYCUTT HILLS

Wind Code: N/A

Wind Speed: Vult= N/A

Exposure Category: N/A

Mean Roof Height (feet): N/A

These truss designs comply with IRC 2015 as well as IRC 2018.

23 Truss Design(s)

Trusses:

F1-01, F1-02, F1-03, F1-04, F1-05, F1-06, F1-08, F1-09, F1-10, F1-11, F1-12, F1-12A, F1-13, F1-14, F1-15, F1-16, F1-17, F1-18, F1-19, F1-20, F1-21, F1-27, F1-28



4/15/2024

Mark Morris

Warning !—Verify design parameters and read notes before use.

This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for*

Job 24-3026-F01	Truss F1-01	Truss Type Floor Supported Gable	Qty 1	Ply 1	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 47608
--------------------	----------------	-------------------------------------	----------	----------	--

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:13 2024 Page 1
ID:5fxLxLn?C6dWjia?SHK4thzkcYI-KLTQMN5hlsRi_plbAc0zpSWIHqzL94LaJjKwBxZQ1yC

0₁-8

Scale = 1:21.5




Plate Offsets (X,Y)-- [5:0-1-8,Edge], [17:0-1-8,Edge], [22:Edge,0-1-8]					
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.06	Vert(LL) n/a - n/a 999	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.01	Vert(CT) n/a - n/a 999		
BCLL 0.0	Rep Stress Incr YES	WB 0.03	Horz(CT) 0.00 12 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH		Weight: 55 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)
 OTHERS 2x4 SP No.3(flat)


BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 13-1-12.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 22, 12, 21, 20, 19, 18, 17, 16, 15, 14, 13

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (6)
 1) Gable requires continuous bottom chord bearing.
 2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 3) Gable studs spaced at 1-4-0 oc.
 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 5) CAUTION. Do not erect truss backwards.

LOAD CASE(S) Standard






4/15/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-02	Floor	5	1	
Job Reference (optional)					# 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:14 2024 Page 1
ID:5fxLxLn?C6dWjia?SHK4thzkcYI-oY1oaj6J3AZZbytoJXCMg2OPM2FuPjYn447zzQ1yB



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.35	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.54	Vert(LL) -0.12 11 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.53	Vert(CT) -0.17 11 >938 360		
BCDL 5.0	Rep Stress Incr NO	Matrix-SH	Horz(CT) 0.03 8 n/a n/a		
	Code IRC2021/TPI2014			Weight: 66 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 14=703/0-7-8 (min. 0-1-8), 8=1109/0-4-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 14-15=-698/0, 1-15=-696/0, 7-8=-1102/0, 1-2=-940/0, 2-3=-2158/0, 3-4=-2605/0, 4-5=-2605/0, 5-6=-2166/0, 6-7=-950/0
BOT CHORD 12-13=0/1759, 11-12=0/2521, 10-11=0/2523, 9-10=0/1772
WEBS 1-13=0/1070, 2-13=-1000/0, 2-12=0/487, 3-12=-443/0, 5-10=-436/0, 6-10=0/481, 6-9=-1004/0, 7-9=0/1121

- NOTES-** (4)
1) Load case(s) 1, 2 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
3) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-14=-10, 1-7=-100
Concentrated Loads (lb)
Vert: 7=-400
2) Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-14=-10, 1-7=-100
Concentrated Loads (lb)
Vert: 7=-400






4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D*Onofrio Drive, Madison, WI 53719.

Job 24-3026-F01	Truss F1-04	Truss Type Floor	Qty 8	Ply 1	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 47608
--------------------	----------------	---------------------	----------	----------	--

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:14 2024 Page 1
ID:5fxLxLn?C6dWjja?SHK4thzkcYI-oY1oaj6J3AZZbytoJXCMg2PCM1ZuPOjYN447zzQ1yB



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.30	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.58	Vert(LL) -0.16 12 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.56	Vert(CT) -0.22 11-12 >764 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.04 9 n/a n/a		
	Code IRC2021/TPI2014			Weight: 71 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 15=758/0-7-8 (min. 0-1-8), 9=764/0-4-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 15-16=-753/0, 1-16=-751/0, 1-2=-1026/0, 2-3=-2400/0, 3-4=-3005/0, 4-5=-3005/0, 5-6=-2721/0, 6-7=-1692/0
BOT CHORD 13-14=0/1923, 12-13=0/2841, 11-12=0/3013, 10-11=0/2396, 9-10=0/950
WEBS 1-14=0/1168, 2-14=-1095/0, 2-13=0/583, 3-13=-539/0, 5-11=-356/0, 6-11=0/398, 6-10=-859/0, 7-10=0/905, 7-9=-1196/0

NOTES- (3)
1) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
2) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-05	Floor Supported Gable	1	1	Job Reference (optional) # 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:14 2024 Page 1
 ID:5fxLxLn?C6dWjja?SHK4thzkcYl-oY1oaj6J3AZZbytoJXCMg2T0MAuXbjYN447zzQ1yB

0-1-8

Scale = 1:23.2




Plate Offsets (X,Y)-- [6:0-1-8,Edge], [18:0-1-8,Edge], [24:Edge,0-1-8]					
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.06	Vert(LL) n/a - n/a 999	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.01	Vert(CT) n/a - n/a 999		
BCLL 0.0	Rep Stress Incr YES	WB 0.03	Horz(CT) 0.00 13 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH		Weight: 59 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)
 OTHERS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 14-1-12.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 24, 13, 23, 22, 21, 20, 19, 18, 17, 16, 15, 14

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (6)
 1) Gable requires continuous bottom chord bearing.
 2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 3) Gable studs spaced at 1-4-0 oc.
 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 5) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



4/15/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-3026-F01	Truss F1-06	Truss Type GABLE	Qty 1	Ply 1	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 47608
--------------------	----------------	---------------------	----------	----------	--

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:14 2024 Page 1
ID:5fxLxLn?C6dWjia?SHK4thzkcY1-oY1oaj6J3AZZbytoJXCMg2SdMAYuXVjYn447zzQ1yB

Scale = 1:12.7




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [3:0-1-8,Edge], [9:0-1-8,Edge], [12:Edge,0-1-8]					
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.08	Vert(LL) n/a - n/a 999	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.01	Vert(CT) n/a - n/a 999		
BCLL 0.0	Rep Stress Incr YES	WB 0.04	Horz(CT) -0.00 9 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-P		Weight: 32 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)
OTHERS 2x4 SP No.3(flat)


BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-11-12 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 6-11-12.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 12, 7, 11, 10, 9, 8

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (5)
1) Gable requires continuous bottom chord bearing.
2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
3) Gable studs spaced at 1-4-0 oc.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-08	Floor	3	1	# 47608


Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:15 2024 Page 1
 ID:5fxLxLn?C6dWjia?SHK4thzkcYI-GkbAn37xqUHQD6S_H12RutbZFMYSYduasn1pdgQzQ1yA

1-3-0

1-4-8

0-10-10

Scale = 1:37.9



LOADING (psf)	SPACING-	1-4-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.35	Vert(LL)	-0.06	22	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.28	Vert(CT)	-0.08	22	>999	360		
BCLL 0.0	Rep Stress Incr	NO	WB 0.43	Horz(CT)	0.01	18	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH							
										Weight: 115 lb FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)


BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. (lb/size) 25=384/0-7-8 (min. 0-1-8), 12=641/0-4-6 (min. 0-1-8), 18=1653/0-4-8 (min. 0-1-8)
 Max Grav 25=405(LC 3), 12=702(LC 4), 18=1653(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-25=-400/0, 11-12=-700/0, 1-2=-517/0, 2-3=-1144/0, 3-4=-1217/0, 4-5=-1217/0, 5-6=-750/59, 6-7=0/514, 7-8=0/779,
 8-9=-544/384, 9-10=-676/123, 10-11=-278/10
 BOT CHORD 23-24=0/969, 22-23=0/1296, 21-22=0/1111, 20-21=0/1111, 19-20=-210/380, 18-19=-1296/0, 17-18=-1305/0,
 16-17=-567/339, 15-16=-567/339, 14-15=-228/724, 13-14=-42/604
 WEBS 7-18=-1624/0, 1-24=0/613, 2-24=-551/0, 5-20=-474/0, 6-20=0/491, 6-19=-793/0, 7-19=0/907, 7-17=0/704, 8-17=-653/0,
 8-15=0/363, 9-15=-331/0, 10-13=-397/39, 11-13=-14/368

NOTES- (5)
 1) Unbalanced floor live loads have been considered for this design.
 2) Load case(s) 1, 2, 3, 4, 5, 6 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 4) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard
 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 12-25=-7, 1-11=-67
 Concentrated Loads (lb)
 Vert: 7=-600 11=-400
 2) Dead: Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 12-25=-7, 1-11=-67
 Concentrated Loads (lb)
 Vert: 7=-600 11=-400
 3) 1st Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 12-25=-7, 1-7=-67, 7-11=-13
 Concentrated Loads (lb)
 Vert: 7=-600 11=-400



4/15/2024

Continued on Page 2 Design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 National Design Standard for Metal Plate Connected Wood Truss Construction and BCSI 1-03 Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-08	Floor	3	1	Job Reference (optional) # 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:15 2024 Page 2
ID:5fxLxLn?C6dWjia?SHK4thzkcYI-GkbAn37xqUhQD6S_H12RutbZFMsmSYduasn1pdgQzQ1yA

LOAD CASE(S) Standard

4) 2nd Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00

Uniform Loads (plf)

Vert: 12-25=-7, 1-7=-13, 7-11=-67

Concentrated Loads (lb)

Vert: 7=-600 11=-400

5) 3rd unbalanced Dead: Lumber Increase=1.00, Plate Increase=1.00

Uniform Loads (plf)

Vert: 12-25=-7, 1-7=-67, 7-11=-13

Concentrated Loads (lb)

Vert: 7=-600 11=-400

6) 4th unbalanced Dead: Lumber Increase=1.00, Plate Increase=1.00

Uniform Loads (plf)

Vert: 12-25=-7, 1-7=-13, 7-11=-67

Concentrated Loads (lb)

Vert: 7=-600 11=-400




4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-09	Floor Supported Gable	1	1	# 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:15 2024 Page 1
 ID:5fxLxLn?C6dWjia?SHK4thzkcYI-GkbAn37xqUHQD6S_H12RutbdemWod_osn1pdgQzQ1yA

Scale = 1:37.3



22-9-2
22-9-2

Plate Offsets (X,Y)-- [1:Edge,0-1-8], [10:0-1-8,Edge], [29:0-1-8,Edge], [38:Edge,0-1-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.07	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	26	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
								Weight: 92 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)
 OTHERS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 22-9-2.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 38, 20, 37, 36, 35, 34, 33, 32, 31, 30, 29, 28, 26, 25, 24, 23, 22, 21

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (5)
 1) Gable requires continuous bottom chord bearing.
 2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 3) Gable studs spaced at 1-4-0 oc.
 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard





4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-10	Floor	6	1	# 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:16 2024 Page 1
 ID:5fxLxLn?C6dWjia?SHK4thzkcyI-kw9Y_P7ZbnqGrG1ArkZgR58fBAoIMKL0?hZACszQ1y9



LOADING (psf)	SPACING-	1-4-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.66	Vert(LL)	-0.06	22	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.31	Vert(CT)	-0.07	22	>999	360		
BCLL 0.0	Rep Stress Incr	NO	WB 0.46	Horz(CT)	0.01	12	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH							
										Weight: 115 lb FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat) *Except* T2: 2x4 SP SS(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 25=362/0-7-8 (min. 0-1-8), 12=435/0-4-8 (min. 0-1-8), 18=2028/0-4-8 (min. 0-1-8)
 Max Grav 25=383(LC 3), 12=497(LC 4), 18=2028(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 25-26=-379/0, 1-26=-378/0, 11-12=-494/0, 1-2=-491/0, 2-3=-1064/0, 3-4=-1087/0,
 4-5=-1087/0, 5-6=-566/236, 6-7=0/745, 7-8=0/810, 8-9=-1003/0, 9-27=-1326/0,
 10-27=-1326/0, 10-11=-536/0
 BOT CHORD 23-24=0/914, 22-23=0/1192, 21-22=-75/955, 20-21=-75/955, 19-20=-414/169,
 18-19=-1549/0, 17-18=-1560/0, 16-17=-390/524, 15-16=-390/524, 14-15=0/1457,
 13-14=0/1174
 WEBS 7-18=-1994/0, 1-24=0/558, 2-24=-516/0, 5-20=-507/0, 6-20=0/525, 6-19=-820/0,
 7-19=0/932, 7-17=0/971, 8-17=-907/0, 8-15=0/698, 9-15=-666/0, 10-13=-778/0,
 11-13=0/706

- NOTES-** (5)
 1) Unbalanced floor live loads have been considered for this design.
 2) Load case(s) 1, 2, 3, 4, 5, 6 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 4) CAUTION, Do not erect truss backwards.

- LOAD CASE(S)**
 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 12-25=-7, 1-11=-67
 Concentrated Loads (lb)
 Vert: 7=-800 27=-350
 2) Dead: Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 12-25=-7, 1-11=-67
 Concentrated Loads (lb)
 Vert: 7=-800 27=-350
 3) 1st Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00



4/15/2024

Continued on Page 2 Design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D*Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-10	Floor	6	1	Job Reference (optional) # 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:16 2024 Page 2
ID:5fxLxLn?C6dWjia?SHK4thzkcYl-kw9Y_P7ZbnqGrG1ArkZgR58fBAoIMKL0?hZACszQ1y9

LOAD CASE(S)

- Uniform Loads (plf)
 - Vert: 12-25=-7, 1-7=-67, 7-11=-13
- Concentrated Loads (lb)
 - Vert: 7=-800 27=-350
- 4) 2nd Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
 - Uniform Loads (plf)
 - Vert: 12-25=-7, 1-7=-13, 7-11=-67
 - Concentrated Loads (lb)
 - Vert: 7=-800 27=-350
- 5) 3rd unbalanced Dead: Lumber Increase=1.00, Plate Increase=1.00
 - Uniform Loads (plf)
 - Vert: 12-25=-7, 1-7=-67, 7-11=-13
 - Concentrated Loads (lb)
 - Vert: 7=-800 27=-350
- 6) 4th unbalanced Dead: Lumber Increase=1.00, Plate Increase=1.00
 - Uniform Loads (plf)
 - Vert: 12-25=-7, 1-7=-13, 7-11=-67
 - Concentrated Loads (lb)
 - Vert: 7=-800 27=-350



4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D*Onofrio Drive, Madison, WI 53719.

Job 24-3026-F01	Truss F1-11	Truss Type Floor	Qty 3	Ply 1	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 47608
--------------------	----------------	---------------------	----------	----------	--

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:16 2024 Page 1
ID:5fxLxLn?C6dWjia?SHK4thzkcYl-kw9Y_P7ZbnqGrG1ArkZgR58ldApAMLp0?hZACszQ1y9





Plate Offsets (X,Y)-- [25:Edge,0-1-8]

LOADING (psf)	SPACING-	1-4-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.31	Vert(LL)	-0.06	22	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.25	Vert(CT)	-0.08	22	>999	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.43	Horz(CT)	0.01	18	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH							
										Weight: 115 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 25=380/0-7-8 (min. 0-1-8), 12=241/0-4-8 (min. 0-1-8), 18=1054/0-4-8 (min. 0-1-8)
Max Grav 25=400(LC 3), 12=303(LC 4), 18=1054(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 25-26=-397/0, 1-26=-396/0, 11-12=-301/0, 1-2=-519/0, 2-3=-1143/0, 3-4=-1216/0, 4-5=-1216/0, 5-6=-748/62,
6-7=0/516, 7-8=0/778, 8-9=-545/384, 9-10=-678/123, 10-11=-281/10
BOT CHORD 23-24=0/967, 22-23=0/1295, 21-22=0/1109, 20-21=0/1109, 19-20=-213/379, 18-19=-1300/0, 17-18=-1306/0,
16-17=-566/339, 15-16=-566/339, 14-15=-228/726, 13-14=-42/607
WEBS 7-18=-1027/0, 1-24=0/589, 2-24=-547/0, 5-20=-475/0, 6-20=0/491, 6-19=-793/0, 7-19=0/909, 7-17=0/706, 8-17=-653/0,
8-15=0/363, 9-15=-332/0, 10-13=-397/39, 11-13=-13/371

- NOTES-** (4)
1) Unbalanced floor live loads have been considered for this design.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
3) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard




4/15/2024


Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-12	Floor	2	1	# 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:17 2024 Page 1
 ID:5fxLxLn?C6dWjia?SHK4thzkcYl-C7ixCl8BM5y7SQbMPR4vzlgvPa875nm9ELIkklzQ1y8



Scale = 1:38.0



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-4-0	TC 0.37	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.27	Vert(LL) -0.06 24 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.45	Vert(CT) -0.08 24 >999 360		
BCDL 5.0	Rep Stress Incr NO	Matrix-SH	Horz(CT) 0.01 14 n/a n/a		
	Code IRC2021/TPI2014			Weight: 119 lb FT = 20%F, 11%E	

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 27=379/0-4-8 (min. 0-1-8), 20=1123/0-4-8 (min. 0-1-8), 14=1081/0-4-8 (min. 0-1-8)
 Max Grav 27=399(LC 3), 20=1123(LC 1), 14=1143(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-27=-395/0, 1-2=-509/0, 2-3=-1121/0, 3-4=-1178/0, 4-5=-1178/0, 5-6=-695/130,
 6-7=0/586, 7-8=0/802, 8-9=-724/218, 9-10=-724/218, 10-11=-991/0, 11-12=-692/0
 BOT CHORD 25-26=0/953, 24-25=0/1265, 23-24=0/1064, 22-23=0/1064, 21-22=-291/319, 20-21=-1412/0,
 19-20=-1421/0, 18-19=-510/397, 17-18=-510/397, 16-17=0/970, 15-16=0/984, 14-15=0/692
 WEBS 7-20=-1095/0, 1-26=0/603, 2-26=-542/0, 5-22=-484/0, 6-22=0/500, 6-21=-804/0,
 7-21=0/948, 7-19=0/809, 8-19=-748/0, 8-17=0/518, 10-17=-403/0, 11-15=-333/158,
 12-14=-1314/0

- NOTES-** (5)
 1) Unbalanced floor live loads have been considered for this design.
 2) Load case(s) 1, 2, 3, 4, 5, 6 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 4) CAUTION, Do not erect truss backwards.

- LOAD CASE(S)**
 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 14-27=-7, 1-13=-67
 Concentrated Loads (lb)
 Vert: 12=-900
 2) Dead: Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 14-27=-7, 1-13=-67
 Concentrated Loads (lb)
 Vert: 12=-900
 3) 1st Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 14-27=-7, 1-7=-67, 7-13=-13
 Concentrated Loads (lb)
 Vert: 12=-900



4/15/2024

Continued on Page 2
 Design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 National Design Standard for Metal Plate Connected Wood Truss Construction and BCSI 1-03 Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-12	Floor	2	1	Job Reference (optional) # 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:17 2024 Page 2
ID:5fxLxLn?C6dWjia?SHK4thzkcYl-C7ixCl8BM5y7SQbMPR4vzlgvPa875nm9ELlkkizQ1y8

LOAD CASE(S)

- 4) 2nd Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
 - Uniform Loads (plf)
 - Vert: 14-27=-7, 1-7=-13, 7-13=-67
 - Concentrated Loads (lb)
 - Vert: 12=-900
- 5) 3rd unbalanced Dead: Lumber Increase=1.00, Plate Increase=1.00
 - Uniform Loads (plf)
 - Vert: 14-27=-7, 1-7=-67, 7-13=-13
 - Concentrated Loads (lb)
 - Vert: 12=-900
- 6) 4th unbalanced Dead: Lumber Increase=1.00, Plate Increase=1.00
 - Uniform Loads (plf)
 - Vert: 14-27=-7, 1-7=-13, 7-13=-67
 - Concentrated Loads (lb)
 - Vert: 12=-900




4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D’Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-12A	Floor	7	1	# 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:17 2024 Page 1
 ID:5fxLxLn?C6dWjia?SHK4thzkcYI-C7ixCl8BM5y7SQbMPR4vzIgtma6t5l_9ELIkklzQ1y8



LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES		GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.47	Vert(LL)	-0.06	25	>999	480	MT20	244/190	
TCDL	10.0	Lumber DOL	1.00	BC	0.42	Vert(CT)	-0.08	16-17	>999	360			
BCLL	0.0	Rep Stress Incr	NO	WB	0.63	Horz(CT)	0.01	13	n/a	n/a			
BCDL	5.0	Code IRC2021/TPI2014		Matrix-SH									Weight: 120 lb FT = 20%F, 11%E

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x4 SP No.3(flat) *Except*		
	W2: 2x4 SP No.2(flat)		

REACTIONS. (lb/size) 28=330/0-4-8 (min. 0-1-8), 21=1944/0-4-8 (min. 0-1-8), 13=1260/0-4-8 (min. 0-1-8)
 Max Grav 28=350(LC 3), 21=1944(LC 1), 13=1322(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-28=-346/0, 1-2=-433/0, 2-3=-905/43, 3-4=-822/254, 4-5=-822/254, 5-6=-194/627,
 6-7=0/1226, 7-8=-340/330, 8-9=-1910/0, 9-10=-1701/0, 10-11=-986/0
 BOT CHORD 26-27=0/807, 25-26=-126/979, 24-25=-410/635, 23-24=-410/635, 22-23=-859/0,
 21-22=-2127/0, 20-21=-2141/0, 19-20=-2141/0, 18-19=0/1853, 17-18=0/1854, 16-17=0/1931,
 15-16=0/1451, 14-15=0/792, 13-14=0/792
 WEBS 7-21=-1897/0, 1-27=0/513, 2-27=-457/4, 5-25=0/261, 5-23=-570/0, 6-23=0/587,
 6-22=-891/0, 7-22=0/1033, 7-19=0/2231, 8-19=-1987/0, 9-16=-280/0, 10-16=0/306,
 10-15=-568/0, 11-15=0/418, 11-13=-1503/0

NOTES- (5)
 1) Unbalanced floor live loads have been considered for this design.
 2) Load case(s) 1, 2, 3, 4, 5, 6 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 4) CAUTION, Do not erect truss backwards.

LOAD CASE(S)
 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 13-28=-7, 1-12=-67
 Concentrated Loads (lb)
 Vert: 8=-950 11=-900
 2) Dead: Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 13-28=-7, 1-12=-67
 Concentrated Loads (lb)
 Vert: 8=-950 11=-900
 3) 1st Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 13-28=-7, 1-7=-67, 7-12=-13



4/15/2024

Continued on Page 2 Design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D*Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-12A	Floor	7	1	Job Reference (optional) # 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:17 2024 Page 2
ID:5fxLxLn?C6dWjia?SHK4thzkcYI-C7ixCl8BM5y7SQbMPR4vzIgtma6t5l_9ELlkkizQ1y8

LOAD CASE(S)

- Concentrated Loads (lb)
Vert: 8=-950 11=-900
- 4) 2nd Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 13-28=-7, 1-7=-13, 7-12=-67
Concentrated Loads (lb)
Vert: 8=-950 11=-900
- 5) 3rd unbalanced Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 13-28=-7, 1-7=-67, 7-12=-13
Concentrated Loads (lb)
Vert: 8=-950 11=-900
- 6) 4th unbalanced Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 13-28=-7, 1-7=-13, 7-12=-67
Concentrated Loads (lb)
Vert: 8=-950 11=-900



4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D*Onofrio Drive, Madison, WI 53719.

Job 24-3026-F01	Truss F1-15	Truss Type Floor	Qty 1	Ply 1	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC	# 47608
--------------------	----------------	---------------------	----------	----------	--	---------

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:18 2024 Page 1
ID:5fxLxLn?C6dWjia?SHK4thzkcYI-gJGJP59q7P4_4aAZy9b8WWd5N_VsqELJT?2HGizQ1y7





Plate Offsets (X,Y)-- [8:0-1-8,Edge], [17:Edge,0-1-8]

LOADING (psf)	SPACING-	1-4-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.29	Vert(LL)	-0.05	14	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.24	Vert(CT)	-0.07	14	>999	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.43	Horz(CT)	0.01	11	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH							
									Weight: 80 lb	FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 17=389/0-3-8 (min. 0-1-8), 9=-348/0-7-8 (min. 0-1-8), 11=1088/0-4-8 (min. 0-1-8)
Max Uplift9=-409(LC 3)
Max Grav 17=389(LC 3), 11=1088(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 17-18=-386/0, 1-18=-385/0, 9-19=0/414, 8-19=0/414, 1-2=-503/0, 2-3=-1090/0, 3-4=-1155/0, 4-5=-1155/0, 5-6=-632/0, 6-7=0/399, 7-8=0/535
BOT CHORD 15-16=0/936, 14-15=0/1219, 13-14=0/986, 11-12=-1178/0, 10-11=-1183/0
WEBS 7-11=-1057/0, 1-16=0/571, 2-16=-529/0, 5-13=-439/0, 6-13=0/472, 6-12=-791/0, 7-12=0/904, 7-10=0/768, 8-10=-654/0

- NOTES-** (5)
- Unbalanced floor live loads have been considered for this design.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 409 lb uplift at joint 9.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-3026-F01	Truss F1-16	Truss Type Floor	Qty 1	Ply 1	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC	Job Reference (optional) # 47608
--------------------	----------------	---------------------	----------	----------	--	--

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:18 2024 Page 1
ID:5fxLxLn?C6dWjia?SHK4thzkcY1-gJGJP59q7P4_4aAZy9b8WWWD2O_NDqBCJT?2HGizQ1y7




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [17:Edge,0-1-8], [19:0-1-8,0-0-8]							
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d
TCLL 40.0	Plate Grip DOL	1.00	TC 0.48	Vert(LL)	-0.24 13-14	>771	480
TCDL 10.0	Lumber DOL	1.00	BC 0.73	Vert(CT)	-0.33 13-14	>559	360
BCLL 0.0	Rep Stress Incr	YES	WB 0.63	Horz(CT)	0.06 10	n/a	n/a
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH				
							PLATES
							MT20
							GRIP
							244/190
							Weight: 80 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 17=846/0-3-8 (min. 0-1-8), 10=846/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 17-18=-841/0, 1-18=-839/0, 1-2=-1163/0, 2-3=-2788/0, 3-4=-3647/0, 4-5=-3647/0, 5-6=-3616/0, 6-7=-2781/0, 7-8=-1878/0
BOT CHORD 15-16=0/2186, 14-15=0/3355, 13-14=0/3798, 12-13=0/3395, 11-12=0/2781, 10-11=0/1026
WEBS 7-12=0/366, 1-16=0/1326, 2-16=-1248/0, 2-15=0/736, 3-15=-691/0, 3-14=0/351, 6-13=0/270, 6-12=-706/0, 7-11=-1070/0, 8-11=0/1039, 8-10=-1319/0

- NOTES-** (3)
1) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
2) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-17	Floor	5	1	Job Reference (optional) # 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:18 2024 Page 1
ID:5fxLxLn?C6dWjia?SHK4thzkcYI-gJGJP59q7P4_4aAZy9b8WWD5S_SeqDeJT?2HGizQ1y7






Plate Offsets (X,Y)-- [7:0-1-8,Edge], [14:Edge,0-1-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.29	Vert(LL)	-0.10	11	>999	480	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.45	Vert(CT)	-0.13	11	>999	360		
BCLL 0.0	Lumber DOL 1.00	WB 0.48	Horz(CT)	0.03	8	n/a	n/a		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH							
	Code IRC2021/TPI2014							Weight: 63 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 14=663/0-3-8 (min. 0-1-8), 8=663/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 14-15=-658/0, 1-15=-656/0, 8-16=-665/0, 7-16=-664/0, 1-2=-877/0, 2-3=-1982/0, 3-4=-2309/0, 4-5=-2309/0, 5-6=-1747/0, 6-7=-459/0
BOT CHORD 12-13=0/1639, 11-12=0/2288, 10-11=0/2179, 9-10=0/1280
WEBS 1-13=0/998, 2-13=-930/0, 2-12=0/418, 3-12=-374/0, 5-10=-527/0, 6-10=0/570, 6-9=-1003/0, 7-9=0/724

NOTES- (2)
1) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D*Onofrio Drive, Madison, WI 53719.


Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-18	GABLE	1	1	Job Reference (optional) # 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:19 2024 Page 1
 ID:5fxLxLn?C6dWjia?SHK4thzkcYI-8VqhdRASuiCrikIIWs7N2jmKjNufZnoSifnqpBzQ1y6

0₁1₈

0₁1₈

Scale = 1:20.4



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	12	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						Weight: 53 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)
 OTHERS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 12-5-0.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 21, 12, 20, 19, 18, 17, 16, 15, 14, 13

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (5)
- Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



4/15/2024


Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-19	GABLE	1	1	Job Reference (optional) # 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:19 2024 Page 1
 ID:5fxLxLn?C6dWjia?SHK4thzkcY1-8VqhdRASuiCrikIiW57N2jmKINulZnqSifnqBzQ1y6

0-1-8

Scale = 1:22.9



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.06	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.01	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Lumber DOL 1.00	WB 0.03	Horz(CT)	0.00	13	n/a		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH					Weight: 59 lb	FT = 20%F, 11%E
	Code IRC2021/TPI2014							

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)
 OTHERS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 13-11-8.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 24, 13, 23, 22, 21, 20, 19, 18, 17, 16, 15, 14

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (6)
- Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION. Do not erect truss backwards.

LOAD CASE(S) Standard



4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-3026-F01	Truss F1-20	Truss Type Floor	Qty 4	Ply 1	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC	# 47608
--------------------	----------------	---------------------	----------	----------	--	---------

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:19 2024 Page 1
ID:5fxLxLn?C6dWjia?SHK4thzkcYI-8VqhdRASuiCrikllWs7N2jmf2NIZZFXSifnqpBzQ1y6






Plate Offsets (X,Y)-- [1:Edge,0-1-8], [15:Edge,0-1-8]					
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.36	Vert(LL) -0.17 11-12 >999 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.59	Vert(CT) -0.23 11-12 >739 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.56	Horz(CT) 0.04 8 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH			Weight: 71 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 15=767/0-7-8 (min. 0-1-8), 8=773/0-4-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 15-16=-762/0, 1-16=-760/0, 1-2=-1038/0, 2-3=-2447/0, 3-4=-3029/0, 4-5=-2818/0, 5-6=-1811/0
 BOT CHORD 13-14=0/1946, 12-13=0/2911, 11-12=0/3120, 10-11=0/3120, 9-10=0/2499, 8-9=0/1084
 WEBS 1-14=0/1182, 2-14=-1108/0, 2-13=0/611, 3-13=-567/0, 4-10=-363/0, 5-10=0/389, 5-9=-840/0, 6-9=0/888, 6-8=-1302/0

NOTES- (3)
 1) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 2) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard




4/15/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-3026-F01	Truss F1-21	Truss Type Floor Girder	Qty 1	Ply 1	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 47608
--------------------	----------------	----------------------------	----------	----------	--

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MITek Industries, Inc. Tue Apr 16 20:55:19 2024 Page 1
ID:5fxLxLn?C6dWjia?SHK4thzkcYl-8VqhdRASuiCrikllWs7N2jml3NoRZdJJSifnqpBzQ1y6



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.17	Vert(LL)	-0.12 12-13	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.41	Vert(CT)	-0.16 12-13	>999	360		
BCLL 0.0	Rep Stress Incr	NO	WB 0.64	Horz(CT)	0.02 8	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
								Weight: 112 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)


BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 17=773/0-7-8 (min. 0-1-8), 8=773/0-4-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-17=-758/0, 7-8=-767/0, 1-2=-1190/0, 2-3=-2824/0, 3-4=-3421/0, 4-5=-3376/0, 5-6=-2521/0, 6-7=-758/0
BOT CHORD 15-16=0/2213, 14-15=0/3199, 13-14=0/3199, 12-13=0/3596, 11-12=0/3183, 10-11=0/3184, 9-10=0/1859
WEBS 3-13=0/255, 4-12=-257/0, 5-12=0/256, 5-10=-758/0, 6-10=0/772, 6-9=-1285/0, 7-9=0/1020, 1-16=0/1346, 2-16=-1194/0, 2-15=0/712, 3-15=-513/0

NOTES- (3)
1) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
2) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.


Job 24-3026-F01	Truss F1-27	Truss Type Floor	Qty 3	Ply 1	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC Job Reference (optional) # 47608
--------------------	----------------	---------------------	----------	----------	--

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:19 2024 Page 1
ID:5fxLxLn?C6dWjia?SHK4thzkcYI-8VqhdRASuiCrikIIWs7N2jmF1NIZZeBSifnqpBzQ1y6

1-3-0

1-2-4

Scale = 1:23.3



LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES		GRIP	
TCLL	40.0	Plate Grip DOL	2-0-0	TC	0.36	Vert(LL)	-0.17	11-12	>999	L/d	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.59	Vert(CT)	-0.23	11-12	>737	L/d	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.58	Horz(CT)	0.04	8	n/a	n/a			
BCDL	5.0	Code IRC2021/TPI2014		Matrix-SH								Weight: 72 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 15=773/0-7-8 (min. 0-1-8), 8=773/0-4-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-15=-766/0, 1-2=-1036/0, 2-3=-2448/0, 3-4=-3029/0, 4-5=-2818/0, 5-6=-1811/0
BOT CHORD 13-14=0/1949, 12-13=0/2911, 11-12=0/3120, 10-11=0/3120, 9-10=0/2499, 8-9=0/1084
WEBS 1-14=0/1227, 2-14=-1115/0, 2-13=0/609, 3-13=-565/0, 4-10=-363/0, 5-10=0/389, 5-9=-840/0, 6-9=0/888, 6-8=-1302/0

- NOTES-** (2-5)
- 1) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 2) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - 3) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - 4) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - 5) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D*Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0042 HONEYCUTT HILLS 170 SHELBY MEADOW LANE ANGIER, NC
24-3026-F01	F1-28	Floor Supported Gable	1	1	Job Reference (optional) # 47608

Run: 8.430 s Feb 12 2021 Print: 8.430 s Feb 12 2021 MiTek Industries, Inc. Tue Apr 16 20:55:20 2024 Page 1
ID:5fxLxLn?C6dWjia?SHK4thzkcY1-dhO3qnB4f0KjItKx4aecbXIVTnD_I3cwJXOLdzQ1y5

Scale = 1:23.2




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [7:0-1-8,Edge], [19:0-1-8,Edge], [24:Edge,0-1-8]					
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.06	Vert(LL) n/a - n/a 999	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.01	Vert(CT) n/a - n/a 999		
BCLL 0.0	Rep Stress Incr YES	WB 0.03	Horz(CT) -0.00 19 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH		Weight: 60 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 14-3-0.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 24, 13, 23, 22, 21, 20, 19, 18, 17, 16, 15, 14

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (5-8)
- Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



4/15/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D*Onofrio Drive, Madison, WI 53719.