

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: BLAKE POND

LOT 99

INITIAL SYSTEM: APPROVED 25% REDUCTION

REPAIR: APPROVED 25% REDUCTION

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION PC 98/99

NO. BEDROOMS: 4

LTAR 0.35 GPO/FT²

SEPTIC TANK SIZE: 1000

PUMP TANK SIZE: NA

LINE	FLAG COLOR	ELEVATION	LENGTH
1	B	106.00	115'
2	R	105.42	115'
3	B	104.92	115'
			<u>345'</u>
4	R	104.84	115'
5	B	104.42	115'
6	R	103.84	115'
			<u>345'</u>

In. full system

BY: M EAKER

DATE 12/2022

TYPICAL PROFILE

0-10 US (UF, wgs)
10-40+ SCL (F, sbl)
or 2 ≥ 34"
INITIAL AT 18"

THERE SHALL BE NO GRADING,
CUTTING, LOGGING OR OTHER SOIL
DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.
 DESIGNS DO NOT GUARANTEE FUNCTIONALITY

Southeastern Soil & Environmental Associates, Inc.

P.O. Box 9321
Fayetteville, NC 28311
Phone/Fax (910) 822-4540
Email mike@southeasternsoil.com

