

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: 3720682
DR HORTON;COLUMBIA;C;MASTER.RT

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Builders FirstSource-Apex,NC.

Pages or sheets covered by this seal: I62834023 thru I62834041

My license renewal date for the state of North Carolina is December 31, 2024.

North Carolina COA: C-0844



January 3, 2024

Gilbert, Eric

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job 3720682	Truss A01G	Truss Type GABLE	Qty 1	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT Job Reference (optional)	162834023
----------------	---------------	---------------------	----------	----------	--	-----------

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:26 2024 Page 1

ID:nEofIS4OxkzImBEk9cc91EyWoyO-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwrcDoi7J4zJC?f

12-9-0	28-9-0	41-9-0	42-5-0
12-9-0	16-0-0	13-0-0	0-8-0

Scale = 1:72.2




Plate Offsets (X,Y)--	[10:0-3-0,0-2-0], [22:0-3-0,0-2-0], [32:0-4-1,Edge]
-----------------------	---

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.04	Vert(LL)	0.00	32	n/r	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	0.00	32	n/r		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.08	Horz(CT)	0.01	32	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S						
								Weight: 351 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3
SLIDER Right 2x4 SP No.1 1-6-7

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 10-22.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 41-9-0.
(lb) - Max Horz 65=100(LC 17)
Max Uplift All uplift 100 lb or less at joint(s) 65, 49, 50, 51, 52, 53, 54, 57, 58, 59, 60, 61, 62, 48, 47, 46, 45, 44, 41, 40, 39, 38, 37, 36, 35, 32 except 63=121(LC 12)
Max Grav All reactions 250 lb or less at joint(s) 65, 49, 50, 51, 52, 53, 54, 56, 57, 58, 59, 60, 61, 62, 63, 64, 48, 47, 46, 45, 44, 42, 41, 40, 39, 38, 37, 36, 35, 34, 32

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) 0-1-12 to 3-1-12, Exterior(2) 3-1-12 to 12-9-0, Corner(3) 12-9-0 to 15-6-8, Exterior(2) 15-6-8 to 28-9-0, Corner(3) 28-9-0 to 31-6-8, Exterior(2) 31-6-8 to 42-5-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) Provide adequate drainage to prevent water ponding.
- 5) All plates are 2x4 MT20 unless otherwise indicated.
- 6) Gable requires continuous bottom chord bearing.
- 7) Gable studs spaced at 1-4-0 oc.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 65, 49, 50, 51, 52, 53, 54, 57, 58, 59, 60, 61, 62, 48, 47, 46, 45, 44, 41, 40, 39, 38, 37, 36, 35, 32 except (jt=lb) 63=121.
- 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.




January 3, 2024

Job 3720682	Truss A02	Truss Type Hip	Qty 1	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT Job Reference (optional)	162834024
----------------	--------------	-------------------	----------	----------	--	-----------

Builders FirstSource (Apex, NC), Apex, NC - 27523, 8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:28 2024 Page 1

ID:nEofIS4OxkzImBEk9cc91EyWoyO-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJc?f



Scale = 1:72.9





Plate Offsets (X,Y)--	[5:0-6-4,Edge], [6:0-6-4,Edge], [9:0-0-0,0-1-9]
-----------------------	---


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.96	Vert(LL)	-0.23 11-13	>999	360	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.77	Vert(CT)	-0.40 13-15	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.25	Horz(CT)	0.10 9	n/a	n/a		
BCDL 10.0	Code IRC2015/TP12014		Matrix-MS	Wind(LL)	0.10 11-13	>999	240	Weight: 248 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1 *Except* 5-6: 2x6 SP DSS, 7-10: 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied, except 2-0-0 oc purlins (4-10-13 max.): 5-6.
BOT CHORD 2x6 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 5-13, 6-13
WEDGE Right: 2x4 SP No.3	
SLIDER Left 2x4 SP No.3 1-11-12	

REACTIONS. (size) 1=Mechanical, 9=0-3-8
 Max Horz 1=-124(LC 13)
 Max Uplift 1=-112(LC 12), 9=-124(LC 13)
 Max Grav 1=1670(LC 1), 9=1710(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-3=-2879/248, 3-5=-2672/270, 5-6=-2193/242, 6-8=-2742/276, 8-9=-2988/252
 BOT CHORD 1-15=-218/2502, 13-15=-72/2047, 11-13=-58/2061, 9-11=-148/2577
 WEBS 3-15=-360/208, 5-15=-61/560, 5-13=-15/369, 6-13=-16/353, 6-11=-69/617,
 8-11=-398/217

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 15-5-0, Exterior(2) 15-5-0 to 19-7-15, Interior(1) 19-7-15 to 26-1-0, Exterior(2) 26-1-0 to 30-3-15, Interior(1) 30-3-15 to 42-5-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=112, 9=124.
 - 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.




January 3, 2024

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbccomponents.com)</p>	<p>ENGINEERING BY TRENCO <small>A MITEK Affiliate</small></p> <p>818 Soundside Road Edenton, NC 27932</p>
---	---

Job 3720682	Truss A03	Truss Type Hip	Qty 1	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT	162834025
----------------	--------------	-------------------	----------	----------	--------------------------------	-----------

Builders FirstSource (Apex, NC), Apex, NC - 27523, 8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:29 2024 Page 1

ID:nEofIS4OxkzImBEk9cc91EyWoyO-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:73.0




Plate Offsets (X,Y)-- [1:0-0-0,0-0-11], [3:0-4-0,0-4-4], [6:0-2-3,0-2-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.53	Vert(LL)	-0.20 12-14	>999	360	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.76	Vert(CT)	-0.35 12-14	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.52	Horz(CT)	0.09 8	n/a	n/a		
BCDL 10.0	Code IRC2015/TP12014		Matrix-MS	Wind(LL)	0.08 12-14	>999	240	Weight: 284 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3


BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-7-11 oc purlins, except 2-0-0 oc purlins (5-1-8 max.): 4-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 4-12, 5-12

REACTIONS. (size) 1=Mechanical, 8=0-3-8
Max Horz 1=-144(LC 13)
Max Uplift 1=-108(LC 12), 8=-121(LC 13)
Max Grav 1=1670(LC 1), 8=1710(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-2941/233, 2-4=-2810/311, 4-5=-2006/256, 5-7=-2892/317, 7-8=-3006/232
BOT CHORD 1-14=-214/2538, 12-14=-30/1934, 10-12=-11/1944, 8-10=-119/2607
WEBS 2-14=-493/265, 4-14=-170/852, 4-12=-66/386, 5-12=-77/378, 5-10=-184/931, 7-10=-522/269

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 18-1-0, Exterior(2) 18-1-0 to 22-3-15, Interior(1) 22-3-15 to 23-5-0, Exterior(2) 23-5-0 to 27-7-15, Interior(1) 27-7-15 to 42-5-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=108, 8=121.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



January 3, 2024

Job 3720682	Truss A05	Truss Type COMMON	Qty 3	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT 162834026
----------------	--------------	----------------------	----------	----------	---

Builders FirstSource (Apex, NC), Apex, NC - 27523, 8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:30 2024 Page 1

ID:fJZOU2ZLpXU3XKYCOPhCD1zheL_RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCdoi7J4zJC?f

-0-8-0	7-2-5	14-1-3	21-0-0	27-10-13	34-9-11	42-0-0	42-8-0
0-8-0	7-2-5	6-10-13	6-10-13	6-10-13	6-10-13	7-2-5	0-8-0

5x6 =

Scale = 1:75.1




Plate Offsets (X,Y)--	[2:0-0-0,0-2-13], [12:0-3-9,0-0-1]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.97	Vert(LL) -0.40 16-18 >999 360	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.92	Vert(CT) -0.70 14-16 >723 240	MT20HS	187/143
BCLL 0.0 *	Rep Stress Incr NO	WB 0.60	Horz(CT) 0.15 12 n/a n/a		
BCDL 10.0	Code IRC2015/TP12014	Matrix-MS	Wind(LL) 0.09 14-16 >999 240	Weight: 224 lb	FT = 20%


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 *Except* 1-5: 2x4 SP No.1, 9-13: 2x4 SP SS	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.1 *Except* 15-17: 2x4 SP SS	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 8-16, 6-16
SLIDER Left 2x4 SP No.3 1-11-12, Right 2x4 SP No.3 1-11-12	

REACTIONS. (size) 2=0-3-8, 12=0-3-8
Max Horz 2=-127(LC 17)
Max Grav 2=2033(LC 1), 12=1768(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-3440/0, 4-6=-3034/0, 6-7=-2055/131, 7-8=-2054/131, 8-10=-2802/107,
10-12=-3035/105
BOT CHORD 2-18=0/2956, 16-18=0/2330, 14-16=0/2240, 12-14=-2/2639
WEBS 7-16=0/1454, 8-16=-744/142, 8-14=0/521, 10-14=-326/146, 6-16=-877/9, 6-18=0/709,
4-18=-544/0

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-8-0 to 2-4-0, Interior(1) 2-4-0 to 21-0-0, Exterior(2) 21-0-0 to 25-2-15, Interior(1) 25-2-15 to 42-8-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - N/A

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15 Uniform Loads (plf) Vert: 1-3=-60, 7-29=-60, 7-13=-60, 19-23=-20 Trapezoidal Loads (plf) Vert: 3=-119-to-29=-70
2) Dead + 0.75 Roof Live (balanced) + 0.75 Uninhab. Attic Storage: Lumber Increase=1.15, Plate Increase=1.15



January 3, 2024

Continued on page 2

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)</p>	<p>818 Soundside Road Edenton, NC 27932</p>
--	---

Job	Truss	Truss Type	Qty	Ply	DR HORTON;COLUMBIA;C;MASTER.RT
3720682	A05	COMMON	3	1	162834026
					Job Reference (optional)

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:30 2024 Page 2
ID:fJZOU2ZLpXU3XKYCOPhCD1zheL_RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

LOAD CASE(S) Standard

Uniform Loads (plf)

Vert: 1-3=-50, 7-29=-50, 7-13=-50, 19-34=-20, 34-35=-50, 35-36=-20, 36-37=-50, 23-37=-20

Trapezoidal Loads (plf)

Vert: 3=-109-to-29=-60

3) Dead + Uninhabitable Attic Without Storage: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-3=-20, 7-29=-20, 7-13=-20, 19-23=-40

Trapezoidal Loads (plf)

Vert: 3=-79-to-29=-30

4) Dead + 0.6 C-C Wind (Pos. Internal) Case 1: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=47, 2-3=25, 7-29=14, 7-31=25, 12-31=14, 12-13=9, 19-23=-12

Horz: 1-2=-59, 2-27=-37, 7-27=-26, 7-31=37, 12-31=26, 12-13=21

Trapezoidal Loads (plf)

Vert: 3=-34-to-27=-30, 27=-41-to-29=4

5) Dead + 0.6 C-C Wind (Pos. Internal) Case 2: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=9, 2-3=14, 29-30=14, 7-30=25, 7-33=14, 12-33=25, 12-13=47, 19-23=-12

Horz: 1-2=-21, 2-30=-26, 7-30=-37, 7-33=26, 12-33=37, 12-13=59

Trapezoidal Loads (plf)

Vert: 3=-45-to-29=4

6) Dead + 0.6 C-C Wind (Neg. Internal) Case 1: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-12, 2-3=-33, 7-29=-33, 7-12=-33, 12-13=-28, 19-23=-20

Horz: 1-2=-8, 2-7=13, 7-12=-13, 12-13=-8

Trapezoidal Loads (plf)

Vert: 3=-92-to-29=-43

7) Dead + 0.6 C-C Wind (Neg. Internal) Case 2: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-28, 2-3=-33, 7-29=-33, 7-12=-33, 12-13=-12, 19-23=-20

Horz: 1-2=8, 2-7=13, 7-12=-13, 12-13=8

Trapezoidal Loads (plf)

Vert: 3=-92-to-29=-43

8) Dead + 0.6 MWFRS Wind (Pos. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=9, 2-3=-2, 7-29=-2, 7-12=9, 12-13=4, 19-23=-12

Horz: 1-2=-21, 2-7=-10, 7-12=21, 12-13=16

Trapezoidal Loads (plf)

Vert: 3=-61-to-29=-12

9) Dead + 0.6 MWFRS Wind (Pos. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=4, 2-3=9, 7-29=9, 7-12=-2, 12-13=9, 19-23=-12

Horz: 1-2=-16, 2-7=-21, 7-12=10, 12-13=21

Trapezoidal Loads (plf)

Vert: 3=-50-to-29=-1

10) Dead + 0.6 MWFRS Wind (Neg. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-15, 2-3=-20, 7-29=-20, 7-12=-9, 12-13=-4, 19-23=-20

Horz: 1-2=-5, 2-7=0, 7-12=11, 12-13=16

Trapezoidal Loads (plf)

Vert: 3=-79-to-29=-30

11) Dead + 0.6 MWFRS Wind (Neg. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-4, 2-3=-9, 7-29=9, 7-12=-20, 12-13=-15, 19-23=-20

Horz: 1-2=-16, 2-7=-11, 7-12=0, 12-13=5

Trapezoidal Loads (plf)

Vert: 3=-68-to-29=-19

12) Dead + 0.6 MWFRS Wind (Pos. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=17, 2-3=22, 7-29=11, 7-12=3, 12-13=-2, 19-23=-12

Horz: 1-2=-29, 2-28=-34, 7-28=-23, 7-12=15, 12-13=10

Trapezoidal Loads (plf)

Vert: 3=-37-to-28=-17, 28=-27-to-29=1

13) Dead + 0.6 MWFRS Wind (Pos. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-2, 2-3=3, 7-29=3, 7-32=11, 12-32=22, 12-13=17, 19-23=-12

Horz: 1-2=-10, 2-7=-15, 7-32=23, 12-32=34, 12-13=29

Trapezoidal Loads (plf)

Vert: 3=-56-to-29=-7

14) Dead + 0.6 MWFRS Wind (Pos. Internal) 3rd Parallel: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=7, 2-3=11, 7-29=11, 7-12=3, 12-13=-2, 19-23=-12

Horz: 1-2=-19, 2-7=-23, 7-12=15, 12-13=10

Trapezoidal Loads (plf)

Vert: 3=-48-to-29=1

Continued on page 3

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DR HORTON;COLUMBIA;C;MASTER.RT
3720682	A05	COMMON	3	1	162834026
					Job Reference (optional)

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:30 2024 Page 3
ID:fJZOU2ZLpXU3XKYCOPhCD1zheI_RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCdoi7J4zJC?f

LOAD CASE(S) Standard

- 15) Dead + 0.6 MWFRS Wind (Pos. Internal) 4th Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-2, 2-3=3, 7-29=3, 7-12=11, 12-13=7, 19-23=-12
Horz: 1-2=-10, 2-7=-15, 7-12=23, 12-13=19
Trapezoidal Loads (plf)
Vert: 3=-56-to-29=-7
- 16) Dead + 0.6 MWFRS Wind (Neg. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=9, 2-3=4, 7-29=-6, 7-12=-15, 12-13=-10, 19-23=-20
Horz: 1-2=-29, 2-28=-24, 7-28=-14, 7-12=5, 12-13=10
Trapezoidal Loads (plf)
Vert: 3=-55-to-28=-34, 28=-44-to-29=-16
- 17) Dead + 0.6 MWFRS Wind (Neg. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-10, 2-3=-15, 7-29=-15, 7-32=-6, 12-32=4, 12-13=9, 19-23=-20
Horz: 1-2=-10, 2-7=-5, 7-32=14, 12-32=24, 12-13=29
Trapezoidal Loads (plf)
Vert: 3=-74-to-29=-25
- 18) Dead + Uninhabitable Attic Storage: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-20, 7-29=-20, 7-13=-20, 19-34=-20, 34-35=-60, 35-36=-20, 36-37=-60, 23-37=-20
Trapezoidal Loads (plf)
Vert: 3=-79-to-29=-30
- 19) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75(0.6 MWFRS Wind (Neg. Int) Left): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-46, 2-3=-50, 7-29=-50, 7-12=-42, 12-13=-38, 19-34=-20, 34-35=-50, 35-36=-20, 36-37=-50, 23-37=-20
Horz: 1-2=-4, 2-7=-0, 7-12=8, 12-13=12
Trapezoidal Loads (plf)
Vert: 3=-109-to-29=-60
- 20) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75(0.6 MWFRS Wind (Neg. Int) Right): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-38, 2-3=-42, 7-29=-42, 7-12=-50, 12-13=-46, 19-34=-20, 34-35=-50, 35-36=-20, 36-37=-50, 23-37=-20
Horz: 1-2=-12, 2-7=-8, 7-12=0, 12-13=4
Trapezoidal Loads (plf)
Vert: 3=-101-to-29=-52
- 21) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75(0.6 MWFRS Wind (Neg. Int) 1st Parallel): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-28, 2-3=-32, 7-29=-40, 7-12=-46, 12-13=-43, 19-34=-20, 34-35=-50, 35-36=-20, 36-37=-50, 23-37=-20
Horz: 1-2=-22, 2-28=-18, 7-28=-10, 7-12=4, 12-13=7
Trapezoidal Loads (plf)
Vert: 3=-91-to-28=-70, 28=-78-to-29=-50
- 22) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75(0.6 MWFRS Wind (Neg. Int) 2nd Parallel): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-43, 2-3=-46, 7-29=-46, 7-32=-40, 12-32=-28, 12-13=-28, 19-34=-20, 34-35=-50, 35-36=-20, 36-37=-50, 23-37=-20
Horz: 1-2=-7, 2-7=-4, 7-32=10, 12-32=18, 12-13=22
Trapezoidal Loads (plf)
Vert: 3=-105-to-29=-56
- 23) 1st Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-60, 7-29=-60, 7-13=-20, 19-23=-20
Trapezoidal Loads (plf)
Vert: 3=-119-to-29=-70
- 24) 2nd Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-20, 7-29=-20, 7-13=-60, 19-23=-20
Trapezoidal Loads (plf)
Vert: 3=-79-to-29=-30
- 25) 3rd Dead + 0.75 Roof Live (unbalanced) + 0.75 Uninhab. Attic Storage: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-50, 7-29=-50, 7-13=-20, 19-34=-20, 34-35=-50, 35-36=-20, 36-37=-50, 23-37=-20
Trapezoidal Loads (plf)
Vert: 3=-109-to-29=-60
- 26) 4th Dead + 0.75 Roof Live (unbalanced) + 0.75 Uninhab. Attic Storage: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-20, 7-29=-20, 7-13=-50, 19-34=-20, 34-35=-50, 35-36=-20, 36-37=-50, 23-37=-20
Trapezoidal Loads (plf)
Vert: 3=-79-to-29=-30

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932

Job 3720682	Truss A05BV	Truss Type SPECIAL	Qty 6	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT	162834027
----------------	----------------	-----------------------	----------	----------	--------------------------------	-----------

Builders FirstSource, Apex, NC 27523

8.630 s Mar 9 2023 MiTek Industries, Inc. Wed Jan 3 11:29:19 2024 Page 1
ID:fJZOU2ZLpXU3XKYCOPhCD1zhel_-x890FZ5d0sKghiUwUV1LzfEZ1ajy4ESGP1IsP?zz4QE

-0-8-0	9-1-11	14-2-3	21-0-0	28-4-13	34-9-11	42-0-0	42-8-0
0-8-0	9-1-11	5-0-8	6-9-13	7-4-13	6-4-13	7-2-5	0-8-0




Plate Offsets (X,Y)--	[2:0-1-6,Edge], [4:0-1-4,0-2-0], [9:Edge,0-1-9], [15:0-4-0,0-2-4], [16:0-5-12,0-3-8], [19:0-5-0,0-2-0], [20:0-5-0,0-2-0]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.98	Vert(LL) -0.45 15-16 >999 360	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.98	Vert(CT) -1.12 15-16 >449 240	MT20HS	187/143
BCLL 0.0 *	Rep Stress Incr NO	WB 0.83	Horz(CT) 0.46 9 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-MS	Wind(LL) 0.23 15-16 >999 240		Weight: 264 lb FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1 *Except* 5-7: 2x4 SP SS, 1-3: 2x6 SP DSS, 7-10: 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x6 SP No.2 *Except* 2-16: 2x4 SP SS, 15-16: 2x4 SP No.1	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 4-16,5-11,17-18: 2x4 SP No.2	WEBS 1 Row at midpt 4-15, 5-11
WEDGE Left: 2x4 SP No.3 , Right: 2x4 SP No.2	

REACTIONS. (lb/size) 2=1709/0-3-8 (min. 0-2-0), 9=1720/0-3-8 (min. 0-2-0)
Max Horz 2=-127(LC 17)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-27=-5862/212, 27-28=-5802/226, 3-28=-5673/248, 3-4=-5606/272, 4-29=-2011/218,
5-29=-1912/240, 5-30=-2866/387, 6-30=-2971/364, 6-7=-2562/195, 7-8=-2722/163,
8-31=-2857/202, 31-32=-2921/184, 9-32=-3022/169
BOT CHORD 2-16=-131/5276, 15-16=-51/2901, 15-33=0/1544, 14-33=0/1548, 13-14=0/1548,
12-13=0/1548, 11-12=0/1548, 9-11=-90/2612
WEBS 15-17=-1/769, 5-17=0/805, 4-15=-1708/156, 4-16=-45/3374, 5-18=-213/1381,
11-18=-217/1424, 6-11=-595/231, 8-11=-355/138

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TC DL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-5-14 to 2-6-2, Interior(1) 2-6-2 to 21-0-0, Exterior(2) 21-0-0 to 25-2-15, Interior(1) 25-2-15 to 42-8-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) All plates are MT20 plates unless otherwise indicated.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - 7) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 8) N/A



LOAD CASE(S)

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MITEK Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DR HORTON;COLUMBIA;C;MASTER.RT	62834027
3720682	A05BV	SPECIAL	6	1	Job Reference (optional)	

Builders FirstSource, Apex, NC 27523

8.630 s Mar 9 2023 MITek Industries, Inc. Wed Jan 3 11:29:19 2024 Page 2
ID:fJZOU2ZLpXU3XKYCOPhCD1zhel_-x890FZ5d0sKghiUwUV1LzfEZ1ajy4ESGP1IsP?zz4QE

LOAD CASE(S)

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-5=-60, 5-10=-60, 16-21=-20, 15-16=-20, 15-24=-20
- 2) Dead + 0.75 Roof Live (balanced) + 0.75 Uninhab. Attic Storage: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-5=-50, 5-10=-50, 16-21=-20, 15-16=-20, 15-33=-20, 13-33=-50, 13-24=-20
- 3) Dead + Uninhabitable Attic Without Storage: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-5=-20, 5-10=-20, 16-21=-40, 15-16=-40, 15-24=-40
- 4) Dead + 0.6 C-C Wind (Pos. Internal) Case 1: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=47, 2-27=25, 5-27=14, 5-30=25, 9-30=14, 9-10=9, 16-21=-12, 15-16=-12, 15-24=-12
Horz: 1-2=-59, 2-27=-37, 5-27=-26, 5-30=37, 9-30=26, 9-10=21
- 5) Dead + 0.6 C-C Wind (Pos. Internal) Case 2: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=9, 2-29=14, 5-29=25, 5-32=14, 9-32=25, 9-10=47, 16-21=-12, 15-16=-12, 15-24=-12
Horz: 1-2=-21, 2-29=-26, 5-29=-37, 5-32=26, 9-32=37, 9-10=59
- 6) Dead + 0.6 C-C Wind (Neg. Internal) Case 1: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-12, 2-5=-33, 5-9=-33, 9-10=-28, 16-21=-20, 15-16=-20, 15-24=-20
Horz: 1-2=-8, 2-5=13, 5-9=-13, 9-10=8
- 7) Dead + 0.6 C-C Wind (Neg. Internal) Case 2: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-28, 2-5=-33, 5-9=-33, 9-10=-12, 16-21=-20, 15-16=-20, 15-24=-20
Horz: 1-2=8, 2-5=13, 5-9=-13, 9-10=8
- 8) Dead + 0.6 MWFRS Wind (Pos. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=9, 2-5=-2, 5-9=9, 9-10=4, 16-21=-12, 15-16=-12, 15-24=-12
Horz: 1-2=-21, 2-5=-10, 5-9=21, 9-10=16
- 9) Dead + 0.6 MWFRS Wind (Pos. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=4, 2-5=9, 5-9=-2, 9-10=9, 16-21=-12, 15-16=-12, 15-24=-12
Horz: 1-2=-16, 2-5=-21, 5-9=10, 9-10=21
- 10) Dead + 0.6 MWFRS Wind (Neg. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-15, 2-5=-20, 5-9=-9, 9-10=-4, 16-21=-20, 15-16=-20, 15-24=-20
Horz: 1-2=-5, 2-5=0, 5-9=11, 9-10=16
- 11) Dead + 0.6 MWFRS Wind (Neg. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-4, 2-5=-9, 5-9=-20, 9-10=-15, 16-21=-20, 15-16=-20, 15-24=-20
Horz: 1-2=-16, 2-5=-11, 5-9=0, 9-10=5
- 12) Dead + 0.6 MWFRS Wind (Pos. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=17, 2-28=22, 5-28=11, 5-9=3, 9-10=-2, 16-21=-12, 15-16=-12, 15-24=-12
Horz: 1-2=-29, 2-28=-34, 5-28=-23, 5-9=15, 9-10=10
- 13) Dead + 0.6 MWFRS Wind (Pos. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-2, 2-5=3, 5-31=11, 9-31=22, 9-10=17, 16-21=-12, 15-16=-12, 15-24=-12
Horz: 1-2=-10, 2-5=-15, 5-31=23, 9-31=34, 9-10=29
- 14) Dead + 0.6 MWFRS Wind (Pos. Internal) 3rd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=7, 2-5=11, 5-9=3, 9-10=-2, 16-21=-12, 15-16=-12, 15-24=-12
Horz: 1-2=-19, 2-5=-23, 5-9=15, 9-10=10
- 15) Dead + 0.6 MWFRS Wind (Pos. Internal) 4th Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-2, 2-5=3, 5-9=11, 9-10=7, 16-21=-12, 15-16=-12, 15-24=-12
Horz: 1-2=-10, 2-5=-15, 5-9=23, 9-10=19
- 16) Dead + 0.6 MWFRS Wind (Neg. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=9, 2-28=4, 5-28=-6, 5-9=-15, 9-10=-10, 16-21=-20, 15-16=-20, 15-24=-20
Horz: 1-2=-29, 2-28=-24, 5-28=-14, 5-9=5, 9-10=10
- 17) Dead + 0.6 MWFRS Wind (Neg. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-10, 2-5=-15, 5-31=-6, 9-31=4, 9-10=9, 16-21=-20, 15-16=-20, 15-24=-20
Horz: 1-2=-10, 2-5=-5, 5-31=14, 9-31=24, 9-10=29
- 18) Dead + Uninhabitable Attic Storage: Lumber Increase=0.90, Plate Increase=0.90 Plt. metal=0.90
Uniform Loads (plf)
Vert: 1-5=-20, 5-10=-20, 16-21=-20, 15-16=-20, 15-33=-20, 13-33=-60, 13-24=-20
- 19) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75(0.6 MWFRS Wind (Neg. Int) Left): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-46, 2-5=-50, 5-9=-42, 9-10=-38, 16-21=-20, 15-16=-20, 15-33=-20, 13-33=-50, 13-24=-20
Horz: 1-2=-4, 2-5=0, 5-9=8, 9-10=12
- 20) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75(0.6 MWFRS Wind (Neg. Int) Right): Lumber Increase=1.60, Plate Increase=1.60

Continued on page 3

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DR HORTON;COLUMBIA;C;MASTER.RT	I62834027
3720682	A05BV	SPECIAL	6	1	Job Reference (optional)	

Builders FirstSource, Apex, NC 27523

8.630 s Mar 9 2023 MiTek Industries, Inc. Wed Jan 3 11:29:19 2024 Page 3
 ID:fJZOU2ZLpXU3XKYCOPhCD1zhel_-x890FZ5d0sKghiUwUV1LzfEZ1ajy4ESGP1IsP?zz4QE

LOAD CASE(S)

Uniform Loads (plf)

Vert: 1-2=-38, 2-5=-42, 5-9=-50, 9-10=-46, 16-21=-20, 15-16=-20, 15-33=-20, 13-33=-50, 13-24=-20
 Horz: 1-2=-12, 2-5=-8, 5-9=0, 9-10=4

21) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75(0.6 MWFRS Wind (Neg. Int) 1st Parallel): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-28, 2-28=-32, 5-28=-40, 5-9=-46, 9-10=-43, 16-21=-20, 15-16=-20, 15-33=-20, 13-33=-50, 13-24=-20
 Horz: 1-2=-22, 2-28=-18, 5-28=-10, 5-9=4, 9-10=7

22) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75(0.6 MWFRS Wind (Neg. Int) 2nd Parallel): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-43, 2-5=-46, 5-31=-40, 9-31=-32, 9-10=-28, 16-21=-20, 15-16=-20, 15-33=-20, 13-33=-50, 13-24=-20
 Horz: 1-2=-7, 2-5=-4, 5-31=10, 9-31=18, 9-10=22

23) 1st Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-5=-60, 5-10=-20, 16-21=-20, 15-16=-20, 15-24=-20

24) 2nd Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-5=-20, 5-10=-60, 16-21=-20, 15-16=-20, 15-24=-20

25) 3rd Dead + 0.75 Roof Live (unbalanced) + 0.75 Uninhab. Attic Storage: Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-5=-50, 5-10=-20, 16-21=-20, 15-16=-20, 15-33=-20, 13-33=-50, 13-24=-20

26) 4th Dead + 0.75 Roof Live (unbalanced) + 0.75 Uninhab. Attic Storage: Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-5=-20, 5-10=-50, 16-21=-20, 15-16=-20, 15-33=-20, 13-33=-50, 13-24=-20

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
 Edenton, NC 27932


Job 3720682	Truss A05V	Truss Type SPECIAL	Qty 3	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT 162834028
----------------	---------------	-----------------------	----------	----------	---

Builders FirstSource (Apex, NC), Apex, NC - 27523, 8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:33 2024 Page 1

ID:fJZOU2ZLpXU3XKYCOPhCD1zheL_-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

-0-8/0 0-8-0	9-4-2 9-4-2	14-2-3 4-10-0	21-0-0 6-9-13	28-4-13 7-4-13	34-9-11 6-4-13	42-0-0 7-2-5	42-8-0 0-8-0
-----------------	----------------	------------------	------------------	-------------------	-------------------	-----------------	-----------------

Scale = 1:77.1



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.93	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.91	Vert(LL) -0.45 11-13 >999 360	MT20HS	187/143
BCLL 0.0 *	Lumber DOL 1.15	WB 0.98	Vert(CT) -1.08 13-14 >466 240		
BCDL 10.0	Rep Stress Incr NO	Matrix-MS	Horz(CT) 0.45 9 n/a n/a		
	Code IRC2015/TPI2014		Wind(LL) 0.20 14 >999 240	Weight: 248 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.1 *Except*
5-7: 2x4 SP SS, 1-3: 2x6 SP DSS, 7-10: 2x4 SP No.2
BOT CHORD 2x4 SP SS *Except*
12-13,9-12: 2x6 SP No.2
WEBS 2x4 SP No.3 *Except*
4-14,5-11: 2x4 SP No.2
WEDGE
Left: 2x4 SP No.3, Right: 2x4 SP No.3


BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 4-13, 5-11

REACTIONS. (size) 2=0-3-8, 9=0-3-8
Max Horz 2=127(LC 17)
Max Grav 2=2034(LC 1), 9=1768(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-6696/0, 3-4=-6332/0, 4-5=-2121/128, 5-6=-3072/285, 6-8=-2823/93,
8-9=-3123/101
BOT CHORD 2-14=0/6030, 13-14=0/3141, 11-13=0/1737, 9-11=0/2702
WEBS 5-13=0/900, 4-13=-1917/0, 4-14=0/3976, 3-14=-349/0, 5-11=-215/1384, 6-11=-595/231,
8-11=-353/140

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-5-14 to 2-6-2, Interior(1) 2-6-2 to 21-0-0, Exterior(2) 21-0-0 to 25-2-15, Interior(1) 25-2-15 to 42-8-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) All plates are MT20 plates unless otherwise indicated.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
6) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
7) N/A

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-21=-60, 5-24=-60, 5-10=-60, 14-15=-20, 13-14=-20, 13-18=-20



January 3, 2024

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DR HORTON;COLUMBIA;C;MASTER.RT
3720682	A05V	SPECIAL	3	1	162834028
					Job Reference (optional)

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:33 2024 Page 2
ID:fJZOU2ZLpXU3XKYCOPhCD1zheL_RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

LOAD CASE(S) Standard

- Trapezoidal Loads (plf)
 - Vert: 21=-120-to-24=-70
- 2) Dead + 0.75 Roof Live (balanced) + 0.75 Uninhab. Attic Storage: Lumber Increase=1.15, Plate Increase=1.15
 - Uniform Loads (plf)
 - Vert: 1-21=-50, 5-24=-50, 5-10=-50, 14-15=-20, 13-14=-20, 13-29=-20, 29-30=-50, 18-30=-20
 - Trapezoidal Loads (plf)
 - Vert: 21=-110-to-24=-60
- 3) Dead + Uninhabitable Attic Without Storage: Lumber Increase=1.25, Plate Increase=1.25
 - Uniform Loads (plf)
 - Vert: 1-21=-20, 5-24=-20, 5-10=-20, 14-15=-40, 13-14=-40, 13-18=-40
 - Trapezoidal Loads (plf)
 - Vert: 21=-80-to-24=-30
- 4) Dead + 0.6 C-C Wind (Pos. Internal) Case 1: Lumber Increase=1.60, Plate Increase=1.60
 - Uniform Loads (plf)
 - Vert: 1-2=47, 2-21=25, 5-24=14, 5-26=25, 9-26=14, 9-10=9, 14-15=-12, 13-14=-12, 13-18=-12
 - Horz: 1-2=-59, 2-22=-37, 5-22=-26, 5-26=37, 9-26=26, 9-10=21
 - Trapezoidal Loads (plf)
 - Vert: 21=-35-to-22=-29, 22=-40-to-24=4
- 5) Dead + 0.6 C-C Wind (Pos. Internal) Case 2: Lumber Increase=1.60, Plate Increase=1.60
 - Uniform Loads (plf)
 - Vert: 1-2=9, 2-21=14, 24-25=14, 5-25=25, 5-28=14, 9-28=25, 9-10=47, 14-15=-12, 13-14=-12, 13-18=-12
 - Horz: 1-2=-21, 2-25=-26, 5-25=-37, 5-28=26, 9-28=37, 9-10=59
 - Trapezoidal Loads (plf)
 - Vert: 21=-46-to-24=4
- 6) Dead + 0.6 C-C Wind (Neg. Internal) Case 1: Lumber Increase=1.60, Plate Increase=1.60
 - Uniform Loads (plf)
 - Vert: 1-2=-12, 2-21=-33, 5-24=-33, 5-9=-33, 9-10=-28, 14-15=-20, 13-14=-20, 13-18=-20
 - Horz: 1-2=-8, 2-5=13, 5-9=-13, 9-10=-8
 - Trapezoidal Loads (plf)
 - Vert: 21=-93-to-24=-43
- 7) Dead + 0.6 C-C Wind (Neg. Internal) Case 2: Lumber Increase=1.60, Plate Increase=1.60
 - Uniform Loads (plf)
 - Vert: 1-2=-28, 2-21=-33, 5-24=-33, 5-9=-33, 9-10=-12, 14-15=-20, 13-14=-20, 13-18=-20
 - Horz: 1-2=8, 2-5=13, 5-9=-13, 9-10=8
 - Trapezoidal Loads (plf)
 - Vert: 21=-93-to-24=-43
- 8) Dead + 0.6 MWFRS Wind (Pos. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
 - Uniform Loads (plf)
 - Vert: 1-2=9, 2-21=-2, 5-24=-2, 5-9=9, 9-10=4, 14-15=-12, 13-14=-12, 13-18=-12
 - Horz: 1-2=-21, 2-5=-10, 5-9=21, 9-10=16
 - Trapezoidal Loads (plf)
 - Vert: 21=-62-to-24=-12
- 9) Dead + 0.6 MWFRS Wind (Pos. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
 - Uniform Loads (plf)
 - Vert: 1-2=4, 2-21=9, 5-24=9, 5-9=-2, 9-10=9, 14-15=-12, 13-14=-12, 13-18=-12
 - Horz: 1-2=-16, 2-5=-21, 5-9=10, 9-10=21
 - Trapezoidal Loads (plf)
 - Vert: 21=-51-to-24=-1
- 10) Dead + 0.6 MWFRS Wind (Neg. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
 - Uniform Loads (plf)
 - Vert: 1-2=-15, 2-21=-20, 5-24=-20, 5-9=-9, 9-10=-4, 14-15=-20, 13-14=-20, 13-18=-20
 - Horz: 1-2=-5, 2-5=0, 5-9=11, 9-10=16
 - Trapezoidal Loads (plf)
 - Vert: 21=-80-to-24=-30
- 11) Dead + 0.6 MWFRS Wind (Neg. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
 - Uniform Loads (plf)
 - Vert: 1-2=-4, 2-21=-9, 5-24=-9, 5-9=-20, 9-10=-15, 14-15=-20, 13-14=-20, 13-18=-20
 - Horz: 1-2=-16, 2-5=-11, 5-9=0, 9-10=5
 - Trapezoidal Loads (plf)
 - Vert: 21=-69-to-24=-19
- 12) Dead + 0.6 MWFRS Wind (Pos. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60
 - Uniform Loads (plf)
 - Vert: 1-2=17, 2-21=22, 5-24=11, 5-9=3, 9-10=-2, 14-15=-12, 13-14=-12, 13-18=-12
 - Horz: 1-2=-29, 2-23=-34, 5-23=-23, 5-9=15, 9-10=10
 - Trapezoidal Loads (plf)
 - Vert: 21=-38-to-23=-17, 23=-27-to-24=1
- 13) Dead + 0.6 MWFRS Wind (Pos. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60
 - Uniform Loads (plf)
 - Vert: 1-2=-2, 2-21=3, 5-24=3, 5-27=11, 9-27=22, 9-10=17, 14-15=-12, 13-14=-12, 13-18=-12
 - Horz: 1-2=-10, 2-5=-15, 5-27=23, 9-27=34, 9-10=29
 - Trapezoidal Loads (plf)
 - Vert: 21=-57-to-24=-7
- 14) Dead + 0.6 MWFRS Wind (Pos. Internal) 3rd Parallel: Lumber Increase=1.60, Plate Increase=1.60

Continued on page 3

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DR HORTON;COLUMBIA;C;MASTER.RT
3720682	A05V	SPECIAL	3	1	162834028
					Job Reference (optional)

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:33 2024 Page 3
ID:fJZOU2ZLpXU3XKYCOPhCD1zheL_RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

LOAD CASE(S) Standard

- Uniform Loads (plf)
Vert: 1-2=7, 2-21=11, 5-24=11, 5-9=3, 9-10=-2, 14-15=-12, 13-14=-12, 13-18=-12
Horz: 1-2=-19, 2-5=-23, 5-9=15, 9-10=10
- Trapezoidal Loads (plf)
Vert: 21=-49-to-24=1
- 15) Dead + 0.6 MWFRS Wind (Pos. Internal) 4th Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-2, 2-21=3, 5-24=3, 5-9=11, 9-10=7, 14-15=-12, 13-14=-12, 13-18=-12
Horz: 1-2=-10, 2-5=-15, 5-9=23, 9-10=19
Trapezoidal Loads (plf)
Vert: 21=-57-to-24=-7
- 16) Dead + 0.6 MWFRS Wind (Neg. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=9, 2-21=4, 5-24=-6, 5-9=-15, 9-10=-10, 14-15=-20, 13-14=-20, 13-18=-20
Horz: 1-2=-29, 2-23=-24, 5-23=-14, 5-9=5, 9-10=10
Trapezoidal Loads (plf)
Vert: 21=-56-to-23=-34, 23=-44-to-24=-16
- 17) Dead + 0.6 MWFRS Wind (Neg. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-10, 2-21=-15, 5-24=-15, 5-27=-6, 9-27=4, 9-10=9, 14-15=-20, 13-14=-20, 13-18=-20
Horz: 1-2=-10, 2-5=-5, 5-27=14, 9-27=24, 9-10=29
Trapezoidal Loads (plf)
Vert: 21=-75-to-24=-25
- 18) Dead + Uninhabitable Attic Storage: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-21=-20, 5-24=-20, 5-10=-20, 14-15=-20, 13-14=-20, 13-29=-20, 29-30=-60, 18-30=-20
Trapezoidal Loads (plf)
Vert: 21=-80-to-24=-30
- 19) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75(0.6 MWFRS Wind (Neg. Int) Left): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-46, 2-21=-50, 5-24=-50, 5-9=-42, 9-10=-38, 14-15=-20, 13-14=-20, 13-29=-20, 29-30=-50, 18-30=-20
Horz: 1-2=-4, 2-5=0, 5-9=8, 9-10=12
Trapezoidal Loads (plf)
Vert: 21=-110-to-24=-60
- 20) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75(0.6 MWFRS Wind (Neg. Int) Right): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-38, 2-21=-42, 5-24=-42, 5-9=-50, 9-10=-46, 14-15=-20, 13-14=-20, 13-29=-20, 29-30=-50, 18-30=-20
Horz: 1-2=-12, 2-5=-8, 5-9=0, 9-10=4
Trapezoidal Loads (plf)
Vert: 21=-102-to-24=-52
- 21) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75(0.6 MWFRS Wind (Neg. Int) 1st Parallel): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-28, 2-21=-32, 5-24=-40, 5-9=-46, 9-10=-43, 14-15=-20, 13-14=-20, 13-29=-20, 29-30=-50, 18-30=-20
Horz: 1-2=-22, 2-23=-18, 5-23=-10, 5-9=4, 9-10=7
Trapezoidal Loads (plf)
Vert: 21=-92-to-23=-70, 23=-78-to-24=-50
- 22) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75(0.6 MWFRS Wind (Neg. Int) 2nd Parallel): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-43, 2-21=-46, 5-24=-46, 5-27=-40, 9-27=-32, 9-10=-28, 14-15=-20, 13-14=-20, 13-29=-20, 29-30=-50, 18-30=-20
Horz: 1-2=-7, 2-5=-4, 5-27=10, 9-27=18, 9-10=22
Trapezoidal Loads (plf)
Vert: 21=-106-to-24=-56
- 23) 1st Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-21=-60, 5-24=-60, 5-10=-20, 14-15=-20, 13-14=-20, 13-18=-20
Trapezoidal Loads (plf)
Vert: 21=-120-to-24=-70
- 24) 2nd Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-21=-20, 5-24=-20, 5-10=-60, 14-15=-20, 13-14=-20, 13-18=-20
Trapezoidal Loads (plf)
Vert: 21=-80-to-24=-30
- 25) 3rd Dead + 0.75 Roof Live (unbalanced) + 0.75 Uninhab. Attic Storage: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-21=-50, 5-24=-50, 5-10=-20, 14-15=-20, 13-14=-20, 13-29=-20, 29-30=-50, 18-30=-20
Trapezoidal Loads (plf)
Vert: 21=-110-to-24=-60
- 26) 4th Dead + 0.75 Roof Live (unbalanced) + 0.75 Uninhab. Attic Storage: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-21=-20, 5-24=-20, 5-10=-50, 14-15=-20, 13-14=-20, 13-29=-20, 29-30=-50, 18-30=-20
Trapezoidal Loads (plf)
Vert: 21=-80-to-24=-30

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932

Job 3720682	Truss A08	Truss Type COMMON	Qty 4	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT 162834029
----------------	--------------	----------------------	----------	----------	---

Builders FirstSource (Apex, NC), Apex, NC - 27523, 8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:34 2024 Page 1

ID:fJZOU2ZLpXU3XKYCOPhCD1zheL_RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



5x6 =

Scale = 1:74.6





Plate Offsets (X,Y)--	[11:0-3-9,0-0-1]
-----------------------	------------------


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.86	Vert(LL)	-0.42	15-17	>999	360	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.95	Vert(CT)	-0.73	15-17	>688	240	MT20HS	187/143
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.56	Horz(CT)	0.14	11	n/a	n/a		
BCDL 10.0	Code IRC2015/TP12014		Matrix-MS	Wind(LL)	0.10	15-17	>999	240		
									Weight: 222 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 *Except*	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins.
1-4: 2x4 SP SS, 8-12: 2x4 SP No.1	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing. Except:
BOT CHORD 2x4 SP No.1 *Except*	2-2-0 oc bracing: 1-17.
14-16: 2x4 SP SS	WEBS 1 Row at midpt 7-15, 5-15
WEBS 2x4 SP No.3	
SLIDER Left 2x4 SP No.3 1-11-12, Right 2x4 SP No.3 1-11-12	

REACTIONS. (size) 1=Mechanical, 11=0-3-8
 Max Horz 1=-132(LC 13)
 Max Grav 1=1670(LC 1), 11=1710(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-3=-2842/205, 3-5=-2628/208, 5-6=-1933/235, 6-7=-1932/233, 7-9=-2683/204, 9-11=-2917/201
 BOT CHORD 1-17=-88/2454, 15-17=-22/2113, 13-15=-26/2131, 11-13=-87/2535
 WEBS 6-15=-67/1346, 7-15=-746/140, 7-13=0/526, 9-13=-330/141, 5-15=-722/139, 5-17=0/478, 3-17=-284/145


- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-3-0 to 3-3-0, Interior(1) 3-3-0 to 21-0-0, Exterior(2) 21-0-0 to 25-2-15, Interior(1) 25-2-15 to 42-8-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.




Job 3720682	Truss A09	Truss Type Hip	Qty 1	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT 162834030
----------------	--------------	-------------------	----------	----------	---

Builders FirstSource (Apex, NC), Apex, NC - 27523, 8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:36 2024 Page 1

ID:nEofIS4OxkzImBEk9cc91EyWoyO-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:73.4



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.52	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.76	Vert(LL) -0.19 13-15 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.50	Vert(CT) -0.34 13-15 >999 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-MS	Horz(CT) 0.09 9 n/a n/a		
	Code IRC2015/TPI2014		Wind(LL) 0.09 15 >999 240	Weight: 287 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x6 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-7-11 oc purlins, except
BOT CHORD 2x6 SP No.2	2-0-0 oc purlins (5-1-4 max.): 5-6.
WEBS 2x4 SP No.3	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
	WEBS 1 Row at midpt 5-13, 6-13

REACTIONS. (size) 2=0-3-8, 9=0-3-8
 Max Horz 2=137(LC 12)
 Max Uplift 2=-121(LC 12), 9=-121(LC 13)
 Max Grav 2=1720(LC 1), 9=1720(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-3025/232, 3-5=-2905/314, 5-6=-2027/255, 6-8=-2905/314, 8-9=-3025/232
 BOT CHORD 2-15=-220/2624, 13-15=-31/1960, 11-13=-11/1960, 9-11=-118/2624
 WEBS 3-15=-521/268, 5-15=-179/926, 5-13=-75/381, 6-13=-75/381, 6-11=-179/926, 8-11=-521/268

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-8-0 to 2-4-0, Interior(1) 2-4-0 to 18-4-0, Exterior(2) 18-4-0 to 22-6-15, Interior(1) 22-6-15 to 23-8-0, Exterior(2) 23-8-0 to 27-10-15, Interior(1) 27-10-15 to 42-8-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=121, 9=121.
 - 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



January 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbccomponents.com)

818 Soundside Road
Edenton, NC 27932

Job 3720682	Truss A10	Truss Type Hip	Qty 1	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT	162834031
----------------	--------------	-------------------	----------	----------	--------------------------------	-----------


Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:37 2024 Page 1

ID:nEofIS4OxkzImBEk9cc91EyWoyO-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f

-0-8-0	7-11-12	15-8-0	26-4-0	34-0-4	42-0-0	42-8-0
0-8-0	7-11-12	7-8-4	10-8-0	7-8-4	7-11-12	0-8-0

Scale = 1:73.2




LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.43	Vert(LL)	-0.19 11-13	>999	360	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.74	Vert(CT)	-0.33 11-13	>999	240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.26	Horz(CT)	0.10 9	n/a	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-MS	Wind(LL)	0.08 13-15	>999	240		
	Code IRC2015/TPI2014						Weight: 277 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x6 SP No.2 *Except* 5-6: 2x6 SP DSS	TOP CHORD Structural wood sheathing directly applied or 4-0-10 oc purlins, except
BOT CHORD 2x6 SP No.2	2-0-0 oc purlins (5-0-0 max.): 5-6.
WEBS 2x4 SP No.3	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
	WEBS 1 Row at midpt 5-13, 6-13

REACTIONS. (size) 2=0-3-8, 9=0-3-8
 Max Horz 2=-117(LC 17)
 Max Uplift 2=-125(LC 12), 9=-125(LC 13)
 Max Grav 2=1720(LC 1), 9=1720(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-3057/256, 3-5=-2810/275, 5-6=-2243/243, 6-8=-2811/275, 8-9=-3057/256
 BOT CHORD 2-15=-231/2650, 13-15=-75/2110, 11-13=-60/2110, 9-11=-150/2650
 WEBS 3-15=-394/215, 5-15=-65/646, 5-13=-19/349, 6-13=-19/349, 6-11=-65/646, 8-11=-394/215

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-8-0 to 2-4-0, Interior(1) 2-4-0 to 15-8-0, Exterior(2) 15-8-0 to 19-10-15, Interior(1) 19-10-15 to 26-4-0, Exterior(2) 26-4-0 to 30-6-15, Interior(1) 30-6-15 to 42-8-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=125, 9=125.
 - 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



January 3, 2024

Job	Truss	Truss Type	Qty	Ply	DR HORTON;COLUMBIA;C;MASTER.RT	162834032
3720682	A11G	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:40 2024 Page 1

ID:nEofIS4OxkzImBEk9cc91EyWoyO-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRCDoi7J4zJC?f

-0-8-0	13-0-0	29-0-0	42-0-0	42-8-0
0-8-0	13-0-0	16-0-0	13-0-0	0-8-0

Scale = 1:73.1




Plate Offsets (X,Y)--	[2:0-3-8,Edge], [12:0-3-0,0-2-0], [24:0-3-0,0-2-0], [34:0-4-1,Edge]
-----------------------	---

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.05	Vert(LL)	0.00	34	n/r	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.04	Vert(CT)	0.00	34	n/r		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.08	Horz(CT)	0.01	34	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S						
								Weight: 355 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3
SLIDER Left 2x4 SP No.3 1-6-7, Right 2x4 SP No.3 1-6-7

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 12-24.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 42-0-0.
(lb) - Max Horz 2=99(LC 12)
Max Uplift All uplift 100 lb or less at joint(s) 2, 51, 52, 53, 54, 55, 56, 59, 60, 61, 62, 63, 64, 65, 50, 49, 48, 47, 46, 43, 42, 41, 40, 39, 38, 37, 34
Max Grav All reactions 250 lb or less at joint(s) 2, 51, 52, 53, 54, 55, 56, 58, 59, 60, 61, 62, 63, 64, 65, 66, 50, 49, 48, 47, 46, 44, 43, 42, 41, 40, 39, 38, 37, 36, 34

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) -0-8-0 to 2-4-0, Exterior(2) 2-4-0 to 13-0-0, Corner(3) 13-0-0 to 16-0-0, Exterior(2) 16-0-0 to 29-0-0, Corner(3) 29-0-0 to 32-0-0, Exterior(2) 32-0-0 to 42-8-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) Provide adequate drainage to prevent water ponding.
- 5) All plates are 2x4 MT20 unless otherwise indicated.
- 6) Gable requires continuous bottom chord bearing.
- 7) Gable studs spaced at 1-4-0 oc.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 51, 52, 53, 54, 55, 56, 59, 60, 61, 62, 63, 64, 65, 50, 49, 48, 47, 46, 43, 42, 41, 40, 39, 38, 37, 34.
- 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



January 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbccomponents.com)




818 Soundside Road
Edenton, NC 27932

Job 3720682	Truss B01G	Truss Type GABLE	Qty 1	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT Job Reference (optional)	162834033
----------------	---------------	---------------------	----------	----------	--	-----------

Builders FirstSource (Apex, NC), Apex, NC - 27523, 8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:41 2024 Page 1

ID:fJZOU2ZLpXU3XKYCOPhCD1zheL_RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



4x6 =

Scale = 1:33.9




Plate Offsets (X,Y)--	[10:0-0-0,0-0-0], [11:0-0-0,0-0-0], [14:0-0-0,0-0-0]
-----------------------	--

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.07	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.04	Vert(LL) -0.00 12 n/r 120		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.05	Vert(CT) -0.00 13 n/r 120		
BCDL 10.0	Rep Stress Incr NO	Matrix-R	Horz(CT) 0.00 14 n/a n/a		
	Code IRC2015/TPI2014			Weight: 86 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	

REACTIONS. All bearings 13-8-0.
 (lb) - Max Horz 24=125(LC 11)
 Max Uplift All uplift 100 lb or less at joint(s) 24, 14, 20, 21, 22, 23, 18, 17, 16, 15
 Max Grav All reactions 250 lb or less at joint(s) 24, 14, 19, 20, 21, 22, 23, 18, 17, 16, 15

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) 0-7-14 to 2-4-2, Exterior(2) 2-4-2 to 6-10-0, Corner(3) 6-10-0 to 9-10-0, Exterior(2) 9-10-0 to 14-3-14 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 4) All plates are 2x4 MT20 unless otherwise indicated.
 - 5) Gable requires continuous bottom chord bearing.
 - 6) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 7) Gable studs spaced at 1-4-0 oc.
 - 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 24, 14, 20, 21, 22, 23, 18, 17, 16, 15.




January 3, 2024

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)</p>	<p>ENGINEERING BY</p> <p>TRENCO</p> <p>A MiTek Affiliate</p> <p>818 Soundside Road Edenton, NC 27932</p>
---	---

Job 3720682	Truss B02-2PL	Truss Type COMMON	Qty 1	Ply 2	DR HORTON;COLUMBIA;C;MASTER.RT Job Reference (optional)	162834034
----------------	------------------	----------------------	----------	----------	--	-----------

Builders FirstSource (Apex, NC), Apex, NC - 27523, 8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:43 2024 Page 1

ID:fJZOU2ZLpXU3XKYCOPhCD1zheL_RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCdoi7J4zJC?f



Scale = 1:33.7

Plate Offsets (X, Y)--	[1:0-0-0,0-3-5], [5:Edge,0-3-5], [6:0-6-0,0-6-0], [7:0-6-0,0-6-0]
------------------------	---

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.39	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.31	Vert(LL) -0.07 6-7 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.83	Vert(CT) -0.13 6-7 >999 240		
BCDL 10.0	Rep Stress Incr NO	Matrix-MS	Horz(CT) 0.01 5 n/a n/a		
	Code IRC2015/TP12014		Wind(LL) 0.06 6-7 >999 240	Weight: 180 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-6-7 oc purlins.
BOT CHORD 2x8 SP DSS	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	
WEDGE	
Left: 2x4 SP No.3 , Right: 2x4 SP No.3	

REACTIONS.	(size)
	1=0-3-8, 5=0-3-8
	Max Horz 1=98(LC 5)
	Max Uplift 1=-573(LC 8), 5=-601(LC 9)
	Max Grav 1=5230(LC 1), 5=5464(LC 1)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	1-2=-6837/760, 2-3=-6731/798, 3-4=-6773/803, 4-5=-6879/766
BOT CHORD	1-7=-662/5609, 6-7=-412/3933, 5-6=-592/5646
WEBS	3-6=-502/4001, 3-7=-491/3918

- NOTES-**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-6-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=573, 5=601.
 - Magnitude of user added load(s) on this truss have been applied uniformly across all gravity load cases with no adjustments.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1600 lb down and 191 lb up at 2-0-0, 1600 lb down and 191 lb up at 4-0-0, 1600 lb down and 191 lb up at 6-0-0, 1600 lb down and 191 lb up at 8-0-0, and 1600 lb down and 191 lb up at 10-0-0, and 1600 lb down and 191 lb up at 12-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard



Continued on page 2

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)</p>	<p>ENGINEERING BY TRENCO A MiTek Affiliate</p> <p>818 Soundside Road Edenton, NC 27932</p>
--	--

Job 3720682	Truss B02-2PL	Truss Type COMMON	Qty 1	Ply 2	DR HORTON;COLUMBIA;C;MASTER.RT I62834034 Job Reference (optional)
----------------	------------------	----------------------	----------	-----------------	---

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:43 2024 Page 2
ID:fJZOU2ZLpXU3XKYCOPhCD1zheL_RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-3=-60, 3-5=-60, 8-11=-20

Concentrated Loads (lb)

Vert: 16=-1600(F) 17=-1600(F) 18=-1600(F) 19=-1600(F) 20=-1600(F) 21=-1600(F)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932

Job 3720682	Truss P01G	Truss Type GABLE	Qty 1	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT Job Reference (optional)	62834035
----------------	---------------	---------------------	----------	----------	--	----------

Builders FirstSource (Apex, NC),

Apex, NC - 27523,

8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:43 2024 Page 1

ID:fJZOU2ZLpXU3XKYCOPhCD1zheL_RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f



Scale = 1:12.2




Plate Offsets (X, Y)--	[2:0-0-0,0-1-2], [2:0-1-5,0-7-9]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.08	Vert(LL) -0.00 1 n/r 120	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.05	Vert(CT) 0.00 1 n/r 120		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.04	Horz(CT) 0.00 5 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-P		Weight: 18 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	
WEDGE	
Left: 2x4 SP No.3	

REACTIONS. (size) 2=4-0-0, 5=4-0-0, 6=4-0-0
 Max Horz 2=55(LC 9)
 Max Uplift 2=-27(LC 8), 5=-5(LC 11), 6=-38(LC 12)
 Max Grav 2=134(LC 1), 5=7(LC 1), 6=208(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-8-0 to 2-4-0, Interior(1) 2-4-0 to 3-10-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Gable studs spaced at 1-4-0 oc.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 5, 6.



January 3, 2024

Job 3720682	Truss P02	Truss Type MONO TRUSS	Qty 6	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT Job Reference (optional)	162834036
----------------	--------------	--------------------------	----------	----------	--	-----------

Builders FirstSource (Apex, NC),


Apex, NC - 27523,

8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:44 2024 Page 1

ID:fJZOU2ZLpXU3XKYCOPhCD1zheL_RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:12.2



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.22	Vert(LL)	0.02	4-7	>999	240	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.15	Vert(CT)	-0.02	4-7	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	2	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MP						Weight: 15 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3


BRACING-
TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 2=0-3-8, 4=0-1-8
Max Horz 2=53(LC 8)
Max Uplift 2=63(LC 8), 4=57(LC 8)
Max Grav 2=198(LC 1), 4=151(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-8-0 to 2-4-0, Interior(1) 2-4-0 to 3-10-4 zone; cantilever left and right exposed; end vertical left exposed; porch left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4.



January 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932


Job 3720682	Truss P03	Truss Type MONO TRUSS	Qty 3	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT Job Reference (optional)	162834037
----------------	--------------	--------------------------	----------	----------	--	-----------

Builders FirstSource (Apex, NC),

Apex, NC - 27523,

8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:45 2024 Page 1

ID:fJZOU2ZLpXU3XKYCOPhCD1zhel_RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f
6-0-0
6-0-0



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.56	Vert(LL)	0.12	4-7	>584	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.38	Vert(CT)	-0.12	4-7	>589		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Horz(CT)	0.02	2	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-MP					Weight: 22 lb	FT = 20%
	Code IRC2015/TPI2014							

LUMBER-
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 WEBS 2x4 SP No.3


BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 2=0-3-8, 4=0-1-8
 Max Horz 2=75(LC 8)
 Max Uplift 2=84(LC 8), 4=87(LC 8)
 Max Grav 2=276(LC 1), 4=232(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-8-0 to 2-4-0, Interior(1) 2-4-0 to 5-10-4 zone; cantilever left and right exposed; end vertical left exposed; porch left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4.



January 3, 2024

Job 3720682	Truss P04G	Truss Type GABLE	Qty 1	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT Job Reference (optional)	162834038
----------------	---------------	---------------------	----------	----------	--	-----------

Builders FirstSource (Apex, NC),

Apex, NC - 27523,

8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:46 2024 Page 1

ID:fJZOU2ZLpXU3XKYCOPhCD1zheL_RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f



2x4 ||

Scale = 1:17.3




Plate Offsets (X,Y)--	[2:0-0-0,0-1-2], [2:0-1-5,0-7-9]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.13	Vert(LL) -0.00 1 n/r 120	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.09	Vert(CT) 0.00 1 n/r 120		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.04	Horz(CT) 0.00 6 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-P		Weight: 27 lb	FT = 20%


LUMBER-
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 WEBS 2x4 SP No.3
 OTHERS 2x4 SP No.3
 WEDGE
 Left: 2x4 SP No.3

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 6-0-0.
 (lb) - Max Horz 2=80(LC 9)
 Max Uplift All uplift 100 lb or less at joint(s) 2, 6, 7, 8
 Max Grav All reactions 250 lb or less at joint(s) 2, 6, 7 except 8=268(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-8-0 to 2-4-0, Interior(1) 2-4-0 to 5-10-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Gable studs spaced at 1-4-0 oc.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 6, 7, 8.



January 3, 2024


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
 Edenton, NC 27932

Job 3720682	Truss V01	Truss Type GABLE	Qty 1	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT 162834039
----------------	--------------	---------------------	----------	----------	---

Builders FirstSource (Apex, NC), Apex, NC - 27523, 8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:47 2024 Page 1
 ID:fJZOU2ZLpXU3XKYCOPhCD1zhel_-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:23.2

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.59	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.41	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.07	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-S					Weight: 38 lb	FT = 20%
	Code IRC2015/TPI2014							

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.3	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.3	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS. (size) 1=10-9-10, 3=10-9-10, 4=10-9-10
 Max Horz 1=70(LC 8)
 Max Uplift 1=24(LC 12), 3=33(LC 13)
 Max Grav 1=192(LC 1), 3=192(LC 1), 4=403(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-4=-258/64

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 5-4-13, Exterior(2) 5-4-13 to 8-4-13, Interior(1) 8-4-13 to 10-3-14 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Gable requires continuous bottom chord bearing.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.



January 3, 2024

Job 3720682	Truss V02	Truss Type GABLE	Qty 1	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT 162834040
----------------	--------------	---------------------	----------	----------	---

Builders FirstSource (Apex, NC),

Apex, NC - 27523,


8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:48 2024 Page 1

ID:fJZOU2ZLpXU3XKYCOPhCD1zheL_-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f



4x6 =

Scale = 1:18.1



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.27	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.20	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.04	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-S					Weight: 27 lb	FT = 20%
	Code IRC2015/TPI2014							

LUMBER-
 TOP CHORD 2x4 SP No.3
 BOT CHORD 2x4 SP No.3
 OTHERS 2x4 SP No.3


BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=7-9-10, 3=7-9-10, 4=7-9-10
 Max Horz 1=-49(LC 8)
 Max Uplift 1=-16(LC 12), 3=-23(LC 13)
 Max Grav 1=133(LC 1), 3=133(LC 1), 4=280(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 3-10-13, Exterior(2) 3-10-13 to 6-10-13, Interior(1) 6-10-13 to 7-3-14 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.



January 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
 Edenton, NC 27932


Job 3720682	Truss V03	Truss Type GABLE	Qty 1	Ply 1	DR HORTON;COLUMBIA;C;MASTER.RT 162834041
----------------	--------------	---------------------	----------	----------	---

Builders FirstSource (Apex, NC),

Apex, NC - 27523,

8.630 s Aug 30 2023 MiTek Industries, Inc. Wed Jan 3 11:27:48 2024 Page 1
ID:fJZOU2ZLpXU3XKYCOPhCD1zhel_-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f

Job Reference (optional)



Scale = 1:10.7

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.11	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.06	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.02	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-P					Weight: 16 lb	FT = 20%
	Code IRC2015/TPI2014							

LUMBER-
TOP CHORD 2x4 SP No.3
BOT CHORD 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 4-9-10 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=4-9-10, 3=4-9-10, 4=4-9-10
Max Horz 1=-27(LC 8)
Max Uplift 1=-13(LC 12), 3=-17(LC 13)
Max Grav 1=82(LC 1), 3=82(LC 1), 4=143(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=120mph Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=32ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Gable requires continuous bottom chord bearing.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.



January 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16\" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in MITek software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.


Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



1 TOP CHORDS
2 Joint ID
3 typ.



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 section 6.3. These truss designs rely on Lumber values established by others.

© 2023 MITek® All Rights Reserved

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability/bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.

MITek

ENGINEERING BY
TRENGO
A MITek Affiliate

MITek Engineering Reference Sheet: MIL-7473 rev. 1/2/2023