

# AVERY

TOBACCO ROAD  
LOT 0174



PLAN ID: 042720.0601

110 VILLAGE TRAIL SUITE 215  
WOODSTOCK, GA. 30188

| DRAWING INDEX |                             |
|---------------|-----------------------------|
| A0.0          | COVER SHEET                 |
| A1.1          | FRONT ELEVATIONS            |
| A2.1          | SIDE & REAR ELEVATIONS      |
| A3.1          | SLAB FOUNDATIONS            |
| A5.1          | FIRST FLOOR PLANS & DETAILS |
| A6.1          | ROOF PLANS                  |
| A7.2          | ELECTRICAL PLANS            |


| AREA TABULATION                       |      |
|---------------------------------------|------|
| FIRST FLOOR                           | 2404 |
| TOTAL                                 | 2404 |
| GARAGE                                | 400  |
| FRONT PORCH B&C<br>MASSINGS (COVERED) | 67   |
| REAR PATIO (COVERED)                  | 120  |
| REAR PATIO EXT                        | 80   |

**GOVERNMENTAL CODES & STANDARDS**  
HOME TO BE BUILT TO CONFORM TO ALL APPLICABLE LOCAL CODES, PRACTICES AND STANDARDS

**BUILDING CODE ANALYSIS / DESIGN CRITERIA**  
HOME TO BE BUILT TO MEET OR EXCEED ALL LOCAL CODES AND DESIGN CRITERIA

| PLAN REVISIONS |     |   |                          |
|----------------|-----|---|--------------------------|
| DATE           | BY  | REVISION  | PAGE #                   |
| 9/10/2019      | AW  | PCR #3209 added clg. mount light to hall by bathroom in finished basement                           | A7.1.1                   |
| 9/10/2019      | AW  | PCR #3214 Removed tempered note from 3050 window in Family Rm. next to rear door                    | A5.1                     |
| 11/4/2019      | AW  | Added grade beam between B-2 & Foyer as part of truss standardization project                       | A3.1                     |
| 1/10/2020      | AW  | Removed optional Study ILO Dining   | A5.1.1, A7.2.1           |
| 2/11/2020      | AW  | PCR #3596 Relocated WP outlet on back patio so when its a deck the post won't interfere with outlet | A7.2                     |
| 4/27/2020      | AW  | Re-centered A roof massing dormers  | A1.1, A1.4, A1.13, A6.1  |
| 4/1/2021       | AW  | PCR #4348 Added led light & switch over tub in the En Suite Bath                                    | A7.2.1                   |
| 9/2/2021       | BB  | ADDED 2 TURTLE BACK VENTS TO C MASSING REAR ELEVATION   | A2.3, A2.9, A6.1.2       |
| 3/1/2022       | AW  | Changed 3050 twin temp at rear of Brkfst to 3050 single non-temp window                             | A2.1-A2.3, A5.1          |
| 7/10/2023      | AW  | PCR #5401 Clean up plumbing dims on slab plan   | A3.1                     |
| 8/1/2023       | AW  | Changed 2x6 walls to 2x4 wall at Bath 3/B3 En Ste bath and back of coat closet                      | A3.1, A5.1, A5.1.1       |
| 9/20/2023      | BB  | Removed shower and tub sizes from all fixtures on all affected pages                                | A3.1, A3.1.1, A5.1-5.1.2 |
| 3/28/2024      | SL  | PCR # 5769 Adjusted two electrical outlet locations in kitchen, added three outlets                 | A7.2                     |
| 5/13/2024      | CLJ | PCR # 5795 Rev kitchen cabinets dimensions to match cabinet layout document                         | A5.1, A7.2               |

# TOBACCO ROAD LOT 0174



FRONT ELEVATION "C"

SCALE: 3/16" = 1'-0"

ALL NON-MASONRY RETURNS TO  
BE HORIZONTAL SIDING

SEE SHEET D3 OF SDH TYPICAL  
DETAILS FOR SOFFIT DETAILS PER  
SOFFIT MATERIAL

| DATE | REVISION | BY | # | # | # | # |
|------|----------|----|---|---|---|---|
|      |          |    |   |   |   |   |
|      |          |    |   |   |   |   |
|      |          |    |   |   |   |   |
|      |          |    |   |   |   |   |




ELEVATION  
FRONT ELEVATION  
AVERY

SMITH DOUGLAS HOMES  
110 VILLAGE TRAIL  
SUITE 215  
WOODSTOCK, GA 30188  
www.smithdouglas.com

SMITH DOUGLAS HOMES  
expressly reserves its  
property rights in these  
plans and drawings.  
These plans and related  
drawings are not to be  
reproduced without written  
consent from SMITH  
DOUGLAS HOMES.


|                 |         |
|-----------------|---------|
| BY: KCC         | CH: AW  |
| DATE: 6/13/2024 |         |
| FACADE OPT: C   |         |
| PLAN ID:        |         |
| FND: ALL        | ELEV: C |
| PAGE NO: A1.1   |         |

# TOBACCO ROAD LOT 0174




LEFT ELEVATION "C"

SCALE: 1/8" = 1'-0"



REAR ELEVATION "C"

SCALE: 1/8" = 1'-0"



RIGHT ELEVATION "C"

SCALE: 1/8" = 1'-0"

| BY | REVISION | DATE |
|----|----------|------|
| #  | #        | #    |
| #  | #        | #    |
| #  | #        | #    |
| #  | #        | #    |
| #  | #        | #    |




ELEVATIONS  
SIDES AND REAR  
AVERY

SMITH DOUGLAS HOMES  
110 VILLAGE TRAIL  
SUITE 215  
WOODSTOCK, GA 30188  
www.smithdouglas.com

SMITH DOUGLAS HOMES  
expressly reserves its  
property rights in these  
plans and drawings.  
These plans and related  
drawings are not to be  
reproduced without written  
consent from SMITH  
DOUGLAS HOMES.

|                 |         |
|-----------------|---------|
| BY: KCC         | CH: AW  |
| DATE: 6/13/2024 |         |
| FACADE OPT: C   |         |
| PLAN ID:        |         |
| FND: ALL        | ELEV: C |
| PAGE NO: A2.1   |         |

# TOBACCO ROAD LOT 0174



SLAB PLAN

SCALE: 1/8" = 1'-0"

\*RADON VENT PROVIDED  
PER LOCAL CODE

REFER TO DETAIL 3/D1  
FOR BRICK LEDGE  
DETAIL WHEN BRICK  
VENEER IS CHOSEN

© SMITH DOUGLAS HOMES 2020

| DATE | REVISION | BY |
|------|----------|----|
| #    | #        | #  |
| #    | #        | #  |
| #    | #        | #  |
| #    | #        | #  |
| #    | #        | #  |



FOUNDATION PLAN  
SLAB PLAN  
AVERY

SMITH DOUGLAS HOMES  
110 VILLAGE TRAIL  
SUITE 215  
WOODSTOCK, GA 30188  
www.smithdouglas.com


SMITH DOUGLAS HOMES  
expressly reserves its  
property rights in these  
plans and drawings.  
These plans and related  
drawings are not to be  
reproduced without written  
consent from SMITH  
DOUGLAS HOMES.

|                 |         |
|-----------------|---------|
| BY: KCC         | CH: AW  |
| DATE: 6/13/2024 |         |
| FACADE OPT: C   |         |
| PLAN ID:        |         |
| FND: ALL        | ELEV: C |
| PAGE NO: A3.1   |         |





# TOBACCO ROAD LOT 0174



ROOF LAYOUT "C"  
SCALE : 1/8" = 1'-0"

| DATE | REVISION | BY |
|------|----------|----|
| #    | #        | #  |
| #    | #        | #  |
| #    | #        | #  |
| #    | #        | #  |
| #    | #        | #  |




ROOF LAYOUT  
ROOF PLAN  
AVERY

SMITH DOUGLAS HOMES  
110 VILLAGE TRAIL  
SUITE 215  
WOODSTOCK, GA 30188  
www.smithdouglas.com

SMITH DOUGLAS HOMES  
expressly reserves its  
property rights in these  
plans and drawings.  
These plans and related  
drawings are not to be  
reproduced without written  
consent from SMITH  
DOUGLAS HOMES.

|                 |         |
|-----------------|---------|
| BY: KCC         | CH: AW  |
| DATE: 6/13/2024 |         |
| FACADE OPT: C   |         |
| PLAN ID:        |         |
| FND: ALL        | ELEV: C |
| PAGE NO: A6.1   |         |

# TOBACCO ROAD LOT 0174



## ELECTRICAL LEGEND

|       |                                  |     |                                |
|-------|----------------------------------|-----|--------------------------------|
| \$    | SWITCH                           | ▼   | TV                             |
| \$3   | 3 WAY SWITCH                     | ⊕   | 120V RECEPTACLE                |
| \$4   | 4 WAY SWITCH                     | ⊕   | 120V SWITCHED RECEPTACLE       |
| ⊗     | CEILING FIXTURE                  | ⊕   | 220V RECEPTACLE                |
| ⊕     | KEYLESS                          | ⊕   | GFCI OUTLET                    |
| ⊗     | WALL MOUNT FIXTURE               | ⊕   | ARCH FAULT CIRCUIT INTERRUPTER |
| ○     | CEILING FIXTURE                  | †GL | GAS LINE                       |
| ●     | FLEX CONDUIT                     | †WL | WATER LINE                     |
| CH    | CHIMES                           | ↓   | HOSE BIBB                      |
| ▼     | TELEPHONE                        | ⊕   | FLOOD LIGHT                    |
| SD/Cd | SMOKE DETECTOR & CARBON MONOXIDE | ⊕   | 1x4 LUMINOUS FIXTURE           |
| SO    | SECURITY OUTLET                  | ⊕   | CEILING FAN                    |
| □     | GARAGE DOOR OPENER               | —   | ELECTRICAL WIRING              |
| ⊕     | EXHAUST FAN                      | ⊕   | CEILING FIXTURE                |
| ⊕     | FAN/LIGHT                        |     |                                |

ELECTRICAL PLANS TO FOLLOW ALL LOCAL CODES

APPROX. FIXTURE HGTS (MEASURED FROM BOTTOM OF FIXTURE)

|                         |                          |
|-------------------------|--------------------------|
| BREAKFAST/DINING ROOM   | 63" ABOVE FINISHED FLOOR |
| KITCHEN PENDANT LIGHTS  | 33" ABOVE COUNTER TOP    |
| TWO STORY FOYER FIXTURE | 96" ABOVE FINISHED FLOOR |
| CEILING FAN             | 96" ABOVE FINISHED FLOOR |

NOTE: FINAL PLACEMENT OF PHONE/CABLE T.B.D. ON SITE BY THE BUILDER

## FIRST FLOOR ELECTRICAL PLAN

SCALE: 1/8" = 1'-0"

| BY   | REVISION |
|------|----------|
| #    | #        |
| #    | #        |
| #    | #        |
| #    | #        |
| #    | #        |
| DATE |          |

**SMITH DOUGLAS HOMES**  
QUALITY | INTEGRITY | VALUE

ELECTRICAL PLAN  
FIRST FLOOR  
AVERY

SMITH DOUGLAS HOMES  
110 VILLAGE TRAIL  
SUITE 215  
WOODSTOCK, GA 30188  
www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves its property rights in these plans and drawings. These plans and related drawings are not to be reproduced without written consent from SMITH DOUGLAS HOMES.

|                 |         |
|-----------------|---------|
| BY: KCC         | CH: AW  |
| DATE: 6/13/2024 |         |
| FACADE OPT: C   |         |
| PLAN ID:        |         |
| FND: ALL        | ELEV: C |
| PAGE NO: A7.2   |         |



**CONNECTION SPECIFICATIONS (TYP. U.N.O.)**

| DESCRIPTION OF BLDG. ELEMENT                 | 3"x0.131" NAILS   | 3"x0.120" NAILS  |
|--|---|--|
| JOIST TO SOLE PLATE                          | (3) TOENAILS<br>NAILS @ 4" o.c.   | (3) TOENAILS*<br>NAILS @ 4" o.c.   |
| SOLE PL. TO JOIST/RIM OR BLK'G STUD TO PLATE | (4) TOENAILS/(3)END NAILS   | (4) TOENAILS/(4)END NAILS*   |
| RIM TO TOP PLATE                             | TOENAILS @ 6" o.c.  | TOENAILS @ 4" o.c.*  |
| BLK'G. BTWN. JOISTS TO TOP PL.               | (3) TOENAILS EA. END  | (3) TOENAILS EA. END*  |
| DOUBLE STUD                                  | NAILS @ 16" o.c.  | NAILS @ 16" o.c.   |
| DOUBLE TOP PLATE                             | NAILS @ 12" o.c.  | NAILS @ 8" o.c.  |
| DOUBLE TOP PLATE LAP SPLICE                  | (12) NAILS IN LAPPED AREA (24" MIN.)  | (15) NAILS IN LAPPED AREA (24" MIN.)   |
| TOP PLATE LAP @ CORNERS & INTERSECTING WALLS | (3) NAILS   | (3) NAILS  |
| RAFTER/TRUSS TO TOP PLATE                    | (4) TOENAILS + (1) SIMPSON H25T   | (4) TOENAILS + (1) SIMPSON H25T  |
| GAB. END TRUSS TO DBL. TOP PL.               | TOENAILS @ 8" o.c.  | TOENAILS @ 6" o.c.   |
| R.T. w/ HEEL HT. 9 1/4" TO 12"               | 2x10 BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE w/ TOENAILS @ 6" o.c.   | 2x10 BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE w/ TOENAILS @ 4" o.c.  |
| R.T. w/ HEEL HT. 12" TO 16"                  | 2x12 BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE w/ TOENAILS @ 6" o.c.   | 2x12 BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE w/ TOENAILS @ 4" o.c.  |
| R.T. w/ HEEL HT. UP TO 24"                   | LAP WALL SHTG. w/ DBL. TOP PL. & INSTALL ON TRUSS VERT. - FASTEN w/ NAILS @ 6" o.c.   | LAP WALL SHTG. w/ DBL. TOP PL. & INSTALL ON TRUSS VERT. - FASTEN w/ NAILS @ 6" o.c.*   |
| R.T. w/ HEEL HT. 24" TO 48"                  | LAP WALL SHTG. w/ DBL. TOP PL. & INSTALL ON TRUSS VERT. - FASTEN w/ NAILS @ 6" o.c. PROVIDE 2x BLK @ EA. BAY AT TOP OF HEEL | LAP WALL SHTG. w/ DBL. TOP PL. & INSTALL ON TRUSS VERT. - FASTEN w/ NAILS @ 6" o.c. PROVIDE 2x BLK @ EA. BAY AT TOP OF HEEL* |
| WALL TO FOUNDATION                           | WALL SHTG. LAP w/ SILL PL. & FASTENED PER SHEAR WALL FASTENING SPEC.  |  |

\* 2 1/2"x0.113 IS AN ACCEPTABLE ALTERNATIVE TO A 3"x0.120", SAME SPACING OR NUMBER OF NAILS. (ONLY ACCEPTABLE WHERE \* ARE SHOWN)

**ADDITIONAL NOTES FOR TRUSS & I-JOIST MANUFACTURER**

ROOF TRUSS AND ENGINEERED JOISTS SHALL BE DESIGNED TO MEET THE DEFLECTION CRITERIA BELOW, UNLESS NOTED OTHERWISE ON PLAN. MULHERN & KULP CANNOT BE HELD RESPONSIBLE FOR ANY STRUCTURAL ISSUES RELATED TO ANY BUILDING COMPONENT IF COMPONENT SHOP DRAWINGS ARE NOT SUBMITTED TO MK FOR REVIEW PRIOR TO FABRICATION, DELIVERY, OR INSTALLATION.

TRUSSES/JOISTS SHALL BE DESIGNED SO THAT DIFFERENTIAL DEFLECTION BETWEEN ADJACENT PARALLEL TRUSSES/JOISTS OR GIRDER TRUSSES/FLUSH BEAMS DO NOT EXCEED THE FOLLOWING:

A. ROOF TRUSSES:  
 1/4" DEAD LOAD  
 ATTIC TRUSSES, & I-JOISTS:  
 1/8" DEAD LOAD

ABSOLUTE DEAD LOAD DEFLECTION OF ATTIC TRUSSES WHEN ADJACENT TO FLOOR FRAMING BY OTHERS SHALL BE LIMITED TO 3/16". (NOT DIFFERENTIAL DEFLECTION)

**VENEER LINTEL SCHEDULE**

| SPAN (MAX) | HEIGHT OF VENEER ABOVE LINTEL | STEEL ANGLE SIZE |
|------------|-------------------------------|------------------|
| 3'-0"      | 20 FT. MAX                    | L3"x3"x1/4"      |
|            | 3 FT. MAX                     | L3"x3"x1/4"      |
| 6'-0"      | 12 FT. MAX                    | L4"x3"x1/4"      |
|            | 20 FT. MAX                    | L5"x3 1/2"x3/8"  |
| 8'-0"      | 3 FT. MAX                     | L4"x4"x1/4" *    |
|            | 12 FT. MAX                    | L5"x3 1/2"x3/8"  |
|            | 16 FT. MAX                    | L6"x3 1/2"x3/8"  |
| 9'-6"      | 12 FT. MAX                    | L6"x3 1/2"x3/8"  |

ALL LINTELS:  
 \* SMALL SUPPORT 2 1/2" - 3 1/2" VENEER w/ 40 PSI MAXIMUM HEIGHT.  
 \* 1/2" SHALL HAVE 4" MIN. BEARING  
 \* 1/4" SHALL HAVE 8" MIN. BEARING  
 \* 1/8" SHALL NOT BE FASTENED BACK TO HEADER.  
 \* 1/4" SHALL BE FASTENED BACK TO WOOD HEADER IN WALL @ 48" o.c. w/ 1/2" DIA. x 3 1/2" LONG LAG SCREWS IN 2" LONG VERTICALLY SLOTTED HOLES.  
 \* MAX. VENEER HT. APPLIES TO ANY PORTION OF BRICK OVER THE OPENING.  
 \* ALL LINTELS SHALL BE LONG LEGS VERTICAL.  
 \* WHEN SUPPORTING VENEER < 3" WIDE THE EXTERIOR TOE OF THE HORIZONTAL LEG MAY BE CUT IN THE FIELD TO BE 3/4" WIDE OVER THE BEARING LENGTH ONLY. THIS IS TO ALLOW FOR MORTAR JOINT FINISHING.  
 \* SEE STRUCTURAL PLANS FOR ANY LINTEL CONDITION NOT ENCOMPASSED BY THE ABOVE PARAMETERS.  
 \* FOR QUEEN VENEER USE L4x3x1/4".

**GENERAL STRUCTURAL NOTES**

**FOUNDATION**

- DESIGN IS BASED ON 2018 NCSBG-RESIDENTIAL CODE & 2018 IRC WITH SOUTH CAROLINA AMENDMENTS
- FOOTING DESIGN - 2,000 PSF NET ALLOWABLE SOIL BEARING PRESSURE IS ASSUMED. BUILDER/CONTRACTOR MUST VERIFY.
- FASTEN 2x4/6 SILL PLATES TO CONC FND WITH A MINIMUM OF 2 ANCHORS PER PLATE, 12" MAX. FROM PLATE ENDS - UTILIZING:
  - 1/2" DIA. ANCHOR BOLTS @ 6'-0" O.C., 7" MIN. EMBEDMENT
  - FA4 ANCHOR STRAPS @ 6'-0" O.C.
- FASTEN 2x10 SILL PLATES TO PRECAST BSMT WALLS WITH A MINIMUM OF 2 ANCHORS PER PLATE, 12" MAX. FROM PLATE ENDS - UTILIZING:
  - 1/2" DIA. BOLTS @ 2'-0" O.C.
- ALL LUMBER EXPOSED TO WEATHER OR IN CONTACT W/ PERIMETER FOUNDATION SHALL BE PRESERVATIVE TREATED SOUTHERN PINE #2.
- BUILDER TO VERIFY CORROSION-RESISTANCE COMPATIBILITY OF HARDWARE & FASTENERS IN CONTACT W/ PRESERVATIVE-TREATED WOOD. CONTACT LUMBER & HARDWARE SUPPLIERS TO COORD.
- FOUNDATION WALLS & FOOTINGS SHALL BE PLAIN CONCRETE, U.N.O.
- CONCRETE DESIGN BASED ON ACI 318. CONCRETE SHALL ATTAIN THE FOLLOWING MIN. COMPRESSIVE STRENGTHS IN 28 DAYS, U.N.O.:
  - f'c = 4000 psi: FOUNDATION WALLS
  - 3000 psi: FOOTINGS & INTERIOR SLABS ON GRADE
  - 3500 psi: GARAGE & EXTERIOR SLABS ON GRADE
  - fy = 60,000 psi
- BASEMENT FOUNDATION WALL DESIGN BASED ON:
  - 8' OR 4' HEIGHT (AS NOTED ON PLANS)
  - TALLER WALLS MUST BE ENGINEERED.
- BASEMENT WALL DESIGN IS BASED ON 30 OR 45 PCF BACKFILL SOIL TYPE CLASSIFICATIONS:
  - 30 PCF TYPE (GM, GP, SM, SP)
  - 45 PCF TYPE (GM, GC, SM, SM-SC, ML)
- IMPORTANT - IF 60 PCF SOIL TYPE (SG, ML-CL, OR CL) IS UTILIZED FOR BACKFILL, CONTACT MULHERN & KULP FOR FURTHER EVALUATION OF FOUNDATION DESIGN.
- BASEMENT WALLS SHALL BE BRACED, PRIOR TO BACKFILLING, BY ADEQUATE TEMPORARY BRACING OR INSTALL 1st FLOOR DECK.
- ALL CONCRETE EXPOSED TO THE WEATHER SHALL NOT HAVE LESS THAN 5% OR MORE THAN 1% AIR ENTRAINMENT.
- ALL FOOTINGS SHALL BEAR BELOW FROST LINE (TYP.) OR 12" MIN IN REGIONS WHERE CODE FROST DEPTH IS NOT APPLICABLE. CONSULT SOILS REPORT OR BUILDING DEPT. FOR MINIMUM DEPTH BELOW GRADE.
- FOOTINGS AND SLABS ON GRADE SHALL BEAR ON VIRGIN SOIL OR 95% COMPACTED FILL.
- PROVIDE CONTROL JOINTS AT ALL INSIDE CORNERS OF SLAB EDGES, AND OTHER LOCATIONS WHERE SLAB CRACKS ARE LIKELY TO DEVELOP.
  - JOINTS SHALL BE LOCATED @ 10'-0" O.C. (RECOMMENDED) OR 15'-0" O.C. (MAXIMUM)
  - JOINT GRID PATTERN SHALL BE AS CLOSE TO SQUARES AS POSSIBLE (1:1 RATIO), WITH A MAXIMUM OF 1:1.5 RATIO
  - CONTROL JOINTS SHALL NOT BE INSTALLED IN STRUCTURAL SLABS
- TYPICAL REINFORCEMENT DETAILS: PROVIDE 3" MIN. CLEAR COVER WHERE CAST AGAINST EARTH, 1 1/2" MIN. CLEAR COVER AGAINST FORMS. LAP ALL REBAR 48 BAR DIAMETERS MIN. (24" FOR #4 BARS) & BEND BARS AND LAP AT CORNERS. PROVIDE 6" HOOK INTO SUPPORTING FOOTINGS WHEN FOOTINGS INTERSECT.
- DIMENSIONS BY OTHERS, BUILDER TO VERIFY.

**LEGEND**

- RT INDICATES ROOF TRUSSES @ 24" O.C. PER ROOF. MANUF. (TYP. U.N.O.)
- OF INDICATES TRUSS OVERFRAMING @ 24" O.C. (TYP. U.N.O.)
- F-1 INDICATES 14" DEEP FLOOR I-JOISTS (24" O.C. MAX SPACING). JOIST SERIES AND SPACING SHALL BE THE RESPONSIBILITY OF THE JOIST MANUFACTURER
- D-1 INDICATES 2x8 P.T. DECK JOISTS @ 16" O.C. (MAX)
- INDICATES LOCATIONS OF POTENTIAL TILE FLOOR. JOIST MANUFACTURER SHALL DESIGN FLOOR SYSTEM FOR ADDL 10 PSF DEAD LOAD AT THESE LOCATIONS.
- INTERIOR BEARING WALL
- BEARING WALL ABOVE (B.W.A.)
- BEAM/HEADER
- METAL HANGER
- INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.

**LATERAL/WALL BRACING & WALL SHEATHING SPECIFICATIONS**

THIS MODEL HAS BEEN DESIGNED TO RESIST LATERAL FORCES RESULTING FROM:  
**120MPH WIND IN 2018 NCSBG-RC & 120MPH WIND IN 2018 IRC**  
 (120 MPH WIND SPEED IN ASCE 7 WIND MAP, PER IRC R301.2.1.1) EXP. B, RISK CAT. 2 & SEISMIC CAT. A/B.

THE DESIGN WAS COMPLETED PER 2015 & 2018 IBC (SECTION 1609) & ASCE 7, AS PERMITTED BY R301.1.3 OF THE 2018 NCSBG-RC & 2018 IRC. ACCORDINGLY, THIS MODEL, AS DOCUMENTED AND DETAILED HEREWITHIN, IS ADEQUATE TO RESIST THE CODE REQUIRED LATERAL FORCES.

DESIGN WIND UPLIFT LOADS HAVE BEEN CALCULATED UTILIZING ASCE 7 (ACCEPTED ENGINEERING PRACTICE) AS ALLOWED PER 2018 NCSBG-RC & 2018 IRC SECTION R802.11.1.1. THIS MODEL HAS BEEN DETAILED WHERE REQUIRED & ENGINEERED TO RESIST THE WIND UPLIFT LOAD PATH PER SECTIONS R602.3.5 & R802.11.

**EXT. WALL SHEATHING SPECIFICATION**


- 7/16" OSB OR 15/32" PLYWOOD:
  - FASTEN SHEATHING w/ 2 3/8"x0.113 NAILS @ 6" o.c. AT EDGES & @ 12" o.c. IN THE PANEL FIELD. (TYP. U.N.O.)
- ALL SHEATHING PANELS SHALL BE ORIENTED VERTICALLY (LONG DIRECTION PARALLEL TO STUDS) AND INSTALLED FULL HEIGHT OF SHEAR WALL - OR - 2x HORIZONTAL BLOCKING SHALL BE PROVIDED TO SUPPORT ALL UNSUPPORTED PANEL EDGES & EDGE FASTENING.
- ALL EXT. WALLS SHALL BE CONTINUOUSLY SHEATHED AND ARE CONSIDERED SHEAR WALLS.
- ALT. STAPLE CONNECTION SPEC: 1 3/4" 16 GA STAPLES (1/6" CROWN) @ 3" o.c. AT EDGES & @ 6" o.c. IN FIELD.

**3" O.C. EDGE NAILING**

- AT DESIGNATED AREAS - FASTEN PANEL EDGES OF WOOD STRUCTURAL WALL SHEATHING TO FRAMING w/ 2 3/8" x 0.113" NAILS @ 3" O.C. AND 12" O.C. IN THE PANEL FIELD NO STAPLE ALTERNATIVE AVAILABLE AT THIS SPEC. ALL SHEATHING PANELS SHALL BE ORIENTED VERTICALLY (LONG DIRECTION PARALLEL TO STUD) AND INSTALLED FULL HEIGHT OF SHEAR WALL - OR - 2x HORIZONTAL BLOCKING SHALL BE PROVIDED TO SUPPORT UNSUPPORTED PANEL EDGES AND 3" O.C. EDGE FASTENING.

**NOTES**

- SEE CONNECTION SPECIFICATIONS CHART FOR STANDARD SHEAR TRANSFER DETAILING. IF ADDITIONAL CAPACITY IS REQUIRED BY DESIGN, IT WILL BE SPECIFICALLY NOTED ON PLAN.
- DESIGN ASSUMES 16" O.C. MAX. STUD SPACING, U.N.O.
- ALL STRUCTURAL PANELS ARE TO BE DIRECTLY APPLIED TO STUD FRAMING.
- PRE-MANUFACTURED PANELIZED WALLS: FASTEN TOGETHER END STUDS OF WALL PANELS SHEATHED w/ OSB OR PLYWOOD w/ 3" x 0.120" NAILS @ 4" O.C. (THRU ONE SIDE ONLY)



**NON-BEARING HEADER SCHEDULE**

| SPAN        | 2x4 NON-BEARING PARTITION WALL | 2x6 NON-BEARING PARTITION WALL |
|-------------|--------------------------------|--------------------------------|
| UP TO 3'-0" | (1)2x4 FLAT                    | (1)2x6 FLAT                    |
| UP TO 6'-0" | (2)2x4                         | (3)2x4                         |
| UP TO 8'-0" | (2)2x6                         | (3)2x6                         |

NOTES:  
 ALL NON-BEARING INTERIOR STUD WALLS SHALL BE CONSTRUCTED WITH 2x 'STUD' GRADE MEMBERS SPACED @ 24" O.C. (MAX.)

**FLOOR FRAMING**

- I-JOISTS SHALL BE DESIGNED BY MANUF. TO MEET OR EXCEED L/480 LIVE LOAD DEFLECTION CRITERIA. EXCLUDES STONE/MARBLE OR NET BED CONSTRUCTED FLOORS - CONTACT MK FOR EXCLUDED FLOOR DESIGNS)
- PER THE GUIDELINES OF THE TILE COUNCIL OF NORTH AMERICA (TCNA HANDBOOK), IT SHALL BE THE FLOOR FINISH INSTALLER'S RESPONSIBILITY TO VERIFY THAT THE FINISHES TO BE INSTALLED MATCH THE DESIGN CRITERIA NOTED ABOVE (UNDER 'DESIGN LOADS').
- FLOOR SYSTEMS & SHEATHING HAVE BEEN DESIGNED TO SUPPORT ADDITIONAL DEAD LOAD FROM CERAMIC TILE (EXCLUDING MARBLE OR STONE). HOWEVER, IT SHALL BE THE FLOOR FINISH INSTALLER'S RESPONSIBILITY TO PROVIDE PROPER UNDERLAYMENT, UNCOUPLING MEMBRANE AND MORTAR/GROUT FOR THE ASSEMBLY DESIGNATIONS IN THE TCNA HANDBOOK (TILE COUNCIL OF NORTH AMERICA).
- AT I-JOIST FLOORS, PROVIDE 1" MIN. OSB RIM BOARD.
- METAL HANGERS SHALL BE SPECIFIED BY MANUFACTURER, U.N.O.
- I-JOIST SHOP DWGS. SHALL BE SUBMITTED TO ARCH. & ENG. FOR REVIEW AND APPROVAL PRIOR TO FABRICATION OR DELIVERY.
- FLOOR SHEATHING SHALL BE 23/32" A.P.A. RATED 'STURD-I-FLOOR' 24" O.C. EXPOSURE 1 (OR APPROVED EQUAL) WITH TONGUE AND GROOVE EDGES. FASTEN TO FRAMING MEMBERS w/ GLUE AND:
  - 2 1/2" x 0.131" NAILS @ 6" o.c. @ PANEL EDGES @ 12" o.c. FIELD.
  - 2 3/8" x 0.120" NAILS @ 4" o.c. @ PANEL EDGES @ 8" o.c. FIELD.
  - 2 3/8" x 0.113" NAILS @ 3" o.c. @ PANEL EDGES @ 6" o.c. IN FIELD.

**ROOF FRAMING**

- ROOF SHEATHING SHALL BE 7/16" A.P.A. RATED SHEATHING 24/16 EXPOSURE 1 (OR APPROVED EQUAL). FASTEN TO FRAMING MEMBERS:
  - w/ 2 1/2" x 0.131" NAILS @ 6" o.c. @ PANEL EDGES @ 12" o.c. FIELD.
  - w/ 2 3/8" x 0.120" NAILS @ 4" o.c. @ PANEL EDGES @ 8" o.c. FIELD.
  - w/ 2 3/8" x 0.113" NAILS @ 3" o.c. @ PANEL EDGES @ 6" o.c. FIELD.
- WITHIN 48" OF ALL ROOF EDGES, RIDGES, & HIPS FASTEN ROOF SHEATHING FIELDS PER EDGE NAILING SPEC.
- FASTEN EACH ROOF TRUSS TO TOP PLATE w/ USP RTTA CLIP (OR APPROVED EQUAL) @ ALL BEARING POINTS. PROVIDE (2) RTTA CLIPS AT 2-PLY GIRDER TRUSSES, (3) RTTA CLIPS AT 3-PLY GIRDER TRUSSES & ROOF BEAMS - AT ALL BEARING POINTS.
- METAL HANGERS SHALL BE SPECIFIED BY THE MANUFACTURER, U.N.O.
- ROOF TRUSS SHOP DWGS. SHALL BE SUBMITTED TO ARCH & ENG. FOR REVIEW AND APPROVAL PRIOR TO FABRICATION OR DELIVERY.
- ERECT AND INSTALL ROOF TRUSSES PER WTA & TPI'S BCSI 1 'GUIDE TO GOOD PRACTICE FOR HANDLING, INSTALLING & BRACING OF METAL PLATE CONNECTED WOOD TRUSSES.'
- SUPPORT SHORT SPAN ROOF TRUSSES w/2x4 LEDGER FASTENED TO FRAMING w/(2) 3" x 0.120" NAILS @ 16" o.c. (UP TO 7' SPAN).

**MEANS & METHODS NOTES**

THE STRUCTURE IS DESIGNED TO BE SELF SUPPORTING AND STABLE AFTER THE BUILDING IS FINISHED AND ALL PLAN, DETAIL, AND NOTE SPECIFICATIONS HAVE BEEN COMPLETED. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE THE ERECTION PROCEDURES AND SEQUENCE TO INSURE THE SAFETY OF THE BUILDING AND ITS COMPONENTS DURING CONSTRUCTION. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF NECESSARY SHORING, SHEETING, TEMPORARY BRACING, GUYS, AND TIE-DOWNS. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SHORING AND BRACING REQUIRED TO STABILIZE AND PROTECT EXISTING AND ADJACENT STRUCTURES AND SYSTEMS DURING COURSE OF DEMOLITION AND CONSTRUCTION OF THE PROJECT.

STRUCTURAL DESIGN AND SPECIFICATIONS ASSUME THAT ALL SUPPORTING AND NON-SUPPORTING ELEMENTS IN CONTACT WITH FLOOR FRAMING ARE LEVEL, INCLUDING, BUT NOT LIMITED TO; FOUNDATIONS, SLABS ON GRADE, BEAMS, WALLS, AND NON-BEARING ELEMENTS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY LEVELNESS AND MAKE ADJUSTMENTS AS NECESSARY, INCLUDING CONSIDERATION OF THOSE AREAS THAT MAY BE WITHIN CONTRACTUAL, INDUSTRY, OR WARRANTY TOLERANCES.

**GENERAL STRUCTURAL NOTES**

- DESIGN IS BASED ON 2018 NCSBG-RESIDENTIAL CODE & 2018 IRC WITH SOUTH CAROLINA AMENDMENTS
- WOOD FRAME ENGINEERING IS BASED ON NDS, "NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION" - LATEST EDITION.
- DESIGN LOADS:
  - ROOF: LIVE = 20 PSF  
DEAD = 7 PSF T.C., 10 PSF B.C.  
LOAD DURATION FACTOR = 1.25
  - FLOOR: LIVE = 40 PSF (30 PSF @ SLEEPING AREAS)  
DEAD = 10 PSF (1-JOISTS)
  - ADD'L 10 PSF @ CERAMIC TILE IN BATHS & LAUND.
  - SOIL: 2,000 PSF ASSUMED ALLOWABLE BEARING PRESSURE (TO BE VERIFIED BY BUILDER)

**GENERAL FRAMING**

- ALL TYP. NAIL FASTENER REQUIREMENTS ARE NOTED IN STANDARD CONNECTIONS TABLE (IRC TABLE R602.3(1)) OR ON PLANS. ALL NAILS SPECIFIED ARE MIN DIAMETER AND LENGTH REQUIRED FOR CONNECTION. ALL HANGER NAILS SHALL BE INSTALLED PER MANUFACTURER'S REQUIREMENTS FOR MAX CHARTED CAPACITY. NOTE: HANGERS USE COMMON NAIL DIAMETERS NOT TYPICAL FRAMING GUN NAILS.
- EXT. & INT. BEARING WALLS SHALL BE 2x4 OR 2x6 (AS SHOWN ON PLANS) @ 16" O.C. SPF/SP 'STUD' GRADE LUMBER, OR BETTER, U.N.O.
  - WALLS OVER 12' TALL SHALL BE PER PLAN.
- ALL INTERIOR BEARING WALLS ARE TO BE SHEATHED w/ GYP WALL BOARD (ONE SIDE MIN.) OR PROVIDE MID HT. BLOCKING.
- ALL HEADERS, BEAMS & OTHER STRUCTURAL MEMBERS SHALL BE SPRUCE-PINE-FIR #2 (SPF) OR SOUTHERN PINE #2 (SP) LUMBER, OR BETTER. SUPPORT ALL HEADERS/ BEAMS w/ (1)2x JACK STUD (1)2x KING STUD, MINIMUM.
  - NUMBER OF STUDS SPECIFIED AT A SUPPORT INDICATES THE NUMBER OF JACK STUDS REQUIRED, U.N.O..
- ALL NON-BEARING INTERIOR STUD WALLS SHALL BE CONSTRUCTED WITH 2x 'STUD' GRADE MEMBERS SPACED @ 24" O.C. (MAX., U.N.O.)
  - HEADERS IN NON-LOAD BEARING WALLS SHALL BE: (1)2x4/6 FLAT @ OPENINGS UP TO 4', (2)2x4/6 FLAT UP TO 8'.
- ALL FRAMING LUMBER SHALL BE DRIED TO 15% MC (KD-15).
- ENGINEERED LUMBER BEAMS TO MEET OR EXCEED THE FOLLOWING:
  - 'LVL' - Fb=2600 psi; Fv=285 psi; E=2.0x10<sup>6</sup> psi
- ENGINEERED LUMBER POSTS TO MEET OR EXCEED THE FOLLOWING:
  - 'LVL' - Fb=2400 psi; Fc11=2500 psi; E=1.8x10<sup>6</sup> psi
- FOR 2 & 3 PLY BEAMS OF EQUAL 1 1/2" MAX. WIDTH, FASTEN PLIES TOGETHER WITH 3 ROWS OF 3"x0.120" NAILS @ 8" O.C. OR 2 ROWS USP #635 SCREWS (OR 3/2" TRUSSLOK SCREWS) @ 16" O.C. USE A MINIMUM OF 4 ROWS FOR BEAM DEPTHS OF 14" OR GREATER. APPLY FASTENING AT BOTH FACES FOR 3-PLY CONDITION. LOCATE TOP & BOTTOM NAILS/SCREWS 2" FROM EDGE. SOLID 3 1/2" OR 5 1/2" BEAMS ARE ACCEPTABLE. USE 2 ROWS OF NAILS FOR 2x6 & 2x8 MEMBERS.
- FOR 4 PLY BEAMS OF EQUAL 1 1/2" MAX. WIDTH, FASTEN PLIES TOGETHER WITH 3 ROWS OF USP #66 SCREWS (OR 6 3/4" TRUSSLOK SCREWS) @ 16" O.C. USE A MINIMUM OF 4 ROWS FOR BEAM DEPTHS OF 14" OR GREATER. APPLY FASTENING AT BOTH FACES (ONE SIDE ONLY FOR TRUSSLOK SCREWS). LOCATE TOP AND BOTTOM SCREWS 2" FROM EDGE. A SOLID 7" BEAM IS ACCEPTABLE.
- PROVIDE SOLID BLOCKING IN FLOOR SYSTEM UNDER ALL POSTS CONTINUOUS TO END/BEARING. BLOCKING TO MATCH POST ABOVE.
- ALL EXTERIOR 4x4 WOOD POSTS SHALL HAVE USP BC522-4 CAP & PA44E BASE, U.N.O.
- CORROSION NOTES:
  - BUILDER RESPONSIBLE TO DETERMINE CORROSION-RESISTANCE REQUIREMENTS AND COMPATIBILITY OF HARDWARE, FASTENERS AND CONNECTORS FOR ENVIRONMENTAL EXPOSURE AND IN CONTACT w/ PRESERVATIVE-TREATED WOOD OF ACTUAL FINAL CONDITIONS AND SOURCED MATERIALS. CONTACT LUMBER & HARDWARE SUPPLIERS TO COORD.
  - ALL FASTENERS AND CONNECTORS EXPOSED TO SALT WATER (WITHIN 300' OF SALT WATER SHORELINE, INCLUDING VENTED SPACES) SHALL BE STAINLESS STEEL.

**TOBACCO Lot 174**

**MULHERN+KULP**  
 RESIDENTIAL STRUCTURAL ENGINEERING  
 3625 Remondino Parkway, Suite 105 - Alpharetta, GA 30022  
 770-777-8874 - mulhern@mulhernkulp.com  
 NC License # C-3825

Mulhern+Kulp project number:  
**256-22014**

project mgr: **SMK**  
 drawn by: **MMD**  
 issue date: **09-29-2023**

REVISIONS:  
 date: initial:

**SMITH DOUGLAS HOMES**

**GENERAL STRUCTURAL NOTES**

**AVERY MODEL**

120 MPH WIND ZONE  
 NORTH CAROLINA

sheet:  
**SO.0**



|                              |            |
|------------------------------|------------|
| Mulhern+Kulp project number: | 256-22014  |
| project mgr:                 | SMK        |
| drawn by:                    | MMD        |
| issue date:                  | 09-29-2023 |
| REVISIONS:                   |            |
| date:                        | initial:   |



SMITH DOUGLAS  
 HOMES

**TOBACCO**  
 Lot 174

REFER TO S.O. FOR TYPICAL  
 STRUCTURAL NOTES & SCHEDULES

MONO-SLAB FOUNDATION  
 AVERY MODEL  
 120 MPH WIND ZONE  
 NORTH CAROLINA

sheet:  
**S1.0**




**2 MONO-SLAB FOUNDATION PLAN**  
 SCALE: 1/4"=1'-0" ON 22x34  
 1/8"=1'-0" ON 11x17  
 ELEV. B, C, E, F, H, K, I, N  
 (SEE ELEV. A FOR ADD'L INFO)


**1 MONO-SLAB FOUNDATION PLAN**  
 SCALE: 1/4"=1'-0" ON 22x34  
 1/8"=1'-0" ON 11x17  
 ELEV. A, D, M

**LEGEND**


- R.T. INDICATES ROOF TRUSSES @ 24" O.C. PER ROOF. MANUF. (TYP. U.N.O.)
- O.F. INDICATES TRUSS OVERFRAMING @ 24" O.C. (TYP. U.N.O.)
- F.J. INDICATES 14" DEEP FLOOR I-JOISTS (24" O.C. MAX SPACING). JOIST SERIES AND SPACING SHALL BE THE RESPONSIBILITY OF THE JOIST MANUFACTURER
- D.J. INDICATES 2x8 P.T. DECK JOISTS @ 16" O.C. (MAX)
- INDICATES LOCATIONS OF POTENTIAL TILE FLOOR. JOIST MANUFACTURER SHALL DESIGN FLOOR SYSTEM FOR ADD'L 10 PSF DEAD LOAD AT THESE LOCATIONS.
- INTERIOR BEARING WALL
- BEARING WALL ABOVE (B.W.A.)
- BEAM/HEADER
- METAL HANGER
- INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.




**1 PARTIAL ROOF FLOOR FRAMING PLAN**  
 SCALE: 1/4"=1'-0" ON 22x34  
 1/8"=1'-0" ON 11x17  
 OPT. EXTENDED COVERED PORCH  
 ELEV. A SHOWN  
 ALL ELEV. SIM.




**2 PARTIAL MONO SLAB FOUNDATION PLAN**  
 SCALE: 1/4"=1'-0" ON 22x34  
 1/8"=1'-0" ON 11x17  
 OPT. EXTENDED PORCH  
 ELEV. A SHOWN  
 ALL ELEV. SIM.



**3 PARTIAL 1ST FLOOR FRAMING PLAN BASEMENT CONDITION**  
 SCALE: 1/4"=1'-0" ON 22x34  
 1/8"=1'-0" ON 11x17  
 OPT. EXTENDED COVERED PORCH  
 ELEV. A SHOWN  
 ALL ELEV. SIM.



**4 PARTIAL BASEMENT FOUNDATION PLAN (SUPERIOR WALLS)**  
 SCALE: 1/4"=1'-0" ON 22x34  
 1/8"=1'-0" ON 11x17  
 OPT. EXTENDED COVERED PORCH  
 ELEV. A SHOWN  
 ALL ELEV. SIM.



**5 PARTIAL BASEMENT FOUNDATION PLAN (C.I.P.)**  
 SCALE: 1/4"=1'-0" ON 22x34  
 1/8"=1'-0" ON 11x17  
 OPT. EXTENDED COVERED PORCH  
 ELEV. A SHOWN  
 ALL ELEV. SIM.

**TOBACCO  
 Lot 174**

REFER TO S0.0 FOR TYPICAL  
 STRUCTURAL NOTES & SCHEDULES


**LEGEND**

|  |  |
|--|--|
|  | INDICATES ROOF TRUSSES @ 24" O.C. PER ROOF. MANUF. (TYP. U.N.O.)   |
|  | INDICATES TRUSS OVERFRAMING @ 24" O.C. (TYP. U.N.O.)   |
|  | INDICATES 14" DEEP FLOOR I-JOISTS (24" O.C. MAX SPACING). JOIST SERIES AND SPACING SHALL BE THE RESPONSIBILITY OF THE JOIST MANUFACTURER |
|  | INDICATES 2x8 P.T. DECK JOISTS @ 16" O.C. (MAX)  |
|  | INDICATES LOCATIONS OF POTENTIAL TILE FLOOR. JOIST MANUFACTURER SHALL DESIGN FLOOR SYSTEM FOR ADDL. 10 PSF DEAD LOAD AT THESE LOCATIONS. |
|  | INTERIOR BEARING WALL  |
|  | BEARING WALL ABOVE (B.W.A.)  |
|  | BEAM/HEADER  |
|  | METAL HANGER   |
|  | INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.   |

**TOBACCO  
 Lot 174**

THIS LEVEL HAS BEEN DESIGNED  
 FOR 9'-1" PLATE HEIGHT  
 REFER TO S.O. FOR TYPICAL  
 STRUCTURAL NOTES & SCHEDULES

| LEGEND |  |
|--------|--|
|        | INDICATES ROOF TRUSSES @ 24" O.C. PER ROOF. MANUF. (TYP. U.N.O.)   |
|        | INDICATES TRUSS OVERFRAMING @ 24" O.C. (TYP. U.N.O.)   |
|        | INDICATES 14" DEEP FLOOR I-JOISTS (24" O.C. MAX SPACING). JOIST SERIES AND SPACING SHALL BE THE RESPONSIBILITY OF THE JOIST MANUFACTURER |
|        | INDICATES 2x8 P.T. DECK JOISTS @ 16" O.C. (MAX)  |
|        | INDICATES LOCATIONS OF POTENTIAL TILE FLOOR. JOIST MANUFACTURER SHALL DESIGN FLOOR SYSTEM FOR ADDL. 10 PSF DEAD LOAD AT THESE LOCATIONS. |
|        | INTERIOR BEARING WALL  |
|        | BEARING WALL ABOVE (B.W.A.)  |
|        | BEAM/HEADER  |
|        | METAL HANGER   |
|        | INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.   |




**1 ROOF FRAMING PLAN**  
 SCALE: 1/4"=1'-0" ON 22x34  
 1/8"=1'-0" ON 11x17  
 ELEV. C, F, & I

ROOF FRAMING PLAN  
 A VERY MODEL  
 120 MPH WIND ZONE  
 NORTH CAROLINA

sheet:  
**S3.1**






**1 PARTIAL ROOF FRAMING PLAN**

SCALE: 1/4"=1'-0" ON 22x34  
 1/8"=1'-0" ON 11x17


OPT. COVERED PORCH  
 ELEV. A SHOWN  
 ALL ELEV. SIM.



**2 PARTIAL MONO SLAB FOUNDATION PLAN**

SCALE: 1/4"=1'-0" ON 22x34  
 1/8"=1'-0" ON 11x17

OPT. COVERED PORCH  
 ELEV. A SHOWN  
 ALL ELEV. SIM.



**3 PARTIAL ROOF FRAMING PLAN**


SCALE: 1/4"=1'-0" ON 22x34  
 1/8"=1'-0" ON 11x17

OPT. BED. 3 EN SUITE  
 ELEV. A SHOWN  
 ALL ELEV. SIM.


**TOBACCO  
 Lot 174**

REFER TO S0.0 FOR TYPICAL  
 STRUCTURAL NOTES & SCHEDULES


| LEGEND |  |
|--------|--|
|        | INDICATES ROOF TRUSSES @ 24" O.C. PER ROOF. MANUF. (TYP. U.N.O.)   |
|        | INDICATES TRUSS OVERFRAMING @ 24" O.C. (TYP. U.N.O.)   |
|        | INDICATES 14" DEEP FLOOR I-JOISTS (24" O.C. MAX SPACING). JOIST SERIES AND SPACING SHALL BE THE RESPONSIBILITY OF THE JOIST MANUFACTURER |
|        | INDICATES 2x8 P.T. DECK JOISTS @ 16" O.C. (MAX)  |
|        | INDICATES LOCATIONS OF POTENTIAL TILE FLOOR. JOIST MANUFACTURER SHALL DESIGN FLOOR SYSTEM FOR ADDL. 10 PSF DEAD LOAD AT THESE LOCATIONS. |
|        | INTERIOR BEARING WALL  |
|        | BEARING WALL ABOVE (B.W.A.)  |
|        | BEAM/HEADER  |
|        | METAL HANGER   |
|        | INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.   |




1 TYPICAL SLAB ON GRADE PERIMETER FOOTING




2 TYPICAL SLAB ON GRADE PERIMETER FOOTING w/ BRICK VENEER




3 TYPICAL SLAB ON GRADE GARAGE PERIMETER FOOTING




4 TYPICAL SLAB ON GRADE GARAGE PERIMETER FOOTING w/ BRICK VENEER




5 TYPICAL SLAB ON GRADE GARAGE ENTRY @ PERIMETER FOOTING




6 TYPICAL SLAB ON GRADE GARAGE ENTRY @ PERIMETER FOOTING w/ BRICK VENEER



7 TYPICAL MONOLITHIC INTERIOR GARAGE FOOTING



8 TYPICAL SLAB ON GRADE PERIMETER FOOTING @ PORCH/PATIO



9 TYPICAL THICKENED SLAB @ INTERIOR BEARING WALL

**MULHERN+KULP**  
 RESIDENTIAL STRUCTURAL ENGINEERING  
 3025 Shuman Blvd., Suite 105 - Alpharetta, GA 30022  
 770-777-8074 - mulhern+kulp.com  
 NC License # C-3825

Mulhern+Kulp project number:  
 256-22014

project mgr: SMK  
 drawn by: MMD  
 issue date: 09-29-2023









REVISIONS:  
 date: initial:

SMITH DOUGLAS  
 HOMES

FOUNDATION DETAILS  
 A VERY MODEL  
 120 MPH WIND ZONE  
 NORTH CAROLINA

TOBACCO  
 Lot 174

sheet:  
**SD1.0**



**MULHERN+KULP**  
 RESIDENTIAL STRUCTURAL ENGINEERING  
 3825 Matthews Parkway, Suite 105 - Alpharetta, GA 30022  
 770-777-8874 - mulhern+kulp.com  
 NC License # C-3825

Mulhern+Kulp project number:  
 256-22014

project mgr: SMK  
 drawn by: MMD  
 issue date: 09-29-2023

REVISIONS:  
 date: initial:

SMITH DOUGLAS  
 HOMES

FOUNDATION DETAILS  
 A VERY MODEL  
 120 MPH WIND ZONE  
 NORTH CAROLINA

TOBACCO  
 Lot 174

sheet:  
 SD1.4



Mulhern+Kulp project number:  
**256-22014**


project mgr: **SMK**  
 drawn by: **MMD**  
 issue date: **09-29-2023**

REVISIONS:  
 date: \_\_\_\_\_ initial: \_\_\_\_\_


SMITH DOUGLAS  
 HOMES

FOUNDATION DETAILS  
 A VERY MODEL  
 120 MPH WIND ZONE  
 NORTH CAROLINA


**TOBACCO**  
 Lot 174




**1** GENERIC FOUNDATION PLAN KEY @ GARAGE  
 SCALE: 1/4"=1'-0"




**2** TYPICAL PERIMETER FOOTING @ GARAGE - BASEMENT FOUNDATION  
 (NON-BRICK)




**3** TYPICAL PERIMETER FOOTING @ GARAGE - BASEMENT FOUNDATION (BRICK)




**4** TYPICAL CONCRETE GRADE BEAM @ GARAGE FDN.  
 SCALE: 3/4"=1'-0"



**5** CONCRETE BSMT. FDN. WALL @ GARAGE










**6** SECTION  
 SCALE: 3/4"=1'-0"



**7** SECTION  
 SCALE: 3/4"=1'-0"








\*NOTE TO G.C.\*:  
 FOR WALLS LESS THAN 18'-0", RUN BLOCKING & SHEATHING SHOWN CONT. FULL LENGTH OF SHEAR WALL. IF PENETRATIONS ARE REQ'D REMOVE SINGLE BAY ONLY AS NEEDED


**GARAGE PORTAL FRAME BRACING ELEVATION**  
 SCALE: N.T.S.  
 BOTH SIDES OF GARAGE DOOR  
 120 MPH WIND SPEED (ULT)

**TOBACCO**  
 Lot 174



**A** TYPICAL GABLE END BRACING DETAIL  
SCALE: NONE  
REQ'D @ GABLE END TRUSS HEIGHT UP TO 9'-0"

BRACE GABLE END TRUSSES PER ABOVE DETAIL WHEN GABLE HEIGHT IS LESS THAN 9'-0". 1" BRACES REQUIRED WHERE NOTED BY TRUSS MANUFACTURER.



**B** TYPICAL GABLE END BRACING DETAIL  
SCALE: NONE  
REQ'D @ GABLE END TRUSS HEIGHT BETWEEN 9'-0" TO 14'-0"

BRACE GABLE END TRUSSES PER ABOVE DETAIL WHEN GABLE HEIGHT EXCEEDS 9'-0". 1" BRACES NOT REQUIRED.

LETTERED DETAILS ARE TYPICAL FOR THIS HOME & SHALL BE IMPLEMENTED IN ALL APPLICABLE AREAS. THESE DETAILS ARE NOT "CUT" ON THE PLANS.

NUMBERED DETAILS ARE PLAN SPECIFIC AND ARE ONLY REQUIRED WHERE SPECIFICALLY INDICATED ("CUT") ON THE PLANS.

10/23/23  
Seal: [Professional Engineer Seal]  
Copyright: MULHERN & KULP Structural Engineering, Inc.

**MULHERN+KULP**  
RESIDENTIAL STRUCTURAL ENGINEERING  
3825 Sandhills Parkway, Suite 105 - Alpharetta, GA 30022  
770-777-8874 - mulhern+kulp.com  
NC License # C-3825



Mulhern+Kulp project number:  
256-22014

project mgr: SMK  
drawn by: MMD  
issue date: 09-29-2023

REVISIONS:  
date: initial:

SMITH DOUGLAS  
HOMES

FRAMING DETAILS

A VERY MODEL


120 MPH WIND ZONE  
NORTH CAROLINA

TOBACCO  
Lot 174

sheet:  
**SD2.1**

TRUSS TO WALL CONNECTIONS, IF SHOWN, ARE FOR UPLIFT ONLY AND DO NOT CONSIDER LATERAL LOADS. ALL CONNECTORS ON THIS PROJECT ARE TO BE INSTALLED PER THE CONNECTOR MANUFACTURER'S SPECIFICATIONS. ALL CONNECTORS SHOWN THAT ARE NOT "TRUSS TO TRUSS" ARE SUGGESTIONS ONLY AND ARE TO BE VERIFIED BY THE BUILDING DESIGNER OR ENGINEER OF SUITABILITY TO THIS PARTICULAR PROJECT. UFP MID-ATLANTIC, LLC, ACCEPTS NO RESPONSIBILITY FOR THE SPECIFIC APPLICATION OR SUITABILITY OF ANY CONNECTOR THAT IS NOT "TRUSS TO TRUSS" AS THEY APPLY TO THIS SPECIFIC STRUCTURE.

# 72414956 174 TOBACCO ROAD



G1 ONLY INCLUDED WITH BRICK ELEVATIONS


## AVERY CFI NO TRAY

ROOF AREA: 3744.43 RIDGE LINE: 60.9 ft \_ VALLEY LINES: 53.78 \_ HIP LINES: 98.72 \_ Indicates Left End of Truss

|  |  |
|--|--|
| <p>NOTES: THIS DRAWING IS THE PROPERTY OF UFP MID-ATLANTIC, LLC. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED TO THE INTEREST OF UFP MID-ATLANTIC, LLC. THIS DRAWING MUST BE USED IN CONJUNCTION WITH ALL OTHER TECHNICAL DRAWINGS SUPPLIED BY UFP MID-ATLANTIC, LLC AND BRACING WOOD TRUSSES, COMMENTARY AND RECOMMENDATIONS AS PUBLISHED BY THE TRUSS MANUFACTURER. UFP MID-ATLANTIC, LLC IS NOT PROVIDING TRUSSES. (FBI) IS LOCATED AT 683 D CONFRID DR, SUITE 200 MADISON, WI 53719 (608) 833-5800</p> |  |
| <p>CUSTOMER<br/><b>SMITH DOUGLAS</b></p>   | <p>Job Name<br/><b>AVERY CFI</b></p>         |
| <p>Drawn By: <b>AS</b></p>   | <p>Date: 6-2-20</p>                          |
| <p>Scale: NTS</p>  | <p>Quality Products for Quality Builders</p> |
| <p>Revision Date: _____</p>  | <p>Revision Date: _____</p>                  |
| <p>Quote Number<br/><b>MASTER</b></p>  | <p>Checked By: _____</p>                     |

**UFP MID-ATLANTIC, LLC**  
A UNIVERSAL FOREST PRODUCTS COMPANY

BURLINGTON, NC PHONE (800) 476-9356  
CHESAPEAKE, VA PHONE (800) 476-3190  
CONWAY, SC PHONE (800) 397-9572  
JEFFERSON GA PHONE (800) 648-4038  
PEARISBURG, VA PHONE (800) 397-9571




1. TEMPORARY BRACING TO BE INSTALLED w/T.P.I. STANDARD BC51-B1.  
2. SEE ENGINEERED DRAWING FOR PERMANENT BRACING MINIMUM REQUIREMENTS.  
3. FRAMER TO VERIFY ALL DIMENSIONS, DROP, & RISE LOCATIONS PRIOR TO TRUSS PLACEMENT.  
4. BLDG/FRAMER RESPONSIBLE FOR ADJUSTMENT OF TRUSS SPACING TO MISS PLUMBING DROPS, UNLESS NOTED OTHERWISE.

This layout is not an engineered drawing. This drawing was created to establish truss placement only. It is the responsibility of the builder to provide adequate support for all the elements shown in this drawing.

TRUSS TO WALL CONNECTIONS, IF SHOWN, ARE FOR UPLIFT ONLY AND DO NOT CONSIDER LATERAL LOADS. ALL CONNECTORS ON THIS PROJECT ARE TO BE INSTALLED PER THE CONNECTOR MANUFACTURER'S SPECIFICATIONS. ALL CONNECTORS SHOWN THAT ARE NOT "TRUSS TO TRUSS" ARE SUGGESTIONS ONLY AND ARE TO BE VERIFIED BY THE BUILDING DESIGNER OR ENGINEER OF SUITABILITY TO THIS PARTICULAR PROJECT. UFP MID-ATLANTIC, LLC, ACCEPTS NO RESPONSIBILITY FOR THE SPECIFIC APPLICATION OR SUITABILITY OF ANY CONNECTOR THAT IS NOT "TRUSS TO TRUSS" AS THEY APPLY TO THIS SPECIFIC STRUCTURE.

72414961 174 TOBACCO ROAD




10X12 OPTIONAL PORCH

ROOF AREA: 3833.13 RIDGE LINE: 136.98 VALLEY LINES: 150.7 HIP LINES: 0 Δ Indicates Left End of Truss

Customer: **SMITH DOUGLAS**  
 Job Name: **AVERY 10X12 PORCH**  
 Date: 10/19/2018  
 Scale: NTS  
 Revision Date 1:  
 Revision Date 2:

NOTES: THIS DRAWING IS THE PROPERTY OF UFP MID-ATLANTIC, LLC AND IS NOT TO BE USED FOR ANY PURPOSE DETRIMENTAL TO THE INTEREST OF UFP MID-ATLANTIC, LLC. THIS DRAWING MUST BE USED IN CONJUNCTION WITH ALL OTHER TECHNICAL DRAWINGS SUPPLIED BY UFP MID-ATLANTIC, LLC. UFP MID-ATLANTIC, LLC TRUSSES, COMMENTARY AND RECOMMENDATIONS ARE PUBLISHED BY THE TRUSS PLATE INSTITUTE FOR INDUSTRY STANDARDS IN RECTANGULAR TRUSSES. (TPI) IS LOCATED AT 685 D'ONOFRIO DR. SUITE 200 MADISON WI 53719 (608) 833-5900



**UFP MID-ATLANTIC, LLC**  
 A UNIVERSAL FOREST PRODUCTS COMPANY  
 BURLINGTON, NC PHONE (800) 476-9356  
 CHESAPEAKE, VA PHONE (800) 476-3190  
 CONWAY, SC PHONE (800) 397-9572  
 JEFFERSON, GA PHONE (800) 648-4038  
 LOCUST, NC PHONE (704) 888-0920  
 LIBERTY, NC PHONE (800) 648-4038  
 PEARISBURG, VA PHONE (800) 397-9571

1. TEMPORARY BRACING TO BE INSTALLED W/ T.P.I. STANDARD BCS-81.
2. SEE ENGINEERED DRAWING FOR PERMANENT BRACING MINIMUM REQUIREMENTS.
3. FRAMER TO VERIFY ALL DIMENSIONS, DROP, & RISE LOCATIONS PRIOR TO TRUSS PLACEMENT.
4. BLDR/FRAMER RESPONSIBLE FOR ADJUSTMENT OF TRUSS SPACING TO MISS PLUMBING DROPS, UNLESS NOTED OTHERWISE.

This layout is not an engineered drawing. This drawing was created to establish truss placement only. It is the responsibility of the builder to provide adequate support for all the elements shown in this drawing.