

RE: 4052116
 Cardinal A - Lot 2 - Fairground Farms

Trenco
 818 Soundside Rd
 Edenton, NC 27932

Site Information:

Customer: Project Name: 4052116
 Lot/Block: Model:
 Address: Subdivision:
 City: State:

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: IRC2015/TPI2014 Design Program: MiTek 20/20 8.6
 Wind Code: Wind Speed: 120 mph
 Roof Load: 40.0 psf Floor Load: N/A psf

This package includes 10 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date
1	I64468012	A01	3/26/2024
2	I64468013	A02	3/26/2024
3	I64468014	A03	3/26/2024
4	I64468015	A04	3/26/2024
5	I64468016	A05	3/26/2024
6	I64468017	A06	3/26/2024
7	I64468018	B01	3/26/2024
8	I64468019	B02	3/26/2024
9	I64468020	C01G	3/26/2024
10	I64468021	C02	3/26/2024


The truss drawing(s) referenced above have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Builders FirstSource (Albermarle,NC).

Truss Design Engineer's Name: Gagan, Iqbal

My license renewal date for the state of North Carolina is December 31, 2024.

North Carolina COA: C-0844

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to TRENCO. Any project specific information included is for TRENCO customers file reference purpose only, and was not taken into account in the preparation of these designs. TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.




March 26, 2024

Job 4052116	Truss A01	Truss Type Common Supported Gable	Qty 1	Ply 1	Cardinal A - Lot 2 - Fairground Farms Job Reference (optional)	164468012
----------------	--------------	--------------------------------------	----------	----------	---	-----------

Builders FirstSource (Albermarle), Albermarle, NC - 28001,

Run: 8.63 S Nov 1 2023 Print: 8.630 S Nov 1 2023 MiTek Industries, Inc. Mon Mar 25 16:48:05
ID:JE67DYA_kvviS6eJKugLHW41Mh-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRCDoi7J4zJC?f

Page: 1




Scale = 1:65.5

Plate Offsets (X, Y): [25:0-2-8,0-1-8], [33:0-2-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	23.1/30.0	Lumber DOL	1.15	BC	0.14	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	0.01	20	n/a	n/a		
BCLL	0.0*	Code	IRC2015/TPI2014	Matrix-S								
BCDL	10.0											
											Weight: 233 lb	FT = 20%

LUMBER	TOP CHORD	1-2=0/43, 2-3=-191/94, 3-4=-121/86, 4-5=-85/106, 5-6=-68/131, 6-8=-57/156, 8-9=-47/180, 9-10=-58/205, 10-11=-64/227, 11-12=-65/219, 12-13=-58/178, 13-14=-49/133, 14-16=-43/91, 16-17=-45/67, 17-18=-35/41, 18-19=-74/22, 19-20=-128/62	5) Unbalanced snow loads have been considered for this design.
TOP CHORD	2x4 SP No.2		
BOT CHORD	2x4 SP No.2		
OTHERS	2x4 SP No.3		
BRACING			
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.		
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.		
WEBS	1 Row at midpt 11-29, 10-30, 12-28		
REACTIONS (size)	2=36-6-0, 20=36-6-0, 21=36-6-0, 22=36-6-0, 23=36-6-0, 24=36-6-0, 26=36-6-0, 27=36-6-0, 28=36-6-0, 29=36-6-0, 30=36-6-0, 31=36-6-0, 32=36-6-0, 34=36-6-0, 35=36-6-0, 36=36-6-0, 37=36-6-0		
Max Horiz	2=167 (LC 12)		
Max Uplift	2=-17 (LC 13), 21=-107 (LC 13), 22=-24 (LC 13), 23=-54 (LC 13), 24=-48 (LC 13), 26=-48 (LC 13), 27=-52 (LC 13), 28=-43 (LC 13), 30=-46 (LC 12), 31=-51 (LC 12), 32=-48 (LC 12), 34=-48 (LC 12), 35=-53 (LC 12), 36=-27 (LC 12), 37=-101 (LC 12)		
Max Grav	2=225 (LC 19), 20=155 (LC 20), 21=376 (LC 20), 22=82 (LC 1), 23=199 (LC 6), 24=209 (LC 4), 26=219 (LC 6), 27=259 (LC 6), 28=273 (LC 6), 29=260 (LC 25), 30=272 (LC 5), 31=256 (LC 5), 32=207 (LC 5), 34=209 (LC 4), 35=197 (LC 5), 36=90 (LC 1), 37=361 (LC 19)		
FORCES	(lb) - Maximum Compression/Maximum Tension		
		NOTES	
		1) Unbalanced roof live loads have been considered for this design.	
		2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; Lumber DOL=1.60 plate grip DOL=1.60	
		3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.	
		4) TCLL: ASCE 7-10; Pr=20.0 psf (roof live load; Lumber DOL=1.15 Plate DOL=1.15); Pg=30.0 psf (ground snow); Pf=23.1 psf (flat roof snow; Lumber DOL=1.15 Plate DOL=1.15); Category II; Exp B; Partially Exp.; Ct=1.10	
		6) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 23.1 psf on overhangs non-concurrent with other live loads.	
		7) All plates are 2x4 MT20 unless otherwise indicated.	
		8) Gable requires continuous bottom chord bearing.	
		9) Gable studs spaced at 2-0-0 oc.	
		10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.	
		11) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 1-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.	
		12) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.	



March 26, 2024

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932

Job 4052116	Truss A01	Truss Type Common Supported Gable	Qty 1	Ply 1	Cardinal A - Lot 2 - Fairground Farms I64468012 Job Reference (optional)
----------------	--------------	--------------------------------------	----------	----------	--


Builders FirstSource (Albermarle), Albermarle, NC - 28001,

Run: 8.63 S Nov 1 2023 Print: 8.630 S Nov 1 2023 MiTek Industries, Inc. Mon Mar 25 16:48:05
ID:jE67DYA_kxvIS6eJKugLHwz41Mh-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

Page: 2

- 13) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 17 lb uplift at joint 2, 46 lb uplift at joint 30, 51 lb uplift at joint 31, 48 lb uplift at joint 32, 48 lb uplift at joint 34, 53 lb uplift at joint 35, 27 lb uplift at joint 36, 101 lb uplift at joint 37, 43 lb uplift at joint 28, 52 lb uplift at joint 27, 48 lb uplift at joint 26, 48 lb uplift at joint 24, 54 lb uplift at joint 23, 24 lb uplift at joint 22 and 107 lb uplift at joint 21.
- 14) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 2, 20.
- 15) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



March 26, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
Edenton, NC 27932

Job 4052116	Truss A02	Truss Type Common	Qty 4	Ply 1	Cardinal A - Lot 2 - Fairground Farms Job Reference (optional)	I64468013
----------------	--------------	----------------------	----------	----------	---	-----------

Builders FirstSource (Albermarle), Albermarle, NC - 28001,

Run: 8.63 S Nov 1 2023 Print: 8.630 S Nov 1 2023 MiTek Industries, Inc. Mon Mar 25 16:48:06
ID:8Lr6_BdB0JZV0oZ_Q91Hkz41M6-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRCDoi7J4zJC?f

Page: 1



Scale = 1:67.3

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.86	Vert(LL)	-0.25	11-13	>999	240	MT20	244/190
Snow (Pf/Pg)	23.1/30.0	Lumber DOL	1.15	BC	0.95	Vert(CT)	-0.45	10-11	>959	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.13	10	n/a	n/a		
BCLL	0.0*	Code	IRC2015/TPI2014	Matrix-S								
BCDL	10.0										Weight: 187 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2 *Except* 8-10:2x4 SP No.1
BOT CHORD 2x4 SP No.1 *Except* 14-12:2x4 SP No.2
WEBS 2x4 SP No.3


BRACING
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 1 Row at midpt 5-13, 7-13

REACTIONS (size) 2=0-3-8, 10= Mechanical
Max Horiz 2=167 (LC 12)
Max Uplift 2=-193 (LC 12), 10=-171 (LC 13)
Max Grav 2=1636 (LC 1), 10=1563 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/44, 2-3=-2920/333, 3-5=-2646/307, 5-6=-1850/258, 6-7=-1849/257, 7-9=-2668/312, 9-10=-2952/342
BOT CHORD 2-15=-374/2537, 13-15=-212/2058, 11-13=-79/2066, 10-11=-232/2575
WEBS 6-13=-111/1212, 3-15=-368/210, 5-15=-42/534, 5-13=-798/241, 7-13=-819/242, 7-11=-48/552, 9-11=-396/219

- 5) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 23.1 psf on overhangs non-concurrent with other live loads.
 - 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 1-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 8) Bearings are assumed to be: Joint 2 SP No.1 crushing capacity of 565 psi.
 - 9) Refer to girder(s) for truss to truss connections.
 - 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 193 lb uplift at joint 2 and 171 lb uplift at joint 10.
 - 11) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- LOAD CASE(S)** Standard

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) TCLL: ASCE 7-10; Pr=20.0 psf (roof live load: Lumber DOL=1.15 Plate DOL=1.15); Pg=30.0 psf (ground snow); Pf=23.1 psf (flat roof snow: Lumber DOL=1.15 Plate DOL=1.15); Category II; Exp B; Partially Exp.; Ct=1.10
 - 4) Unbalanced snow loads have been considered for this design.



March 26, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)


ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job 4052116	Truss A03	Truss Type Common	Qty 3	Ply 1	Cardinal A - Lot 2 - Fairground Farms Job Reference (optional)	I64468014
----------------	--------------	----------------------	----------	----------	---	-----------

Builders FirstSource (Albermarle), Albermarle, NC - 28001,

Run: 8.63 S Nov 1 2023 Print: 8.630 S Nov 1 2023 MiTek Industries, Inc. Mon Mar 25 16:48:06
ID:qX3KkwTf70dNYgGXdxXbAnz41H8-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWkRCDoi7J4zJC?f

Page: 1



Scale = 1:70.3

Plate Offsets (X, Y): [2:0-1-4,0-0-9], [7:0-3-0,Edge], [12:0-1-4,0-0-9]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	-0.37	13-15	>999	240	MT20	244/190
Snow (Pf/Pg)	23.1/30.0	Lumber DOL	1.15	BC	0.73	Vert(CT)	-0.50	13-15	>875	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.95	Horz(CT)	0.09	12	n/a	n/a		
BCLL	0.0*	Code	IRC2015/TPI2014	Matrix-S								
BCDL	10.0											
											Weight: 235 lb	FT = 20%


LUMBER
TOP CHORD 2x4 SP 2400F 2.0E or 2x4 SP DSS or 2x4 SP SS
BOT CHORD 2x6 SP No.2 *Except* 19-17:2x4 SP No.2, 21-14:2x6 SP 2400F 2.0E or 2x6 SP DSS
WEBS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-2-9 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing. Except: 6-0-0 oc bracing: 17-19

REACTIONS (size) 2=0-3-8, 12= Mechanical
Max Horiz 2=168 (LC 12)
Max Uplift 2=-142 (LC 12), 12=-120 (LC 13)
Max Grav 2=1733 (LC 4), 12=1672 (LC 4)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/51, 2-3=-3304/212, 3-4=-3271/309, 4-6=-2687/140, 6-7=-147/29, 7-8=-145/29, 8-10=-2691/138, 10-11=-3321/322, 11-12=-3339/219
BOT CHORD 2-22=-265/2882, 20-22=-151/2593, 16-20=0/2108, 15-16=0/2108, 13-15=-2/2606, 12-13=-123/2925, 18-19=-8/8, 17-18=-8/8
WEBS 11-13=-357/183, 3-22=-316/167, 19-20=-15/843, 6-19=0/915, 8-17=0/924, 15-17=-16/852, 6-8=-2061/193, 4-22=-183/631, 4-20=-660/270, 10-13=-195/682, 10-15=-684/271, 16-18=-251/0

- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-10; Pr=20.0 psf (roof live load: Lumber DOL=1.15 Plate DOL=1.15); Pg=30.0 psf (ground snow); Pf=23.1 psf (flat roof snow: Lumber DOL=1.15 Plate DOL=1.15); Category II; Exp B; Partially Exp.; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 23.1 psf on overhangs non-concurrent with other live loads.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 1-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Bearings are assumed to be: Joint 2 SP No.2 crushing capacity of 565 psi.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 142 lb uplift at joint 2 and 120 lb uplift at joint 12.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- LOAD CASE(S)** Standard



March 26, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcomponents.com)




818 Soundside Road
Edenton, NC 27932

Job 4052116	Truss A04	Truss Type Common	Qty 3	Ply 1	Cardinal A - Lot 2 - Fairground Farms Job Reference (optional)	164468015
----------------	--------------	----------------------	----------	----------	---	-----------

Builders FirstSource (Albermarle), Albermarle, NC - 28001,

Run: 8.63 S Nov 1 2023 Print: 8.630 S Nov 1 2023 MiTek Industries, Inc. Mon Mar 25 16:48:07
ID:8w_Oo0AYuwlvO2pWayH4Pz418V-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKwRCDoi7J4zJC7f

Page: 1



Scale = 1:70.3

Plate Offsets (X, Y): [7:0-3:0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.47	Vert(LL)	-0.37	21-23	>999	240	MT20	244/190
Snow (Pf/Pg)	23.1/30.0	Lumber DOL	1.15	BC	0.72	Vert(CT)	-0.48	21-23	>897	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.94	Horz(CT)	0.09	12	n/a	n/a		
BCLL	0.0*	Code	IRC2015/TPI2014	Matrix-S								
BCDL	10.0											
											Weight: 236 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP 2400F 2.0E or 2x4 SP DSS or 2x4 SP SS
BOT CHORD 2x6 SP No.2 *Except* 20-18:2x4 SP No.2, 22-15:2x6 SP 2400F 2.0E or 2x6 SP DSS
WEBS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-4-14 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing. Except: 6-0-0 oc bracing: 18-20


REACTIONS (size) 2=0-3-8, 12=0-3-8
Max Horiz 2=160 (LC 16)
Max Uplift 2=-142 (LC 12), 12=-142 (LC 13)
Max Grav 2=1729 (LC 4), 12=1729 (LC 4)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/51, 2-3=-3295/212, 3-4=-3261/309, 4-6=-2675/138, 6-7=-146/30, 7-8=-146/30, 8-10=-2675/138, 10-11=-3261/309, 11-12=-3295/212, 12-13=0/51
BOT CHORD 2-23=-256/2874, 21-23=-142/2583, 17-21=0/2097, 16-17=0/2097, 14-16=0/2583, 12-14=-97/2874, 19-20=-8/8, 18-19=-8/8
WEBS 20-21=-15/841, 6-20=0/913, 8-18=0/913, 16-18=-15/841, 6-8=-2049/190, 3-23=-315/167, 11-14=-315/168, 4-23=-183/632, 4-21=-669/270, 10-14=-184/632, 10-16=-669/271, 17-19=-251/0

- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-10; Pr=20.0 psf (roof live load: Lumber DOL=1.15 Plate DOL=1.15); Pg=30.0 psf (ground snow); Pf=23.1 psf (flat roof snow: Lumber DOL=1.15 Plate DOL=1.15); Category II; Exp B; Partially Exp.; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 23.1 psf on overhangs non-concurrent with other live loads.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 1-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 142 lb uplift at joint 2 and 142 lb uplift at joint 12.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

NOTES
1) Unbalanced roof live loads have been considered for this design.



March 26, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)


ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job 4052116	Truss A05	Truss Type Common	Qty 6	Ply 1	Cardinal A - Lot 2 - Fairground Farms Job Reference (optional)	164468016
----------------	--------------	----------------------	----------	----------	---	-----------

Builders FirstSource (Albermarle), Albemarle, NC - 28001,

Run: 8.63 S Nov 1 2023 Print: 8.630 S Nov 1 2023 MiTek Industries, Inc. Mon Mar 25 16:48:07
ID:H7XZCbNk08MyrnX_kWkKB?z415e-RfC?PsB70Hq3NSgPqnL8w3uTXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:67

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.86	Vert(LL)	-0.25	12-14	>999	240	MT20	244/190
Snow (Pf/Pg)	23.1/30.0	Lumber DOL	1.15	BC	0.94	Vert(CT)	-0.45	12-14	>973	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.12	10	n/a	n/a		
BCLL	0.0*	Code	IRC2015/TPI2014	Matrix-S								
BCDL	10.0											
											Weight: 188 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.1 *Except* 15-13:2x4 SP No.2
WEBS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 1 Row at midpt 5-14, 7-14

REACTIONS

(size) 2=0-3-8, 10=0-3-8
Max Horiz 2=160 (LC 16)
Max Uplift 2=-193 (LC 12), 10=-193 (LC 13)
Max Grav 2=1631 (LC 1), 10=1631 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/44, 2-3=-2910/333, 3-5=-2636/306, 5-6=-1840/256, 6-7=-1840/256, 7-9=-2636/306, 9-10=-2910/333, 10-11=0/44
BOT CHORD 2-16=-367/2529, 14-16=-204/2049, 12-14=-72/2049, 10-12=-207/2529
WEBS 6-14=-110/1204, 3-16=-368/210, 5-16=-43/533, 5-14=-807/241, 7-14=-807/241, 7-12=-43/533, 9-12=-368/210

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; Lumber DOL=1.60 plate grip DOL=1.60
- 3) TCLL: ASCE 7-10; Pr=20.0 psf (roof live load: Lumber DOL=1.15 Plate DOL=1.15); Pg=30.0 psf (ground snow); Pf=23.1 psf (flat roof snow: Lumber DOL=1.15 Plate DOL=1.15); Category II; Exp B; Partially Exp.; Ct=1.10

- 4) Unbalanced snow loads have been considered for this design.
- 5) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 23.1 psf on overhangs non-concurrent with other live loads.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 1-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 8) All bearings are assumed to be SP No.1 crushing capacity of 565 psi.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 193 lb uplift at joint 2 and 193 lb uplift at joint 10.
- 10) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



March 26, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
Edenton, NC 27932

Job 4052116	Truss A06	Truss Type Common Supported Gable	Qty 1	Ply 1	Cardinal A - Lot 2 - Fairground Farms Job Reference (optional)	164468017
----------------	--------------	--------------------------------------	----------	----------	---	-----------

Builders FirstSource (Albermarle), Albermarle, NC - 28001,

Run: 8.63 S Nov 1 2023 Print: 8.630 S Nov 1 2023 MiTek Industries, Inc. Mon Mar 25 16:48:07
ID:3NiS2SX_tmhC78C9uXDX421s-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRcDoi7J4zJC7f

Page: 1



Scale = 1:67

Plate Offsets (X, Y): [26:0-2-8,0-1-8], [34:0-2-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	23.1/30.0	Lumber DOL	1.15	BC	0.13	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	0.01	20	n/a	n/a		
BCLL	0.0*	Code	IRC2015/TPI2014	Matrix-S								
BCDL	10.0											
											Weight: 234 lb	FT = 20%

LUMBER	TOP CHORD	1-2=0/43, 2-3=-188/99, 3-4=-119/92, 4-5=-82/112, 5-6=-67/137, 6-8=-56/162, 8-9=-48/186, 9-10=-58/211, 10-11=-65/232, 11-12=-65/225, 12-13=-58/184, 13-14=-48/139, 14-16=-43/96, 16-17=-45/70, 17-18=-39/44, 18-19=-68/24, 19-20=-121/60, 20-21=0/43	5) Unbalanced snow loads have been considered for this design.
TOP CHORD	2x4 SP No.2		
BOT CHORD	2x4 SP No.2		
OTHERS	2x4 SP No.3		
BRACING			
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.		
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.		
WEBS	1 Row at midpt 11-30, 10-31, 12-29		
REACTIONS (size)	2=36-6-0, 20=36-6-0, 22=36-6-0, 23=36-6-0, 24=36-6-0, 25=36-6-0, 27=36-6-0, 28=36-6-0, 29=36-6-0, 30=36-6-0, 31=36-6-0, 32=36-6-0, 33=36-6-0, 35=36-6-0, 36=36-6-0, 37=36-6-0, 38=36-6-0		
Max Horiz	2=-160 (LC 13)		
Max Uplift	2=-19 (LC 13), 22=-101 (LC 13), 23=-27 (LC 13), 24=-53 (LC 13), 25=-48 (LC 13), 27=-48 (LC 13), 28=-52 (LC 13), 29=-43 (LC 13), 31=-46 (LC 12), 32=-51 (LC 12), 33=-48 (LC 12), 35=-48 (LC 12), 36=-53 (LC 12), 37=-27 (LC 12), 38=-101 (LC 12)		
Max Grav	2=225 (LC 19), 20=225 (LC 20), 22=361 (LC 20), 23=90 (LC 1), 24=197 (LC 6), 25=209 (LC 4), 27=219 (LC 6), 28=259 (LC 6), 29=273 (LC 6), 30=263 (LC 25), 31=273 (LC 5), 32=259 (LC 5), 33=219 (LC 5), 35=209 (LC 4), 36=197 (LC 5), 37=90 (LC 1), 38=361 (LC 19)		
FORCES	(lb) - Maximum Compression/Maximum Tension		
		NOTES	
		1) Unbalanced roof live loads have been considered for this design.	
		2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60	
		3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.	
		4) TCLL: ASCE 7-10; Pr=20.0 psf (roof live load: Lumber DOL=1.15 Plate DOL=1.15); Pg=30.0 psf (ground snow); Pf=23.1 psf (flat roof snow: Lumber DOL=1.15 Plate DOL=1.15); Category II; Exp B; Partially Exp.; Ct=1.10	
			6) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 23.1 psf on overhangs non-concurrent with other live loads.
			7) All plates are 2x4 MT20 unless otherwise indicated.
			8) Gable requires continuous bottom chord bearing.
			9) Gable studs spaced at 2-0-0 oc.
			10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
			11) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 1-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
			12) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.



March 26, 2024

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932

Job 4052116	Truss A06	Truss Type Common Supported Gable	Qty 1	Ply 1	Cardinal A - Lot 2 - Fairground Farms I64468017 Job Reference (optional)
----------------	--------------	--------------------------------------	----------	----------	--

Builders FirstSource (Albermarle), Albermarle, NC - 28001,

Run: 8.63 S Nov 1 2023 Print: 8.630 S Nov 1 2023 MiTek Industries, Inc. Mon Mar 25 16:48:07
ID:3NIsZSX_trmhC78C9uxDXz412s-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f

Page: 2

- 13) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 2, 46 lb uplift at joint 31, 51 lb uplift at joint 32, 48 lb uplift at joint 33, 48 lb uplift at joint 35, 53 lb uplift at joint 36, 27 lb uplift at joint 37, 101 lb uplift at joint 38, 43 lb uplift at joint 29, 52 lb uplift at joint 28, 48 lb uplift at joint 27, 48 lb uplift at joint 25, 53 lb uplift at joint 24, 27 lb uplift at joint 23 and 101 lb uplift at joint 22.
- 14) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 2, 20.
- 15) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



March 26, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
Edenton, NC 27932

Job 4052116	Truss B01	Truss Type Common	Qty 4	Ply 1	Cardinal A - Lot 2 - Fairground Farms Job Reference (optional)	164468018
----------------	--------------	----------------------	----------	----------	---	-----------

Builders FirstSource (Albermarle), Albermarle, NC - 28001,

Run: 8.63 S Nov 1 2023 Print: 8.630 S Nov 1 2023 MiTek Industries, Inc. Mon Mar 25 16:48:07
ID:MFGM9T1iDRytcQn43?AYNAz412D-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:41.3

Plate Offsets (X, Y): [8:0-4-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.36	Vert(LL)	-0.16	2-8	>999	240	MT20	244/190
Snow (Pf/Pg)	23.1/30.0	Lumber DOL	1.15	BC	0.93	Vert(CT)	-0.34	2-8	>659	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.23	Horz(CT)	0.03	6	n/a	n/a		
BCLL	0.0*	Code	IRC2015/TPI2014	Matrix-S								
BCDL	10.0											
											Weight: 84 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-7-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.

REACTIONS

(size) 2=0-3-8, 6=0-3-8
Max Horiz 2=87 (LC 12)
Max Uplift 2=-110 (LC 12), 6=-110 (LC 13)
Max Grav 2=873 (LC 1), 6=873 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/44, 2-3=-1337/178, 3-4=-1002/107, 4-5=-1002/107, 5-6=-1337/178, 6-7=0/44
BOT CHORD 2-6=-172/1145
WEBS 4-8=-2/563, 3-8=-402/197, 5-8=-402/198

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; Lumber DOL=1.60 plate grip DOL=1.60
- 3) TCLL: ASCE 7-10; Pr=20.0 psf (roof live load: Lumber DOL=1.15 Plate DOL=1.15); Pg=30.0 psf (ground snow); Pf=23.1 psf (flat roof snow: Lumber DOL=1.15 Plate DOL=1.15); Category II; Exp B; Partially Exp.; Ct=1.10
- 4) Unbalanced snow loads have been considered for this design.
- 5) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 23.1 psf on overhangs non-concurrent with other live loads.

- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 1-00-00 wide will fit between the bottom chord and any other members.
- 8) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 110 lb uplift at joint 2 and 110 lb uplift at joint 6.
- 10) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



March 26, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Cardinal A - Lot 2 - Fairground Farms	I64468019
4052116	B02	Common Supported Gable	1	1	Job Reference (optional)	

Builders FirstSource (Albermarle), Albemarle, NC - 28001,

Run: 8.63 S Nov 1 2023 Print: 8.630 S Nov 1 2023 MiTek Industries, Inc. Mon Mar 25 16:48:07
 ID:YNRWTE9bepKJR77BCps7KVz4122-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRCDoi7J4zJC?f

Page: 1



Scale = 1:40.9
 Plate Offsets (X, Y): [15:0-3-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.13	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	23.1/30.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.06	Horz(CT)	0.00	10	n/a	n/a		
BCLL	0.0*	Code	IRC2015/TPI2014	Matrix-S								
BCDL	10.0											
											Weight: 92 lb	FT = 20%

LUMBER
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size)
 2=18-11-0, 10=18-11-0,
 12=18-11-0, 13=18-11-0,
 14=18-11-0, 15=18-11-0,
 16=18-11-0, 17=18-11-0,
 18=18-11-0
 Max Horiz 2=87 (LC 12)
 Max Uplift 2=-17 (LC 13), 10=-24 (LC 13),
 12=-79 (LC 13), 13=-38 (LC 13),
 14=-53 (LC 13), 16=-54 (LC 12),
 17=-37 (LC 12), 18=-80 (LC 12)
 Max Grav 2=199 (LC 1), 10=199 (LC 1),
 12=288 (LC 1), 13=133 (LC 20),
 14=239 (LC 20), 15=221 (LC 25),
 16=239 (LC 19), 17=133 (LC 19),
 18=288 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/43, 2-3=-99/69, 3-4=-59/77,
 4-5=-41/99, 5-6=-57/123, 6-7=-57/116,
 7-8=-41/70, 8-9=-53/40, 9-10=-72/43,
 10-11=0/43
 BOT CHORD 2-18=-3/81, 17-18=-3/81, 16-17=-3/81,
 14-16=-3/81, 13-14=-3/81, 12-13=-3/81,
 10-12=-3/81
 WEBS 6-15=-115/0, 5-16=-195/79, 4-17=-108/58,
 3-18=-211/113, 7-14=-195/78, 8-13=-108/59,
 9-12=-211/112

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-10; Pr=20.0 psf (roof live load: Lumber DOL=1.15 Plate DOL=1.15); Pg=30.0 psf (ground snow); Pf=23.1 psf (flat roof snow: Lumber DOL=1.15 Plate DOL=1.15); Category II; Exp B; Partially Exp.; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 23.1 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 1-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 17 lb uplift at joint 2, 24 lb uplift at joint 10, 54 lb uplift at joint 16, 37 lb uplift at joint 17, 80 lb uplift at joint 18, 53 lb uplift at joint 14, 38 lb uplift at joint 13 and 79 lb uplift at joint 12.

- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 2.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



March 26, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
 Edenton, NC 27932

Job 4052116	Truss C01G	Truss Type Common Girder	Qty 1	Ply 2	Cardinal A - Lot 2 - Fairground Farms Job Reference (optional)	I64468020
----------------	---------------	-----------------------------	----------	----------	---	-----------

Builders FirstSource (Albermarle), Albemarle, NC - 28001,

Run: 8.63 S Nov 1 2023 Print: 8.630 S Nov 1 2023 MiTek Industries, Inc. Mon Mar 25 16:48:08
ID:cXMcBAYg5eMmG1ZL4XRedFz411Y-RFC?PsB70Hq3NSgPqnL8w3uITXbGKwRcDoi7J4zJC?f

Page: 1



Scale = 1:35.1

Plate Offsets (X, Y): [1:0-3-4,0-0-7], [5:0-3-4,0-0-7], [6:0-7-0,0-8-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.49	Vert(LL)	-0.09	1-6	>999	240	MT20	244/190
Snow (Pf/Pg)	23.1/30.0	Lumber DOL	1.15	BC	0.56	Vert(CT)	-0.17	5-6	>972	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.83	Horz(CT)	0.02	5	n/a	n/a		
BCLL	0.0*	Code	IRC2015/TPI2014	Matrix-S								
BCDL	10.0											
											Weight: 188 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x10 SP 2400F 2.0E or 2x10 SP DSS
 WEBS 2x4 SP No.3 *Except* 6-3:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-11-2 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 1=0-3-8, 5=0-3-8
 Max Horiz 1=-56 (LC 36)
 Max Uplift 1=-600 (LC 12), 5=-530 (LC 13)
 Max Grav 1=5325 (LC 1), 5=5311 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-8240/909, 2-3=-7880/845,
 3-4=-7880/844, 4-5=-8241/909
 BOT CHORD 1-6=-836/7423, 5-6=-778/7424
 WEBS 3-6=-698/6800, 4-6=-492/171, 2-6=-490/173

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
 Bottom chords connected as follows: 2x10 - 2 rows staggered at 0-5-0 oc.
 Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-10; Pr=20.0 psf (roof live load: Lumber DOL=1.15 Plate DOL=1.15); Pg=30.0 psf (ground snow); Pf=23.1 psf (flat roof snow: Lumber DOL=1.15 Plate DOL=1.15); Category II; Exp B; Partially Exp.; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 1-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP DSS or 2400F 2.0E crushing capacity of 660 psi.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 600 lb uplift at joint 1 and 530 lb uplift at joint 5.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1543 lb down and 183 lb up at 2-0-12, 1543 lb down and 183 lb up at 4-0-12, 1543 lb down and 183 lb up at 6-0-12, 1543 lb down and 183 lb up at 8-0-12, and 1652 lb down and 132 lb up at 10-0-12, and 1652 lb down and 132 lb up at 12-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard


- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (lb/ft)

Vert: 1-3=-66, 3-5=-66, 1-5=-20

Concentrated Loads (lb)

Vert: 9=-1543 (F), 10=-1543 (F), 11=-1543 (F), 12=-1543 (F), 13=-1628 (F), 14=-1628 (F)



March 26, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
 Edenton, NC 27932

Job 4052116	Truss C02	Truss Type Common Supported Gable	Qty 1	Ply 1	Cardinal A - Lot 2 - Fairground Farms Job Reference (optional)	164468021
----------------	--------------	--------------------------------------	----------	----------	---	-----------

Builders FirstSource (Albermarle), Albermarle, NC - 28001,

Run: 8.63 S Nov 1 2023 Print: 8.630 S Nov 1 2023 MiTek Industries, Inc. Mon Mar 25 16:48:08
ID:VwmhRQq98Djk_KgijoLUwbz41?u-RfC?PsB70Hq3NSgPqnlL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.11	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (P/Pg)	23.1/30.0	Lumber DOL	1.15	BC	0.07	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	0.00	8	n/a	n/a		
BCLL	0.0*	Code	IRC2015/TPI2014	Matrix-S								
BCDL	10.0											
											Weight: 65 lb	FT = 20%

LUMBER
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS (size)
 2=14-3-8, 8=14-3-8, 10=14-3-8,
 11=14-3-8, 12=14-3-8, 13=14-3-8,
 14=14-3-8
 Max Horiz 2=67 (LC 16)
 Max Uplift 2=-18 (LC 12), 8=-31 (LC 13),
 10=-71 (LC 13), 11=-44 (LC 13),
 13=-45 (LC 12), 14=-71 (LC 12)
 Max Grav 2=190 (LC 1), 8=190 (LC 1),
 10=259 (LC 1), 11=178 (LC 20),
 12=161 (LC 1), 13=178 (LC 19),
 14=259 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/43, 2-3=-81/59, 3-4=-51/72,
 4-5=-52/94, 5-6=-52/86, 6-7=-51/46,
 7-8=-60/37, 8-9=0/43
 BOT CHORD 2-14=-1/62, 13-14=-1/62, 12-13=-1/62,
 11-12=-1/62, 10-11=-1/62, 8-10=-1/62
 WEBS 5-12=-115/0, 4-13=-150/66, 3-14=-190/103,
 6-11=-150/66, 7-10=-190/103

NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-10; Vult=130mph (3-second gust)
 Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft;
 Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-10; Pr=20.0 psf (roof live load: Lumber DOL=1.15 Plate DOL=1.15); Pg=30.0 psf (ground snow); Pf=23.1 psf (flat roof snow: Lumber DOL=1.15 Plate DOL=1.15); Category II; Exp B; Partially Exp.; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 23.1 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 1-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 18 lb uplift at joint 2, 31 lb uplift at joint 8, 45 lb uplift at joint 13, 71 lb uplift at joint 14, 44 lb uplift at joint 11 and 71 lb uplift at joint 10.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 2.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



March 26, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
 Edenton, NC 27932

Symbols


PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16\" from outside edge of truss.




This symbol indicates the required direction of slots in connector plates.

* Plate location details available in MITek software or upon request.

PLATE SIZE


4 X 4
The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 section 6.3. These truss designs rely on Lumber values established by others.

© 2023 MITek® All Rights Reserved

MITek

ENGINEERING BY
TRENGO
A MITek Affiliate

MITek Engineering Reference Sheet: MIL-7473 rev. 1/2/2023

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability/bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.