

Takla Engineering, PLLC

Page 1 of 1

THCARO

ESSI0

SFAL

Electronically segr

Andy A. Taklas Date:2024.06.19 Time:4:19:42 PM

Consulting | Design | Efficiency PO Box 71298 Durham, NC 27722 | Office@TaklaEngr.com Alfred A. Takla, PE Andy A. Takla, PE AlfredTakla@TaklaEngr.com AndyTakla@TaklaEngr.com NC PE License # 047507 NC PE License # 050695

- Project: 2715 Ashe Ave.
- Dunn, NC Location:
- Company: STE General Contractors

provide formal documentation of the following:

- Care Of: Shane McLeod
- Subject: Rebar Omission
- **Job Number:** 2-2754-24

ATE As requested, Andy Takla, PE prepared this report on June 19th, 2024 to

We have reviewed the structural plans for the proposed build - Plan Name: BB-2282R ; Designed by "House Plan Zone".

On sheet 2, details 203, 205, 220, 221 and 223 all note steel reinforcement in the footing detail.

Based on review, provided the soil quality is found suitable and firm (no less than 2000 PSF) the per plans rebar may be deemed optional (IE not required by code nor calculations).

Notes on Reinforcement:

1- We do however strongly recommend the use of welded wire fabric and/or fiber reinforcement in the slab.

2- Where unbalanced conditions of the foundation wall (IE distance between top of slab and grade) meet or exceed 36"; we recommend the installation of vertical rebar within the footings, stem wall, and slab. Specifically, we recommend

A - (2) continuous #4 rebar in footings. B - Vertical rebar with a 6" hook into footings, and 24" spline into the slab. Rebar shall be #4 spaced at 32" (for 3' to 4' unbalanced) and 24" (for 4'-5' unbalanced).

These reinforcement need only be installed at areas of greater unbalanced fill (if any). All stem walls shall be filled solid with grout or concrete regardless of unbalanced height.

