

**J.S. THOMPSON**  
ENGINEERING, INC

September 9, 2024

Josh Arnott  
Davidson Homes LLC  
4208 Six Forks Road  
Suite 100  
Raleigh, NC 27609

Dear Mr. Arnott:

The plan was reviewed for lot #51 Tobacco Road subdivision in Angier, North Carolina to address the floor joist above the Owner's Bath with holes drilled for drain lines.

The reinforced floor joist with holes drilled for drain lines is sufficient; however, the existing 3/4" OSB scabs on both sides are to be fastened with (3) rows of 8d nails at 6" o.c. This configuration will provide the required support for all applied loads.

Please call me if you have any questions.

Sincerely,

J.S. Thompson Engineering, Inc.  
N.C. License No. C-1733

Joshua Grantham, E.I.



Matthew G. Strother, P.E.



9/9/2024