

# Reaction Summary of Quote



REQ. QUOTE DATE	/ /	ORDER #	
ORDER DATE	/ /	QUOTE #	B0924-5192
DELIVERY DATE	/ /	CUSTOMER ACCT #	0000006850
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	Greg Caulder	INVOICE #	
COUNTY	Wake	TERMS	
SUPERINTENDANT	Greg Caulder	SALES REP	Scot Duncan
JOBSITE PHONE #	(910) 424-3311	SALES AREA	Michael Turner

SHEET NO	<b>GMC Construction of NC, Inc.</b> 9820 US Hwy 301 North Lumberton, NC 28360 (910) 802-4959	<b>JOB NAME:</b> Lot 006 River Rd. <b>LOT #</b> 6352 <b>SUBDIV:</b> River Rd. <b>MODEL:</b> Roof <b>TAG:</b> Derbyville <b>JOB CATEGORY:</b> WCall - Will Call
		DELIVERY INSTRUCTIONS:  PLAN SEAL DATE:
SHEET NO	<b>GMC Const. of NC</b> 6352 River Rd. Fuquay Varina, NC	SPECIAL INSTRUCTIONS:

BUILDING DEPARTMENT Roof Order	OVERHANG INFO	HEEL HEIGHT	00-04-03	REQ. LAYOUTS	REQ. ENGINEERING	QUOTE	BY	DATE
	END CUT	RETURN				LAYOUT		/ /
	PLUMB		GABLE STUDS	24 IN. OC	JOBSITE	1	CUTTING	/ /

<b>ROOF TRUSSES</b>	LOADING INFORMATION	TCLL-TCDL-BCLL-BCDL	STRESS INCR.	ROOF TRUSS SPACING: 24.0 IN. O.C. (TYP.)
		20.0,10.0,0.0,10.0	1.15	

PROFILE	QTY	PITCH		TYPE ID	BASE O/A	LUMBER		OVERHANG		REACTIONS
		PLY	TOP			BOT	TOP	BOT	LEFT	
	1	12.00	6.00	SPECIAL A01	10-08-00 10-08-00	2 X 4	2 X 4			Joint 8 182.6 lbs. -73.0 lbs. Joint 9 230.0 lbs. -132.0 lbs. Joint 10 265.1 lbs. 24.1 lbs. Joint 11 232.2 lbs. -134.0 lbs. Joint 12 217.4 lbs. -114.2 lbs.
	1	12.00	6.00	GABLE B01	23-00-08 23-00-08	2 X 4	2 X 4			Joint 14 417.5 lbs. -232.0 lbs. Joint 15 334.3 lbs. -719.1 lbs. Joint 16 183.1 lbs. -152.2 lbs. Joint 17 243.8 lbs. -306.6 lbs. Joint 18 278.6 lbs. -263.0 lbs.
	4	12.00	6.00	SPECIAL B02	23-00-08 23-00-08	2 X 4	2 X 4			Joint 9 1041.3 lbs. -551.6 lbs. Joint 13 1050.5 lbs. -576.3 lbs.
	4	12.00	0.00	COMMON B03	20-07-08 20-07-08	2 X 4	2 X 4			Joint 6 862.2 lbs. -163.9 lbs. Joint 10 862.2 lbs. -163.9 lbs.
	3	12.00	0.00	COMMON B04	20-07-08 12-08-00	2 X 4	2 X 4			Joint 6 498.3 lbs. 29.1 lbs. Joint 8 668.0 lbs. -316.6 lbs.
	1	12.00	0.00	GABLE B05	20-07-08 12-08-00	2 X 4	2 X 4			Joint 5 496.6 lbs. 25.9 lbs. Joint 8 673.9 lbs. -316.7 lbs.
	1	12.00	0.00	COMMON C01	15-01-00 15-01-00	2 X 4	2 X 4			Joint 10 258.7 lbs. -137.7 lbs. Joint 11 274.7 lbs. -254.6 lbs. Joint 12 207.3 lbs. -108.6 lbs. Joint 13 375.9 lbs. 67.6 lbs. Joint 14 206.2 lbs. -107.6 lbs.
	6	12.00	0.00	COMMON C02	15-01-00 15-01-00	2 X 4	2 X 4			Joint 2 1472.9 lbs. 122.4 lbs. Joint 6 603.3 lbs. -111.7 lbs. Joint 8 603.3 lbs. -111.7 lbs. Joint 10 1431.6 lbs. 129.3 lbs.
	2	12.00	0.00	COMMON C03	12-08-00 12-08-00	2 X 4	2 X 4			Joint 4 495.0 lbs. -105.4 lbs. Joint 6 495.0 lbs. -105.4 lbs.
	1	10.00	0.00	COMMON D01	11-03-00 11-03-00	2 X 4	2 X 4			Joint 8 203.2 lbs. -102.2 lbs. Joint 9 231.2 lbs. -156.6 lbs. Joint 10 254.6 lbs. 77.0 lbs. Joint 11 233.6 lbs. -158.7 lbs. Joint 12 205.2 lbs. -105.1 lbs.
	3	10.00	0.00	COMMON D02	11-03-00 11-03-00	2 X 4	2 X 4			Joint 6 450.0 lbs. -94.7 lbs. Joint 8 450.0 lbs. -94.7 lbs.
	1	12.00	6.00	GABLE E01	13-07-08 13-07-08	2 X 4	2 X 4			Joint 5 449.8 lbs. -106.6 lbs. Joint 9 628.5 lbs. -110.9 lbs.
	1	12.00	6.00	SPECIAL E02	13-07-08 13-07-08	2 X 4	2 X 4			Joint 5 449.8 lbs. -106.6 lbs. Joint 7 628.5 lbs. -110.9 lbs.
	4	12.00	6.00	SPECIAL E03	13-07-08 13-07-08	2 X 4	2 X 4			Joint 5 429.5 lbs. -103.2 lbs. Joint 8 628.2 lbs. -108.0 lbs.
	1	12.00	6.00	HALF HIP E04	13-02-14 13-02-14	2 X 4	2 X 4	00-04-10		Joint 5 429.5 lbs. -186.5 lbs. Joint 8 628.2 lbs. -36.8 lbs.

# Reaction Summary of Quote



REQ. QUOTE DATE	//	ORDER #	
ORDER DATE	//	QUOTE #	B0924-5192
DELIVERY DATE	//	CUSTOMER ACCT #	0000006850
DATE OF INVOICE	//	CUSTOMER PO #	
ORDERED BY	Greg Caulder	INVOICE #	
COUNTY	Wake	TERMS	
SUPERINTENDANT	Greg Caulder	SALES REP	Scot Duncan
JOBSITE PHONE #	(910) 424-3311	SALES AREA	Michael Turner

SCHEDULE	<b>GMC Construction of NC, Inc.</b> 9820 US Hwy 301 North Lumberton, NC 28360 (910) 802-4959	<b>JOB NAME:</b> Lot 006 River Rd. <b>LOT #</b> 6352 <b>SUBDIV:</b> River Rd. <b>MODEL:</b> Roof <b>TAG:</b> Derbyville <b>JOB CATEGORY:</b> WCall - Will Call
	<b>GMC Const. of NC</b> 6352 River Rd. Fuquay Varina, NC	<b>DELIVERY INSTRUCTIONS:</b>  <b>PLAN SEAL DATE:</b>
<b>SPECIAL INSTRUCTIONS:</b>		

<b>BUILDING DEPARTMENT</b>	<b>OVERHANG INFO</b>	<b>HEEL HEIGHT</b>	00-04-03	<b>REQ. LAYOUTS</b>	<b>REQ. ENGINEERING</b>	<b>QUOTE</b>		<b>BY</b>	<b>DATE</b>
Roof Order	END CUT	RETURN							//
	PLUMB		GABLE STUDS	24 IN. OC	JOBSITE	1	JOBSITE	1	CUTTING

<b>ROOF TRUSSES</b>	<b>LOADING INFORMATION</b>	TCLL-TCDL-BCLL-BCDL	STRESS INCR.	<b>ROOF TRUSS SPACING:</b> 24.0 IN. O.C. (TYP.)
		20.0,10.0,0.0,10.0	1.15	

PROFILE	QTY	PITCH		TYPE ID	BASE O/A	LUMBER		OVERHANG		REACTIONS				
		PLY	TOP			BOT	TOP	BOT	LEFT	RIGHT	Joint 5	Joint 6	Joint 8	Joint 9
	1	12.00	0.00	HALF HIP E05	13-03-06 13-03-06	2 X 4	2 X 4		00-04-02	495.1 lbs.	4680.0 lbs.	614.9 lbs.	4055.1 lbs.	747.3 lbs.
										-270.5 lbs.	-310.3 lbs.	13.5 lbs.	-285.0 lbs.	-123.5 lbs.
	1	12.00	0.00	HALF HIP E06	13-03-08 13-03-06	2 X 4	2 X 4			774.4 lbs.	595.3 lbs.	603.4 lbs.	2207.8 lbs.	
										-93.1 lbs.	-396.6 lbs.	-94.7 lbs.	-118.3 lbs.	
	1	12.00	0.00	MONOPITCH E07	11-08-00 11-07-14	2 X 6	2 X 6			681.3 lbs.	488.1 lbs.			
										-480.8 lbs.	118.8 lbs.			
	1	12.00	0.00	MONOPITCH E08	11-07-14 11-07-14	2 X 6	2 X 6		00-04-02	664.8 lbs.	495.4 lbs.			
										-459.1 lbs.	125.0 lbs.			
	1	12.00	0.00	MONOPITCH E09	11-07-14 11-07-14	2 X 6	2 X 6		00-04-02	1591.9 lbs.	1599.0 lbs.			
										-978.9 lbs.	-267.7 lbs.			
	1	4.00	6.86	GABLE G01	31-09-08 31-09-08	2 X 6	2 X 6			383.1 lbs.	470.3 lbs.	1601.7 lbs.		
										-273.1 lbs.	-101.5 lbs.	-474.1 lbs.		
	2	4.00	6.86	ROOF G02	31-09-08 31-09-08	2 X 6	2 X 6			383.1 lbs.	575.1 lbs.	575.1 lbs.	470.3 lbs.	1601.7 lbs.
										-273.1 lbs.	-96.2 lbs.	-96.2 lbs.	-101.5 lbs.	-474.1 lbs.
	1	4.00	6.86	ROOF G04	31-09-08 31-09-08	2 X 6	2 X 6			383.1 lbs.	470.3 lbs.	1601.7 lbs.		
										-147.4 lbs.	-101.5 lbs.	-474.1 lbs.		
	1	4.00	6.86	ROOF G05	31-09-08 31-09-08	2 X 6	2 X 6			383.1 lbs.	470.3 lbs.	1601.7 lbs.		
										-273.1 lbs.	-101.5 lbs.	-474.1 lbs.		
	1	4.00	6.86	HALF HIP G06	31-09-08 31-09-08	2 X 6	2 X 6			370.5 lbs.	497.6 lbs.	1577.5 lbs.		
										-101.6 lbs.	-192.8 lbs.	-475.0 lbs.		
	1	4.00	6.86	HALF HIP G07	31-09-08 31-09-08	2 X 6	2 X 6			318.0 lbs.	1680.8 lbs.	414.4 lbs.		
										-124.1 lbs.	-522.4 lbs.	-174.1 lbs.		
	1	4.00	6.86	HALF HIP G08	31-09-08 31-09-08	2 X 6	2 X 6			365.7 lbs.	1591.8 lbs.	491.3 lbs.		
										-121.7 lbs.	-435.8 lbs.	-308.1 lbs.		
	2	4.00	6.86	ROOF G09	31-09-08 31-09-08	2 X 6	2 X 6			378.4 lbs.	1568.8 lbs.	574.5 lbs.		
										-121.5 lbs.	-399.7 lbs.	-376.8 lbs.		
	1	10.00	0.00	ATTIC TRUSS H01	33-08-08 33-08-08	2 X 6	2 X 12			6591.2 lbs.	3696.4 lbs.	5289.8 lbs.		
										-992.0 lbs.	1626.7 lbs.	-1953.8 lbs.		
	1	10.00	0.00	ATTIC TRUSS H02	33-08-08 33-08-08	2 X 6	2 X 12			2222.3 lbs.	669.0 lbs.	2096.9 lbs.		
										-171.9 lbs.	-177.9 lbs.	-256.2 lbs.		

# Reaction Summary of Quote



REQ. QUOTE DATE	//	ORDER #	
ORDER DATE	//	QUOTE #	B0924-5192
DELIVERY DATE	//	CUSTOMER ACCT #	0000006850
DATE OF INVOICE	//	CUSTOMER PO #	
ORDERED BY	Greg Caulder	INVOICE #	
COUNTY	Wake	TERMS	
SUPERINTENDANT	Greg Caulder	SALES REP	Scot Duncan
JOBSITE PHONE #	(910) 424-3311	SALES AREA	Michael Turner

SPECIAL TO	<b>GMC Construction of NC, Inc.</b> 9820 US Hwy 301 North Lumberton, NC 28360 (910) 802-4959	<b>JOB NAME:</b> Lot 006 River Rd. <b>LOT #</b> 6352 <b>SUBDIV:</b> River Rd. <b>MODEL:</b> Roof <b>TAG:</b> Derbyville <b>JOB CATEGORY:</b> WCall - Will Call
		DELIVERY INSTRUCTIONS:  PLAN SEAL DATE:
SHIP TO	<b>GMC Const. of NC</b> 6352 River Rd. Fuquay Varina, NC	SPECIAL INSTRUCTIONS:

BUILDING DEPARTMENT	OVERHANG INFO	HEEL HEIGHT	00-04-03	REQ. LAYOUTS	REQ. ENGINEERING	QUOTE	BY	DATE
	END CUT	RETURN				LAYOUT		//
	PLUMB		GABLE STUDS	24 IN. OC	JOBSITE	1	CUTTING	//

<b>ROOF TRUSSES</b>	LOADING INFORMATION	TCLL-TCDL-BCLL-BCDL	STRESS INCR.	ROOF TRUSS SPACING: 24.0 IN. O.C. (TYP.)
		20.0,10.0,0.0,10.0	1.15	

PROFILE	QTY	PITCH		TYPE ID	BASE O/A	LUMBER		OVERHANG		REACTIONS				
		PLY	TOP			BOT	TOP	BOT	LEFT	RIGHT				
	2	10.00	0.00	ATTIC TRUSS H03	35-04-00 35-04-00	2 X 6	2 X 12			Joint 11 1940.4 lbs. -144.6 lbs.	Joint 16 766.1 lbs. -111.5 lbs.	Joint 18 1953.1 lbs. -161.6 lbs.		
	1	4.00	0.00	ATTIC H04	47-06-00 47-06-00	2 X 6	2 X 12	01-07-08		Joint 14 1928.3 lbs. -98.7 lbs.	Joint 18 2329.5 lbs. -279.4 lbs.	Joint 22 1347.5 lbs. -423.7 lbs.		
	2	4.00	0.00	ATTIC H05	47-06-00 47-06-00	2 X 6	2 X 8	01-07-08		Joint 1 1468.1 lbs. -201.1 lbs.	Joint 13 1930.0 lbs. 97.7 lbs.	Joint 17 2186.7 lbs. -3.6 lbs.		
	7	4.00	0.00	MONOPITCH J01	06-09-08 06-09-08	2 X 6	2 X 6	01-07-08		Joint 1 129.9 lbs. -19.6 lbs.	Joint 3 129.9 lbs. -24.7 lbs.	Joint 4 189.5 lbs. 19.4 lbs.		
	3	12.00	0.00	MONOPITCH J02	02-07-00 02-07-00	2 X 4	2 X 4			Joint 3 17.0 lbs. -208.2 lbs.	Joint 4 356.5 lbs. 5.3 lbs.			
	2	3.50	0.00	JACK-OPEN J03	02-04-12 02-04-12	2 X 4	2 X 6	00-10-08		Joint 1 100.2 lbs. -39.0 lbs.	Joint 2 75.2 lbs. -70.4 lbs.	Joint 3 50.1 lbs. 12.5 lbs.		
	1	12.00	6.00	GABLE K01	19-11-00 19-11-00	2 X 6	2 X 4			Joint 12 285.5 lbs. -168.6 lbs.	Joint 13 312.4 lbs. -271.1 lbs.	Joint 14 165.7 lbs. -139.7 lbs.	Joint 15 209.4 lbs. -100.5 lbs.	Joint 16 601.0 lbs. -87.8 lbs.
	2	12.00	6.00	SPECIAL K02	19-11-00 19-11-00	2 X 6	2 X 4			Joint 6 792.4 lbs. -145.8 lbs.	Joint 8 792.4 lbs. -145.8 lbs.			
	4	12.00	6.00	SPECIAL K03	18-03-08 18-03-08	2 X 6	2 X 4			Joint 6 639.0 lbs. -138.2 lbs.	Joint 8 801.9 lbs. -143.8 lbs.			
	1 2 Ply	12.00	0.00	COMMON K04	18-03-08 18-02-08	2 X 6	2 X 12			Joint 2 1218.1 lbs. 16.5 lbs.	Joint 5 8400.8 lbs. -1756.4 lbs.	Joint 8 2988.2 lbs. 29.1 lbs.		
	1	2.48	0.00	JACK-OPEN KJ01	03-03-15 03-03-15	2 X 4	2 X 6	01-02-14		Joint 2 227.2 lbs. -119.2 lbs.	Joint 3 74.2 lbs. -51.0 lbs.	Joint 4 62.1 lbs. 15.5 lbs.		
	1	12.00	0.00	COMMON L01	14-03-00 14-03-00	2 X 4	2 X 4			Joint 11 343.1 lbs. -239.0 lbs.	Joint 12 324.2 lbs. -239.3 lbs.	Joint 13 461.8 lbs. 134.9 lbs.	Joint 14 325.4 lbs. -241.0 lbs.	Joint 15 344.5 lbs. -240.2 lbs.
	1 2 Ply	12.00	0.00	COMMON L02	11-00-00 11-00-00	2 X 4	2 X 10			Joint 6 6063.4 lbs. -947.8 lbs.	Joint 9 1454.8 lbs. -244.0 lbs.			
	2 2 Ply	12.00	0.00	JACK-CLOSED M01	10-09-02 10-09-02	2 X 6	2 X 10			Joint 6 3404.8 lbs. 881.8 lbs.	Joint 7 3322.7 lbs. 1271.7 lbs.			
	2	12.00	0.00	MONOPITCH M02	10-09-02 10-09-02	2 X 6	2 X 4			Joint 6 455.3 lbs. -417.4 lbs.	Joint 7 495.9 lbs. 89.8 lbs.			

# Reaction Summary of Quote



REQ. QUOTE DATE	//	ORDER #	
ORDER DATE	//	QUOTE #	B0924-5192
DELIVERY DATE	//	CUSTOMER ACCT #	0000006850
DATE OF INVOICE	//	CUSTOMER PO #	
ORDERED BY	Greg Caulder	INVOICE #	
COUNTY	Wake	TERMS	
SUPERINTENDANT	Greg Caulder	SALES REP	Scot Duncan
JOBSITE PHONE #	(910) 424-3311	SALES AREA	Michael Turner

SHEET	<b>GMC Construction of NC, Inc.</b> 9820 US Hwy 301 North Lumberton, NC 28360 (910) 802-4959	<b>JOB NAME:</b> Lot 006 River Rd. <b>LOT #</b> 6352 <b>SUBDIV:</b> River Rd. <b>MODEL:</b> Roof <b>TAG:</b> Derbyville <b>JOB CATEGORY:</b> WCall - Will Call
		DELIVERY INSTRUCTIONS:  PLAN SEAL DATE:
SHEET	<b>GMC Const. of NC</b> 6352 River Rd. Fuquay Varina, NC	SPECIAL INSTRUCTIONS:

<b>BUILDING DEPARTMENT</b>	Roof Order	<b>OVERHANG INFO</b>	<b>HEEL HEIGHT</b>	00-04-03	<b>REQ. LAYOUTS</b>	<b>REQ. ENGINEERING</b>	<b>QUOTE</b>		//
		<b>END CUT</b>	<b>RETURN</b>				<b>LAYOUT</b>		//
		<b>PLUMB</b>	<b>GABLE STUDS</b>	24 IN. OC	<b>JOBSITE</b>	1	<b>CUTTING</b>		//

<b>ROOF TRUSSES</b>	<b>LOADING INFORMATION</b>	TCLL-TCDL-BCLL-BCDL	STRESS INCR.	<b>ROOF TRUSS SPACING:</b> 24.0 IN. O.C. (TYP.)
		20.0,10.0,0.0,10.0	1.15	

PROFILE	QTY	PITCH		TYPE ID	BASE O/A	LUMBER		OVERHANG		REACTIONS				
		PLY	TOP			BOT	TOP	BOT	LEFT	RIGHT				
	1	12.00	0.00	HALF HIP M03	10-09-02 10-09-02	2 X 6	2 X 6			Joint 5 528.0 lbs. -347.9 lbs.	Joint 6 546.3 lbs. 95.9 lbs.			
	1	12.00	0.00	HALF HIP M04	10-09-02 10-09-02	2 X 4	2 X 6			Joint 3 258.4 lbs. -74.1 lbs.	Joint 4 27.4 lbs. -355.2 lbs.	Joint 5 898.2 lbs. -88.8 lbs.	Joint 7 461.4 lbs. -242.7 lbs.	Joint 8 562.4 lbs. 27.7 lbs.
	4	12.00	0.00	COMMON M05	10-09-02 10-09-02	2 X 4	2 X 4			Joint 6 457.7 lbs. -65.0 lbs.	Joint 7 568.6 lbs. -5.6 lbs.			
	1	12.00	0.00	HALF HIP M06	10-09-02 10-09-02	2 X 6	2 X 6			Joint 5 431.1 lbs. -385.7 lbs.	Joint 6 488.4 lbs. 94.4 lbs.			
	3	12.00	0.00	COMMON M07	10-09-02 10-09-02	2 X 6	2 X 6			Joint 5 427.2 lbs. -375.5 lbs.	Joint 6 485.5 lbs. 94.1 lbs.			
	1	3.50	0.00	MONOPITCH N01	02-05-08 02-05-08	2 X 4	2 X 6	00-10-08		Joint 2 149.8 lbs. -71.0 lbs.	Joint 6 88.5 lbs. -36.2 lbs.			
	4	3.50	0.00	MONOPITCH N02	06-05-08 06-05-08	2 X 4	2 X 6	00-10-08		Joint 2 303.7 lbs. -153.7 lbs.	Joint 4 171.3 lbs. -72.9 lbs.			
	6	3.50	0.00	MONOPITCH N03	06-01-08 06-01-08	2 X 4	2 X 6	00-10-08		Joint 2 299.3 lbs. -148.3 lbs.	Joint 4 229.0 lbs. -130.5 lbs.			
	1	3.50	0.00	HALF HIP N04	06-05-08 06-05-08	2 X 4	2 X 6	00-10-08		Joint 2 312.3 lbs. -163.2 lbs.	Joint 5 242.7 lbs. -126.5 lbs.			
	1	3.50	0.00	HALF HIP N05	06-05-08 06-05-08	2 X 4	2 X 6	00-10-08		Joint 2 332.8 lbs. -187.3 lbs.	Joint 5 265.5 lbs. -141.0 lbs.			
	4	10.00	0.00	PIGGYBACK PB1	08-08-08 08-08-08	2 X 4	2 X 4			Joint 2 227.8 lbs. -78.4 lbs.	Joint 4 227.8 lbs. -93.0 lbs.	Joint 6 290.3 lbs. -7.1 lbs.		
	1	10.00	0.00	PIGGYBACK PB2	08-08-09 08-08-09	2 X 4	2 X 4			Joint 2 121.2 lbs. -99.0 lbs.	Joint 5 121.2 lbs. -102.6 lbs.	Joint 7 253.0 lbs. -93.2 lbs.	Joint 8 253.0 lbs. -114.9 lbs.	