

**Adams Soil Consulting, PLLC**  
**1676 Mitchell Road**  
**Angier, NC 27501**  
**919-414-6761**  
**alexadams@bcsoil.com**


---

November 28, 2024  
Project #1915

RE: 257 Grading Stick Ct. - Angier, NC 27501– (Harnett County, NC PIN# 0693-25-6427)

**OWNER ACCEPTANCE OF SEPTIC SYSTEM**

I certify that Drees Homes is accepting the subsurface wastewater (septic) system installed at 257 Grading Stick Ct. The acceptance includes the AOWE permit as issued and designed by Adams Soil Consulting, PLLC and installed by Full Circle Septic.

Owner’s Representative (print):  Bradley Weekley Bradley weekley  
4E761125D09C444...

Owner’s Representative – (Signature Date: 12/2/2024 | 10:03:52 AM EST)

**Adams Soil Consulting  
1676 Mitchell Road  
Angier, NC 27501  
919-414-6761**

---

November 28, 2024  
Project #1907

*This document is submitted in addition to the "Notice of Intent to Construct" submittal package previously supplied to the local health department in pursuant to G.S. 130A-336.1*


RE: 257 Grading Stick Ct- Angier, NC 27501– (Harnett County, NC PIN# 0693-25-6427)

To whom it may concern:

This letter is to notify the Harnett County Environmental Health Department that the construction of the wastewater system has been completed. The system was installed to acceptable construction standards. The installation was constructed in conformance to the original construction documents. This document may serve as "Authorization to Operate" the installed system.

**Operation and Management Program**

Have the effluent filter in the septic tank cleaned periodically by a professional. Have the solids pumped out of the septic tank every 3-5 years by a professional. Maintain adequate vegetative cover over the drainfield. Keep surface waters away from the tank and drainfield. Do not pour grease or oil down the sink. Contact a professional for periodic maintenance.



Alex Adams  
Adams Soils Consulting, PLLC  
NC Licensed Soil Scientist #1247



**North Carolina Onsite Wastewater Contractor Inspector Certification Board  
 Authorized Onsite Wastewater Evaluator Permit Option for Non-Engineered Systems  
 Notice of Intent (NOI) to Construct**

New  Expansion  Repair  Relocation  Relocation of Repair Area

Owner or Legal Representative Information: Teri Treffzs  
 Name: Drees Homes Company  
 Mailing address: 211 Grandview Drive - Suite 102 City: Ft. Mitchell State: KY Zip: 41017  
 Phone: 919-256-5478 Email: ttreffzs@dreeshomes.com

Authorized Onsite Wastewater Evaluator Information:  
 Name: Alex Adams Certification #: AOWE# 10021E  
 Mailing address: 1676 Mitchell Road City: Angier State: NC Zip: 27501  
 Phone: 919-414-6761 Email: alexadams@bcsoil.com

Site Location Information:  
 Site address: Lot #50 (Tobacco Road) 257 Grading Stick Ct. - Angier, NC 27501  
 Tax parcel identification number or subdivision lot, block number of property: PIN# 0693-25-6427  
 County: Harnett

System Information: Accepted Status  
 Wastewater System Type: Type III (g)  
 Daily Design Flow: 600 gallons/day  
 Sapro-lite System:  Yes  No Subsurface Operator Required:  Yes  No  
 Water Supply Type:  Private Well  Public Water Supply  Spring  Other:

Facility Type:  
 Residential  # Bedrooms  10 Maximum # of Occupants  
 Business Type of Business and Basis for Flow: \_\_\_\_\_  
 Public Assembly Type of Public Assembly and Basis for Flow: \_\_\_\_\_

Require Attachments:  
 Plat or Siteplan  
 Evaluation of Soil and Site Features by Licensed Soil Scientist

Attest: On this the 18 Day of July 2024 by signature below I hereby attest that the information required to be included with this NOI to Construct is accurate and complete to the best of my knowledge. Furthermore, I hereby attest that I have adhered to the laws and rules governing onsite wastewater systems in the state of North Carolina.  
 This NOI shall expire on 18th day of July 2029.  
 Signature of Authorized Onsite Wastewater Evaluator: Alex Adams  
 Signature of Owner or Legal Representative: \_\_\_\_\_

Disclosure: The owner may apply for a building permit for the project upon submitting a complete NOI to Construct and the fee required (if any) to the local health department. An onsite wastewater system authorized by an authorized onsite wastewater evaluator shall be transferable to a new owner with the consent of the authorized onsite wastewater evaluator.

Local Health Department Receipt Acknowledgement:  
 Signature of Local Health Department Representative: \_\_\_\_\_ Date: \_\_\_\_\_

**Adams Soil Consulting, PLLC**  
**1676 Mitchell Road**  
**Angier, NC 27501**  
**919-414-6761**  
**alexadams@bcsoil.com**

---

July 18, 2024  
Project #1215

*“This AOWE/PE submittal is pursuant to and meets the requirements of G.S. 130A-336.2*

RE: Tobacco Road -Lot #50, 257 Grading Stick Ct.. - Angier, NC - 5-bedroom Single Family Residence (PIN# 0693-25-6427)

To whom it may concern:

Adams Soil Consulting (ASC) conducted a preliminary soil evaluation on the above referenced parcel to determine the areas of soils which are suitable for subsurface wastewater disposal systems (conventional & LPP). The soil/site evaluation was performed using hand auger borings during moist soil conditions based on the criteria found in the State Subsurface Rules 15ANCAC 18E. From this evaluation, ASC is providing the attached septic system design for a new single-family home sized for a 600 gallon/day septic system.

The suitable soils found on the subject property were somewhat variable in the initial and repair areas. The area designated for the initial/primary septic system (see attached septic plan) was found to contain soils with greater than 24 inches in depth before a restrictive horizon was encountered.


The initial and primary septic fields for the new home were sized based on a flow rate of 600 gallons/day and utilizing Accepted Status system for the initial and a PPBPS repair system. Any unauthorized site disturbance, filling, soil removal, or layout changes may result in the permit being revoked.

The septic installer contractor shall install the repair (if needed) system on contour, see attached site plan for the primary system and repair. No underground utilities, water lines, or sprinkler systems shall be placed into the initial or repair septic areas. Installation must meet all state and local county regulations for septic system installation. The trenches must be installed in the same location as the site plan. If flags trench flags are missing at the time of installation, they must be remarked by Adams Soil Consulting staff. Contact Alex Adams at 919-414-6761. A preconstruction conference is required with the septic installer prior to construction activities at least 14 days in advance of construction activities.

This report does not guarantee the future function of any waste water disposal system installed.

If you have any questions regarding the findings on the attached site plan or in this report, please feel free to contact me anytime.

Sincerely,



Alex Adams  
NC Licensed Soil Scientist #1247  
AOWE Certification: 10021E




**Tobacco Road S/D**  
**5-Bedroom Septic Design**  
**Lot #50 - 257 Grading Stick Ct.**  
**Drees Homes**

**Harnett County PIN: 0693-25-6427**

\*Not a Survey  
 Sketched from a plot plan supplied by owner


System: Gravity to D-Box  
 Lines: 1-3 (390')  
 0.4 LTAR  
 18" Max Trench Bottom  
 Accepted Status System  
 Repair: Pressure Manifold  
 Lines: 4-5 (260')  
 0.4 LTAR  
 18" Max Trench Bottom  
 T&J Panel Block - 50% Reduction System



**\*\*1250 Gallon Septic and Pump Tank**  
 Tank and trenches to be located minimum of 10' from any property line and minimum of 5' from any building foundation.  
 \*Do Not Cut, Fill, or Alter Drainfield or Repair Area  
 \*Comply with all setbacks  
 \*Contact Alex Adams prior to or during installation with any questions or concerns.

\*Contact Alex Adams at least 10 days prior to installation.

Adams  
 Soil Consulting  
 919-414-6761  
 Job #1215  
 7-18-24




# Tobacco Road S/D 5-Bedroom Septic Design Lot #50 - 257 Grading Stick Ct. Drees Homes

Harnett County PIN: 0693-25-6427


\*Not a Survey  
Sketched from a plot plan supplied by owner

System: Gravity to D-Box  
Lines: 1-3 (390')  
0.4 LTAR  
18" Max Trench Bottom  
Accepted Status System  
Repair: Pressure Manifold  
Lines: 4-5 (260')  
0.4 LTAR  
18" Max Trench Bottom  
T&J Panel Block - 50% Reduction System




- ① Profile Description #1  
See Soil/Site Evaluation Data Form
- ② Profile Description #2  
See Soil/Site Evaluation Data Form
- ③ Profile Description #3  
See Soil/Site Evaluation Data Form

Adams  
Soil Consulting  
919-414-6761  
Job #1215  
7-18-24




LINE TABLE		
LINE	BEARING	DISTANCE
L1	S 47°07'30" E	100.00'
L2	N 17°05'27" E	55.02'

PROPOSED IMPERVIOUS SURFACES:  
 TOTAL LOT AREA=35,263 S.F.  
 HOUSE/PORCHES=2,706 S.F.  
 DRIVEWAYS/ETC.=1,189 S.F.  
 TOTAL IMPERVIOUS AREA=3,895 S.F.  
 MAX. IMPERVIOUS AREA=5,500 S.F.




REFERENCES:  
 1. D.B. 4218, PG. 193  
 PIN 0693-25-6427.000  
 PID 040693 0030 31



**SETBACKS**  
 FRONT YARD-35'  
 SIDE YARD-10'  
 REAR YARD-25'  
 CORNER SIDE-20'

**LEGEND**  
 (EOP)-EDGE OF PAVEMENT  
 (LP)-LIGHT POLE  
 (PD)-PROPOSED DRIVEWAY  
 (WM)-WATER METER  
 (AC)-AIR CONDITIONER


- NOTES:
1. ALL EASEMENTS, RIGHTS OF WAY AND BOUNDARY INFORMATION TAKEN FROM P.B. 2023, PG 563-568 UNLESS OTHERWISE NOTED.
  2. PROPERTY IS SUBJECT TO ALL EASEMENTS AND RESTRICTIONS OF RECORD. NO TITLE EXAMINATION HAS BEEN DONE BY ROBINSON & PLANTE, P.C.
  3. INDIVIDUAL ON SITE SEPTIC SYSTEM FOR ALL LOTS
  4. WATER TO BE PROVIDED BY HARNETT COUNTY PUBLIC UTILITIES
  5. NO ENCROACHMENTS INTO THE WETLANDS WILL BE ALLOWED. LOTS TO BE INTERNALLY ACCESSED ONLY.
  6. ONLY N.C. DEPARTMENT OF TRANSPORTATION APPROVED STRUCTURES ARE TO BE CONSTRUCTED ON PUBLIC RIGHT OF WAY.
  7. ANY PARCELS OR EXCLUDED AREAS ARE TO BE SERVED INTERNALLY WITH NO ACCESS ONTO DEPARTMENTAL RIGHT OF WAY.
  8. ALL DRAINAGE EASEMENTS SHALL BE DEDICATED AS PUBLIC AND SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNERS TO MAINTAIN THE DRAINAGE EASEMENTS AND ANY DRAINAGE STRUCTURES THERE IS SO AS TO MAINTAIN THE INTEGRITY OF DRAINAGE SYSTEM AND INSURE POSITIVE DRAINAGE
  9. PROPERTY FRONTAGE SHALL NOT PIPED WITHOUT AN APPROVED ENCROACHMENT AGREEMENT FROM NCDOT. THE EASEMENT ALLOWS NCDOT THE RIGHT TO ACCESS THE DRAINAGE EASEMENTS AND PERFORM WORK IT DEEMS NECESSARY OR PRUDENT TO ALLEVIATE ANY ISSUES JEOPARDIZING THE INTEGRITY OF THE ROADWAY.



**PRELIMINARY PLAT- NOT FOR RECORDATION, CONVEYANCE, OR SALE**

**LOT 50 TOBACCO ROAD SUBDIVISION  
 PHASE 1 & 3  
 257 GRADING STICK COURT  
 HARNETT COUNTY  
 ANGIER, NC 27501**

**SURVEY FOR  
 DREES HOMES**



REFERENCE: BOOK OF MAPS 2023 PAGE 563-568

FILE: TBRDLOT50PP

I CERTIFY THAT THIS MAP WAS DRAWN UNDER MY SUPERVISION FROM AN ACTUAL SURVEY MADE UNDER MY SUPERVISION DESCRIPTION RECORDED IN REFERENCES AS SHOWN; THAT THE BOUNDARIES NOT SURVEYED ARE INDICATED AS DRAWN FROM INFORMATION IN \_\_\_\_\_; THAT THE RATIO OF PRECISION IS 1:10,000; AND THAT THIS MAP MEET THE REQUIREMENTS OF THE STANDARDS OF PRACTICE FOR LAND SURVEYING IN NORTH CAROLINA (21 NCAC 56.16000). THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, 2024.

VANDERBURGH  
 ELEV. P  
 SEALED CRAWL SPACE  
 SCREENED IN OUTDOOR LIVING  
 CARRIAGE GARAGE  
 GARAGE RIGHT SIDE

**ROBINSON & PLANTE PC**  
 LAND SURVEYING  
 C-2687  
 970 TRINITY ROAD  
 RALEIGH, N.C. 27607  
 PHONE (919) 859-6030  
 FAX (919) 859-6032

PROFESSIONAL LAND SURVEYOR L-4433

DATE: 6-14-24 SCALE: 1"=60'



**SOIL/SITE EVALUATION**  
**for ON-SITE WASTEWATER SYSTEM**  
 (Complete all fields in full)

OWNER: Drees Homes,  
 ADDRESS:  
 PROPOSED FACILITY: Single Family, 5-bedroom PROPOSED DESIGN FLOW (.1949): 600 gpd  
 LOCATION OF SITE: 332 Golden Leaf, Angier, NC, 27501  
 WATER SUPPLY: Public Water  
 EVALUATION METHOD: Auger Boring

APPLICATION DATE:  
 DATE EVALUATED: 07/18/2024  
 PROPERTY SIZE: ~0.81 Acres

TYPE OF WASTEWATER: Sewage

P R O F I L E  #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941)		OTHER PROFILE FACTORS				PROFILE CLASS & LTAR
			.1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	.1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	
1	Linear Slope/5%	0-36	GR/SL	VFR,NS,NP,SEXP	N/A	40"	N/A	N/A	P.S/.6
		36-40	SBK/SCL	FR,SS,SP,SEXP					
2	Linear Slope/5%	0-24	GR/SL	VFR,NS,NP,SEXP	N/A	40"	N/A	N/A	P.S .4
		24-32	SBK/SCL	FR,SS,SP,SEXP					
3	Linear Slope/5%	0-40	GR/SL	VFR,NS,NP,SEXP	N/A	40"	N/A	N/A	P.S .6
4									

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM	OTHER FACTORS (.1946): _____ SITE CLASSIFICATION (.1948): U/PS  EVALUATED BY: A. Adams OTHER(S) PRESENT:
Available Space (.1945)	S	S	
System Type(s)	Type III B	Type III B	
Site LTAR	0.4	0.4	

COMMENTS:  
 Updated February 2014



# CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)

1/17/2024

**THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.**

**IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).**

<b>PRODUCER</b> Wade Associates, LLC 250 Pollock St.  New Bern NC 28560	<b>CONTACT NAME:</b> Angela Sensenig <b>PHONE (A/C, No, Ext):</b> (252) 631-5269 <b>FAX (A/C, No):</b> (252) 649-2443 <b>E-MAIL ADDRESS:</b> asensenig@wadeict.com
<b>INSURER(S) AFFORDING COVERAGE</b>	
<b>INSURER A:</b> Markel Insurance Company	
<b>NAIC #</b> 38970	
<b>INSURED</b> Alex Adams, DBA: Adams Soil Consulting 1676 Mitchell Rd.  Angier NC 27501	<b>INSURER B:</b> <b>INSURER C:</b> <b>INSURER D:</b> <b>INSURER E:</b> <b>INSURER F:</b>

**COVERAGES** **CERTIFICATE NUMBER: 24-25** **REVISION NUMBER:**

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDL INSD	SUBR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
	<b>COMMERCIAL GENERAL LIABILITY</b> <input type="checkbox"/> CLAIMS-MADE <input type="checkbox"/> OCCUR  GEN'L AGGREGATE LIMIT APPLIES PER: <input type="checkbox"/> POLICY <input type="checkbox"/> PRO-JECT <input type="checkbox"/> LOC OTHER:						EACH OCCURRENCE \$ DAMAGE TO RENTED PREMISES (Ea occurrence) \$ MED EXP (Any one person) \$ PERSONAL & ADV INJURY \$ GENERAL AGGREGATE \$ PRODUCTS - COMP/OP AGG \$ \$
	<b>AUTOMOBILE LIABILITY</b> <input type="checkbox"/> ANY AUTO <input type="checkbox"/> ALL OWNED AUTOS <input type="checkbox"/> SCHEDULED AUTOS <input type="checkbox"/> HIRED AUTOS <input type="checkbox"/> NON-OWNED AUTOS						COMBINED SINGLE LIMIT (Ea accident) \$ BODILY INJURY (Per person) \$ BODILY INJURY (Per accident) \$ PROPERTY DAMAGE (Per accident) \$ \$
	<b>UMBRELLA LIAB</b> <input type="checkbox"/> OCCUR <b>EXCESS LIAB</b> <input type="checkbox"/> CLAIMS-MADE DED    RETENTION \$						EACH OCCURRENCE \$ AGGREGATE \$ \$
	<b>WORKERS COMPENSATION AND EMPLOYERS' LIABILITY</b> ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below						<input type="checkbox"/> Y <input checked="" type="checkbox"/> N/A PER STATUTE    OTH-ER E.L. EACH ACCIDENT \$ E.L. DISEASE - EA EMPLOYEE \$ E.L. DISEASE - POLICY LIMIT \$
<b>A</b>	<b>Errors &amp; Omissions</b>			MEO1118-06	1/31/2024	1/31/2025	General Aggregate \$1,000,000 Each Occurrence \$1,000,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

**CERTIFICATE HOLDER**

**CANCELLATION**

**\*FOR INFORMATIONAL PURPOSES ONLY\***  
 XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX  
 XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX  
 XXXXXXXXXXXXXXXXXXXXXXXX

SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.

AUTHORIZED REPRESENTATIVE

N Whitsett/RACHEL