

RE: J0824-4837  
 Lot 13 Magnolia Hills

**Trenco**  
 818 Soundside Rd  
 Edenton, NC 27932

**Site Information:**

Customer: Project Name: J0824-4837  
 Lot/Block: Model:  
 Address: Subdivision:  
 City: State:

**General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):**

Design Code: IRC2015/TPI2014 Design Program: MiTek 20/20 8.4  
 Wind Code: ASCE 7-10 Wind Speed: 130 mph  
 Roof Load: 40.0 psf Floor Load: N/A psf

This package includes 23 individual, dated Truss Design Drawings and 0 Additional Drawings.

| No. | Seal#     | Truss Name | Date     | No. | Seal#     | Truss Name | Date     |
|-----|-----------|------------|----------|-----|-----------|------------|----------|
| 1   | I64635009 | A1         | 4/2/2024 | 21  | I64635029 | V4         | 4/2/2024 |
| 2   | I64635010 | A1GE       | 4/2/2024 | 22  | I64635030 | V5         | 4/2/2024 |
| 3   | I64635011 | A2         | 4/2/2024 | 23  | I64635031 | V6         | 4/2/2024 |
| 4   | I64635012 | A3         | 4/2/2024 |     |           |            |          |
| 5   | I64635013 | A3GE       | 4/2/2024 |     |           |            |          |
| 6   | I64635014 | B1GE       | 4/2/2024 |     |           |            |          |
| 7   | I64635015 | B2         | 4/2/2024 |     |           |            |          |
| 8   | I64635016 | C1         | 4/2/2024 |     |           |            |          |
| 9   | I64635017 | C1-GR      | 4/2/2024 |     |           |            |          |
| 10  | I64635018 | C1GE       | 4/2/2024 |     |           |            |          |
| 11  | I64635019 | G1         | 4/2/2024 |     |           |            |          |
| 12  | I64635020 | G1GE       | 4/2/2024 |     |           |            |          |
| 13  | I64635021 | J1         | 4/2/2024 |     |           |            |          |
| 14  | I64635022 | J2         | 4/2/2024 |     |           |            |          |
| 15  | I64635023 | J2GE       | 4/2/2024 |     |           |            |          |
| 16  | I64635024 | J3         | 4/2/2024 |     |           |            |          |
| 17  | I64635025 | J3GE       | 4/2/2024 |     |           |            |          |
| 18  | I64635026 | V1         | 4/2/2024 |     |           |            |          |
| 19  | I64635027 | V2         | 4/2/2024 |     |           |            |          |
| 20  | I64635028 | V3         | 4/2/2024 |     |           |            |          |

The truss drawing(s) referenced above have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Comtech, Inc - Fayetteville.

Truss Design Engineer's Name: Gilbert, Eric

My license renewal date for the state of North Carolina is December 31, 2024.

North Carolina COA: C-0844

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to TRENCO. Any project specific information included is for TRENCO customers file reference purpose only, and was not taken into account in the preparation of these designs. TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



April 02, 2024




|                   |               |                     |          |          |   |           |
|-------------------|---------------|---------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>A1GE | Truss Type<br>GABLE | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | 164635010 |
|-------------------|---------------|---------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,


8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:00 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



5x5 =

Scale = 1:67.5



| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d | PLATES         | GRIP     |
|---------------|----------------------|-------|----------|----------|----------|--------|-----|----------------|----------|
| TCLL 20.0     | Plate Grip DOL       | 1.15  | TC 0.04  | Vert(LL) | -0.00    | 20     | n/r | MT20           | 244/190  |
| TCDL 10.0     | Lumber DOL           | 1.15  | BC 0.02  | Vert(CT) | 0.00     | 20     | n/r |                |          |
| BCLL 0.0 *    | Rep Stress Incr      | YES   | WB 0.13  | Horz(CT) | 0.01     | 20     | n/a |                |          |
| BCDL 10.0     | Code IRC2015/TPI2014 |       | Matrix-S |          |          |        |     | Weight: 283 lb | FT = 20% |


**LUMBER-**  
 TOP CHORD 2x6 SP No.1  
 BOT CHORD 2x6 SP No.1  
 OTHERS 2x4 SP No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
 WEBS T-Brace: 2x4 SPF No.2 - 11-30, 10-31, 12-29  
 Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c., with 3in minimum end distance.  
 Brace must cover 90% of web length.

**REACTIONS.** All bearings 33-0-0.  
 (lb) - Max Horz 2=306(LC 11)  
 Max Uplift All uplift 100 lb or less at joint(s) 2, 20, 31, 32, 34, 35, 36, 37, 38, 29, 28, 26, 25, 24, 23, 22  
 Max Grav All reactions 250 lb or less at joint(s) 2, 20, 30, 31, 32, 34, 35, 36, 37, 38, 29, 28, 26, 25, 24, 23, 22

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-277/226, 10-11=-242/277, 11-12=-242/277

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - All plates are 2x4 MT20 unless otherwise indicated.
  - Gable requires continuous bottom chord bearing.
  - Gable studs spaced at 2-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 20, 31, 32, 34, 35, 36, 37, 38, 29, 28, 26, 25, 24, 23, 22.
  - Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.



April 2, 2024


**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road  
 Edenton, NC 27932

|                   |             |                      |          |          |   |           |
|-------------------|-------------|----------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>A2 | Truss Type<br>COMMON | Qty<br>4 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635011 |
|-------------------|-------------|----------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314, 8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:01 2024 Page 1



5x5 = Scale = 1:67.5



|                       |                                  |
|-----------------------|----------------------------------|
| Plate Offsets (X,Y)-- | [8:0-2-6,0-0-9], [8:0-0-2,1-1-1] |
|-----------------------|----------------------------------|

| LOADING (psf) | SPACING-             | CSI.     | DEFL.                         | PLATES         | GRIP     |
|---------------|----------------------|----------|-------------------------------|----------------|----------|
| TCLL 20.0     | 2-0-0                | TC 0.65  | in (loc) l/defl L/d           | MT20           | 244/190  |
| TCDL 10.0     | Plate Grip DOL 1.15  | BC 0.60  | Vert(LL) -0.15 10-13 >999 360 |                |          |
| BCLL 0.0 *    | Lumber DOL 1.15      | WB 0.31  | Vert(CT) -0.26 8-10 >999 240  |                |          |
| BCDL 10.0     | Rep Stress Incr YES  | Matrix-S | Horz(CT) 0.05 8 n/a n/a       |                |          |
|               | Code IRC2015/TPI2014 |          | Wind(LL) 0.05 2-13 >999 240   | Weight: 223 lb | FT = 20% |


**LUMBER-**  
TOP CHORD 2x6 SP No.1  
BOT CHORD 2x6 SP No.1  
WEBS 2x4 SP No.2  
WEDGE  
Right: 2x6 SP No.1

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 4-11-2 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 2=0-3-8, 8=0-3-8  
Max Horz 2=245(LC 11)  
Max Uplift 2=-91(LC 12), 8=-91(LC 13)  
Max Grav 2=1525(LC 19), 8=1525(LC 20)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-2295/423, 3-5=-2090/464, 5-7=-2091/464, 7-8=-2296/423  
BOT CHORD 2-13=-222/2070, 10-13=-9/1347, 8-10=-233/1886  
WEBS 3-13=-544/300, 5-13=-140/991, 5-10=-139/991, 7-10=-544/300

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) -1-0-6 to 3-4-7, Interior(1) 3-4-7 to 16-6-0, Exterior(2) 16-6-0 to 20-10-13, Interior(1) 20-10-13 to 34-0-6 zone; cantilever right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 8.





|                   |               |                     |          |          |   |           |
|-------------------|---------------|---------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>A3GE | Truss Type<br>GABLE | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635013 |
|-------------------|---------------|---------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,


8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:03 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



5x5 =

Scale = 1:66.2



|                      |                      |       |             |              |          |        |     |                |             |
|----------------------|----------------------|-------|-------------|--------------|----------|--------|-----|----------------|-------------|
| <b>LOADING</b> (psf) | <b>SPACING-</b>      | 2-0-0 | <b>CSI.</b> | <b>DEFL.</b> | in (loc) | l/defl | L/d | <b>PLATES</b>  | <b>GRIP</b> |
| TCLL 20.0            | Plate Grip DOL       | 1.15  | TC 0.04     | Vert(LL)     | -0.00    | 1      | n/r | MT20           | 244/190     |
| TCDL 10.0            | Lumber DOL           | 1.15  | BC 0.02     | Vert(CT)     | 0.00     | 1      | n/r |                |             |
| BCLL 0.0 *           | Rep Stress Incr      | YES   | WB 0.13     | Horz(CT)     | 0.01     | 20     | n/a |                |             |
| BCDL 10.0            | Code IRC2015/TPI2014 |       | Matrix-S    |              |          |        |     | Weight: 280 lb | FT = 20%    |


**LUMBER-**  
 TOP CHORD 2x6 SP No.1  
 BOT CHORD 2x6 SP No.1  
 OTHERS 2x4 SP No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
 WEBS T-Brace: 2x4 SPF No.2 - 11-29, 10-30, 12-28  
 Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c., with 3in minimum end distance.  
 Brace must cover 90% of web length.

**REACTIONS.** All bearings 33-0-0.  
 (lb) - Max Horz 2=301(LC 9)  
 Max Uplift All uplift 100 lb or less at joint(s) 2, 20, 30, 31, 33, 34, 35, 36, 37, 28, 27, 25, 24, 23, 22 except 21=-107(LC 13)  
 Max Grav All reactions 250 lb or less at joint(s) 2, 20, 29, 30, 31, 33, 34, 35, 36, 37, 28, 27, 25, 24, 23, 22, 21

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-280/222, 10-11=-236/265, 11-12=-236/265

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - 4) All plates are 2x4 MT20 unless otherwise indicated.
  - 5) Gable requires continuous bottom chord bearing.
  - 6) Gable studs spaced at 2-0-0 oc.
  - 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 8) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 20, 30, 31, 33, 34, 35, 36, 37, 28, 27, 25, 24, 23, 22 except (jt=lb) 21=107.
  - 10) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.



April 2, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road  
 Edenton, NC 27932

|                   |               |                     |          |          |   |           |
|-------------------|---------------|---------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>B1GE | Truss Type<br>GABLE | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635014 |
|-------------------|---------------|---------------------|----------|----------|---|-----------|


Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:03 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f



Scale = 1:23.2



|                       |                                  |             |                                  |               |             |
|-----------------------|----------------------------------|-------------|----------------------------------|---------------|-------------|
| Plate Offsets (X,Y)-- | [2:0-1-7,0-1-8], [8:0-1-7,0-1-8] |             |                                  |               |             |
| <b>LOADING</b> (psf)  | <b>SPACING-</b> 2-0-0            | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b> | <b>GRIP</b> |
| TCLL 20.0             | Plate Grip DOL 1.15              | TC 0.14     | Vert(LL) -0.02 10-11 >999 360    | MT20          | 244/190     |
| TCDL 10.0             | Lumber DOL 1.15                  | BC 0.19     | Vert(CT) -0.03 10-11 >999 240    |               |             |
| BCLL 0.0 *            | Rep Stress Incr YES              | WB 0.09     | Horz(CT) 0.01 8 n/a n/a          |               |             |
| BCDL 10.0             | Code IRC2015/TPI2014             | Matrix-S    | Wind(LL) 0.03 10-11 >999 240     | Weight: 65 lb | FT = 20%    |


**LUMBER-**  
 TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x6 SP No.1  
 WEBS 2x4 SP No.2  
 OTHERS 2x4 SP No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 2=0-3-0, 8=0-3-0  
 Max Horz 2=-73(LC 17)  
 Max Uplift 2=-143(LC 9), 8=-143(LC 8)  
 Max Grav 2=550(LC 1), 8=550(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-617/666, 3-4=-570/687, 4-5=-561/740, 5-6=-561/740, 6-7=-570/688, 7-8=-617/666  
 BOT CHORD 2-14=-494/491, 13-14=-494/491, 12-13=-494/491, 11-12=-494/491, 10-11=-494/491,  
 8-10=-494/491  
 WEBS 5-12=-513/328

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - 4) All plates are 2x4 MT20 unless otherwise indicated.
  - 5) Gable studs spaced at 2-0-0 oc.
  - 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 7) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=143, 8=143.



April 2, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




|                   |             |                      |          |          |   |           |
|-------------------|-------------|----------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>B2 | Truss Type<br>COMMON | Qty<br>4 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635015 |
|-------------------|-------------|----------------------|----------|----------|---|-----------|


Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:04 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale: 1/2"=1'



| LOADING (psf) | SPACING-             | CSI.     | DEFL.    | in (loc) | l/defl | L/d  | PLATES        | GRIP     |
|---------------|----------------------|----------|----------|----------|--------|------|---------------|----------|
| TCLL 20.0     | 2-0-0                | TC 0.29  | Vert(LL) | -0.01    | 4-6    | >999 | MT20          | 244/190  |
| TCDL 10.0     | Plate Grip DOL 1.15  | BC 0.15  | Vert(CT) | -0.02    | 4-6    | >999 |               |          |
| BCLL 0.0 *    | Lumber DOL 1.15      | WB 0.07  | Horz(CT) | 0.01     | 4      | n/a  |               |          |
| BCDL 10.0     | Rep Stress Incr YES  | Matrix-S | Wind(LL) | 0.03     | 4-6    | >999 |               |          |
|               | Code IRC2015/TPI2014 |          |          |          |        |      | Weight: 57 lb | FT = 20% |

**LUMBER-**  
 TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x6 SP No.1  
 WEBS 2x4 SP No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 2=0-3-0, 4=0-3-0  
 Max Horz 2=-47(LC 10)  
 Max Uplift 2=-109(LC 9), 4=-109(LC 8)  
 Max Grav 2=550(LC 1), 4=550(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-640/667, 3-4=-640/667  
 BOT CHORD 2-6=-457/485, 4-6=-457/485  
 WEBS 3-6=-394/296

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TC DL=6.0psf; BC DL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) -1-2-8 to 3-2-5, Interior(1) 3-2-5 to 6-0-0, Exterior(2) 6-0-0 to 10-4-13, Interior(1) 10-4-13 to 13-2-8 zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=109, 4=109.



April 2, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road  
 Edenton, NC 27932




|                   |             |                      |          |          |   |           |
|-------------------|-------------|----------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>C1 | Truss Type<br>COMMON | Qty<br>5 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635016 |
|-------------------|-------------|----------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:04 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f



Scale = 1:56.3

| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d  | PLATES         | GRIP     |
|---------------|----------------------|-------|----------|----------|----------|--------|------|----------------|----------|
| TCLL 20.0     | Plate Grip DOL       | 1.15  | TC 0.49  | Vert(LL) | -0.10    | 4-7    | >999 | MT20           | 244/190  |
| TCDL 10.0     | Lumber DOL           | 1.15  | BC 0.54  | Vert(CT) | -0.17    | 4-7    | >999 |                |          |
| BCLL 0.0 *    | Rep Stress Incr      | YES   | WB 0.19  | Horz(CT) | 0.01     | 4      | n/a  |                |          |
| BCDL 10.0     | Code IRC2015/TPI2014 |       | Matrix-S | Wind(LL) | 0.06     | 2-7    | >999 |                |          |
|               |                      |       |          |          |          |        |      | Weight: 129 lb | FT = 20% |


**LUMBER-**  
 TOP CHORD 2x6 SP No.1  
 BOT CHORD 2x6 SP No.1  
 WEBS 2x4 SP No.2  
 WEDGE  
 Left: 2x4 SP No.3, Right: 2x4 SP No.3

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 6'-0-0 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.

**REACTIONS.** (size) 4=0-3-8, 2=0-3-8  
 Max Horz 2=-221(LC 10)  
 Max Uplift 4=-48(LC 13), 2=-48(LC 12)  
 Max Grav 4=1044(LC 20), 2=1044(LC 19)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-1118/210, 3-4=-1118/210  
 BOT CHORD 2-7=0/784, 4-7=0/784  
 WEBS 3-7=0/822

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) -1-0-8 to 3-4-4, Interior(1) 3-4-4 to 10-0-0, Exterior(2) 10-0-0 to 14-4-13, Interior(1) 14-4-13 to 21-0-8 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3'-6-0 tall by 2'-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2.



April 2, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road  
 Edenton, NC 27932

|                   |                |                             |          |          |   |           |
|-------------------|----------------|-----------------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>C1-GR | Truss Type<br>COMMON GIRDER | Qty<br>1 | Ply<br>2 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635017 |
|-------------------|----------------|-----------------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:05 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f



Scale = 1:56.3

|                       |  |             |                                  |                |             |
|-----------------------|--|-------------|----------------------------------|----------------|-------------|
| Plate Offsets (X,Y)-- | [2:0-0-0,0-0-9], [6:Edge,0-0-9], [9:0-5-0,0-6-4] |             |                                  |                |             |
| <b>LOADING</b> (psf)  | <b>SPACING-</b> 2-0-0                            | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b>  | <b>GRIP</b> |
| TCLL 20.0             | Plate Grip DOL 1.15                              | TC 0.61     | Vert(LL) -0.07 9-10 >999 360     | MT20           | 244/190     |
| TCDL 10.0             | Lumber DOL 1.15                                  | BC 0.45     | Vert(CT) -0.13 9-10 >999 240     |                |             |
| BCLL 0.0 *            | Rep Stress Incr NO                               | WB 0.85     | Horz(CT) 0.03 6 n/a n/a          |                |             |
| BCDL 10.0             | Code IRC2015/TPI2014                             | Matrix-S    | Wind(LL) 0.05 9-10 >999 240      | Weight: 341 lb | FT = 20%    |

|                             |   |
|-----------------------------|---|
| <b>LUMBER-</b>              | <b>BRACING-</b>   |
| TOP CHORD 2x6 SP No.1       | TOP CHORD Structural wood sheathing directly applied or 5-7-9 oc purlins. |
| BOT CHORD 2x8 SP 2400F 2.0E | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.            |
| WEBS 2x4 SP No.2            |   |

**REACTIONS.** (size) 6=0-3-8, 2=0-3-8  
 Max Horz 2=217(LC 26)  
 Max Uplift 6=-424(LC 9), 2=-437(LC 8)  
 Max Grav 6=6844(LC 2), 2=6838(LC 2)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-8399/550, 3-4=-5693/462, 4-5=-5691/461, 5-6=-8413/547  
 BOT CHORD 2-10=-410/6080, 9-10=-410/6081, 7-9=-340/6084, 6-7=-340/6083  
 WEBS 4-9=-485/6901, 5-9=-2367/286, 5-7=-162/3485, 3-9=-2363/282, 3-10=-164/3461

- NOTES-**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
 Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.  
 Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-7-0 oc.  
 Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
  - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
  - Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); Lumber DOL=1.60 plate grip DOL=1.60
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=424, 2=437.
  - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1360 lb down and 95 lb up at 2-0-12, 1360 lb down and 95 lb up at 4-0-12, 1360 lb down and 95 lb up at 6-0-12, 1360 lb down and 95 lb up at 8-0-12, 1360 lb down and 95 lb up at 10-0-12, 1360 lb down and 95 lb up at 12-0-12, 1360 lb down and 95 lb up at 14-0-12, and 1360 lb down and 95 lb up at 16-0-12, and 1360 lb down and 95 lb up at 18-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

**LOAD CASE(S)** Standard  
 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
 Uniform Loads (plf)  
 Vert: 1-4=-60, 4-6=-60, 2-6=-20



April 2, 2024

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

**ENGINEERING BY**  
**TRENCO**  
 A MiTek Affiliate  
 818 Soundside Road  
 Edenton, NC 27932

|                   |                |                             |          |                 |  |
|-------------------|----------------|-----------------------------|----------|-----------------|--|
| Job<br>J0824-4837 | Truss<br>C1-GR | Truss Type<br>COMMON GIRDER | Qty<br>1 | Ply<br><b>2</b> | Lot 13 Magnolia Hills<br>I64635017<br>Job Reference (optional) |
|-------------------|----------------|-----------------------------|----------|-----------------|--|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:05 2024 Page 2  
ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

**LOAD CASE(S)** Standard

Concentrated Loads (lb)

Vert: 9=-1290(F) 11=-1290(F) 12=-1290(F) 13=-1290(F) 14=-1290(F) 15=-1290(F) 16=-1290(F) 17=-1290(F) 18=-1290(F)


**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacomponents.com](http://www.sbcacomponents.com))




818 Soundside Road  
Edenton, NC 27932

|  |       |            |     |     |                       |  |
|--|-------|------------|-----|-----|-----------------------|--|
| Job  | Truss | Truss Type | Qty | Ply | Lot 13 Magnolia Hills | I64635018  |
| J0824-4837   | C1GE  | GABLE      | 1   | 1   |                       |  |
| Comtech, Inc. Fayetteville, NC - 28314,                                    |       |            |     |     |                       | 8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:05 2024 Page 1 |
| ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f |       |            |     |     |                       | Job Reference (optional)   |



6x6 =

Scale = 1:54.8



| LOADING (psf) | SPACING-             | CSI.     | DEFL.    | in (loc)    | l/defl | L/d | PLATES         | GRIP     |
|---------------|----------------------|----------|----------|-------------|--------|-----|----------------|----------|
| TCLL 20.0     | 2-0-0                | TC 0.20  | Vert(LL) | -0.09 15-16 | >999   | 360 | MT20           | 244/190  |
| TCDL 10.0     | Plate Grip DOL 1.15  | BC 0.40  | Vert(CT) | -0.14 15-16 | >999   | 240 |                |          |
| BCLL 0.0 *    | Lumber DOL 1.15      | WB 0.40  | Horz(CT) | 0.01 12     | n/a    | n/a |                |          |
| BCDL 10.0     | Rep Stress Incr YES  | Matrix-S | Wind(LL) | 0.15 21-22  | >999   | 240 |                |          |
|               | Code IRC2015/TPI2014 |          |          |             |        |     | Weight: 180 lb | FT = 20% |

**LUMBER-**  
 TOP CHORD 2x6 SP No.1  
 BOT CHORD 2x6 SP No.1  
 WEBS 2x4 SP No.2  
 OTHERS 2x4 SP No.2  
 WEDGE  
 Left: 2x4 SP No.3 , Right: 2x4 SP No.3

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 12=0-3-8, 2=0-3-8  
 Max Horz 2=-276(LC 10)  
 Max Uplift 12=-169(LC 13), 2=-169(LC 12)  
 Max Grav 12=860(LC 1), 2=860(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-870/130, 3-4=-749/172, 4-5=-705/231, 5-6=-739/304, 6-7=-776/383, 7-8=-776/383,  
 8-9=-739/304, 9-10=-705/231, 10-11=-749/172, 11-12=-870/129  
 BOT CHORD 2-23=-39/567, 22-23=-39/567, 21-22=-39/567, 20-21=-39/567, 19-20=-39/567,  
 17-19=-39/567, 16-17=-39/567, 15-16=-39/567, 14-15=-39/567, 12-14=-39/567  
 WEBS 7-19=-309/660

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - All plates are 2x4 MT20 unless otherwise indicated.
  - Gable studs spaced at 2-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 12=169, 2=169.




April 2, 2024


|                   |             |                      |          |          |   |           |
|-------------------|-------------|----------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>G1 | Truss Type<br>COMMON | Qty<br>6 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | 164635019 |
|-------------------|-------------|----------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:06 2024 Page 1



Scale = 1:87.6



|                       |   |
|-----------------------|---|
| Plate Offsets (X,Y)-- | [2:0-4-0,0-1-15], [4:0-3-0,Edge], [7:0-3-0,Edge], [10:0-3-0,Edge], [12:0-4-0,0-1-15], [17:0-1-12,0-3-0], [19:0-1-8,0-2-4] |
|-----------------------|---|

| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d  | PLATES         | GRIP     |
|---------------|----------------------|-------|----------|----------|----------|--------|------|----------------|----------|
| TCLL 20.0     | Plate Grip DOL       | 1.15  | TC 0.26  | Vert(LL) | -0.24    | 15-17  | >999 | MT20           | 244/190  |
| TCDL 10.0     | Lumber DOL           | 1.15  | BC 0.44  | Vert(CT) | -0.40    | 15-17  | >739 |                |          |
| BCLL 0.0 *    | Rep Stress Incr      | YES   | WB 0.42  | Horz(CT) | 0.03     | 12     | n/a  |                |          |
| BCDL 10.0     | Code IRC2015/TP12014 |       | Matrix-S | Wind(LL) | 0.16     | 15-17  | >999 |                |          |
|               |                      |       |          |          |          |        |      | Weight: 376 lb | FT = 20% |

| LUMBER-  | BRACING-   |
|--|--|
| TOP CHORD 2x6 SP No.1 *Except*<br>1-4,10-13: 2x4 SP No.1   | TOP CHORD Structural wood sheathing directly applied or 3-11-0 oc purlins.<br>BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing. Except: |
| BOT CHORD 2x8 SP 2400F 2.OE *Except*<br>17-19: 2x6 SP No.1 | 8-5-9 oc bracing: 18-19<br>7-9-4 oc bracing: 17-18.  |
| WEBS 2x4 SP No.2   | WEBS 1 Row at midpt 9-17, 6-19, 5-19, 6-8  |

**REACTIONS.** (size) 2=0-3-8, 12=0-3-8, 18=0-3-8  
 Max Horz 2=156(LC 11)  
 Max Uplift 2=-66(LC 12), 12=-168(LC 13), 18=-120(LC 12)  
 Max Grav 2=1250(LC 1), 12=1365(LC 24), 18=1447(LC 19)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-2175/456, 3-5=-1759/445, 5-6=-1250/413, 6-7=-378/186, 7-8=-350/181,  
 8-9=-1235/382, 9-11=-2082/468, 11-12=-2367/451  
 BOT CHORD 2-22=-304/1880, 21-22=-304/1880, 19-21=-194/1515, 18-19=-52/1043, 17-18=-48/1031,  
 15-17=-245/1812, 14-15=-325/2045, 12-14=-325/2045  
 WEBS 9-17=-1058/260, 9-15=-26/593, 5-19=-875/234, 5-21=-23/446, 3-21=-393/120,  
 11-15=-281/104, 6-8=-846/319

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) -1-2-7 to 3-2-5, Interior(1) 3-2-5 to 23-0-0, Exterior(2) 23-0-0 to 27-4-13, Interior(1) 27-4-13 to 47-2-7 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 12=168, 18=120.



|                   |               |                                    |          |          |   |           |
|-------------------|---------------|------------------------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>G1GE | Truss Type<br>COMMON SUPPORTED GAB | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635020 |
|-------------------|---------------|------------------------------------|----------|----------|---|-----------|


Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:07 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f

|       |        |        |        |
|-------|--------|--------|--------|
| 1-2-8 | 23-0-0 | 46-0-0 | 47-2-8 |
| 1-2-8 | 23-0-0 | 23-0-0 | 1-2-8  |

Scale = 1:81.1



|                       |   |
|-----------------------|---|
| Plate Offsets (X,Y)-- | [6:0-1-9,Edge], [22:0-1-9,Edge], [34:0-4-0,0-4-8], [42:0-4-0,0-4-8] |
|-----------------------|---|

| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d | PLATES         | GRIP     |
|---------------|----------------------|-------|----------|----------|----------|--------|-----|----------------|----------|
| TCLL 20.0     | Plate Grip DOL       | 1.15  | TC 0.07  | Vert(LL) | -0.00    | 27     | n/r | MT20           | 244/190  |
| TCDL 10.0     | Lumber DOL           | 1.15  | BC 0.03  | Vert(CT) | -0.00    | 27     | n/r |                |          |
| BCLL 0.0 *    | Rep Stress Incr      | YES   | WB 0.18  | Horz(CT) | 0.01     | 26     | n/a |                |          |
| BCDL 10.0     | Code IRC2015/TPI2014 |       | Matrix-S |          |          |        |     |                |          |
|               |                      |       |          |          |          |        |     | Weight: 376 lb | FT = 20% |

| LUMBER-               | BRACING-  |
|-----------------------|---|
| TOP CHORD 2x4 SP No.1 | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.   |
| BOT CHORD 2x6 SP No.1 | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  |
| OTHERS 2x4 SP No.2    | WEBS T-Brace: 2x4 SPF No.2 - 14-38, 13-39, 12-40, 11-41, 15-37, 16-36, 17-35  |
|                       | Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c., with 3in minimum end distance. Brace must cover 90% of web length. |

**REACTIONS.** All bearings 46-0-0.  
 (lb) - Max Horz 2=245(LC 16)  
 Max Uplift All uplift 100 lb or less at joint(s) 2, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 37, 36, 35, 34, 33, 32, 31, 30, 29, 28, 26  
 Max Grav All reactions 250 lb or less at joint(s) 2, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 37, 36, 35, 34, 33, 32, 31, 30, 29, 28, 26

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-322/96, 11-12=-106/275, 12-13=-127/337, 13-14=-146/387, 14-15=-146/387, 15-16=-127/337, 16-17=-106/275  
 BOT CHORD 2-48=-82/271, 47-48=-82/271, 46-47=-82/271, 45-46=-82/271, 44-45=-82/271, 43-44=-82/271, 42-43=-82/271, 41-42=-82/271, 40-41=-82/271, 39-40=-82/271, 38-39=-82/271, 37-38=-82/271, 36-37=-82/271, 35-36=-82/271, 34-35=-82/271, 33-34=-82/271, 32-33=-82/271, 31-32=-82/271, 30-31=-82/271, 29-30=-82/271, 28-29=-82/271, 26-28=-82/271

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - 4) All plates are 2x4 MT20 unless otherwise indicated.
  - 5) Gable requires continuous bottom chord bearing.
  - 6) Gable studs spaced at 2-0-0 oc.
  - 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 8) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 37, 36, 35, 34, 33, 32, 31, 30, 29, 28, 26.
  - 10) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.



April 2, 2024

|   |  |
|---|--|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria and DSB-22</b> available from Truss Plate Institute (www.tpinst.org) and <b>BCSI Building Component Safety Information</b> available from the Structural Building Component Association (www.sbcacomponents.com)</p> | <p>ENGINEERING BY<br/> <b>TRENCO</b><br/>         A MiTek Affiliate</p> <p>818 Soundside Road<br/>         Edenton, NC 27932</p> |
|---|--|

|                   |             |                          |          |          |   |           |
|-------------------|-------------|--------------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>J1 | Truss Type<br>MONO TRUSS | Qty<br>4 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635021 |
|-------------------|-------------|--------------------------|----------|----------|---|-----------|


Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:08 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:14.8



| Plate Offsets (X,Y)-- [2:0-2-15,Edge] |                      | CSI.  |          | DEFL.    |       | PLATES |      | GRIP          |          |
|---------------------------------------|----------------------|-------|----------|----------|-------|--------|------|---------------|----------|
| LOADING (psf)                         | SPACING-             | 2-0-0 | TC       | in       | (loc) | l/defl | L/d  | MT20          | 244/190  |
| TCLL 20.0                             | Plate Grip DOL       | 1.15  | 0.41     | Vert(LL) | -0.01 | 2-4    | >999 |               |          |
| TCDL 10.0                             | Lumber DOL           | 1.15  | 0.12     | Vert(CT) | -0.03 | 2-4    | >999 |               |          |
| BCLL 0.0 *                            | Rep Stress Incr      | YES   | 0.00     | Horz(CT) | 0.00  | n/a    | n/a  |               |          |
| BCDL 10.0                             | Code IRC2015/TPI2014 |       | Matrix-P | Wind(LL) | 0.03  | 2-4    | >999 | 240           |          |
|                                       |                      |       |          |          |       |        |      | Weight: 29 lb | FT = 20% |

| LUMBER-   |             | BRACING-  |   |
|-----------|-------------|-----------|---|
| TOP CHORD | 2x4 SP No.1 | TOP CHORD | Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD | 2x6 SP No.1 | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS      | 2x6 SP No.1 |           |   |


**REACTIONS.** (size) 2=0-3-8, 4=0-1-8  
 Max Horz 2=83(LC 8)  
 Max Uplift 2=-132(LC 8), 4=-90(LC 8)  
 Max Grav 2=316(LC 1), 4=215(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) -1-2-8 to 3-2-5, Interior(1) 3-2-5 to 5-9-4 zone; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - 5) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 2=132.



April 2, 2024

|   |  |
|---|--|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria and DSB-22</b> available from Truss Plate Institute (www.tpinst.org) and <b>BCSI Building Component Safety Information</b> available from the Structural Building Component Association (www.sbcacomponents.com)</p> | <p>ENGINEERING BY</p>  <p>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|---|--|

|            |       |            |     |     |                          |           |
|------------|-------|------------|-----|-----|--------------------------|-----------|
| Job        | Truss | Truss Type | Qty | Ply | Lot 13 Magnolia Hills    | I64635022 |
| J0824-4837 | J2    | MONOPIITCH | 6   | 1   |                          |           |
|            |       |            |     |     | Job Reference (optional) |           |


Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:08 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCdoi7J4zJC?f



Scale = 1:12.5



|                       |                 |
|-----------------------|-----------------|
| Plate Offsets (X,Y)-- | [2:0-2-15,Edge] |
|-----------------------|-----------------|


| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d  | PLATES        | GRIP     |
|---------------|----------------------|-------|----------|----------|----------|--------|------|---------------|----------|
| TCLL 20.0     | Plate Grip DOL       | 1.15  | TC 0.26  | Vert(LL) | -0.01    | 2-4    | >999 | MT20          | 244/190  |
| TCDL 10.0     | Lumber DOL           | 1.15  | BC 0.08  | Vert(CT) | -0.01    | 2-4    | >999 |               |          |
| BCLL 0.0 *    | Rep Stress Incr      | YES   | WB 0.00  | Horz(CT) | 0.00     | n/a    | n/a  |               |          |
| BCDL 10.0     | Code IRC2015/TPI2014 |       | Matrix-P | Wind(LL) | 0.01     | 2-4    | >999 | Weight: 24 lb | FT = 20% |

| LUMBER-               | BRACING-  |
|-----------------------|---|
| TOP CHORD 2x4 SP No.1 | TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x6 SP No.1 | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x6 SP No.1      |   |

**REACTIONS.** (size) 2=0-3-0, 4=0-1-8  
 Max Horz 2=72(LC 8)  
 Max Uplift 2=-119(LC 8), 4=-72(LC 8)  
 Max Grav 2=277(LC 1), 4=174(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) -1-2-8 to 3-2-5, Interior(1) 3-2-5 to 4-9-4 zone; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - 5) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 2=119.





|                   |               |                                   |          |          |   |           |
|-------------------|---------------|-----------------------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>J2GE | Truss Type<br>MONOPITCH SUPPORTED | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635023 |
|-------------------|---------------|-----------------------------------|----------|----------|---|-----------|


Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:09 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKwrcDoi7J4zJC?f



Scale = 1:12.7



| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d | PLATES        | GRIP     |
|---------------|----------------------|-------|----------|----------|----------|--------|-----|---------------|----------|
| TCLL 20.0     | Plate Grip DOL       | 1.15  | TC 0.07  | Vert(LL) | 0.00     | 1      | n/r | MT20          | 244/190  |
| TCDL 10.0     | Lumber DOL           | 1.15  | BC 0.02  | Vert(CT) | 0.00     | 1      | n/r |               |          |
| BCLL 0.0 *    | Rep Stress Incr      | YES   | WB 0.03  | Horz(CT) | -0.00    | 5      | n/a |               |          |
| BCDL 10.0     | Code IRC2015/TPI2014 |       | Matrix-P |          |          |        |     | Weight: 24 lb | FT = 20% |

**LUMBER-**  
TOP CHORD 2x4 SP No.1  
BOT CHORD 2x6 SP No.1  
WEBS 2x4 SP No.2  
OTHERS 2x4 SP No.2


**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** All bearings 5-0-0.  
(lb) - Max Horz 2=104(LC 8)  
Max Uplift All uplift 100 lb or less at joint(s) 5, 6, 2, 7  
Max Grav All reactions 250 lb or less at joint(s) 5, 6, 2, 7

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) Gable requires continuous bottom chord bearing.
- 4) Gable studs spaced at 2-0-0 oc.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 6, 2, 7.
- 8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 2.



April 2, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road  
Edenton, NC 27932

|                   |             |                        |          |          |   |           |
|-------------------|-------------|------------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>J3 | Truss Type<br>MONOPICH | Qty<br>9 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635024 |
|-------------------|-------------|------------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:09 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:10.1

|                       |                       |             |                                  |               |             |
|-----------------------|-----------------------|-------------|----------------------------------|---------------|-------------|
| Plate Offsets (X,Y)-- | [2:0-2-15,Edge]       |             |                                  |               |             |
| <b>LOADING</b> (psf)  | <b>SPACING-</b> 2-0-0 | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b> | <b>GRIP</b> |
| TCLL 20.0             | Plate Grip DOL 1.15   | TC 0.09     | Vert(LL) -0.00 2-4 >999 360      | MT20          | 244/190     |
| TCDL 10.0             | Lumber DOL 1.15       | BC 0.03     | Vert(CT) -0.00 2-4 >999 240      |               |             |
| BCLL 0.0 *            | Rep Stress Incr YES   | WB 0.01     | Horz(CT) 0.00 n/a n/a            |               |             |
| BCDL 10.0             | Code IRC2015/TPI2014  | Matrix-P    | Wind(LL) 0.00 2 **** 240         | Weight: 17 lb | FT = 20%    |

|                       |   |
|-----------------------|---|
| <b>LUMBER-</b>        | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.1 | TOP CHORD Structural wood sheathing directly applied or 3-6-0 oc purlins. |
| BOT CHORD 2x6 SP No.1 | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.            |
| WEBS 2x6 SP No.1      |   |

**REACTIONS.** (size) 2=0-3-8, 4=0-1-8  
 Max Horz 2=56(LC 8)  
 Max Uplift 2=-69(LC 8), 4=-14(LC 12)  
 Max Grav 2=224(LC 1), 4=107(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - 5) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4.




|                   |               |                                   |          |          |   |           |
|-------------------|---------------|-----------------------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>J3GE | Truss Type<br>MONOPITCH SUPPORTED | Qty<br>2 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635025 |
|-------------------|---------------|-----------------------------------|----------|----------|---|-----------|


Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:09 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:10.3



| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d | PLATES        | GRIP     |
|---------------|----------------------|-------|----------|----------|----------|--------|-----|---------------|----------|
| TCLL 20.0     | Plate Grip DOL       | 1.15  | TC 0.07  | Vert(LL) | 0.00     | 4      | n/r | MT20          | 244/190  |
| TCDL 10.0     | Lumber DOL           | 1.15  | BC 0.02  | Vert(CT) | 0.00     | 4      | n/r |               |          |
| BCLL 0.0 *    | Rep Stress Incr      | YES   | WB 0.02  | Horz(CT) | 0.00     |        | n/a |               |          |
| BCDL 10.0     | Code IRC2015/TPI2014 |       | Matrix-P |          |          |        |     | Weight: 15 lb | FT = 20% |

**LUMBER-**  
TOP CHORD 2x4 SP No.1  
BOT CHORD 2x4 SP No.1  
WEBS 2x4 SP No.2


**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 3-6-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 7=3-6-0, 2=3-6-0, 8=3-6-0  
Max Horz 2=79(LC 8)  
Max Uplift 7=-26(LC 8), 2=-91(LC 8), 8=-38(LC 12)  
Max Grav 7=52(LC 1), 2=164(LC 1), 8=125(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) Gable requires continuous bottom chord bearing.
- 4) Gable studs spaced at 2-0-0 oc.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7, 2, 8.



April 2, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road  
Edenton, NC 27932

|                   |             |                      |          |          |   |           |
|-------------------|-------------|----------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>V1 | Truss Type<br>VALLEY | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635026 |
|-------------------|-------------|----------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:10 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f



Scale = 1:46.7


|                       |                       |             |                                  |               |             |
|-----------------------|-----------------------|-------------|----------------------------------|---------------|-------------|
| Plate Offsets (X,Y)-- | [4:0-0-0,0-0-0]       |             |                                  |               |             |
| <b>LOADING</b> (psf)  | <b>SPACING-</b> 2-0-0 | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b> | <b>GRIP</b> |
| TCLL 20.0             | Plate Grip DOL 1.15   | TC 0.23     | Vert(LL) n/a - n/a 999           | MT20          | 244/190     |
| TCDL 10.0             | Lumber DOL 1.15       | BC 0.18     | Vert(CT) n/a - n/a 999           |               |             |
| BCLL 0.0 *            | Rep Stress Incr YES   | WB 0.13     | Horz(CT) 0.00 5 n/a n/a          |               |             |
| BCDL 10.0             | Code IRC2015/TPI2014  | Matrix-S    |                                  | Weight: 84 lb | FT = 20%    |

|                       |   |
|-----------------------|---|
| <b>LUMBER-</b>        | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.1 | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins. |
| BOT CHORD 2x4 SP No.1 | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.            |
| OTHERS 2x4 SP No.2    |   |

**REACTIONS.** All bearings 18-5-5.  
 (lb) - Max Horz 1=177(LC 11)  
 Max Uplift All uplift 100 lb or less at joint(s) 1 except 9=-172(LC 12), 6=-172(LC 13)  
 Max Grav All reactions 250 lb or less at joint(s) 1, 5 except 8=411(LC 22), 9=560(LC 19), 6=560(LC 20)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 WEBS 2-9=-428/293, 4-6=-428/292

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) 0-4-13 to 4-9-10, Interior(1) 4-9-10 to 9-3-1, Exterior(2) 9-3-1 to 13-7-14, Interior(1) 13-7-14 to 18-1-6 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Gable requires continuous bottom chord bearing.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1 except (jt=lb) 9=172, 6=172.



April 2, 2024

|   |   |
|---|---|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria and DSB-22</b> available from Truss Plate Institute (www.tpinst.org) and <b>BCSI Building Component Safety Information</b> available from the Structural Building Component Association (www.sbcacomponents.com)</p> | <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|---|---|

|                   |             |                      |          |          |   |           |
|-------------------|-------------|----------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>V2 | Truss Type<br>VALLEY | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635027 |
|-------------------|-------------|----------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:10 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



4x4 =

Scale = 1:41.4




Plate Offsets (X,Y)-- [4:0-0-0,0-0-0]

| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d | PLATES        | GRIP     |
|---------------|----------------------|-------|----------|----------|----------|--------|-----|---------------|----------|
| TCLL 20.0     | Plate Grip DOL       | 1.15  | TC 0.15  | Vert(LL) | n/a      | -      | n/a | MT20          | 244/190  |
| TCDL 10.0     | Lumber DOL           | 1.15  | BC 0.17  | Vert(CT) | n/a      | -      | n/a |               |          |
| BCLL 0.0 *    | Rep Stress Incr      | YES   | WB 0.10  | Horz(CT) | 0.00     | 5      | n/a |               |          |
| BCDL 10.0     | Code IRC2015/TPI2014 |       | Matrix-S |          |          |        |     | Weight: 69 lb | FT = 20% |

**LUMBER-**  
TOP CHORD 2x4 SP No.1  
BOT CHORD 2x4 SP No.1  
OTHERS 2x4 SP No.2


**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** All bearings 15-7-11.  
(lb) - Max Horz 1=-149(LC 8)  
Max Uplift All uplift 100 lb or less at joint(s) 1 except 8=-143(LC 12), 6=-142(LC 13)  
Max Grav All reactions 250 lb or less at joint(s) 1, 5 except 7=411(LC 19), 8=429(LC 19), 6=429(LC 20)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
WEBS 2-8=-356/254, 4-6=-356/254

**NOTES-**

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) 0-4-13 to 4-9-10, Interior(1) 4-9-10 to 7-10-5, Exterior(2) 7-10-5 to 12-3-1, Interior(1) 12-3-1 to 15-3-12 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1 except (jt=lb) 8=143, 6=142.



April 2, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road  
Edenton, NC 27932

|                   |             |                      |          |          |   |           |
|-------------------|-------------|----------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>V3 | Truss Type<br>VALLEY | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635028 |
|-------------------|-------------|----------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:11 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:34.4


|                       |                       |             |                                  |               |             |
|-----------------------|-----------------------|-------------|----------------------------------|---------------|-------------|
| Plate Offsets (X,Y)-- | [4:0-0-0,0-0-0]       |             |                                  |               |             |
| <b>LOADING</b> (psf)  | <b>SPACING-</b> 2-0-0 | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b> | <b>GRIP</b> |
| TCLL 20.0             | Plate Grip DOL 1.15   | TC 0.13     | Vert(LL) n/a - n/a 999           | MT20          | 244/190     |
| TCDL 10.0             | Lumber DOL 1.15       | BC 0.09     | Vert(CT) n/a - n/a 999           |               |             |
| BCLL 0.0 *            | Rep Stress Incr YES   | WB 0.07     | Horz(CT) 0.00 5 n/a n/a          |               |             |
| BCDL 10.0             | Code IRC2015/TPI2014  | Matrix-S    |                                  | Weight: 54 lb | FT = 20%    |

|                       |  |
|-----------------------|--|
| <b>LUMBER-</b>        | <b>BRACING-</b>  |
| TOP CHORD 2x4 SP No.1 | TOP CHORD Structural wood sheathing directly applied or 6'-0-0 oc purlins. |
| BOT CHORD 2x4 SP No.1 | BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.            |
| OTHERS 2x4 SP No.2    |  |

**REACTIONS.** All bearings 12-10-1.  
 (lb) - Max Horz 1=-121(LC 8)  
 Max Uplift All uplift 100 lb or less at joint(s) 1, 5 except 8=-124(LC 12), 6=-124(LC 13)  
 Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7 except 8=330(LC 19), 6=330(LC 20)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 WEBS 2-8=-314/239, 4-6=-314/239

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TC DL=6.0psf; BC DL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) 0-4-13 to 4-9-10, Interior(1) 4-9-10 to 6-5-8, Exterior(2) 6-5-8 to 10-10-5, Interior(1) 10-10-5 to 12-6-3 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 8=124, 6=124.
  - Non Standard bearing condition. Review required.




|                   |             |                      |          |          |   |           |
|-------------------|-------------|----------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>V4 | Truss Type<br>VALLEY | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635029 |
|-------------------|-------------|----------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:11 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:27.1

| LOADING (psf) | SPACING-             | CSI.     | DEFL.    | in (loc) | l/defl | L/d | PLATES        | GRIP     |
|---------------|----------------------|----------|----------|----------|--------|-----|---------------|----------|
| TCLL 20.0     | 2-0-0                | TC 0.23  | Vert(LL) | n/a      | -      | n/a | MT20          | 244/190  |
| TCDL 10.0     | Plate Grip DOL 1.15  | BC 0.16  | Vert(CT) | n/a      | -      | n/a |               |          |
| BCLL 0.0 *    | Lumber DOL 1.15      | WB 0.06  | Horz(CT) | 0.00     | 3      | n/a |               |          |
| BCDL 10.0     | Rep Stress Incr YES  | Matrix-S |          |          |        |     | Weight: 38 lb | FT = 20% |
|               | Code IRC2015/TPI2014 |          |          |          |        |     |               |          |

**LUMBER-**  
 TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 OTHERS 2x4 SP No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 1=10-0-8, 3=10-0-8, 4=10-0-8  
 Max Horz 1=93(LC 11)  
 Max Uplift 1=22(LC 13), 3=30(LC 13)  
 Max Grav 1=199(LC 1), 3=199(LC 1), 4=347(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TC DL=6.0psf; BC DL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Gable requires continuous bottom chord bearing.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.



April 2, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road  
 Edenton, NC 27932

|                   |             |                      |          |          |   |           |
|-------------------|-------------|----------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>V5 | Truss Type<br>VALLEY | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635030 |
|-------------------|-------------|----------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,


8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:12 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



4x4 =

Scale = 1:21.0



| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d | PLATES        | GRIP     |
|---------------|----------------------|-------|----------|----------|----------|--------|-----|---------------|----------|
| TCLL 20.0     | Plate Grip DOL       | 1.15  | TC 0.15  | Vert(LL) | n/a      | -      | n/a | MT20          | 244/190  |
| BCDL 10.0     | Lumber DOL           | 1.15  | BC 0.08  | Vert(CT) | n/a      | -      | n/a |               |          |
| BCLL 0.0 *    | Rep Stress Incr      | YES   | WB 0.02  | Horz(CT) | 0.00     | 3      | n/a |               |          |
| BCDL 10.0     | Code IRC2015/TPI2014 |       | Matrix-P |          |          |        |     | Weight: 27 lb | FT = 20% |

**LUMBER-**  
 TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 OTHERS 2x4 SP No.2


**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 1=7-2-14, 3=7-2-14, 4=7-2-14  
 Max Horz 1=-65(LC 8)  
 Max Uplift 1=-23(LC 13), 3=-29(LC 13)  
 Max Grav 1=151(LC 1), 3=151(LC 1), 4=220(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TC DL=6.0psf; BC DL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- 6) Non Standard bearing condition. Review required.



April 2, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road  
 Edenton, NC 27932




|                   |             |                      |          |          |   |           |
|-------------------|-------------|----------------------|----------|----------|---|-----------|
| Job<br>J0824-4837 | Truss<br>V6 | Truss Type<br>VALLEY | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635031 |
|-------------------|-------------|----------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:12 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f



Scale = 1:12.2

| LOADING (psf) | SPACING-             | CSI.     | DEFL.    | in (loc) | l/defl | L/d | PLATES        | GRIP     |
|---------------|----------------------|----------|----------|----------|--------|-----|---------------|----------|
| TCLL 20.0     | 2-0-0                | TC 0.05  | Vert(LL) | n/a      | -      | n/a | MT20          | 244/190  |
| TCDL 10.0     | Plate Grip DOL 1.15  | BC 0.03  | Vert(CT) | n/a      | -      | n/a |               |          |
| BCLL 0.0 *    | Lumber DOL 1.15      | WB 0.01  | Horz(CT) | 0.00     | 3      | n/a |               |          |
| BCDL 10.0     | Rep Stress Incr YES  | Matrix-P |          |          |        |     | Weight: 16 lb | FT = 20% |
|               | Code IRC2015/TPI2014 |          |          |          |        |     |               |          |

**LUMBER-**  
 TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 OTHERS 2x4 SP No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 4-6-3 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 1=4-5-5, 3=4-5-5, 4=4-5-5  
 Max Horz 1=-37(LC 8)  
 Max Uplift 1=-13(LC 13), 3=-16(LC 13)  
 Max Grav 1=86(LC 1), 3=86(LC 1), 4=125(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Gable requires continuous bottom chord bearing.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.



April 2, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY  
**TRENCO**  
 A MiTek Affiliate


818 Soundside Road  
 Edenton, NC 27932

# Symbols


## PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0-  $\frac{1}{16}$ \" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

\* Plate location details available in MITek software or upon request.

## PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

## LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

## BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.


## Industry Standards:

ANSI/TFP 1: National Design Specification for Metal Plate Connected Wood Truss Construction.  
DSB-22: Design Standard for Bracing.  
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

# Numbering System



1 TOP CHORDS  
2 JOINT ID  
3 typ.



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

# Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282  
ESR-4722, ESL-1388

# Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TFP 1 section 6.3. These truss designs rely on Lumber values established by others.

© 2023 MITek® All Rights Reserved

# General Safety Notes

## Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor 1 bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TFP 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TFP 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TFP 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.


**MITek**

ENGINEERING BY  
**TRENGO**  
A MITek Affiliate

MITek Engineering Reference Sheet: MIL-7473 rev. 1/2/2023

**BM1 Kerto-S LVL 1.750" X 16.000" 2-Ply - PASSED**

Level: Level



**Member Information**

|                     |               |                |             |
|---------------------|---------------|----------------|-------------|
| Type:               | Girder        | Application:   | Floor       |
| Plies:              | 2             | Design Method: | ASD         |
| Moisture Condition: | Dry           | Building Code: | IBC 2012    |
| Deflection LL:      | 480           | Load Sharing:  | No          |
| Deflection TL:      | 240           | Deck:          | Not Checked |
| Importance:         | Normal - II   |                |             |
| Temperature:        | Temp <= 100°F |                |             |

**Reactions UNPATTERNED lb (Uplift)**

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1   | Vertical  | 3333 | 1217 | 0    | 0    | 0     |
| 2   | Vertical  | 3333 | 1217 | 0    | 0    | 0     |

**Bearings**

| Bearing | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb. |
|---------|--------|------|------|--------------|-------|----------|-----------|
| 1 - SPF | 3.500" | Vert | 87%  | 1217 / 3333  | 4551  | L        | D+L       |
| 2 - SPF | 3.500" | Vert | 87%  | 1217 / 3333  | 4551  | L        | D+L       |

**Analysis Results**

| Analysis     | Actual        | Location   | Allowed       | Capacity     | Comb. | Case |
|--------------|---------------|------------|---------------|--------------|-------|------|
| Moment       | 17931 ft-lb   | 8'3 3/4"   | 34565 ft-lb   | 0.519 (52%)  | D+L   | L    |
| Unbraced     | 17931 ft-lb   | 8'3 3/4"   | 17951 ft-lb   | 0.999 (100%) | D+L   | L    |
| Shear        | 4391 lb       | 15'        | 11947 lb      | 0.368 (37%)  | D+L   | L    |
| LL Defl inch | 0.286 (L/678) | 8'3 13/16" | 0.405 (L/480) | 0.707 (71%)  | L     | L    |
| TL Defl inch | 0.391 (L/497) | 8'3 13/16" | 0.809 (L/240) | 0.483 (48%)  | D+L   | L    |

**Design Notes**

- Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- Fasten all plies using 4 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- Refer to last page of calculations for fasteners required for specified loads.
- Girders are designed to be supported on the bottom edge only.
- Top must be laterally braced at a maximum of 6'5 3/4" o.c.
- Bottom must be laterally braced at end bearings.
- Lateral slenderness ratio based on single ply width.

| ID | Load Type   | Location | Trib Width | Side      | Dead 0.9 | Live 1  | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|-------------|----------|------------|-----------|----------|---------|-----------|----------|-------------|----------|
| 1  | Uniform     |          |            | Near Face | 134 PLF  | 401 PLF | 0 PLF     | 0 PLF    | 0 PLF       | F4       |
|    | Self Weight |          |            |           | 12 PLF   |         |           |          |             |          |

**Notes**

Calculated Structural Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

- Dry service conditions, unless noted otherwise
- LVL not to be treated with fire retardant or corrosive

chemicals

**Handling & Installation**

- LVL beams must not be cut or drilled
- Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
- Damaged Beams must not be used
- Design assumes top edge is laterally restrained
- Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026

**Manufacturer Info**


Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
[www.metsawood.com/us](http://www.metsawood.com/us)

Comtech, Inc.  
 1001 S Reilly Rd., NC  
 28314  
 (910) 864-8787



**BM1 Kerto-S LVL 1.750" X 16.000" 2-Ply - PASSED**

Level: Level



**Multi-Ply Analysis**

Fasten all plies using 4 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

|                          |           |
|--------------------------|-----------|
| Capacity                 | 81.7 %    |
| Load                     | 267.5 PLF |
| Yield Limit per Foot     | 327.4 PLF |
| Yield Limit per Fastener | 81.9 lb.  |
| C <sub>m</sub>           | 1         |
| Yield Mode               | IV        |
| Edge Distance            | 1 1/2"    |
| Min. End Distance        | 3"        |
| Load Combination         | D+L       |
| Duration Factor          | 1.00      |

**Notes**

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

**Handling & Installation**

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026

**Manufacturer Info**


Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
[www.metsawood.com/us](http://www.metsawood.com/us)

Comtech, Inc.  
 1001 S Reilly Rd., NC  
 28314  
 (910) 864-8787



**BM2 Kerto-S LVL 1.750" X 16.000" 2-Ply - PASSED**

Level: Level



**Member Information**

|                     |               |                |             |
|---------------------|---------------|----------------|-------------|
| Type:               | Girder        | Application:   | Floor       |
| Plies:              | 2             | Design Method: | ASD         |
| Moisture Condition: | Dry           | Building Code: | IBC 2012    |
| Deflection LL:      | 480           | Load Sharing:  | No          |
| Deflection TL:      | 240           | Deck:          | Not Checked |
| Importance:         | Normal - II   |                |             |
| Temperature:        | Temp <= 100°F |                |             |

**Reactions UNPATTERNED lb (Uplift)**

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1   | Vertical  | 400  | 2409 | 135  | 0    | 0     |
| 2   | Vertical  | 400  | 2409 | 135  | 0    | 0     |

**Bearings**

| Bearing | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb.   |
|---------|--------|------|------|--------------|-------|----------|-------------|
| 1 - SPF | 3.500" | Vert | 54%  | 2409 / 401   | 2811  | L        | D+0.75(L+S) |
| 2 - SPF | 3.500" | Vert | 54%  | 2409 / 401   | 2811  | L        | D+0.75(L+S) |

**Analysis Results**

| Analysis     | Actual         | Location  | Allowed       | Capacity     | Comb.       | Case |
|--------------|----------------|-----------|---------------|--------------|-------------|------|
| Moment       | 13439 ft-lb    | 10'       | 34565 ft-lb   | 0.389 (39%)  | D+L         | L    |
| Unbraced     | 13439 ft-lb    | 10'       | 13492 ft-lb   | 0.996 (100%) | D+L         | L    |
| Shear        | 2461 lb        | 18'4 1/2" | 11947 lb      | 0.206 (21%)  | D+L         | L    |
| LL Defl inch | 0.059 (L/3960) | 10' 1/16" | 0.489 (L/480) | 0.121 (12%)  | 0.75(L+S)   | L    |
| TL Defl inch | 0.415 (L/565)  | 10' 1/16" | 0.978 (L/240) | 0.425 (42%)  | D+0.75(L+S) | L    |

**Design Notes**

- Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- Refer to last page of calculations for fasteners required for specified loads.
- Girders are designed to be supported on the bottom edge only.
- Top loads must be supported equally by all plies.
- Top must be laterally braced at a maximum of 8'9 7/16" o.c.
- Bottom must be laterally braced at end bearings.
- Lateral slenderness ratio based on single ply width.

| ID | Load Type   | Location        | Trib Width | Side      | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments         |
|----|-------------|-----------------|------------|-----------|----------|--------|-----------|----------|-------------|------------------|
| 1  | Uniform     |                 |            | Top       | 200 PLF  | 0 PLF  | 0 PLF     | 0 PLF    | 0 PLF       | Wall Above, C1GE |
| 2  | Tie-In      | 0-0-0 to 20-0-0 | 1-0-0      | Far Face  | 15 PSF   | 40 PSF | 0 PSF     | 0 PSF    | 0 PSF       | Floor Load       |
| 3  | Tie-In      | 0-0-0 to 20-0-0 | 0-6-0      | Near Face | 27 PSF   | 0 PSF  | 27 PSF    | 0 PSF    | 0 PSF       | J3               |
|    | Self Weight |                 |            |           | 12 PLF   |        |           |          |             |                  |

**Notes**

Calculated Structural Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

- Dry service conditions, unless noted otherwise
- LVL not to be treated with fire retardant or corrosive chemicals

**Handling & Installation**

- LVL beams must not be cut or drilled
- Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
- Damaged Beams must not be used
- Design assumes top edge is laterally restrained
- Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026

**Manufacturer Info**


Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
[www.metsawood.com/us](http://www.metsawood.com/us)

Comtech, Inc.  
 1001 S Reilly Rd., NC  
 28314  
 (910) 864-8787



**BM2 Kerto-S LVL 1.750" X 16.000" 2-Ply - PASSED**

Level: Level



**Multi-Ply Analysis**

Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

|                          |           |
|--------------------------|-----------|
| Capacity                 | 11.2 %    |
| Load                     | 27.5 PLF  |
| Yield Limit per Foot     | 245.6 PLF |
| Yield Limit per Fastener | 81.9 lb.  |
| C <sub>m</sub>           | 1         |
| Yield Mode               | IV        |
| Edge Distance            | 1 1/2"    |
| Min. End Distance        | 3"        |
| Load Combination         | D+L       |
| Duration Factor          | 1.00      |

**Notes**

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

**Handling & Installation**

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026

**Manufacturer Info**


Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
[www.metsawood.com/us](http://www.metsawood.com/us)

Comtech, Inc.  
 1001 S Reilly Rd., NC  
 28314  
 (910) 864-8787



**BM3 S-P-F #2 2.000" X 10.000" 2-Ply - PASSED**

Level: Level



**Member Information**

|                     |               |                |             |
|---------------------|---------------|----------------|-------------|
| Type:               | Girder        | Application:   | Floor       |
| Plies:              | 2             | Design Method: | ASD         |
| Moisture Condition: | Dry           | Building Code: | IBC 2012    |
| Deflection LL:      | 480           | Load Sharing:  | No          |
| Deflection TL:      | 360           | Deck:          | Not Checked |
| Importance:         | Normal - II   | Ceiling:       | Gypsum 1/2" |
| Temperature:        | Temp <= 100°F |                |             |

**Reactions UNPATTERNED Ib (Uplift)**

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1   | Vertical  | 0    | 607  | 607  | 0    | 0     |
| 2   | Vertical  | 0    | 607  | 607  | 0    | 0     |

**Bearings**

| Bearing           | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb. |
|-------------------|--------|------|------|--------------|-------|----------|-----------|
| 1 - SPF End Grain | 3.500" | Vert | 27%  | 607 / 607    | 1214  | L        | D+S       |
| 2 - SPF End Grain | 3.500" | Vert | 27%  | 607 / 607    | 1214  | L        | D+S       |

**Analysis Results**

| Analysis     | Actual         | Location | Allowed       | Capacity    | Comb. | Case |
|--------------|----------------|----------|---------------|-------------|-------|------|
| Moment       | 2852 ft-lb     | 5'1 3/4" | 3946 ft-lb    | 0.723 (72%) | D+S   | L    |
| Unbraced     | 2852 ft-lb     | 5'1 3/4" | 2937 ft-lb    | 0.971 (97%) | D+S   | L    |
| Shear        | 964 lb         | 1' 3/4"  | 2872 lb       | 0.336 (34%) | D+S   | L    |
| LL Defl inch | 0.090 (L/1317) | 5'1 3/4" | 0.246 (L/480) | 0.365 (36%) | S     | L    |
| TL Defl inch | 0.179 (L/658)  | 5'1 3/4" | 0.328 (L/360) | 0.547 (55%) | D+S   | L    |

**Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|-----------|----------|------------|------|----------|--------|-----------|----------|-------------|----------|
| 1  | Uniform   |          |            | Top  | 118 PLF  | 0 PLF  | 118 PLF   | 0 PLF    | 0 PLF       | B2       |

**Manufacturer Info**


Comtech, Inc.  
 1001 S Reilly Rd., NC  
 28314  
 (910) 864-8787



This design is valid until 6/28/2026

**BM3 S-P-F #2 2.000" X 10.000" 2-Ply - PASSED**

Level: Level



**Multi-Ply Analysis**

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

|                          |           |
|--------------------------|-----------|
| Capacity                 | 0.0 %     |
| Load                     | 0.0 PLF   |
| Yield Limit per Foot     | 157.4 PLF |
| Yield Limit per Fastener | 78.7 lb.  |
| C <sub>m</sub>           | 1         |
| Yield Mode               | IV        |
| Edge Distance            | 1 1/2"    |
| Min. End Distance        | 3"        |
| Load Combination         |           |
| Duration Factor          | 1.00      |



|                          |   |
|--------------------------|---|
| <b>Manufacturer Info</b> | Comtech, Inc.<br>1001 S Reilly Rd., NC<br>28314<br>(910) 864-8787 |
|                          |   |

This design is valid until 6/28/2026



**BM4 Kerto-S LVL 1.750" X 9.250" 2-Ply - PASSED**

Level: Level



**Member Information**

|                     |               |                |             |
|---------------------|---------------|----------------|-------------|
| Type:               | Girder        | Application:   | Floor       |
| Plies:              | 2             | Design Method: | ASD         |
| Moisture Condition: | Dry           | Building Code: | IBC 2012    |
| Deflection LL:      | 480           | Load Sharing:  | No          |
| Deflection TL:      | 360           | Deck:          | Not Checked |
| Importance:         | Normal - II   |                |             |
| Temperature:        | Temp <= 100°F |                |             |

**Reactions UNPATTERNED lb (Uplift)**

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1   | Vertical  | 2149 | 1903 | 0    | 0    | 0     |
| 2   | Vertical  | 2149 | 1903 | 0    | 0    | 0     |

**Bearings**

| Bearing           | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb. |
|-------------------|--------|------|------|--------------|-------|----------|-----------|
| 1 - SPF End Grain | 3.500" | Vert | 39%  | 1903 / 2149  | 4053  | L        | D+L       |
| 2 - SPF End Grain | 3.500" | Vert | 39%  | 1903 / 2149  | 4053  | L        | D+L       |

**Analysis Results**

| Analysis     | Actual         | Location | Allowed       | Capacity    | Comb. | Case |
|--------------|----------------|----------|---------------|-------------|-------|------|
| Moment       | 5774 ft-lb     | 3'3 1/2" | 12542 ft-lb   | 0.460 (46%) | D+L   | L    |
| Unbraced     | 5774 ft-lb     | 3'3 1/2" | 9934 ft-lb    | 0.581 (58%) | D+L   | L    |
| Shear        | 2750 lb        | 1'3/4"   | 6907 lb       | 0.398 (40%) | D+L   | L    |
| LL Defl inch | 0.056 (L/1320) | 3'3 1/2" | 0.153 (L/480) | 0.364 (36%) | L     | L    |
| TL Defl inch | 0.105 (L/700)  | 3'3 1/2" | 0.204 (L/360) | 0.514 (51%) | D+L   | L    |

**Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

| ID | Load Type   | Location | Trib Width | Side | Dead 0.9 | Live 1  | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments   |
|----|-------------|----------|------------|------|----------|---------|-----------|----------|-------------|------------|
| 1  | Uniform     |          |            | Top  | 102 PLF  | 304 PLF | 0 PLF     | 0 PLF    | 0 PLF       | F2         |
| 2  | Uniform     |          |            | Top  | 349 PLF  | 349 PLF | 0 PLF     | 0 PLF    | 0 PLF       | A1         |
| 3  | Uniform     |          |            | Top  | 120 PLF  | 0 PLF   | 0 PLF     | 0 PLF    | 0 PLF       | Wall Above |
|    | Self Weight |          |            |      | 7 PLF    |         |           |          |             |            |

**Notes**

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive

chemicals

**Handling & Installation**

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026

**Manufacturer Info**


Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
[www.metsawood.com/us](http://www.metsawood.com/us)

Comtech, Inc.  
 1001 S Reilly Rd., NC  
 28314  
 (910) 864-8787



**BM4 Kerto-S LVL 1.750" X 9.250" 2-Ply - PASSED**

Level: Level



**Multi-Ply Analysis**

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

|                          |           |
|--------------------------|-----------|
| Capacity                 | 0.0 %     |
| Load                     | 0.0 PLF   |
| Yield Limit per Foot     | 163.7 PLF |
| Yield Limit per Fastener | 81.9 lb.  |
| C <sub>m</sub>           | 1         |
| Yield Mode               | IV        |
| Edge Distance            | 1 1/2"    |
| Min. End Distance        | 3"        |
| Load Combination         |           |
| Duration Factor          | 1.00      |

**Notes**

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive

chemicals

**Handling & Installation**

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026

**Manufacturer Info**



Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
[www.metsawood.com/us](http://www.metsawood.com/us)

Comtech, Inc.  
 1001 S Reilly Rd., NC  
 28314  
 (910) 864-8787



# BM5 Kerto-S LVL 1.750" X 11.875" 2-Ply - PASSED

Level: Level



### Member Information

|                     |               |                |             |
|---------------------|---------------|----------------|-------------|
| Type:               | Girder        | Application:   | Floor       |
| Plies:              | 2             | Design Method: | ASD         |
| Moisture Condition: | Dry           | Building Code: | IBC 2012    |
| Deflection LL:      | 480           | Load Sharing:  | No          |
| Deflection TL:      | 240           | Deck:          | Not Checked |
| Importance:         | Normal - II   |                |             |
| Temperature:        | Temp <= 100°F |                |             |

### Reactions UNPATTERNED lb (Uplift)

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1   | Vertical  | 1772 | 2203 | 1044 | 0    | 0     |
| 2   | Vertical  | 1753 | 2179 | 1033 | 0    | 0     |

### Bearings

| Bearing           | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb.   |
|-------------------|--------|------|------|--------------|-------|----------|-------------|
| 1 - SPF End Grain | 4.625" | Vert | 32%  | 2203 / 2112  | 4314  | L        | D+0.75(L+S) |
| 2 - SPF End Grain | 4.063" | Vert | 36%  | 2179 / 2089  | 4268  | L        | D+0.75(L+S) |

### Analysis Results

| Analysis     | Actual         | Location  | Allowed       | Capacity    | Comb.       | Case |
|--------------|----------------|-----------|---------------|-------------|-------------|------|
| Moment       | 7478 ft-lb     | 4' 5/8"   | 19911 ft-lb   | 0.376 (38%) | D+L         | L    |
| Unbraced     | 8118 ft-lb     | 4' 5/8"   | 11006 ft-lb   | 0.738 (74%) | D+0.75(L+S) | L    |
| Shear        | 2737 lb        | 1' 1/2"   | 8867 lb       | 0.309 (31%) | D+L         | L    |
| LL Defl inch | 0.059 (L/1643) | 4' 11/16" | 0.203 (L/480) | 0.292 (29%) | 0.75(L+S)   | L    |
| TL Defl inch | 0.121 (L/804)  | 4' 11/16" | 0.406 (L/240) | 0.298 (30%) | D+0.75(L+S) | L    |

### Design Notes


- Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- Refer to last page of calculations for fasteners required for specified loads.
- Girders are designed to be supported on the bottom edge only.
- Top loads must be supported equally by all plies.
- Top must be laterally braced at end bearings.
- Bottom must be laterally braced at end bearings.
- Lateral slenderness ratio based on single ply width.

| ID | Load Type     | Location        | Trib Width | Side | Dead 0.9 | Live 1  | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments   |
|----|---------------|-----------------|------------|------|----------|---------|-----------|----------|-------------|------------|
| 1  | Part. Uniform | 0-0-0 to 8-8-11 |            | Top  | 135 PLF  | 404 PLF | 0 PLF     | 0 PLF    | 0 PLF       | F3         |
| 2  | Uniform       |                 |            | Top  | 120 PLF  | 0 PLF   | 0 PLF     | 0 PLF    | 0 PLF       | Wall Above |
| 3  | Uniform       |                 |            | Top  | 238 PLF  | 0 PLF   | 238 PLF   | 0 PLF    | 0 PLF       | C1         |
|    | Self Weight   |                 |            |      | 9 PLF    |         |           |          |             |            |

|  |  |  |  |   |
|--|--|--|--|---|
| <b>Notes</b><br>Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.<br><b>Lumber</b><br>1. Dry service conditions, unless noted otherwise<br>2. LVL not to be treated with fire retardant or corrosive chemicals | <b>Handling &amp; Installation</b><br>1. LVL beams must not be cut or drilled<br>2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals<br>3. Damaged Beams must not be used<br>4. Design assumes top edge is laterally restrained<br>5. Provide lateral support at bearing points to avoid lateral displacement and rotation | 6. For flat roofs provide proper drainage to prevent ponding | <b>Manufacturer Info</b><br>Metsä Wood<br>301 Merritt 7 Building, 2nd Floor<br>Norwalk, CT 06851<br>(800) 622-5850<br><a href="http://www.metsawood.com/us">www.metsawood.com/us</a> | Comtech, Inc.<br>1001 S Reilly Rd., NC<br>28314<br>(910) 864-8787 |
|  |  |  | This design is valid until 6/28/2026   |   |

**BM5 Kerto-S LVL 1.750" X 11.875" 2-Ply - PASSED**

Level: Level



**Multi-Ply Analysis**

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

|                          |           |
|--------------------------|-----------|
| Capacity                 | 0.0 %     |
| Load                     | 0.0 PLF   |
| Yield Limit per Foot     | 163.7 PLF |
| Yield Limit per Fastener | 81.9 lb.  |
| C <sub>m</sub>           | 1         |
| Yield Mode               | IV        |
| Edge Distance            | 1 1/2"    |
| Min. End Distance        | 3"        |
| Load Combination         |           |
| Duration Factor          | 1.00      |

**Notes**

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive

chemicals

**Handling & Installation**

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026

**Manufacturer Info**


Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
[www.metsawood.com/us](http://www.metsawood.com/us)

Comtech, Inc.  
 1001 S Reilly Rd., NC  
 28314  
 (910) 864-8787



**GDH Kerto-S LVL 1.750" X 11.875" 2-Ply - PASSED**

Level: Level



**Member Information**

|                     |               |                |             |
|---------------------|---------------|----------------|-------------|
| Type:               | Girder        | Application:   | Floor       |
| Plies:              | 2             | Design Method: | ASD         |
| Moisture Condition: | Dry           | Building Code: | IBC 2012    |
| Deflection LL:      | 480           | Load Sharing:  | No          |
| Deflection TL:      | 240           | Deck:          | Not Checked |
| Importance:         | Normal - II   |                |             |
| Temperature:        | Temp <= 100°F |                |             |

**Reactions UNPATTERNED lb (Uplift)**

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1   | Vertical  | 0    | 1054 | 471  | 0    | 0     |
| 2   | Vertical  | 0    | 1054 | 471  | 0    | 0     |

**Bearings**

| Bearing | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb. |
|---------|--------|------|------|--------------|-------|----------|-----------|
| 1 - SPF | 3.500" | Vert | 29%  | 1054 / 471   | 1525  | L        | D+S       |
| 2 - SPF | 3.500" | Vert | 29%  | 1054 / 471   | 1525  | L        | D+S       |

**Analysis Results**

| Analysis     | Actual         | Location  | Allowed       | Capacity     | Comb. | Case |
|--------------|----------------|-----------|---------------|--------------|-------|------|
| Moment       | 6075 ft-lb     | 8'5"      | 22897 ft-lb   | 0.265 (27%)  | D+S   | L    |
| Unbraced     | 6075 ft-lb     | 8'5"      | 6086 ft-lb    | 0.998 (100%) | D+S   | L    |
| Shear        | 1413 lb        | 1'3 3/8"  | 10197 lb      | 0.139 (14%)  | D+S   | L    |
| LL Defl inch | 0.098 (L/2006) | 8'5 1/16" | 0.409 (L/480) | 0.239 (24%)  | S     | L    |
| TL Defl inch | 0.317 (L/620)  | 8'5 1/16" | 0.819 (L/240) | 0.387 (39%)  | D+S   | L    |

**Design Notes**

- Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- Refer to last page of calculations for fasteners required for specified loads.
- Girders are designed to be supported on the bottom edge only.
- Top loads must be supported equally by all plies.
- Top must be laterally braced at end bearings.
- Bottom must be laterally braced at end bearings.
- Lateral slenderness ratio based on single ply width.

| ID | Load Type   | Location | Trib Width | Side      | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments   |
|----|-------------|----------|------------|-----------|----------|--------|-----------|----------|-------------|------------|
| 1  | Uniform     |          |            | Near Face | 56 PLF   | 0 PLF  | 56 PLF    | 0 PLF    | 0 PLF       | J3         |
| 2  | Uniform     |          |            | Top       | 60 PLF   | 0 PLF  | 0 PLF     | 0 PLF    | 0 PLF       | Wall Above |
|    | Self Weight |          |            |           | 9 PLF    |        |           |          |             |            |

**Notes**

Calculated Structural Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

- Dry service conditions, unless noted otherwise
- LVL not to be treated with fire retardant or corrosive chemicals

**Handling & Installation**

- LVL beams must not be cut or drilled
- Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
- Damaged Beams must not be used
- Design assumes top edge is laterally restrained
- Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026

**Manufacturer Info**


Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
[www.metsawood.com/us](http://www.metsawood.com/us)

Comtech, Inc.  
 1001 S Reilly Rd., NC  
 28314  
 (910) 864-8787



**GDH Kerto-S LVL 1.750" X 11.875" 2-Ply - PASSED**

Level: Level



**Multi-Ply Analysis**

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

|                          |           |
|--------------------------|-----------|
| Capacity                 | 29.7 %    |
| Load                     | 56.0 PLF  |
| Yield Limit per Foot     | 188.3 PLF |
| Yield Limit per Fastener | 94.1 lb.  |
| C <sub>m</sub>           | 1         |
| Yield Mode               | IV        |
| Edge Distance            | 1 1/2"    |
| Min. End Distance        | 3"        |
| Load Combination         | D+S       |
| Duration Factor          | 1.15      |

**Notes**

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

**Handling & Installation**

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026

**Manufacturer Info**



Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
[www.metsawood.com/us](http://www.metsawood.com/us)

Comtech, Inc.  
 1001 S Reilly Rd., NC  
 28314  
 (910) 864-8787



**GDH2 S-P-F #2 2.000" X 12.000" 2-Ply - PASSED**

Level: Level



**Member Information**

|                     |               |
|---------------------|---------------|
| Type:               | Girder        |
| Plies:              | 2             |
| Moisture Condition: | Dry           |
| Deflection LL:      | 480           |
| Deflection TL:      | 360           |
| Importance:         | Normal - II   |
| Temperature:        | Temp <= 100°F |

|                |             |
|----------------|-------------|
| Application:   | Floor       |
| Design Method: | ASD         |
| Building Code: | IBC 2012    |
| Load Sharing:  | No          |
| Deck:          | Not Checked |

**Reactions UNPATTERNED Ib (Uplift)**

| Brg | Direction | Live | Dead | Snow | Wind | Const |
|-----|-----------|------|------|------|------|-------|
| 1   | Vertical  | 0    | 1413 | 1148 | 0    | 0     |
| 2   | Vertical  | 0    | 1413 | 1148 | 0    | 0     |

**Bearings**

| Bearing           | Length | Dir. | Cap. | React D/L lb | Total | Ld. Case | Ld. Comb. |
|-------------------|--------|------|------|--------------|-------|----------|-----------|
| 1 - SPF End Grain | 3.500" | Vert | 57%  | 1413 / 1148  | 2562  | L        | D+S       |
| 2 - SPF End Grain | 3.500" | Vert | 57%  | 1413 / 1148  | 2562  | L        | D+S       |

**Analysis Results**

| Analysis     | Actual         | Location  | Allowed       | Capacity     | Comb. | Case |
|--------------|----------------|-----------|---------------|--------------|-------|------|
| Moment       | 5085 ft-lb     | 4'5"      | 5306 ft-lb    | 0.958 (96%)  | D+S   | L    |
| Unbraced     | 5085 ft-lb     | 4'5"      | 5088 ft-lb    | 0.999 (100%) | D+S   | L    |
| Shear        | 1849 lb        | 7'7 1/4"  | 3493 lb       | 0.529 (53%)  | D+S   | L    |
| LL Defl inch | 0.058 (L/1740) | 4'5 1/16" | 0.209 (L/480) | 0.276 (28%)  | S     | L    |
| TL Defl inch | 0.129 (L/780)  | 4'5 1/16" | 0.279 (L/360) | 0.461 (46%)  | D+S   | L    |

**Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at a maximum of 3'3 5/8" o.c.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments   |
|----|-----------|----------|------------|------|----------|--------|-----------|----------|-------------|------------|
| 1  | Uniform   |          |            | Top  | 60 PLF   | 0 PLF  | 0 PLF     | 0 PLF    | 0 PLF       | Wall Above |
| 2  | Uniform   |          |            | Top  | 260 PLF  | 0 PLF  | 260 PLF   | 0 PLF    | 0 PLF       | G1         |

**Manufacturer Info**


Comtech, Inc.  
 1001 S Reilly Rd., NC  
 28314  
 (910) 864-8787



This design is valid until 6/28/2026

**GDH2 S-P-F #2 2.000" X 12.000" 2-Ply - PASSED**

Level: Level



**Multi-Ply Analysis**

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

|                          |           |
|--------------------------|-----------|
| Capacity                 | 0.0 %     |
| Load                     | 0.0 PLF   |
| Yield Limit per Foot     | 157.4 PLF |
| Yield Limit per Fastener | 78.7 lb.  |
| C <sub>m</sub>           | 1         |
| Yield Mode               | IV        |
| Edge Distance            | 1 1/2"    |
| Min. End Distance        | 3"        |
| Load Combination         |           |
| Duration Factor          | 1.00      |

|                          |   |
|--------------------------|---|
| <b>Manufacturer Info</b> | Comtech, Inc.<br>1001 S Reilly Rd., NC<br>28314<br>(910) 864-8787 |
|                          |   |

This design is valid until 6/28/2026



RE: J0824-4838  
 Lot 13 Magnolia Hills

**Trenco**  
 818 Soundside Rd  
 Edenton, NC 27932

**Site Information:**

Customer: Project Name: J0824-4838  
 Lot/Block: Model:  
 Address: Subdivision:  
 City: State:

**General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):**

Design Code: IRC2015/TPI2014 Design Program: MiTek 20/20 8.4  
 Wind Code: N/A Wind Speed: N/A mph  
 Roof Load: N/A psf Floor Load: 55.0 psf

This package includes 10 individual, dated Truss Design Drawings and 0 Additional Drawings.

| No. | Seal#     | Truss Name | Date     |
|-----|-----------|------------|----------|
| 1   | I64635032 | ET1        | 4/2/2024 |
| 2   | I64635033 | ET2        | 4/2/2024 |
| 3   | I64635034 | ET3        | 4/2/2024 |
| 4   | I64635035 | F1         | 4/2/2024 |
| 5   | I64635036 | F2         | 4/2/2024 |
| 6   | I64635037 | F3         | 4/2/2024 |
| 7   | I64635038 | F4         | 4/2/2024 |
| 8   | I64635039 | F4A        | 4/2/2024 |
| 9   | I64635040 | F5         | 4/2/2024 |
| 10  | I64635041 | FG1        | 4/2/2024 |


The truss drawing(s) referenced above have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Comtech, Inc - Fayetteville.

Truss Design Engineer's Name: Gilbert, Eric

My license renewal date for the state of North Carolina is December 31, 2024.

North Carolina COA: C-0844

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to TRENCO. Any project specific information included is for TRENCO customers file reference purpose only, and was not taken into account in the preparation of these designs. TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



April 02, 2024

|                   |              |                     |          |          |   |           |
|-------------------|--------------|---------------------|----------|----------|---|-----------|
| Job<br>J0824-4838 | Truss<br>ET1 | Truss Type<br>GABLE | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635032 |
|-------------------|--------------|---------------------|----------|----------|---|-----------|


Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:31 2024 Page 1  
ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

0-1/8

0-1/8

Scale = 1:55.0




| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d | PLATES         | GRIP            |
|---------------|----------------------|-------|----------|----------|----------|--------|-----|----------------|-----------------|
| TCLL 40.0     | Plate Grip DOL       | 1.00  | TC 0.06  | Vert(LL) | n/a      | -      | n/a | MT20           | 244/190         |
| TCDL 10.0     | Lumber DOL           | 1.00  | BC 0.01  | Vert(CT) | n/a      | -      | n/a |                |                 |
| BCLL 0.0      | Rep Stress Incr      | YES   | WB 0.03  | Horz(CT) | -0.00    | 38     | n/a |                |                 |
| BCDL 5.0      | Code IRC2015/TPI2014 |       | Matrix-S |          |          |        |     |                |                 |
|               |                      |       |          |          |          |        |     | Weight: 147 lb | FT = 20%F, 11%E |

| LUMBER-                     | BRACING-  |
|-----------------------------|---|
| TOP CHORD 2x4 SP No.1(flat) | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.1(flat) | BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.                                   |
| WEBS 2x4 SP No.3(flat)      |   |
| OTHERS 2x4 SP No.3(flat)    |   |


**REACTIONS.** All bearings 32-11-0.  
(lb) - Max Grav All reactions 250 lb or less at joint(s) 56, 29, 55, 54, 53, 52, 51, 50, 49, 48, 46, 45, 44, 43, 42, 41, 40, 38, 37, 36, 35, 34, 33, 32, 31, 30

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 2) Plates checked for a plus or minus 1 degree rotation about its center.
  - 3) Gable requires continuous bottom chord bearing.
  - 4) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 5) Gable studs spaced at 1-4-0 oc.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



April 2, 2024

|  |   |
|--|---|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TP1 Quality Criteria and DSB-22</b> available from Truss Plate Institute (www.tpinst.org) and <b>BCSI Building Component Safety Information</b> available from the Structural Building Component Association (www.sbcacomponents.com)</p> | <p>ENGINEERING BY</p>  <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|---|


|            |       |            |     |     |                          |
|------------|-------|------------|-----|-----|--------------------------|
| Job        | Truss | Truss Type | Qty | Ply | Lot 13 Magnolia Hills    |
| J0824-4838 | ET2   | GABLE      | 1   | 1   | I64635033                |
|            |       |            |     |     | Job Reference (optional) |

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:32 2024 Page 1  
ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

0-1-8

Scale = 1:30.5



|       |       |       |       |       |       |       |        |        |        |        |        |        |        |
|-------|-------|-------|-------|-------|-------|-------|--------|--------|--------|--------|--------|--------|--------|
| 1-4-0 | 2-8-0 | 4-0-0 | 5-4-0 | 6-8-0 | 8-0-0 | 9-4-0 | 10-8-0 | 12-0-0 | 13-4-0 | 14-8-0 | 16-0-0 | 17-4-0 | 18-4-0 |
| 1-4-0 | 1-4-0 | 1-4-0 | 1-4-0 | 1-4-0 | 1-4-0 | 1-4-0 | 1-4-0  | 1-4-0  | 1-4-0  | 1-4-0  | 1-4-0  | 1-4-0  | 1-0-0  |


|   |                      |       |             |              |          |        |     |               |                 |
|---|----------------------|-------|-------------|--------------|----------|--------|-----|---------------|-----------------|
| Plate Offsets (X,Y)-- [7:0-1-8,Edge], [24:0-1-8,Edge] |                      |       |             |              |          | PLATES |     | GRIP          |                 |
| <b>LOADING</b> (psf)                                  | <b>SPACING-</b>      | 2-0-0 | <b>CSI.</b> | <b>DEFL.</b> | in (loc) | l/defl | L/d | MT20          | 244/190         |
| TCLL 40.0   | Plate Grip DOL       | 1.00  | TC 0.07     | Vert(LL)     | n/a      | -      | n/a |               |                 |
| TCDL 10.0   | Lumber DOL           | 1.00  | BC 0.01     | Vert(CT)     | n/a      | -      | n/a |               |                 |
| BCLL 0.0  | Rep Stress Incr      | NO    | WB 0.03     | Horz(CT)     | 0.00     | 17     | n/a |               |                 |
| BCDL 5.0  | Code IRC2015/TPI2014 |       | Matrix-S    |              |          |        |     | Weight: 84 lb | FT = 20%F, 11%E |

|                             |   |
|-----------------------------|---|
| <b>LUMBER-</b>              | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.1(flat) | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.1(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)      |   |
| OTHERS 2x4 SP No.3(flat)    |   |


**REACTIONS.** All bearings 18-4-0.  
(lb) - Max Grav All reactions 250 lb or less at joint(s) 32, 17, 31, 30, 29, 28, 27, 25, 24, 23, 22, 21, 20, 19, 18

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- All plates are 1.5x3 MT20 unless otherwise indicated.
  - Plates checked for a plus or minus 1 degree rotation about its center.
  - Gable requires continuous bottom chord bearing.
  - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - Gable studs spaced at 1-4-0 oc.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - CAUTION, Do not erect truss backwards.



April 2, 2024

|  |  |
|--|--|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TP1 Quality Criteria and DSB-22</b> available from Truss Plate Institute (www.tpinst.org) and <b>BCSI Building Component Safety Information</b> available from the Structural Building Component Association (www.sbcacomponents.com)</p> | <p>ENGINEERING BY</p>  <p>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|--|


|                   |              |                     |          |          |   |           |
|-------------------|--------------|---------------------|----------|----------|---|-----------|
| Job<br>J0824-4838 | Truss<br>ET3 | Truss Type<br>GABLE | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635034 |
|-------------------|--------------|---------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:32 2024 Page 1  
ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

0-1-8

Scale: 3/8"=1'



|       |       |       |       |       |       |       |        |        |        |        |        |        |        |        |
|-------|-------|-------|-------|-------|-------|-------|--------|--------|--------|--------|--------|--------|--------|--------|
| 1-0-0 | 2-4-0 | 3-8-0 | 5-0-0 | 6-4-0 | 7-8-0 | 9-0-0 | 10-4-0 | 11-8-0 | 13-0-0 | 14-4-0 | 15-8-0 | 17-0-0 | 18-4-0 | 19-4-8 |
| 1-0-0 | 1-4-0 | 1-4-0 | 1-4-0 | 1-4-0 | 1-4-0 | 1-4-0 | 1-4-0  | 1-4-0  | 1-4-0  | 1-4-0  | 1-4-0  | 1-4-0  | 1-4-0  | 1-0-8  |

|   |                       |             |                                  |               |                 |
|---|-----------------------|-------------|----------------------------------|---------------|-----------------|
| Plate Offsets (X,Y)-- [9:0-1-8,Edge], [24:0-1-8,Edge] |                       |             |                                  |               |                 |
| <b>LOADING</b> (psf)                                  | <b>SPACING-</b> 2-0-0 | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b> | <b>GRIP</b>     |
| TCLL 40.0   | Plate Grip DOL 1.00   | TC 0.06     | Vert(LL) n/a - n/a 999           | MT20          | 244/190         |
| TCDL 10.0   | Lumber DOL 1.00       | BC 0.01     | Vert(CT) n/a - n/a 999           |               |                 |
| BCLL 0.0  | Rep Stress Incr YES   | WB 0.03     | Horz(CT) 0.00 18 n/a n/a         |               |                 |
| BCDL 5.0  | Code IRC2015/TPI2014  | Matrix-S    |                                  | Weight: 89 lb | FT = 20%F, 11%E |

|                             |   |
|-----------------------------|---|
| <b>LUMBER-</b>              | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.1(flat) | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.1(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)      |   |
| OTHERS 2x4 SP No.3(flat)    |   |

**REACTIONS.** All bearings 19-4-8.  
(lb) - Max Grav All reactions 250 lb or less at joint(s) 34, 18, 33, 32, 31, 30, 29, 27, 26, 25, 24, 23, 22, 21, 20, 19

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 2) Plates checked for a plus or minus 1 degree rotation about its center.
  - 3) Gable requires continuous bottom chord bearing.
  - 4) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 5) Gable studs spaced at 1-4-0 oc.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 7) CAUTION, Do not erect truss backwards.



April 2, 2024


|  |  |
|--|--|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TP1 Quality Criteria and DSB-22</b> available from Truss Plate Institute (www.tpinst.org) and <b>BCSI Building Component Safety Information</b> available from the Structural Building Component Association (www.sbcacomponents.com)</p> | <p>ENGINEERING BY</p> <p>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|--|

|                   |             |                     |          |          |                                    |
|-------------------|-------------|---------------------|----------|----------|------------------------------------|
| Job<br>J0824-4838 | Truss<br>F1 | Truss Type<br>Floor | Qty<br>7 | Ply<br>1 | Lot 13 Magnolia Hills<br>I64635035 |
|-------------------|-------------|---------------------|----------|----------|------------------------------------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:33 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f



|                       |  |
|-----------------------|--|
| Plate Offsets (X,Y)-- | [6:0-3-0,0-0-0], [17:0-1-8,Edge], [27:0-1-8,Edge], [36:0-1-8,Edge] |
|-----------------------|--|

| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d  | PLATES | GRIP    |
|---------------|----------------------|-------|----------|----------|----------|--------|------|--------|---------|
| TCLL 40.0     | Plate Grip DOL       | 1.00  | TC 0.63  | Vert(LL) | -0.20    | 27     | >999 | MT20   | 244/190 |
| TCDL 10.0     | Lumber DOL           | 1.00  | BC 0.82  | Vert(CT) | -0.27    | 26-27  | >820 |        |         |
| BCLL 0.0      | Rep Stress Incr      | YES   | WB 0.63  | Horz(CT) | 0.04     | 24     | n/a  |        |         |
| BCDL 5.0      | Code IRC2015/TPI2014 |       | Matrix-S |          |          |        |      |        |         |

Weight: 180 lb FT = 20%F, 11%E

| LUMBER-                     | BRACING-  |
|-----------------------------|---|
| TOP CHORD 2x4 SP No.1(flat) | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.1(flat) | BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.                                   |
| WEBS 2x4 SP No.3(flat)      |   |

**REACTIONS.** (size) 40=0-3-8, 24=0-3-8, 33=0-3-8  
 Max Grav 40=662(LC 3), 24=882(LC 4), 33=2190(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1110/36, 3-4=-1659/212, 4-5=-1659/219, 5-6=-1602/621, 6-7=-1602/621, 7-10=-392/1404, 10-11=0/2571, 11-12=0/2571, 12-13=-40/475, 13-14=-1631/0, 14-15=-1631/0, 15-17=-2564/0, 17-18=-2931/0, 18-19=-2931/0, 19-20=-2592/0, 20-21=-2592/0, 21-22=-1586/0


BOT CHORD 39-40=0/704, 38-39=-106/1489, 37-38=-621/1602, 36-37=-621/1602, 35-36=-1086/1024, 33-35=-1709/0, 32-33=-1291/0, 31-32=-200/935, 29-31=0/2220, 28-29=0/2931, 27-28=0/2931, 26-27=0/2856, 25-26=0/2193, 24-25=0/952

WEBS 2-40=935/0, 2-39=-59/564, 3-39=-528/98, 4-38=-325/0, 5-38=0/648, 22-24=-1266/0, 22-25=0/881, 21-25=-845/0, 21-26=0/542, 19-26=-358/0, 19-27=-253/331, 12-33=-1704/0, 12-32=0/1314, 10-33=-1399/0, 10-35=0/993, 7-35=-1033/0, 7-36=0/1214, 6-36=-690/0, 13-32=-1288/0, 13-31=0/991, 15-31=-835/0, 15-29=0/579, 17-29=-718/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are 3x4 MT20 unless otherwise indicated.
  - 3) Plates checked for a plus or minus 1 degree rotation about its center.
  - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 5) CAUTION, Do not erect truss backwards.



April 2, 2024


|  |  |
|--|--|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria and DSB-22</b> available from Truss Plate Institute (www.tpinst.org) and <b>BCSI Building Component Safety Information</b> available from the Structural Building Component Association (www.sbccomponents.com)</p> | <p>ENGINEERING BY</p>  <p>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|--|



|            |       |            |     |     |                          |
|------------|-------|------------|-----|-----|--------------------------|
| Job        | Truss | Truss Type | Qty | Ply | Lot 13 Magnolia Hills    |
| J0824-4838 | F3    | Floor      | 9   | 1   | I64635037                |
|            |       |            |     |     | Job Reference (optional) |

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:34 2024 Page 1  
ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



|                       |                                |
|-----------------------|--------------------------------|
| Plate Offsets (X,Y)-- | [6:0-1-8,Edge], [7:0-1-8,Edge] |
|-----------------------|--------------------------------|


|                      |                       |             |                                  |                                |             |
|----------------------|-----------------------|-------------|----------------------------------|--------------------------------|-------------|
| <b>LOADING</b> (psf) | <b>SPACING-</b> 2-0-0 | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b>                  | <b>GRIP</b> |
| TCLL 40.0            | Plate Grip DOL 1.00   | TC 0.56     | Vert(LL) -0.33 18-19 >724 480    | MT20                           | 244/190     |
| TCDL 10.0            | Lumber DOL 1.00       | BC 0.95     | Vert(CT) -0.45 18-19 >526 360    | M18AHS                         | 186/179     |
| BCLL 0.0             | Rep Stress Incr YES   | WB 0.55     | Horz(CT) 0.08 14 n/a n/a         | Weight: 106 lb FT = 20%F, 11%E |             |
| BCDL 5.0             | Code IRC2015/TP12014  | Matrix-S    |                                  |                                |             |

|                             |   |
|-----------------------------|---|
| <b>LUMBER-</b>              | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.1(flat) | TOP CHORD Structural wood sheathing directly applied or 5-9-6 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.1(flat) | BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.                                   |
| WEBS 2x4 SP No.3(flat)      |   |

**REACTIONS.** (size) 24=0-3-0, 14=0-3-0  
Max Grav 24=1075(LC 1), 14=1075(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-2005/0, 3-4=-3408/0, 4-5=-3408/0, 5-6=-4160/0, 6-7=-4391/0, 7-9=-4160/0, 9-10=-3408/0, 10-11=-3408/0, 11-12=-2005/0  
BOT CHORD 23-24=0/1172, 21-23=0/2810, 20-21=0/3918, 19-20=0/4391, 18-19=0/4391, 17-18=0/4391, 16-17=0/3918, 15-16=0/2810, 14-15=0/1172  
WEBS 2-24=-1557/0, 2-23=0/1160, 3-23=-1119/0, 3-21=0/814, 5-21=-693/0, 5-20=0/469, 6-20=-575/87, 12-14=-1557/0, 12-15=0/1160, 11-15=-1119/0, 11-16=0/814, 9-16=-693/0, 9-17=0/469, 7-17=-575/87

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 4) Plates checked for a plus or minus 1 degree rotation about its center.
  - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



April 2, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road  
Edenton, NC 27932

|                   |             |                     |           |          |                                    |
|-------------------|-------------|---------------------|-----------|----------|------------------------------------|
| Job<br>J0824-4838 | Truss<br>F4 | Truss Type<br>Floor | Qty<br>10 | Ply<br>1 | Lot 13 Magnolia Hills<br>I64635038 |
|-------------------|-------------|---------------------|-----------|----------|------------------------------------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:35 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



|                        |                                 |             |                                  |                |                 |
|------------------------|---------------------------------|-------------|----------------------------------|----------------|-----------------|
| Plate Offsets (X, Y)-- | [7:0-3-0,Edge], [21:0-1-8,Edge] |             |                                  |                |                 |
| <b>LOADING</b> (psf)   | <b>SPACING-</b> 2-0-0           | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b>  | <b>GRIP</b>     |
| TCLL 40.0              | Plate Grip DOL 1.00             | TC 0.39     | Vert(LL) -0.29 20 >806 480       | MT20           | 244/190         |
| TCDL 10.0              | Lumber DOL 1.00                 | BC 0.88     | Vert(CT) -0.40 20 >587 360       | M18AHS         | 186/179         |
| BCLL 0.0               | Rep Stress Incr YES             | WB 0.54     | Horz(CT) 0.08 16 n/a n/a         |                |                 |
| BCDL 5.0               | Code IRC2015/TP12014            | Matrix-S    |                                  |                |                 |
|                        |                                 |             |                                  | Weight: 112 lb | FT = 20%F, 11%E |

|                             |   |
|-----------------------------|---|
| <b>LUMBER-</b>              | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.1(flat) | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.1(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)      |   |

**REACTIONS.** (size) 25=0-3-0, 16=Mechanical  
Max Grav 25=1062(LC 1), 16=1068(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1976/0, 3-4=-3346/0, 4-6=-3350/0, 6-7=-4437/0, 7-8=-4437/0, 8-10=-4140/0, 10-11=-3354/0, 11-13=-3354/0, 13-14=-1976/0

BOT CHORD 24-25=0/1156, 22-24=0/2765, 21-22=0/3951, 20-21=0/4437, 19-20=0/4437, 18-19=0/3823, 17-18=0/2764, 16-17=0/1157

WEBS 2-25=-1537/0, 2-24=0/1140, 3-24=-1097/0, 3-22=0/790, 6-22=-803/0, 6-21=0/970, 7-21=-557/0, 14-16=-1541/0, 14-17=0/1139, 13-17=-1096/0, 13-18=0/802, 10-18=-637/0, 10-19=0/581, 8-19=-621/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) All plates are 3x4 MT20 unless otherwise indicated.
  - 4) Plates checked for a plus or minus 1 degree rotation about its center.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 7) CAUTION, Do not erect truss backwards.



April 2, 2024

|  |   |
|--|---|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TP1 Quality Criteria and DSB-22</b> available from Truss Plate Institute (www.tpinst.org) and <b>BCSI Building Component Safety Information</b> available from the Structural Building Component Association (www.sbcacomponents.com)</p> | <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|---|




|            |       |            |     |     |                          |           |
|------------|-------|------------|-----|-----|--------------------------|-----------|
| Job        | Truss | Truss Type | Qty | Ply | Lot 13 Magnolia Hills    | I64635039 |
| J0824-4838 | F4A   | Floor      | 1   | 1   | Job Reference (optional) |           |

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:35 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



|                       |  |        |         |         |        |        |
|-----------------------|--|--------|---------|---------|--------|--------|
|                       | 13-11-4  | 15-5-4 | 16-7-10 | 17-10-0 | 19-4-0 | 19-8-0 |
|                       | 13-11-4  | 1-6-0  | 1-2-6   | 1-2-6   | 1-6-0  | 0-4-0  |
| Plate Offsets (X,Y)-- | [13:0-1-8,Edge], [15:0-3-0,0-0-0], [18:0-1-8,Edge] |        |         |         |        |        |


|                      |                      |       |             |              |          |        |      |                |                 |
|----------------------|----------------------|-------|-------------|--------------|----------|--------|------|----------------|-----------------|
| <b>LOADING</b> (psf) | <b>SPACING-</b>      | 2-0-0 | <b>CSI.</b> | <b>DEFL.</b> | in (loc) | l/defl | L/d  | <b>PLATES</b>  | <b>GRIP</b>     |
| TCLL 40.0            | Plate Grip DOL       | 1.00  | TC 0.40     | Vert(LL)     | -0.08    | 26     | >999 | MT20           | 244/190         |
| TCDL 10.0            | Lumber DOL           | 1.00  | BC 0.38     | Vert(CT)     | -0.11    | 26     | >999 |                |                 |
| BCLL 0.0             | Rep Stress Incr      | YES   | WB 0.37     | Horz(CT)     | 0.03     | 20     | n/a  |                |                 |
| BCDL 5.0             | Code IRC2015/TPI2014 |       | Matrix-S    |              |          |        |      |                |                 |
|                      |                      |       |             |              |          |        |      | Weight: 115 lb | FT = 20%F, 11%E |

|                             |   |
|-----------------------------|---|
| <b>LUMBER-</b>              | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.1(flat) | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.       |
| BOT CHORD 2x4 SP No.1(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 19-20,18-19. |
| WEBS 2x4 SP No.3(flat)      |   |

**REACTIONS.** (size) 31=0-3-0, 16=0-3-8, 20=0-3-8  
 Max Grav 31=730(LC 8), 16=275(LC 4), 20=1157(LC 7)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-1331/0, 3-4=-1331/0, 4-5=-1969/0, 5-6=-1969/0, 6-7=-1961/0, 7-8=-1961/0, 8-9=-1306/0, 9-11=-1306/0, 11-12=0/365, 12-13=0/364, 13-15=-276/99, 15-16=-253/96  
 BOT CHORD 30-31=0/775, 29-30=0/775, 28-29=0/1732, 27-28=0/1732, 26-27=0/2047, 24-26=0/2047, 23-24=0/1717, 22-23=0/1717, 21-22=0/750, 20-21=0/750, 19-20=-96/253, 18-19=-96/253  
 WEBS 16-18=-125/330, 2-31=-1021/0, 2-29=0/751, 4-29=-541/0, 4-27=0/319, 8-24=0/345, 8-22=-569/0, 11-22=0/769, 11-20=-1229/0, 13-20=-575/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are 3x6 MT20 unless otherwise indicated.
  - 3) Plates checked for a plus or minus 1 degree rotation about its center.
  - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 5) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
  - 6) CAUTION, Do not erect truss backwards.



April 2, 2024

|  |   |
|--|---|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPH Quality Criteria and DSB-22</b> available from Truss Plate Institute (www.tpinst.org) and <b>BCSI Building Component Safety Information</b> available from the Structural Building Component Association (www.sbcacomponents.com)</p> | <p>ENGINEERING BY</p> <p><b>TRENCO</b></p> <p>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|---|

|                   |             |                     |          |          |   |           |
|-------------------|-------------|---------------------|----------|----------|---|-----------|
| Job<br>J0824-4838 | Truss<br>F5 | Truss Type<br>FLOOR | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635040 |
|-------------------|-------------|---------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:36 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRCDoi7J4zJC?f

0-1-8



Scale = 1:11.4





Plate Offsets (X,Y)-- [2:0-1-8,Edge], [4:0-3-0,Edge], [7:0-1-8,Edge], [10:0-1-8,0-1-8]

| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d  | PLATES | GRIP          |                 |
|---------------|----------------------|-------|----------|----------|----------|--------|------|--------|---------------|-----------------|
| TCLL 40.0     | Plate Grip DOL       | 1.00  | TC 0.21  | Vert(LL) | -0.01    | 7      | >999 | 480    | MT20          | 244/190         |
| TCDL 10.0     | Lumber DOL           | 1.00  | BC 0.12  | Vert(CT) | -0.01    | 7      | >999 | 360    |               |                 |
| BCLL 0.0      | Rep Stress Incr      | YES   | WB 0.18  | Horz(CT) | -0.01    | 5      | n/a  | n/a    |               |                 |
| BCDL 5.0      | Code IRC2015/TPI2014 |       | Matrix-S |          |          |        |      |        |               |                 |
|               |                      |       |          |          |          |        |      |        | Weight: 32 lb | FT = 20%F, 11%E |

**LUMBER-**

TOP CHORD 2x4 SP No.1(flat)  
 BOT CHORD 2x4 SP No.1(flat)  
 WEBS 2x4 SP No.3(flat)

**BRACING-**

TOP CHORD Structural wood sheathing directly applied or 5-10-8 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.**


(size) 9=0-3-8, 5=0-3-8  
 Max Grav 9=288(LC 1), 5=294(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-4=-322/0, 4-5=-298/0  
 BOT CHORD 8-9=0/298, 7-8=0/298  
 WEBS 2-9=-386/0, 5-7=0/387

**NOTES-**

- 1) Unbalanced floor live loads have been considered for this design.
- 2) Plates checked for a plus or minus 1 degree rotation about its center.
- 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 4) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
- 5) CAUTION, Do not erect truss backwards.



April 2, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road  
 Edenton, NC 27932

|                   |              |                     |          |          |   |           |
|-------------------|--------------|---------------------|----------|----------|---|-----------|
| Job<br>J0824-4838 | Truss<br>FG1 | Truss Type<br>FLOOR | Qty<br>1 | Ply<br>1 | Lot 13 Magnolia Hills<br>Job Reference (optional) | I64635041 |
|-------------------|--------------|---------------------|----------|----------|---|-----------|

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Tue Apr 2 11:08:36 2024 Page 1

ID:aTXuLo?nW09qtpROz2WQ0wydkZW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [9:0-1-8,0-1-8], [10:0-1-8,0-1-8]

| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d  | PLATES | GRIP          |                 |
|---------------|----------------------|-------|----------|----------|----------|--------|------|--------|---------------|-----------------|
| TCLL 40.0     | Plate Grip DOL       | 1.00  | TC 0.12  | Vert(LL) | -0.01    | 6      | >999 | 480    | MT20          | 244/190         |
| TCDL 10.0     | Lumber DOL           | 1.00  | BC 0.17  | Vert(CT) | -0.01    | 6-7    | >999 | 360    |               |                 |
| BCLL 0.0      | Rep Stress Incr      | NO    | WB 0.19  | Horz(CT) | 0.01     | 5      | n/a  | n/a    |               |                 |
| BCDL 5.0      | Code IRC2015/TP12014 |       | Matrix-S |          |          |        |      |        |               |                 |
|               |                      |       |          |          |          |        |      |        | Weight: 34 lb | FT = 20%F, 11%E |

| LUMBER-                     | BRACING-  |
|-----------------------------|---|
| TOP CHORD 2x4 SP No.1(flat) | TOP CHORD Structural wood sheathing directly applied or 5-6-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.1(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)      |   |

**REACTIONS.** (size) 8=0-3-8, 5=0-3-8  
Max Grav 8=456(LC 1), 5=478(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-685/0  
BOT CHORD 7-8=0/685, 6-7=0/685, 5-6=0/685  
WEBS 2-8=-806/0, 3-5=-804/0

**NOTES-**  
1) Unbalanced floor live loads have been considered for this design.  
2) Plates checked for a plus or minus 1 degree rotation about its center.  
3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.


**LOAD CASE(S)** Standard  
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00  
Uniform Loads (plf)  
Vert: 5-8=-10, 1-4=-100  
Concentrated Loads (lb)  
Vert: 3=-175 11=-194




April 2, 2024

# Symbols


## PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0-<sup>1</sup>/<sub>16</sub>\"/>



This symbol indicates the required direction of slots in connector plates.

\* Plate location details available in MITek software or upon request.

## PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

## LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

## BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

## Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.  
DSB-22: Design Standard for Bracing.  
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

# Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

# Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282  
ESR-4722, ESL-1388

# Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 section 6.3. These truss designs rely on Lumber values established by others.

© 2023 MITek® All Rights Reserved

# General Safety Notes

## Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.

**MITek**

ENGINEERING BY  
**TRENGO**  
A MITek Affiliate

MITek Engineering Reference Sheet: MI1-7473 rev. 1/2/2023