


Job 72430120	Truss F200	Truss Type Truss	Qty 2	Ply 1	PBS\SMITHFIELD FC RH 2ND FL OW Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFPI Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Misti Presley

Run: 8.73 S Jul 24 2024 Print: 8.730 S Jul 24 2024 MiTek Industries, Inc. Mon Sep 23 12:13:14

Page: 1

ID:qMPgz1xPQuFsrTwhwcX5tGztSco-meWbE?XxtO8jjCry55g1dazXYCHRPTxBkUYZTYamPZ



Scale = 1:44.5

Loading	(psf)	Spacing	1-7-3	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.64	Vert(LL)	-0.30	16-17	>803	480	MT18HS 244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.76	Vert(CT)	-0.41	16-17	>584	360	MT20 244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.51	Horz(CT)	0.07	12	n/a	n/a	
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 101 lb FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS	(lb/size)	12=863/0-3-8, (min. 0-1-8), 20=863/0-3-8, (min. 0-1-8)
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD	2-3=-2224/0, 3-4=-3073/0, 4-5=-3515/0, 5-6=-3515/0, 6-7=-3515/0, 7-8=-3515/0, 8-9=-3070/0, 9-10=-2224/0	
BOT CHORD	19-20=0/1665, 18-19=0/2752, 17-18=0/3373, 16-17=0/3515, 15-16=0/3375, 14-15=0/3375, 13-14=0/2752, 12-13=0/1666	
WEBS	7-16=-275/25, 2-20=-1829/0, 2-19=0/776, 3-19=-735/0, 3-18=0/447, 4-18=-417/0, 4-17=-122/493, 10-12=-1829/0, 10-13=0/777, 9-13=-733/0, 9-14=0/443, 8-14=-427/0, 8-16=-118/511	

- NOTES**
- Unbalanced floor live loads have been considered for this design.
 - All plates are MT20 plates unless otherwise indicated.
 - All plates are 3x3 MT20 unless otherwise indicated.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 72430120	Truss F201	Truss Type Truss	Qty 7	Ply 1	PBS\SMITHFIELD FC RH 2ND FL OW Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Misti Presley

Run: 8.73 S Jul 24 2024 Print: 8.730 S Jul 24 2024 MiTek Industries, Inc. Mon Sep 23 12:13:14

Page: 1

ID: IYy2ANy1BCNjSdVtTK2KQTztScn-meWbE?XxtO8jjCry55g1dazJyCGBPsOBkUYZTYamPZ



Scale = 1:56.5

Plate Offsets (X, Y):		[17:0-2-0,Edge], [26:0-1-8,Edge], [28:0-2-0,Edge]										
Loading	(psf)	Spacing	1-7-3	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.87	Vert(LL)	-0.26	19-20	>901	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.78	Vert(CT)	-0.36	19-20	>657	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.54	Horz(CT)	0.05	17	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 141 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 5-8-3 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 27-28,26-27,25-26.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS	(lb/size)	17=784/0-3-8, (min. 0-1-8), 25=1487/0-3-8, (min. 0-1-8), 28=160/0-3-8, (min. 0-1-8)
	Max Uplift	28=-77 (LC 4)
	Max Grav	17=794 (LC 7), 25=1487 (LC 1), 28=281 (LC 3)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-356/382, 3-4=-356/382, 4-5=-356/382, 5-6=0/1292, 6-7=0/1297, 7-8=-1323/0, 8-9=-2304/0, 9-10=-2954/0, 10-11=-2954/0, 11-12=-2954/0, 12-13=-2954/0, 13-14=-2713/0, 14-15=-2000/0
BOT CHORD	27-28=-117/258, 26-27=-382/356, 25-26=-811/38, 24-25=0/686, 23-24=0/1923, 22-23=0/1923, 21-22=0/2685, 20-21=0/2954, 19-20=0/2932, 18-19=0/2459, 17-18=0/1515
WEBS	4-26=-339/0, 11-21=-289/0, 2-28=-341/155, 2-27=-360/133, 5-25=-748/0, 5-26=0/737, 7-25=-1956/0, 7-24=0/906, 8-24=-857/0, 8-22=0/549, 9-22=-554/0, 9-21=0/609, 15-17=-1663/0, 15-18=0/675, 14-18=-638/0, 14-19=0/353, 13-19=-307/0, 13-20=-235/334

- NOTES**
- Unbalanced floor live loads have been considered for this design.
 - All plates are 3x3 MT20 unless otherwise indicated.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 77 lb uplift at joint 28.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job 72430120	Truss F202	Truss Type Truss	Qty 2	Ply 1	PBS\SMITHFIELD FC RH 2ND FL OW Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Misti Presley

Run: 8.73 S Jul 24 2024 Print: 8.730 S Jul 24 2024 MiTek Industries, Inc. Mon Sep 23 12:13:14

Page: 1

ID:Yy2ANy1BCNjSdVtTK2KQTztScn-meWbE?XxtO8jCry55g1dazV9CG3PsBBkUYZTzYamPZ




Plate Offsets (X, Y): [18:0-2-0,Edge], [32:0-2-0,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFLL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.80	Vert(LL)	-0.25	20-21	>927	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.79	Vert(CT)	-0.35	20-21	>674	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.55	Horz(CT)	0.04	18	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 147 lb	FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 5-6-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS
All bearings 0-3-8.
(lb) - Max Uplift All uplift 100 (lb) or less at joint(s) except 32=332 (LC 4)
Max Grav All reactions 250 (lb) or less at joint(s) 32 except 18=768 (LC 13), 26=1294 (LC 14), 29=609 (LC 13)

FORCES
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=0/504, 3-4=0/1082, 4-5=0/1082, 5-6=0/1245, 6-7=0/1540, 7-8=0/1544, 8-9=972/0, 9-10=-2006/0, 10-11=-2738/0, 11-12=-2738/0, 12-13=-2738/0, 13-14=-2738/0, 14-15=-2575/0, 15-16=-1914/0
BOT CHORD 31-32=-504/0, 30-31=-504/0, 29-30=-504/0, 28-29=-1245/0, 27-28=-1245/0, 26-27=-1245/0, 25-26=0/314, 24-25=0/1598, 23-24=0/1598, 22-23=0/2419, 21-22=0/2738, 20-21=0/2761, 19-20=0/2346, 18-19=0/1457
WEBS 12-22=-296/0, 5-29=-135/272, 6-26=-505/0, 3-29=-845/0, 2-32=0/661, 3-30=0/260, 8-26=-2002/0, 8-25=0/921, 9-25=-876/0, 9-23=0/571, 10-23=-579/0, 10-22=0/626, 16-18=-1599/0, 16-19=0/636, 15-19=-601/0, 15-20=0/319, 14-20=-280/0, 14-21=-252/294

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x3 MT20 unless otherwise indicated.
 - 3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 331 lb uplift at joint 32.
 - 4) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 72430120	Truss F203	Truss Type Truss	Qty 1	Ply 1	PBS/SMITHFIELD FC RH 2ND FL OW Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFPI Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Misti Presley

Run: 8.73 S Jul 24 2024 Print: 8.730 S Jul 24 2024 MiTek Industries, Inc. Mon Sep 23 12:13:14

Page: 1

ID:1VrJsNX24ii?zbtPgwEPdrzS9R2-meWbE?Xxt08jjCry55g1dazUgCHRPsvBkUYZTYamPZ



Scale = 1:51.3

Plate Offsets (X, Y):		[15:0-2-0,Edge], [26:0-2-0,Edge]										
Loading	(psf)	Spacing	1-7-3	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.89	Vert(LL)	-0.27	17-18	>891	480	MT18HS	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.76	Vert(CT)	-0.36	17-18	>648	360	MT20	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.53	Horz(CT)	0.06	15	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 126 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 25-26,24-25,23-24.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS	(lb/size)	15=804/0-3-8, (min. 0-1-8), 23=1370/0-3-8, (min. 0-1-8), 26=48/0-3-8, (min. 0-1-8)
	Max Uplift	26=-188 (LC 4)
	Max Grav	15=807 (LC 7), 23=1370 (LC 1), 26=128 (LC 3)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-50/409, 3-4=0/949, 4-5=0/951, 5-6=-1494/0, 6-7=-2448/0, 7-8=-3058/0, 8-9=-3058/0, 9-10=-3058/0, 10-11=-3058/0, 11-12=-2779/0, 12-13=-2042/0
BOT CHORD	25-26=-409/50, 24-25=-409/50, 23-24=-409/50, 22-23=0/875, 21-22=0/2078, 20-21=0/2814, 19-20=0/2814, 18-19=0/3058, 17-18=0/3014, 16-17=0/2513, 15-16=0/1543
WEBS	8-19=-273/0, 3-23=-811/0, 2-26=-62/540, 5-23=-1930/0, 5-22=0/868, 6-22=-821/0, 6-21=0/522, 7-21=-518/0, 7-19=0/572, 13-15=-1694/0, 13-16=0/694, 12-16=-655/0, 12-17=0/370, 11-17=-339/0, 11-18=-199/380

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) All plates are 3x3 MT20 unless otherwise indicated.
 - 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 188 lb uplift at joint 26.
 - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 7) CAUTION, Do not erect truss backwards.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job 72430120	Truss F204	Truss Type Truss	Qty 3	Ply 1	PBS/SMITHFIELD FC RH 2ND FL OW Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Misti Presley

Run: 8.73 S Jul 24 2024 Print: 8.730 S Jul 24 2024 MiTek Industries, Inc. Mon Sep 23 12:13:15

Page: 1

ID:1VrJsNX24iI?zbpGwEPdRzS9R2-Eq4zRLYaehGaLMQ8foBGAoWftCaH8KcKz8l60?yamPY




Plate Offsets (X, Y): [16:0-2-0,Edge], [23:0-1-8,Edge], [26:0-2-0,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFLL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.89	Vert(LL)	-0.20	24-25	>696	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.92	Vert(CT)	-0.28	24-25	>507	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.42	Horz(CT)	0.04	16	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 125 lb	FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS	(lb/size)
	16=537/0-3-8, (min. 0-1-8), 22=1089/0-3-8, (min. 0-1-8), 26=500/0-3-8, (min. 0-1-8)
	Max Grav 16=544 (LC 7), 22=1089 (LC 1), 26=528 (LC 10)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-1174/0, 3-4=-1150/0, 4-5=-1150/0, 5-6=-1150/0, 6-7=-169/344, 7-8=-169/344, 8-9=-901/0, 9-10=-901/0, 10-11=-1391/0, 11-12=-1391/0, 12-13=-1391/0, 13-14=-919/0
BOT CHORD	25-26=0/947, 24-25=0/1335, 23-24=0/1150, 22-23=-137/617, 21-22=0/544, 20-21=0/1222, 19-20=0/1222, 18-19=0/1391, 17-18=0/1233, 16-17=0/580
WEBS	5-23=-471/0, 6-22=-679/0, 6-23=0/872, 14-16=-770/0, 14-17=0/471, 13-17=-437/0, 13-18=0/328, 2-26=-1038/0, 2-25=0/316, 3-24=-321/0, 8-22=-810/0, 8-21=0/525, 10-21=-498/0, 10-19=0/325

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x3 MT20 unless otherwise indicated.
 - 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backyards.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job 72430120	Truss F205	Truss Type Truss	Qty 4	Ply 1	PBS\SMITHFIELD FC RH 2ND FL OW Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Misti Presley

Run: 8.73 S Jul 24 2024 Print: 8.730 S Jul 24 2024 MiTek Industries, Inc. Mon Sep 23 12:13:15

Page: 1

ID:ViPh4jYgr0QrbIS0qeleA3zS9R1-Eq4zRLYaehGaLMQ8foBGaoWwhcfn8JQKz8l60?yamPY




Plate Offsets (X, Y): [16:0-1-8,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.73	Vert(LL)	-0.33	13-15	>708	480	MT18HS	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.63	Vert(CT)	-0.45	13-15	>513	360	MT20	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.49	Horz(CT)	0.06	11	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 97 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP SS(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS	(lb/size)	11=841/ Mechanical, (min. 0-1-8), 18=841/ Mechanical, (min. 0-1-8)
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD		2-3=-2137/0, 3-4=-3282/0, 4-5=-3282/0, 5-6=-3282/0, 6-7=-2981/0, 7-8=-2981/0, 8-9=-2148/0
BOT CHORD		17-18=0/1616, 16-17=0/2648, 15-16=0/3282, 14-15=0/3249, 13-14=0/3249, 12-13=0/2660, 11-12=0/1617
WEBS		4-16=-288/0, 2-18=-1775/0, 2-17=0/724, 3-17=-711/0, 3-16=0/884, 9-11=-1775/0, 9-12=0/739, 8-12=-712/0, 8-13=0/448, 6-13=-372/0, 6-15=-241/426

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 72430120	Truss F206	Truss Type Truss	Qty 4	Ply 1	PBS/SMITHFIELD FC RH 2ND FL OW Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Misti Presley

Run: 8.73 S Jul 24 2024 Print: 8.730 S Jul 24 2024 MiTek Industries, Inc. Mon Sep 23 12:13:15

Page: 1

ID:ViPh4jYgr0QrblS0qeleA3zS9R1-Eq4zRLYaehGalMQ8foBGAoWesceL8JHKz8l60?yamPY



Scale = 1:44.2

Plate Offsets (X, Y):	[16:0-1-8,Edge]											
Loading	(psf)	Spacing	1-7-3	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.93	Vert(LL)	-0.36	13-15	>656	480	MT18HS	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.66	Vert(CT)	-0.49	13-15	>478	360	MT20	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.06	11	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 98 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP SS(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS	(lb/size)	11=854/ Mechanical, (min. 0-1-8), 18=854/0-3-8, (min. 0-1-8)
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD		2-3=-2182/0, 3-4=-3397/0, 4-5=-3397/0, 5-6=-3397/0, 6-7=-3397/0, 7-8=-3048/0, 8-9=-2189/0
BOT CHORD		17-18=0/1644, 16-17=0/2706, 15-16=0/3397, 14-15=0/3328, 13-14=0/3328, 12-13=0/2714, 11-12=0/1645
WEBS		5-16=-262/0, 2-18=-1805/0, 2-17=0/748, 3-17=-729/0, 3-16=0/927, 9-11=-1806/0, 9-12=0/757, 8-12=-730/0, 8-13=0/464, 7-13=-390/0, 7-15=-220/461

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job 72430120	Truss F207	Truss Type Truss	Qty 3	Ply 1	PBS\SMITHFIELD FC RH 2ND FL OW Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Misti Presley

Run: 8.73 S Jul 24 2024 Print: 8.730 S Jul 24 2024 MiTek Industries, Inc. Mon Sep 23 12:13:15

Page: 1

ID: uz4H3YJcYiDv1COLGtiGzS9R0-Eq4zRLYaehGalMQ8foBGAoWgLceE8J9Kz8l60?yamPY




Plate Offsets (X, Y): [15:0-1-8,Edge], [16:0-1-8,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFLL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.77	Vert(LL)	-0.37	14-15	>646	480	MT18HS 244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.66	Vert(CT)	-0.51	14-15	>469	360	MT20 244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.51	Horz(CT)	0.06	11	n/a	n/a	
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 99 lb FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 5-8-3 oc purlins, except end verticals.
BOT CHORD 2x4 SP SS(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS	(lb/size)
	11=867/0-3-8, (min. 0-1-8), 18=867/0-3-8, (min. 0-1-8)
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-2220/0, 3-4=-3492/0, 4-5=-3492/0, 5-6=-3492/0, 6-7=-3492/0, 7-8=-3120/0, 8-9=-2229/0
BOT CHORD	17-18=0/1671, 16-17=0/2758, 15-16=0/3492, 14-15=0/3418, 13-14=0/2767, 12-13=0/2767, 11-12=0/1672
WEBS	5-16=-282/0, 2-18=-1835/0, 2-17=0/764, 3-17=-748/0, 3-16=0/975, 9-11=-1836/0, 9-12=0/774, 8-12=-749/0, 8-14=0/491, 7-14=-414/0, 7-15=-230/487

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 72430120	Truss F208	Truss Type Truss	Qty 5	Ply 1	PBS/SMITHFIELD FC RH 2ND FL OW Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Misti Presley

Run: 8.73 S Jul 24 2024 Print: 8.730 S Jul 24 2024 MiTek Industries, Inc. Mon Sep 23 12:13:16

Page: 1

ID: uz4H3YJcJYiDv1COLGtiGzS9R0-i0eLfgZCP?ORzW?LDWIWI?2rZ?_VtmXTCo1fYsyamPX



Scale = 1:44.2

Plate Offsets (X, Y):	[15:0-1-8,Edge], [16:0-1-8,Edge]											
Loading	(psf)	Spacing	1-7-3	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.80	Vert(LL)	-0.36	13-15	>651	480	MT18HS	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.66	Vert(CT)	-0.50	13-15	>471	360	MT20	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.06	11	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 98 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 5-3-4 oc purlins, except end verticals.
BOT CHORD	2x4 SP SS(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS	(lb/size)	11=854/0-3-8, (min. 0-1-8), 18=854/ Mechanical, (min. 0-1-8)
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD		2-3=-2175/0, 3-4=-3374/0, 4-5=-3374/0, 5-6=-3374/0, 6-7=-3374/0, 7-8=-3055/0, 8-9=-2187/0
BOT CHORD		17-18=0/1643, 16-17=0/2702, 15-16=0/3374, 14-15=0/3338, 13-14=0/3338, 12-13=0/2713, 11-12=0/1645
WEBS		5-16=-298/0, 2-18=-1804/0, 2-17=0/740, 3-17=-733/0, 3-16=0/926, 9-11=-1806/0, 9-12=0/755, 8-12=-732/0, 8-13=0/475, 7-13=-394/0, 7-15=-250/449

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 72430120	Truss F209	Truss Type Truss	Qty 2	Ply 1	PBS\SMITHFIELD FC RH 2ND FL OW Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Misti Presley

Run: 8.73 S Jul 24 2024 Print: 8.730 S Jul 24 2024 MiTek Industries, Inc. Mon Sep 23 12:13:16

Page: 1

ID:Ex4pb2zljpdRixfGbl4oVuztScl-i0eLfgZCP?ORzW?LDWiWi?2xa?0TptITCo1fYsyamPX



Scale = 1:37.3

Plate Offsets (X, Y): [9:0-2-0,Edge], [14:0-2-0,Edge]

Loading	(psf)	Spacing	1-4-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.42	Vert(LL)	-0.10	12-13	>999	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.54	Vert(CT)	-0.13	12-13	>999	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.29	Horz(CT)	0.03	9	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 75 lb	FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD	TOP CHORD
BOT CHORD	BOT CHORD
WEBS	
OTHERS	

REACTIONS (lb/size) 9=524/ Mechanical, (min. 0-1-8), 14=524/0-3-8, (min. 0-1-8)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1228/0, 3-4=-1552/0, 4-5=-1552/0, 5-6=-1552/0, 6-7=-1224/0

BOT CHORD 13-14=0/970, 12-13=0/1456, 11-12=0/1552, 10-11=0/1460, 9-10=0/969

WEBS 2-14=-1064/0, 2-13=0/359, 3-13=-316/0, 3-12=-30/295, 7-9=-1062/0, 7-10=0/355, 6-10=-329/0, 6-11=-29/354

- NOTES**
- Unbalanced floor live loads have been considered for this design.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 72430120	Truss K200	Truss Type Truss	Qty 1	Ply 1	PBS\SMITHFIELD FC RH 2ND FL OW Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Misti Presley

Run: 8.73 S Jul 24 2024 Print: 8.730 S Jul 24 2024 MiTek Industries, Inc. Mon Sep 23 12:13:16

Page: 1

ID:_uz4H3YJcJYiDv1COLGtiGzS9R0-i0eLfgZCP?ORzW?LDWIWI?205?8fttyTC01fYSyamPX



Loading	(psf)	Spacing	1-7-3	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horiz(TL)	0.00	18	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-R							Weight: 86 lb	FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS All bearings 19-6-0.
 (lb) - Max Grav All reactions 250 (lb) or less at joint(s) 18, 19, 20, 21, 22, 23, 24, 25, 27, 28, 29, 30, 31, 32, 33, 34

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 2) Gable requires continuous bottom chord bearing.
 - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 4) Gable studs spaced at 1-4-0 oc.
 - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 72430120	Truss K201	Truss Type Truss	Qty 1	Ply 1	PBS\SMITHFIELD FC RH 2ND FL OW Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Misti Presley

Run: 8.73 S Jul 24 2024 Print: 8.730 S Jul 24 2024 MiTek Industries, Inc. Mon Sep 23 12:13:16

Page: 1

ID:Ex4pb2zljpdRixfGbl4oVuztSci-i0eLfgZCP?ORzW?LDWIWI?20v?8hhttTC01fYsyamPX



Scale = 1:36.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horiz(TL)	0.00	13	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-R							Weight: 65 lb	FT = 20%F, 11%E

LUMBER
 TOP CHORD 2x4 SP No.2(flat)
 BOT CHORD 2x4 SP No.2(flat)
 WEBS 2x4 SP No.3(flat)
 OTHERS 2x4 SP No.3(flat)

BRACING
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS All bearings 14-8-0.
 (lb) - Max Grav All reactions 250 (lb) or less at joint(s) 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- All plates are 1.5x3 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1'-4" oc.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.

