

Mark Morris, P.E.

#126, 1317-M, Summerville, SC 29483

843 209-5784, Fax (866)-213-4614

The truss drawing(s) listed below have been prepared by **Atlantic Building Components** under my direct supervision based on the parameters provided by the truss designers.

AST #: 53754

JOB: 24-9455-F02

JOB NAME: LOT 0.0026 HONEYCUTT HILLS

Wind Code: N/A

Wind Speed: Vult= N/A

Exposure Category: N/A

Mean Roof Height (feet): N/A

These truss designs comply with IRC 2018 as well as IRC 2021.

26 Truss Design(s)

Trusses:

F201, F202, F203, F204, F205, F206, F207, F208, F210, F211, F212, F213, F214, F215, F216, F217, F218, F219, F220, F222, F223, F227, F228, F229, F230, F231



10/29/2024

Mark Morris


Warning !—Verify design parameters and read notes before use.

This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSL/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI

Job	Truss	Truss Type	Qty	Ply	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC
24-9455-F02	F201	Floor Supported Gable	1	1	Job Reference (optional) # 53754

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 22:59:55 2024 Page 1
 ID:oDuW00MhLxMOj2fwcp2aKqzMG6w-c1u3N9lalvWZ_PdyR9pPHwGt6dRAh1?L2dSA3jyOQT1

Scale = 1:20.6



13-1-14
13-1-14

Plate Offsets (X,Y)-- [6:0-1-8,Edge], [18:0-1-8,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	18	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
								Weight: 56 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)
 OTHERS 2x4 SP No.3(flat)


BRACING-
 TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 13-1-14.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 22, 12, 21, 20, 19, 18, 17, 16, 15, 14, 13

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (6)
 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 2) Gable requires continuous bottom chord bearing.
 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 4) Gable studs spaced at 1-4-0 oc.
 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




10/29/2024


Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F202	Truss Type Floor	Qty 5	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 53754
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 22:59:56 2024 Page 1
ID:oDuWOOMhLxMOj2fwcp2aKqzMG6w-4ESSaUmD3DeQbZn9?tlEq8p?z1exQONUHCj9yOQTH



Scale = 1:21.9



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.31	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.61	Vert(LL) -0.11 11-12 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.41	Vert(CT) -0.14 11-12 >999 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.03 9 n/a n/a		
	Code IRC2021/TPI2014			Weight: 66 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 16=717/0-3-8 (min. 0-1-8), 9=717/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-959/0, 3-4=-1908/0, 4-5=-2215/0, 5-6=-1908/0, 6-7=-959/0
BOT CHORD 15-16=0/298, 14-15=0/1592, 13-14=0/2215, 12-13=0/2215, 11-12=0/2215, 10-11=0/1592, 9-10=0/298
WEBS 4-14=-521/0, 3-14=0/436, 3-15=-825/0, 2-15=0/860, 2-16=-848/0, 5-11=-521/0, 6-11=0/436, 6-10=-825/0, 7-10=0/860, 7-9=-848/0

NOTES- (4)
1) Unbalanced floor live loads have been considered for this design.
2) All plates are 3x4 MT20 unless otherwise indicated.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F203	Truss Type Floor	Qty 4	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 53754
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 22:59:57 2024 Page 1
ID:oDuW00MhLxMOj2fwcp2aKqzMG6w-YQ0qoqmrqWmHDjMLZastMLM8tQwi9qOdVxxH8cyOQTG



Scale = 1:22.6





Plate Offsets (X,Y)-- [1:Edge,0-1-8], [3:0-1-8,Edge], [4:0-1-8,Edge], [15:Edge,0-1-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.43	Vert(LL)	-0.16 10-11	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.83	Vert(CT)	-0.21 10-11	>795	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.49	Horz(CT)	0.03 8	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
								Weight: 69 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 15=752/Mechanical, 8=752/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-15=-749/0, 1-2=-797/0, 2-3=-1949/0, 3-4=-2416/0, 4-5=-2276/0, 5-6=-1510/0
BOT CHORD 13-14=0/1537, 12-13=0/2416, 11-12=0/2416, 10-11=0/2416, 9-10=0/2065, 8-9=0/926
WEBS 3-13=-688/0, 2-13=0/539, 2-14=-964/0, 1-14=0/1025, 4-10=-395/49, 5-10=0/355, 5-9=-723/0, 6-9=0/760, 6-8=-1157/0

NOTES- (5)
1) Unbalanced floor live loads have been considered for this design.
2) All plates are 3x4 MT20 unless otherwise indicated.
3) Refer to girder(s) for truss to truss connections.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



10/29/2024


Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F204	Truss Type Floor	Qty 3	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC	# 53754
--------------------	---------------	---------------------	----------	----------	--	---------

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 22:59:58 2024 Page 1
 ID:oDuW00MhLxMOj2fwcp2aKqzMG6w-0cZC?AnTbqu7rtxX7IN6vZuJVqGwuHmkbhgq2yOQTF



Scale = 1:35.8



2-6-12	3-6-12	4-6-12	5-9-4	6-10-4	12-10-7	13-10-7	14-10-7	21-5-6
2-6-12	1-0-0	1-0-0	1-1-0	1-1-0	5-10-11	1-0-0	1-0-0	6-6-15
Plate Offsets (X,Y)-- [2:0-1-8,Edge], [3:0-1-8,Edge], [8:0-1-8,Edge], [9:0-1-8,Edge]								

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.44	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.84	Vert(LL) -0.16 15-16 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.48	Vert(CT) -0.21 15-16 >826 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.03 13 n/a n/a		
	Code IRC2021/TPI2014				Weight: 106 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 26=275/0-3-8 (min. 0-1-8), 13=742/0-3-6 (min. 0-1-8), 21=1329/0-3-8 (min. 0-1-8)
 Max Grav 26=347(LC 3), 13=753(LC 7), 21=1329(LC 8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-26=-348/0, 1-2=-260/27, 2-3=-506/170, 3-4=-103/494, 4-5=0/822, 5-6=-820/0, 6-7=-820/0, 7-8=-1951/0,
 8-9=-2423/0, 9-10=-2280/0, 10-11=-1512/0
 BOT CHORD 24-25=-170/506, 23-24=-170/506, 22-23=-170/506, 21-22=-822/0, 19-20=0/1532, 18-19=0/1532, 17-18=0/2423,
 16-17=0/2423, 15-16=0/2423, 14-15=0/2068, 13-14=0/927
 WEBS 4-21=-468/0, 2-25=-314/183, 1-25=-36/355, 3-22=-737/0, 4-22=0/512, 8-18=-693/0, 7-18=0/585, 7-20=-961/0,
 5-20=0/999, 5-21=-1066/0, 9-15=-346/52, 10-15=0/323, 10-14=-724/0, 11-14=0/761, 11-13=-1159/0


- NOTES-** (5)
 1) Unbalanced floor live loads have been considered for this design.
 2) All plates are 3x4 MT20 unless otherwise indicated.
 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 4) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.



Scale = 1:39.5




Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge], [9:0-1-8,Edge], [10:0-1-8,Edge]					
LOADING (psf)	SPACING-	CSI.	DEFL.		PLATES GRIP
TCLL 40.0	2-0-0	TC 0.59	in (loc) l/defl L/d		MT20 244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.82	Vert(LL) -0.16 16-17 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.48	Vert(CT) -0.21 16-17 >828 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.04 14 n/a n/a		
	Code IRC2021/TPI2014				Weight: 117 lb FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. (lb/size) 28=428/0-3-8 (min. 0-1-8), 14=745/0-3-6 (min. 0-1-8), 22=1415/0-3-8 (min. 0-1-8)
 Max Grav 28=494(LC 3), 14=755(LC 7), 22=1415(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-28=-485/0, 1-2=-332/0, 2-3=-957/5, 3-4=-966/195, 4-5=-343/559, 5-6=0/858,
 6-7=-846/0, 7-8=-846/0, 8-9=-1972/0, 9-10=-2438/0, 10-11=-2291/0, 11-12=-1517/0
 BOT CHORD 26-27=0/824, 25-26=-195/966, 24-25=-195/966, 23-24=-195/966, 22-23=-858/0,
 20-21=0/1555, 19-20=0/1555, 18-19=0/2438, 17-18=0/2438, 16-17=0/2438, 15-16=0/2076,
 14-15=0/930
 WEBS 4-24=0/283, 5-22=-519/0, 2-27=-641/0, 1-27=0/531, 4-23=-999/0, 5-23=0/648,
 9-19=-671/0, 8-19=0/590, 8-21=-963/0, 6-21=0/1001, 6-22=-1088/0, 10-16=-356/25,
 11-16=0/329, 11-15=-727/0, 12-15=0/764, 12-14=-1162/0

- NOTES-** (5-6)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) CAUTION, Do not erect truss backwards.
 - 5) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - 6) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard




10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F206	Truss Type Floor Supported Gable	Qty 1	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC Job Reference (optional) # 53754
--------------------	---------------	-------------------------------------	----------	----------	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:00 2024 Page 1
ID:oDuWOOmHxMOJ2fwcp2aKqzMG6w-z?hyQspj7R8r4A5wEiPaIze8LMHG4CvAxlyOQQTd



LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES		GRIP			
TCLL	40.0	Plate Grip DOL	2-0-0	TC	0.06	Vert(LL)	n/a	(loc)	-	l/defl	n/a	L/d	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(CT)	n/a	-	n/a	999					
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	5	n/a	n/a					
BCDL	5.0	Code IRC2021/TPI2014		Matrix-P											
Weight: 21 lb FT = 20%F, 11%E															

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)
OTHERS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 4-0-0.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 8, 5, 7, 6

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (5-6)
- Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard




10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F207	Truss Type Floor	Qty 1	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC
					Job Reference (optional) # 53754

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:01 2024 Page 1
ID:oDuWOOMhLxMOj2fwcp2aKqzMG6w-RBFLdCqLtiGiiKg6oQwpXBWtS2U35kCDQZvUHNyOQTc

Scale: 3/8"=1'



	9-8-4	10-8-4	11-8-4	19-0-4
	9-8-4	1-0-0	1-0-0	7-4-0
Plate Offsets (X,Y)--	[7:0-1-8,Edge], [8:0-1-8,Edge], [12:0-1-8,Edge]			

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.20	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.04	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.05	Horz(CT)	0.00	13	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						Weight: 96 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. All bearings 19-0-4.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 24, 13, 19, 18, 20, 23, 17, 14 except 21=312(LC 1), 22=278(LC 1), 15=323(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (4-5)
- 1) All plates are 3x4 MT20 unless otherwise indicated.
 - 2) Gable requires continuous bottom chord bearing.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - 5) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard




10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F208	Truss Type FLOOR	Qty 5	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 53754
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:02 2024 Page 1
ID:oDuWOOMhLxMOj2fwcp2aKqzMG6w-vNpjrYqze3OZJUFIM7R23P3ulRcJq2WNfDf2ppyOQTb



Scale = 1:31.1




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [7:0-1-8,Edge], [8:0-1-8,Edge], [12:0-1-8,Edge], [25:Edge,0-1-8]					
LOADING (psf)	SPACING- 1-4-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.87	Vert(LL) -0.37 19-20 >609 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.93	Vert(CT) -0.51 19-20 >443 360	MT20HS	187/143
BCLL 0.0	Rep Stress Incr NO	WB 0.62	Horz(CT) 0.07 13 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH			Weight: 99 lb FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 5-5-7 oc purlins, except end verticals.
BOT CHORD 2x4 SP SS(flat) *Except* B2: 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat) *Except* W2: 2x4 SP No.2(flat)	

REACTIONS. (lb/size) 25=1402/Mechanical, 13=779/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-25=-1392/0, 12-13=-774/0, 1-2=-1760/0, 2-3=-3021/0, 3-4=-3021/0, 4-5=-3715/0,
5-6=-3715/0, 6-7=-3932/0, 7-8=-3753/0, 8-9=-3153/0, 9-10=-2107/0, 10-11=-2107/0,
11-12=-531/0
BOT CHORD 23-24=0/2665, 22-23=0/2665, 21-22=0/3443, 20-21=0/3956, 19-20=0/3753, 18-19=0/3753,
17-18=0/3753, 16-17=0/2699, 15-16=0/2699, 14-15=0/1384
WEBS 7-19=-294/46, 8-18=-25/315, 1-24=0/2208, 2-24=-1601/0, 7-20=-234/450, 6-21=-309/0,
4-21=0/346, 4-22=-550/0, 2-22=0/520, 8-17=-886/0, 9-17=0/626, 9-15=-756/0,
11-15=0/922, 11-14=-1111/0, 12-14=0/893

- NOTES-** (7-8)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) All plates are 3x4 MT20 unless otherwise indicated.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.
 - 7) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - 8) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 13-25=-7, 1-12=-67
Concentrated Loads (lb)
Vert: 2=-800




10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC
24-9455-F02	F210	Floor Supported Gable	1	1	Job Reference (optional) # 53754

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:03 2024 Page 1
 ID:oDuWOOMhLxMOj2fwcp2aKqzMG6w-NaN52urcPMWQxeqVvrZHcccF5rA2Ze_WutObLFyOQTa

Scale = 1:34.6



22-0-12
22-0-12

Plate Offsets (X,Y)-- [9:0-1-8,Edge], [30:0-1-8,Edge]

LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.06	Vert(LL) n/a - n/a 999	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.01	Vert(CT) n/a - n/a 999		
BCLL 0.0	Rep Stress Incr YES	WB 0.03	Horz(CT) -0.00 29 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH		Weight: 92 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)
 OTHERS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 22-0-12.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 38, 20, 37, 36, 35, 34, 33, 32, 30, 29, 28, 27, 26, 25, 24, 23, 22, 21

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (6-7)
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 2) Gable requires continuous bottom chord bearing.
 - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 4) Gable studs spaced at 1-4-0 oc.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - 7) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard




10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F211	Truss Type Floor	Qty 1	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 53754
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:04 2024 Page 1
ID:oDuW00MhLxMOj2fwcp2aKqzMG6w-rmxTGEsEAgfHZoPhTYUW9q8NnFWZ15mf6X88uiyOQT9



Scale = 1:8.4

LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.26	Vert(LL) -0.00 5 >999 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.05	Vert(CT) -0.00 4-5 >999 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.06	Horz(CT) 0.00 4 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-P		Weight: 21 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-8-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 6=191/0-3-8 (min. 0-1-8), 4=191/Mechanical

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-4=-271/0

NOTES- (3)
1) Refer to girder(s) for truss to truss connections.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.


Job	Truss	Truss Type	Qty	Ply	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC
24-9455-F02	F212	Floor Girder	1	1	

Job Reference (optional) # 53754

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:04 2024 Page 1
ID:oDuW00MhLxMOj2fwcp2aKqzMG6w-rmxTGEsEAgfHZoPhTYUW9q8N3FUP1Yf6X88uiyOQT9



Scale = 1:11.8



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.31	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.19	Vert(LL) -0.01 6 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.27	Vert(CT) -0.01 6-7 >999 360		
BCDL 5.0	Rep Stress Incr NO	Matrix-P	Horz(CT) 0.00 5 n/a n/a		
	Code IRC2021/TPI2014			Weight: 33 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 8=459/0-3-8 (min. 0-1-8), 5=424/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-8=-453/0, 1-2=-443/0, 2-3=-667/0
BOT CHORD 6-7=0/843, 5-6=0/458
WEBS 1-7=0/566, 2-7=-521/0, 3-6=0/272, 3-5=-592/0

NOTES- (5)

- 1) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 2) Use Simpson Strong-Tie THA422 (Single Chord Girder) or equivalent at 2-7-12 from the left end to connect truss(es) F213 (1 ply 2x4 SP) to front face of top chord, skewed 0.0 deg to the right, sloping 0.0 deg. down.
- 3) Fill all nail holes where hanger is in contact with lumber.
- 4) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 5-8=-10, 1-4=-100
Concentrated Loads (lb)
Vert: 2=-186(F)




10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F213	Truss Type FLOOR GIRDER	Qty 1	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 53754
--------------------	---------------	----------------------------	----------	----------	--	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MITek Industries, Inc. Tue Oct 29 23:00:05 2024 Page 1
ID: oDuWOOMhLxMOj2fwcp2aKqzMG6w-JyVrTZtsx_n8Ay_t1G?lh1hTFfqE1WmpLBtiQ8yOQ78



Scale = 1:8.4

LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.53	Vert(LL) -0.00 5 >999 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.09	Vert(CT) -0.00 5 >999 360		
BCLL 0.0	Rep Stress Incr NO	WB 0.14	Horz(CT) 0.00 4 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-P			
				Weight: 25 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 3-5-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 6=837/0-8-0 (min. 0-1-8), 4=287/Mechanical

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-6=-831/0
 BOT CHORD 4-5=0/353
 WEBS 2-4=-627/0

- NOTES-** (6)
- 1) Refer to girder(s) for truss to truss connections.
 - 2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 3) Use Simpson Strong-Tie THA422 (6-16d Girder, 6-10d Truss) or equivalent at 0-6-4 from the left end to connect truss(es) F216 (1 ply 2x4 SP) to back face of top chord, skewed 0.0 deg.to the left, sloping 0.0 deg. down.
 - 4) Fill all nail holes where hanger is in contact with lumber.
 - 5) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 4-6=-10, 1-3=-100
 Concentrated Loads (lb)
 Vert: 7=-769(B)



10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F214	Truss Type Floor Supported Gable	Qty 1	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC Job Reference (optional) # 53754
--------------------	---------------	-------------------------------------	----------	----------	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:06 2024 Page 1
ID:oDuW00MhLxMOj2fwcp2aKqzMG6w-n92EhvtUiHv?o5Y4bzW_EFDIK3Blm?jyardFyayOQT7

Scale = 1:24.8




Plate Offsets (X,Y)-- [7:0-1-8,Edge], [21:0-1-8,Edge]		15-9-6		15-9-6					
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	-0.00	19	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
								Weight: 67 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 15-9-6.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 26, 14, 25, 24, 23, 22, 21, 20, 19, 18, 17, 16, 15

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (6-7)
- All plates are 1.5x3 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard



10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F215	Truss Type Floor	Qty 2	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 53754
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:06 2024 Page 1
ID:oDuW00MhLxMOj2fwcp2aKqzMG6w-n92EhvtUiHv?o5Y4bzW_EFDdX3?HmtlyardFyayOQT7



Scale = 1:26.3





Plate Offsets (X,Y)-- [1:Edge,0-1-8], [3:0-1-8,Edge], [4:0-1-8,Edge]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.63	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.80	Vert(LL) -0.26 13-14 >736 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.57	Vert(CT) -0.35 13-14 >539 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.04 10 n/a n/a		
	Code IRC2021/TPI2014			Weight: 78 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP SS(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 18=861/0-3-6 (min. 0-1-8), 10=861/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-18=-860/0, 1-2=-939/0, 2-3=-2351/0, 3-4=-3060/0, 4-5=-3159/0, 5-6=-2644/0, 6-7=-2644/0, 7-8=-1396/0
BOT CHORD 16-17=0/1796, 15-16=0/3060, 14-15=0/3060, 13-14=0/3060, 12-13=0/3087, 11-12=0/2147, 10-11=0/612
WEBS 3-15=0/333, 4-14=-301/28, 3-16=-972/0, 2-16=0/722, 2-17=-1115/0, 1-17=0/1203, 4-13=-260/330, 5-13=-25/273,
5-12=-566/0, 7-12=0/635, 7-11=-977/0, 8-11=0/1020, 8-10=-1068/0

- NOTES-** (4-5)
- Unbalanced floor live loads have been considered for this design.
 - All plates are 3x4 MT20 unless otherwise indicated.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard



10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [3:0-1-8,Edge], [4:0-1-8,Edge], [10:Edge,0-1-8]		
LOADING (psf) TCLL 40.0 TC DL 10.0 BC LL 0.0 BC DL 5.0	SPACING- 2-0-0 Plate Grip DOL 1.00 Lumber DOL 1.00 Rep Stress Incr YES Code IRC2021/TPI2014	CSI. TC 0.58 BC 0.76 WB 0.56 Matrix-SH
DEFL. in (loc) l/defl L/d Vert(LL) -0.23 13-14 >786 480 Vert(CT) -0.32 13-14 >578 360 Horz(CT) 0.04 10 n/a n/a	PLATES MT20 GRIP 244/190 Weight: 79 lb FT = 20%F, 11%E	

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP SS(flat)
 WEBS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 18=842/0-3-6 (min. 0-1-8), 10=842/Mechanical

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-18=-840/0, 1-2=-915/0, 2-3=-2280/0, 3-4=-2946/0, 4-5=-3000/0, 5-6=-2439/0, 6-7=-2439/0, 7-8=-1142/0
 BOT CHORD 16-17=0/1751, 15-16=0/2946, 14-15=0/2946, 13-14=0/2946, 12-13=0/2901, 11-12=0/1914, 10-11=0/339
 WEBS 3-15=-7/312, 4-14=-280/38, 3-16=-921/0, 2-16=0/688, 2-17=-1088/0, 1-17=0/1172, 4-13=-284/278, 5-13=0/288,
 5-12=-591/0, 7-12=0/670, 7-11=-1005/0, 8-11=0/1045, 8-10=-1000/0

- NOTES-** (5-6)
- Unbalanced floor live loads have been considered for this design.
 - All plates are 3x4 MT20 unless otherwise indicated.
 - Refer to girder(s) for truss connections.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard




10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.



Scale = 1:25.7



	5-2-14 5-2-14	6-2-14 1-0-0	7-2-14 1-0-0	13-1-14 5-11-0	13-3-6 0-1-8	15-5-12 2-2-6
Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge], [8:0-1-8,Edge]						

LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.36	Vert(LL) -0.13 13-14 >999 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.69	Vert(CT) -0.16 13-14 >984 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.46	Horz(CT) 0.03 11 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH			
				Weight: 79 lb	FT = 20%F, 11%E

LUMBER- TOP CHORD 2x4 SP No.1(flat) BOT CHORD 2x4 SP No.1(flat) WEBS 2x4 SP No.3(flat)	BRACING- TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
--	---

REACTIONS. (lb/size) 18=701/0-3-6 (min. 0-1-8), 11=975/0-3-8 (min. 0-1-8)
 Max Grav 18=715(LC 3), 11=975(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-18=-710/0, 1-2=-759/0, 2-3=-1817/0, 3-4=-2196/0, 4-5=-1971/0, 5-6=-1104/0
 BOT CHORD 16-17=0/1459, 15-16=0/2196, 14-15=0/2196, 13-14=0/2196, 12-13=0/1704, 11-12=-84/484
 WEBS 7-11=-284/0, 3-16=-587/0, 2-16=0/476, 2-17=-911/0, 1-17=0/972, 4-13=-496/0, 5-13=0/421, 5-12=-802/0, 6-12=0/831, 6-11=-886/0

- NOTES-** (5-6)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) CAUTION, Do not erect truss backwards.
 - 5) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - 6) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard



10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F218	Truss Type Floor	Qty 1	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 53754
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:09 2024 Page 1
ID:oDuW00MhLxMOj2fwcp2aKqzMG6w-CkkMJxwM?CHafZHeG53hstrB2G49zFuPGprvZvyOQT4



Scale = 1:32.4




Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge]							
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d
TCLL 40.0	Plate Grip DOL	1.00	TC 0.42	Vert(LL)	-0.09 20-21	>999	480
TCDL 10.0	Lumber DOL	1.00	BC 0.60	Vert(CT)	-0.12 20-21	>999	360
BCLL 0.0	Rep Stress Incr	YES	WB 0.45	Horz(CT)	0.02 16	n/a	n/a
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH				
							PLATES
							MT20
							GRIP
							244/190
							Weight: 97 lb
							FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 23=617/0-3-6 (min. 0-1-8), 12=129/0-3-8 (min. 0-1-8), 16=1380/0-3-8 (min. 0-1-8)
Max Uplift 12=-107(LC 3)
Max Grav 23=623(LC 3), 12=272(LC 4), 16=1380(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-23=-616/0, 1-2=-646/0, 2-3=-1479/0, 3-4=-1654/0, 4-5=-1223/0, 7-8=0/1317, 8-9=0/844, 9-10=-298/324
BOT CHORD 21-22=0/1248, 20-21=0/1654, 19-20=0/1654, 18-19=0/1654, 17-18=0/829, 16-17=-815/0, 15-16=-1317/0, 14-15=-552/306, 13-14=-552/306, 12-13=-130/257
WEBS 8-16=-615/0, 3-21=-287/0, 2-21=0/302, 2-22=-783/0, 1-22=0/828, 4-18=-568/0, 5-18=0/524, 5-17=-917/0, 7-17=0/954, 7-16=-997/0, 8-15=0/717, 9-15=-658/0, 9-13=-10/297, 10-13=-252/54, 10-12=-351/177

- NOTES-** (6-7)
- Unbalanced floor live loads have been considered for this design.
 - All plates are 3x4 MT20 unless otherwise indicated.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 107 lb uplift at joint 12.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.
 - Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard



10/29/2024


Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F219	Truss Type Floor	Qty 1	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 53754
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:10 2024 Page 1
ID:oDuW00MhLxMOj2fwcp2aKqzMG6w-gwlkWHx?mWPQHjsrpbwO5OMogQOii8YVTbT5MyOQT3



Scale = 1:32.4



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.42	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.60	Vert(LL) -0.09 20-21 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.45	Vert(CT) -0.12 20-21 >999 360		
BCLD 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.02 16 n/a n/a		
	Code IRC2021/TPI2014			Weight: 97 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)


BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. (lb/size) 23=617/0-3-6 (min. 0-1-8), 12=129/0-3-8 (min. 0-1-8), 16=1380/0-3-8 (min. 0-1-8)
Max Uplift 12=-107(LC 3)
Max Grav 23=623(LC 3), 12=272(LC 4), 16=1380(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-23=-616/0, 1-2=-646/0, 2-3=-1479/0, 3-4=-1654/0, 4-5=-1223/0, 7-8=0/1317, 8-9=0/844, 9-10=-298/324
BOT CHORD 21-22=0/1248, 20-21=0/1654, 19-20=0/1654, 18-19=0/1654, 17-18=0/829, 16-17=-815/0, 15-16=-1317/0, 14-15=-552/306, 13-14=-552/306, 12-13=-130/257
WEBS 8-16=-615/0, 3-21=-287/0, 2-21=0/302, 2-22=-783/0, 1-22=0/828, 4-18=-568/0, 5-18=0/524, 5-17=-917/0, 7-17=0/954, 7-16=-997/0, 8-15=0/717, 9-15=-658/0, 9-13=-10/297, 10-13=-252/54, 10-12=-351/177

- NOTES-** (6-7)
- Unbalanced floor live loads have been considered for this design.
 - All plates are 3x4 MT20 unless otherwise indicated.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 107 lb uplift at joint 12.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.
 - Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard



10/29/2024


Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F220	Truss Type Floor	Qty 3	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC
					# 53754

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:11 2024 Page 1
ID:oDuWOOmHlXMOj2fwcp2aKqzMG6w-86s7kdxXqXHutR1NW69xIxXd4InR9Fhj7K0doyOQT2



Scale = 1:37.5



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.41	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.66	Vert(LL) -0.10 24-25 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.46	Vert(CT) -0.13 24-25 >999 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.02 13 n/a n/a		
	Code IRC2021/TPI2014			Weight: 114 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. (lb/size) 27=611/0-3-6 (min. 0-1-8), 13=379/Mechanical, 20=1500/0-3-8 (min. 0-1-8)
Max Grav 27=647(LC 3), 13=437(LC 4), 20=1500(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-27=-640/0, 12-13=-426/0, 1-2=-676/0, 2-3=-1568/0, 3-4=-1796/0, 4-5=-1418/0,
5-6=-387/371, 6-7=-387/371, 7-8=0/1410, 8-9=0/828, 9-10=-599/250, 10-11=-809/32,
11-12=-373/0
BOT CHORD 25-26=0/1303, 24-25=0/1796, 23-24=0/1796, 22-23=0/1796, 21-22=-150/1057, 20-21=-845/0,
19-20=-1410/0, 18-19=-433/346, 17-18=-433/346, 16-17=-32/809, 15-16=-32/809,
14-15=-32/809
WEBS 8-20=-709/0, 3-25=-291/57, 2-25=0/345, 2-26=-817/0, 1-26=0/865, 4-22=-643/0,
5-22=0/549, 5-21=-935/0, 7-21=0/973, 7-20=-979/0, 10-17=-460/0, 9-17=0/446,
9-19=-844/0, 8-19=0/820, 11-14=-557/67, 12-14=0/498

- NOTES-** (6-7)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Refer to girder(s) for truss to truss connections.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backwards.
 - 6) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - 7) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard




10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F222	Truss Type Floor	Qty 13	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 53754
--------------------	---------------	---------------------	-----------	----------	--	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:12 2024 Page 1
ID:oDuW00MhLxMoj2fwcp2aKqzMG6w-cJQVxzyFI7f8W00DxEoTWTIDT1DAemryn4aAEyOQT1



Scale = 1:26.4




Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge]				
LOADING (psf)	SPACING- 1-4-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.42	Vert(LL) -0.18 13-14 >999 480	MT20 244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.83	Vert(CT) -0.25 13-14 >755 360	
BCLL 0.0	Rep Stress Incr YES	WB 0.38	Horz(CT) 0.03 10 n/a n/a	
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH		Weight: 79 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 18=576/0-3-6 (min. 0-1-8), 10=576/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-18=-575/0, 1-2=-628/0, 2-3=-1575/0, 3-4=-2049/0, 4-5=-2117/0, 5-6=-1779/0, 6-7=-1779/0, 7-8=-951/0
 BOT CHORD 16-17=0/1200, 15-16=0/2049, 14-15=0/2049, 13-14=0/2049, 12-13=0/2074, 11-12=0/1449, 10-11=0/430
 WEBS 3-16=-649/0, 2-16=0/488, 2-17=-746/0, 1-17=0/804, 5-12=-376/0, 7-12=0/421, 7-11=-649/0, 8-11=0/678, 8-10=-723/0

- NOTES-** (4-5)
- Unbalanced floor live loads have been considered for this design.
 - All plates are 3x4 MT20 unless otherwise indicated.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard



10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC
24-9455-F02	F223	Floor	2	1	
					# 53754

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:13 2024 Page 1
 ID:oDuW00MhLxMOj2fwcp2aKqzMG6w-4Vzt9lzt3Rn?8AbQVx8d0j0vNtSEv5x_BRp7igyOQT0



Scale = 1:22.6





Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge]

LOADING (psf)	SPACING-	1-4-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.27	Vert(LL)	-0.10 10-11	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.53	Vert(CT)	-0.13 10-11	>999	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.32	Horz(CT)	0.02 8	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
								Weight: 67 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 15=495/0-3-6 (min. 0-1-8), 8=495/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-15=-492/0, 1-2=-528/0, 2-3=-1278/0, 3-4=-1571/0, 4-5=-1460/0, 5-6=-929/0
 BOT CHORD 13-14=0/1014, 12-13=0/1571, 11-12=0/1571, 10-11=0/1571, 9-10=0/1308, 8-9=0/531
 WEBS 3-13=-438/0, 2-13=0/347, 2-14=-633/0, 1-14=0/676, 4-10=-275/13, 5-9=-494/0, 6-9=0/518, 6-8=-706/0

- NOTES-** (4-5)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - 5) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard




10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F227	Truss Type Floor Supported Gable	Qty 1	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC Job Reference (optional) # 53754
--------------------	---------------	-------------------------------------	----------	----------	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:14 2024 Page 1
ID:oDuW00MhLxMOj2fwcp2aKqzMG6w-YhXFMe_VqlvslKAc3ftsZxZ7JHwdedi8Q5ZgE7yOQT?

Scale = 1:19.6



12-5-14
12-5-14

Plate Offsets (X,Y)-- [6:0-1-8,Edge], [18:0-1-8,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	-0.00	17	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH							
									Weight: 54 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)
OTHERS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 12-5-14.
(lb) - Max Uplift All uplift 100 lb or less at joint(s) 12
Max Grav All reactions 250 lb or less at joint(s) 22, 12, 21, 20, 19, 18, 17, 16, 15, 14, 13

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (7)
1) All plates are 1.5x3 MT20 unless otherwise indicated.
2) Gable requires continuous bottom chord bearing.
3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
4) Gable studs spaced at 1-4-0 oc.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 12.
6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F228	Truss Type Floor	Qty 3	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 53754
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:15 2024 Page 1
ID:oDuWOOMhLxMOj2fwcp2aKqzMG6w-0t5dZ__7a21jNUkocMA5585Bah6ANy6HellEmZyOQT_

0-5-4 1-3-0

2-0-0

0-5-8

Scale = 1:32.9




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [7:0-1-8,Edge], [8:0-1-8,Edge], [25:Edge,0-1-8]

LOADING (psf)	SPACING-	1-7-3	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.54	Vert(LL)	-0.36	20	>660	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.69	Vert(CT)	-0.50	20	>480	360	MT20HS	187/143
BCLL 0.0	Rep Stress Incr	YES	WB 0.54	Horz(CT)	0.07	14	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH							
									Weight: 102 lb	FT = 20%F, 11%E

LUMBER-

TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP SS(flat) *Except*
B2: 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 25=872/Mechanical, 14=872/0-3-8 (min. 0-1-8)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-25=-872/0, 1-2=-442/0, 2-3=-2137/0, 3-4=-3356/0, 4-5=-3356/0, 5-6=-3356/0, 6-7=-3980/0, 7-8=-4104/0,
8-9=-3723/0, 9-10=-2828/0, 10-11=-2828/0, 11-12=-1321/0
BOT CHORD 23-24=0/1407, 22-23=0/2842, 21-22=0/3800, 20-21=0/4104, 19-20=0/4104, 18-19=0/4104, 17-18=0/3387, 16-17=0/3387,
15-16=0/2164, 14-15=0/457
WEBS 7-21=-468/166, 6-21=0/378, 6-22=-567/0, 3-22=0/657, 3-23=-917/0, 2-23=0/950, 2-24=-1256/0, 1-24=0/931,
8-18=-689/0, 9-18=0/517, 9-16=-713/0, 11-16=0/848, 11-15=-1097/0, 12-15=0/1124, 12-14=-1023/0

NOTES- (6-7)

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are MT20 plates unless otherwise indicated.
- 3) All plates are 3x4 MT20 unless otherwise indicated.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 6) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
- 7) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard




10/29/2024

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F229	Truss Type Floor	Qty 6	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC	# 53754
--------------------	---------------	---------------------	----------	----------	--	---------

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:16 2024 Page 1
 ID:oDuW00MhLxMOj2fwcp2aKqzMG6w-V4f0nK?ILM9a?eJ?A3hKeMeLb5RC6RqQtP2nl?yOQSZ



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.59	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.77	Vert(LL) -0.26 16-17 >760 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.44	Vert(CT) -0.36 16-17 >554 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.04 11 n/a n/a		
	Code IRC2021/TPI2014			Weight: 84 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP SS(flat) *Except*
 B2: 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 21=726/Mechanical, 11=726/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-21=-725/0, 10-11=-730/0, 1-2=-363/0, 2-3=-1710/0, 3-4=-1710/0, 4-5=-2559/0, 5-6=-2559/0, 6-7=-2831/0, 7-8=-2622/0, 8-9=-1921/0, 9-10=-661/0
 BOT CHORD 19-20=0/1154, 18-19=0/2237, 17-18=0/2855, 16-17=0/2622, 15-16=0/2622, 14-15=0/2622, 13-14=0/1395, 12-13=0/1395
 WEBS 7-16=-301/0, 8-15=0/327, 7-17=-128/410, 6-18=-377/0, 4-18=0/412, 4-19=-686/0, 2-19=0/724, 2-20=-1029/0, 1-20=0/764, 8-14=-924/0, 9-14=0/685, 9-12=-955/0, 10-12=0/926

NOTES- (5-6)
 1) Unbalanced floor live loads have been considered for this design.
 2) All plates are 3x4 MT20 unless otherwise indicated.
 3) Refer to girder(s) for truss to truss connections.
 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 5) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 6) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard



10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 24-9455-F02	Truss F230	Truss Type Floor	Qty 3	Ply 1	LOT 0.0026 HONEYCUTT HILLS 437 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 53754
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.430 s Feb 12 2021 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Oct 29 23:00:16 2024 Page 1
ID:oDuW00MhLxMOj2fwcp2aKqzMG6w-V4f0nK?ILM9a?eJ?A3hKeMeOB5P76R3QtP2nl?yOQsZ



Scale = 1:24.7




Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge], [8:0-1-8,Edge]					
LOADING (psf)	SPACING- 1-7-3	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.42	Vert(LL) -0.17 12-13 >999 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.84	Vert(CT) -0.23 12-13 >772 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.43	Horz(CT) 0.03 9 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH			
				Weight: 74 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 17=646/0-3-6 (min. 0-1-8), 9=646/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-17=-645/0, 8-9=-644/0, 1-2=-699/0, 2-3=-1727/0, 3-4=-2198/0, 4-5=-2181/0, 5-6=-1669/0, 6-7=-1669/0, 7-8=-558/0
BOT CHORD 15-16=0/1338, 14-15=0/2198, 13-14=0/2198, 12-13=0/2198, 11-12=0/2067, 10-11=0/1219
WEBS 3-15=-663/0, 2-15=0/506, 2-16=-833/0, 1-16=0/895, 4-12=-261/150, 5-12=0/252, 5-11=-509/0, 7-11=0/573, 7-10=-861/0, 8-10=0/797

- NOTES-** (4-5)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - 5) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard



10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.



Scale = 1:30.3




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [3:0-1-8,Edge], [4:0-1-8,Edge]		
LOADING (psf) TCLL 40.0 TC DL 10.0 BC LL 0.0 BC DL 5.0	SPACING- Plate Grip DOL 1.00 Lumber DOL 1.00 Rep Stress Incr YES Code IRC2021/TPI2014	CSI. TC 0.80 BC 0.90 WB 0.54 Matrix-SH
DEFL. in (loc) l/defl L/d Vert(LL) -0.35 17-18 >620 480 Vert(CT) -0.48 17-18 >451 360 Horz(CT) 0.05 12 n/a n/a	PLATES MT20 GRIP 244/190 Weight: 90 lb FT = 20%F, 11%E	

LUMBER- TOP CHORD 2x4 SP No.1(flat) BOT CHORD 2x4 SP SS(flat) *Except* B2: 2x4 SP No.1(flat) WEBS 2x4 SP No.3(flat)	BRACING- TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals. BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
--	--

REACTIONS. (lb/size) 22=793/0-3-6 (min. 0-1-8), 12=793/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-22=-795/0, 1-2=-880/0, 2-3=-2261/0, 3-4=-3062/0, 4-5=-3379/0, 5-6=-3223/0, 6-7=-3223/0, 7-8=-2533/0, 8-9=-2533/0, 9-10=-1237/0

BOT CHORD 20-21=0/1677, 19-20=0/3062, 18-19=0/3062, 17-18=0/3062, 16-17=0/3467, 15-16=0/2976, 14-15=0/1977, 13-14=0/1977, 12-13=0/476

WEBS 3-19=0/383, 4-18=-357/0, 3-20=-1056/0, 2-20=0/761, 2-21=-1037/0, 1-21=0/1127, 4-17=-84/546, 5-16=-318/0, 7-16=0/321, 7-15=-565/0, 9-15=0/710, 9-13=-963/0, 10-13=0/991, 10-12=-949/0

- NOTES-** (4-5)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
 - 5) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard



10/29/2024

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.