

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: BLAKE POND

LOT 130

INITIAL SYSTEM: APPROVED 25% REDUCTION

REPAIR: APPROVED 25% REDUCTION

DISTRIBUTION: P-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION PC 130/131

NO. BEDROOMS: 4

LTAR 0.35 GPD/FT²

SEPTIC TANK SIZE: 1000

PUMP TANK SIZE: 1000

LINE	FLAG COLOR	ELEVATION	LENGTH
------	------------	-----------	--------

1	R	100.60	90'
2	G	99.92	90'
3	R	99.92	90'
4	G	99.50	90'
			<u>360'</u>

5	R	99.25	90'
6	G	98.75	90'
7	R	98.34	90'
8	G	97.92	90'
			<u>360'</u>

INITIAL SYSTEM

BY: M EAKER

DATE 12/2022

TYPICAL PROFILE

0-10 LI (VF₁, wgs)
10-36+ SCL (F₁, sbll)
CR 2 ≥ 34"
INITIAL AT 18"

THERE SHALL BE NO GRADING,
CUTTING, LOGGING OR OTHER SOIL
DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.
 DESIGNS DO NOT GURANTEE FUNCTIONALITY

Southeastern Soil & Environmental Associates, Inc.

P.O. Box 9321
Fayetteville, NC 28311
Phone/Fax (910) 822-4540
Email mike@southeasternsoil.com

