

51 W Sawyer Ln
 2-Bedroom Septic Proposal
 Harnett County, NC (PIN#:0588-87-8727)
 TNT of Coats, LLC

*Not a Survey
 Sketched from Public Records



System: Pump to serial
 Lines: 4-6 (220')
 Proposed LTAR - 0.35 LTAR
 15" Trench Bottom
 Accepted Status System
 Repair: Pressure Manifold
 Lines: 1-3 (150')
 0.35 LTAR
 18" Max Trench Bottom
 PPBPS - (50% reduction system)

****1000 Gallon Septic and Pump Tank**
 Tank and trenches to be located minimum of 10'
 from any property line and minimum of 5'
 from any building foundation.
 *Do Not Cut, Fill, or Alter Drainfield or Repair Area
 *Comply with all setbacks

GRAPHIC SCALE
 1" = 100'



Adams
 Soil Consulting
 919-414-6761
 Project #1551

51 W Sawyer Ln
2-Bedroom Septic Proposal
Harnett County, NC (PIN#:0588-87-8727)
TNT of Coats, LLC

*Not a Survey
Sketched from Public Records

Grace Road

- #1 - Pink 35'
- #2 - Orange 50'
- #3 - Blue 65'
- #4 Yellow 80'
- #5 - Purple 80'
- #6 Pink 50'

WA Sawyer Ln

System: Pump to serial
Lines: 4-6 (220')
Proposed LTAR - 0.35 LTAR
15" Trench Bottom
Accepted Status System
Repair: Pressure Manifold
Lines: 1-3 (150')
0.35 LTAR
18" Max Trench Bottom
PPBPS - (50% reduction system)

**1000 Gallon Septic and Pump Tank
Tank and trenches to be located minimum of 10'
from any property line and minimum of 5'
from any building foundation.
*Do Not Cut, Fill, or Alter Drainfield or Repair Area
*Comply with all setbacks

GRAPHIC SCALE
1" = 50'



Adams
Soil Consulting
919-414-6761
Project #1551