



Wasco-Seal® Plus

Flexible Membrane

Key Properties

- ARC coating surface for better adhesion to sealants and adhesives
- Better than Wasco-Seal
 - 5 times the breaking strength
 - 7 times the burst strength
 - 14 times the tear strength
 - 3.6 times the puncture resistance
- No plasticizers
 - Does not become brittle or crack
- Flexible, easy to cut and form by hand
- 3-year UV exposure: to prevent damage, the product must be concealed within 180 days



Certified to
NSF/ANSI/CAN 61

Available in:
12", 16", 18", 24", 36" x 150'
Custom sizes upon request.

Description

Wasco-Seal® Plus has been designed with a flexible sheet of waterproof, cross woven polyethylene with an ARC coating. The ARC provides UV resistance, and a great surface for sealants and adhesives to adhere to.

Compatible With

- Air barriers
- Below grade waterproofing
- Roofing membranes
- Construction sealants and adhesives

Joining of Material

Joint shall be made by lapping a minimum of 6" and coating the contacting surfaces with a construction adhesive or sealant, like York's UniverSeal US-100.

	Wasco-Seal® Plus	Wasco Seal® (Original)
Abrasion, Tear and Puncture Resistant		
Sealant and Adhesive Compatibility		
Long-Term Flexibility		
UV Exposure		
Ease of Installation		
Longevity		
Price		

BEST VALUE