

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Rolling Springs

LOT 126

INITIAL SYSTEM: <sup>Pump</sup> APPROVED 25% REDUCTION

REPAIR <sup>Pump</sup> Approved 25% Reduction

DISTRIBUTION: D-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION BC IRON 126 mid

NO. BEDROOMS: 4

LTAR 0.5 gpd/ft<sup>2</sup>

LINE	FLAG COLOR	ELEVATION	LENGTH
1a	Y	99.67	50
2a	P	99.67	50
3a	Y	97.93	50
4a	P	96.91	50
5a	Y	96.25	50
			250

1b	Y	99.67	50
2b	P	99.67	50
3b	Y	97.93	50
4b	P	96.91	50
5b	Y	96.25	50
			250

BY B.C. Raynor

DATE 11/11/2022

TYPICAL PROFILE

THERE SHALL BE NO GRADING,

0-12 ls vfr. gran

CUTTING, LOGGING OR OTHER SOIL

12-36 scl firm SBK

DISTURBANCE IN SEPTIC AREA

Am/cr2 ≥ 36"

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

# Southeastern Soil & Environmental Associates, Inc.

P.O. Box 9321  
Fayetteville, NC 28311  
Phone/Fax (910) 822-4540  
Email [mike@southeasternsoil.com](mailto:mike@southeasternsoil.com)

