SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Rolling Springs

LOT 127

INITIAL SYSTEM: Pump APPROVED 25% REDUCTION

REPAIR Pump Approved 25% Reduction

DISTRIBUTION: D-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION BC IRON 126/127

NO. BEDROOMS: 4

LTAR 0.6 gpd/ft²

	LINE	FLAG COLOR	ELEVATION	LENGTH
I	1	B	100.50	100
	2	P	100.33	100
				200
R	3	W	100.09	100
	4	P	99.93	100
				200

BY B. C. Raynor

DATE 11/11/2022

TYPICAL PROFILE

0-22 ls vfri gran

22-48 sloam fri gran

Pm/Cm2 ≥ 48"

THERE SHALL BE NO GRADING, CUTTING, LOGGING OR OTHER SOIL DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GURANTEE FUNCTIONALITY