SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Rolling Springs

LOT 130

INITIAL SYSTEM: Pump APPROVED 25% REDUCTION

REPAIR Pump Approved 25% Reduction

DISTRIBUTION: D-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION BC IRON 129/130

NO. BEDROOMS: 4

LTAR 0.9 gpd/ft²

	LINE	FLAG COLOR	ELEVATION	LENGTH
I	1	B	98.33	75
	2	Y	98.25	75
				150
R	3	B	98.00	75
	4	Y	97.93	75
				150

BY B.C. Raynor

DATE 11/11/2022

TYPICAL PROFILE

0-32 LS vfri gran

32-48 Sloam fri gran

Pm/CR2 ≥ 48"

THERE SHALL BE NO GRADING, CUTTING, LOGGING OR OTHER SOIL DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GURANTEE FUNCTIONALITY.