

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Rolling Springs
INITIAL SYSTEM: Pump to APPROVED 25% REDUCTION
DISTRIBUTION: D-Box
BENCHMARK: 100.0
NO. BEDROOMS: 4

LOT 131
REPAIR: Pump to APPROVED 25% REDUCTION
DISTRIBUTION D-Box
LOCATION BC IRON 130/131
LTAR 0.9 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
<u>1</u>	<u>P</u>	<u>99.25</u>	<u>75</u>
<u>2</u>	<u>Y</u>	<u>99.25</u>	<u>75</u>
			<u>150</u>
<u>3</u>	<u>B</u>	<u>97.75</u>	<u>75</u>
<u>4</u>	<u>W</u>	<u>97.41</u>	<u>75</u>
			<u>150</u>

BY B.C. Raynor
TYPICAL PROFILE
0-39 LS vfri gran
39-48 sloam fri gran
pm/cr2 \geq 48"

DATE 11/11/2022
THERE SHALL BE NO GRADING,
CUTTING, LOGGING OR OTHER SOIL
DISTURBANCE IN SEPTIC AREA
HEALTH DEPARTMENT USE ONLY.
DESIGNS DO NOT GUARANTEE FUNCTIONALITY