






FRONT ELEVATION  
SCALE 1/4" = 1'-0"



REAR ELEVATION  
SCALE 1/8" = 1'-0"



LEFT ELEVATION  
SCALE 1/8" = 1'-0"



RIGHT ELEVATION  
SCALE 1/8" = 1'-0"


THE CHARLESTON  
LEFT REAR PORCH  
POPE BUILDERS, LLC

HEATED FOOTAGE:  
#1270

SQUARE FOOTAGE:  
FIRST FLOOR = 1270  
FRONT PORCH = 240  
REAR PORCH = 50

HEATHER HALL  
165 HEATHERSTONE CT  
BENSON NC 27504  
(919) 207-1403

H SQUARED HOME DESIGN, INC.




ANY DEVIATION OF THE SPECIFIED REQUIREMENTS IS THE RESPONSIBILITY OF THE CLIENT AND NOT H SQUARED HOME DESIGN, INC.'S LIABILITY. THIS PLAN HAS BEEN DRAWN IN ACCORDANCE WITH NORTH CAROLINA BUILDING CODES 2018 EDITION.

DATE: 03/10/2023

1 STORY

FILE: 030123



A  
8" FOUN.  
STEM WALL  
ON MIN. 1/2"X8"  
CONC. FTG.


4" CONC. SLAB (TABLE R402.2) w/  
FIBERMESH OR WIREMESH ON 1/8 MIL  
VAPOR RETARDER (AS REQUIRED)  
ON BASE COURSE (R506.2.2). SEE  
R506.2.1 FOR FILL REQUIREMENTS.

4" CONC.  
PORCH  
SLAB

4" CONC.  
PORCH  
SLAB

REFER TO BASIC DETAIL SHEET(S)  
FOR STANDARD DETAILS, BRACING  
DETAILS, AND STRUCTURAL NOTES

FOUNDATION PLAN  
SCALE 1/4" = 1'-0"



THE CHARLESTON  
LEFT REAR PORCH  
POPE BUILDERS, LLC

HEATED FOOTAGE:  
#1270

SQUARE FOOTAGE:  
FIRST FLOOR = 1270  
FRONT PORCH = 240  
REAR PORCH = 50

HEATHER HALL  
165 HEATHERSTONE CT  
BENSON NC 27504  
(919) 207-1403


H SQUARED  
HOME  
DESIGN, INC.  
**HS**

ANY DEVIATION OF THE  
SPECIFIED REQUIREMENTS  
BY H SQUARED HOME  
DESIGN, INC.'S LIABILITY.  
THIS PLAN HAS BEEN DRAWN  
IN ACCORDANCE WITH NORTH  
CAROLINA BUILDING CODES 2018 EDITION.

DATE:  
03/10/2023


1 STORY

FILE:  
030123



REFER TO BASIC DETAIL SHEET(S)  
FOR STANDARD DETAILS, BRACING  
DETAILS, AND STRUCTURAL NOTES

**FIRST FLOOR PLAN**  
SCALE 1/4" = 1'-0"



**THE CHARLESTON**  
LEFT REAR PORCH  
**POPE BUILDERS, LLC**

HEATED FOOTAGE:  
**#1270**

SQUARE FOOTAGE:  
FIRST FLOOR = 1270  
FRONT PORCH = 240  
REAR PORCH = 50

HEATHER HALL  
165 HEATHERSTONE CT  
BENSON NC 27504  
(919) 207-1403


**H SQUARED HOME DESIGN, INC.**

ANY DEVIATION OF THE THIS  
OR DIMENSIONS VOID  
INC'S LIABILITY.  
THIS PLAN HAS BEEN DRAWN  
FOR THE PROJECT AND IS NOT  
TO BE USED FOR ANY OTHER  
BUILDING CODES 2018 EDITION.

DATE:  
03/10/2023

1 STORY

FILE:  
030123




**ATTIC VENTILATION:**

THE NET FREE VENTILATING AREA SHALL BE NOT LESS THAN 1 TO 150 OF THE AREA OF THE SPACE VENTILATED EXCEPT THAT THE AREA MAY BE 1 TO 300, PROVIDED AT LEAST 50 PERCENT OF THE REQUIRED VENTILATING AREA IS PROVIDED BY VENTILATORS LOCATED IN THE UPPER PORTION OF THE SPACE TO BE VENTILATED AT LEAST 3 FEET ABOVE EAVE OR CORNICE VENTS WITH THE BALANCE OF THE REQUIRED VENTILATION TO BE PROVIDED BY EAVE OR CORNICE VENTS.

GROSS ATTIC AREA TO BE VENTILATED 1540 SQ.FT.  
 1540/150 = 10.4 SQ.FT. NET FREE AREA

REFER TO BASIC DETAIL SHEET(S)  
 FOR STANDARD DETAILS, BRACING  
 DETAILS, AND STRUCTURAL NOTES

**ROOF PLAN**  
 SCALE 1/4" = 1'-0"




**THE CHARLESTON**  
 LEFT REAR PORCH  
 POPE BUILDERS, LLC

HEATED FOOTAGE:  
**#1270**

SQUARE FOOTAGE:  
 FIRST FLOOR = 1270  
 FRONT PORCH = 240  
 REAR PORCH = 50

HEATHER HALL  
 165 HEATHERSTONE CT  
 BENSON NC 27504  
 (919) 207-1403

**H SQUARED HOME DESIGN, INC.**



ANY DEVIATION OF THE SPECIFIED REQUIREMENTS BY H SQUARED HOME DESIGN, INC.'S LIABILITY.  
 THIS PLAN HAS BEEN DRAWN IN ACCORDANCE WITH NORTH CAROLINA BUILDING CODES 2008 EDITION.

DATE:  
 03/10/2023

1 STORY

FILE:  
 030123

# STRUCTURAL NOTES

1) ALL CONSTRUCTION SHALL CONFORM TO THE LATEST REQUIREMENTS OF THE NORTH CAROLINA STATE RESIDENTIAL CODE - 2018 EDITION, PLUS ALL LOCAL CODES AND REGULATIONS. THE STRUCTURAL ENGINEER OR DESIGNER IS NOT RESPONSIBLE FOR, AND WILL NOT HAVE CONTROL OF, CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES, OR FOR SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE CONSTRUCTION WORK. NOR WILL THE ENGINEER OR DESIGNER BE RESPONSIBLE FOR THE CONTRACTOR'S FAILURE TO CARRY OUT THE CONSTRUCTION WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. "CONSTRUCTION REVIEW" SERVICES ARE NOT PART OF OUR CONTRACT. ALL MEMBERS SHALL BE FRAMED, ANCHORED, TIED AND BRACED IN ACCORDANCE WITH GOOD CONSTRUCTION PRACTICE AND THE BUILDING CODE.

	LIVE LOAD (PSF)	DEAD LOAD (PSF)	DEFLECTION (LL)
ROOMS OTHER THAN SLEEPING ROOMS	40	10	L/360
SLEEPING ROOMS	30	10	L/360
ATTIC WITH PERMANENT STAIR	40	10	L/360
ATTIC WITH OUT PERMANENT STAIR	20	10	L/360
ATTIC WITH OUT STORAGE	10	10	L/240
STAIRS	40	---	L/360
EXTERIOR BALCONIES	60	10	L/360
DECKS	40	10	L/360
GUARDRAILS AND HANDRAILS	200	---	---
PASSENGER VEHICLE GARAGES	50	10	L/360
FIRE ESCAPES	40	10	L/360
SNOW	20	---	---
WIND LOAD (BASED ON 115/120 MPH WIND VELOCITY & EXPOSURE B)			

- 3) WALL BRACING: BRACED WALL PANELS SHALL BE CONSTRUCTED ACCORDING TO SECTION R602.10.3. THE AMOUNT AND LOCATION OF BRACING SHALL COMPLY WITH TABLE R602.10.1. THE LENGTH OF BRACED PANELS SHALL BE DETERMINED BY SECTION R602.10.4. LATERAL BRACING SHALL BE SATISFIED PER METHOD 3 BY CONTINUOUSLY SHEATHING WALLS WITH STRUCTURAL SHEATHING PER SECTION R602.10.3. NOTE THAT ANY SPECIFIC BRACED WALL DETAIL SHALL BE INSTALLED AS SPECIFIED.
- 4) CONCRETE SHALL HAVE A MINIMUM 28 DAY STRENGTH OF 3000 PSI AND A MAXIMUM SLUMP OF 5 INCHES UNLESS NOTED OTHERWISE (UNO). AIR ENTRAINED PER TABLE 402.2. ALL CONCRETE SHALL BE PROPORTIONED, MIXED, HANDLED, SAMPLED, TESTED, AND PLACED IN ACCORDANCE WITH ACI STANDARDS. ALL SAMPLES FOR PUMPING SHALL BE TAKEN FROM THE EXIT END OF THE PUMP.
- 5) ALLOWABLE SOIL BEARING PRESSURE ASSUMED TO BE 2000 PSF. THE CONTRACTOR MUST CONTACT A GEOTECHNICAL ENGINEER AND THE STRUCTURAL ENGINEER IF UNSATISFACTORY SUBSURFACE CONDITIONS ARE ENCOUNTERED. THE SURFACE AREA ADJACENT TO THE FOUNDATION WALL SHALL BE PROVIDED WITH ADEQUATE DRAINAGE, AND SHALL BE GRADED SO AS TO DRAIN SURFACE WATER AWAY FROM FOUNDATION WALLS.
- 6) ALL FRAMING LUMBER SHALL BE SPF #2 (Fb = 875 PSI) UNLESS NOTED OTHERWISE (UNO). ALL TREATED LUMBER SHALL BE SYP #2 (Fb=975 PSI). PLATE MATERIAL MAY BE SPF #3 OR SYP #3 (Fcp(perm) = 425 PSI - MIN).
- 7) ALL WOODEN BEAMS AND HEADERS SHALL HAVE THE FOLLOWING END SUPPORTS: (1) 2x4 STUD COLUMN FOR 4'-0" MAX. BEAM SPAN (UNO), (2) 2x4 STUDS FOR BEAM SPAN GREATER THAN 4'-0" (UNO).
- 8) L.V.L. SHALL BE LAMINATED VENEER LUMBER: Fb=2400 PSI, Fv=285 PSI, E=1.9x10<sup>6</sup> PSI. P.S.L. SHALL BE PARALLEL STRAND LUMBER: Fb=2900 PSI, Fv=290 PSI, E=2.0x10<sup>6</sup> PSI. L.S.L. SHALL BE LAMINATED STRAND LUMBER: Fb=2250 PSI, Fv=400 PSI, E=1.55x10<sup>6</sup> PSI. INSTALL ALL CONNECTIONS PER MANUFACTURERS INSTRUCTIONS.
- 9) ALL ROOF TRUSS AND I-JOIST LAYOUTS SHALL BE PREPARED IN ACCORDANCE WITH ANY SEALED STRUCTURAL DRAWINGS. TRUSSES AND I-JOISTS SHALL BE INSTALLED ACCORDING TO THE MANUFACTURE'S SPECIFICATIONS. ANY CHANGE IN TRUSS OR I-JOIST LAYOUT SHALL BE COORDINATED WITH DESIGNER OR ENGINEER.
- 10) ALL STRUCTURAL STEEL SHALL BE ASTM A-36. STEEL BEAMS SHALL BE SUPPORTED AT EACH END WITH A MINIMUM BEARING LENGTH OF 3 1/2" INCHES AND FULL FLANGE WIDTH. PROVIDE SOLID BEARING FROM BEAM SUPPORT TO FOUNDATION. BEAMS SHALL BE ATTACHED TO EACH SUPPORT WITH TWO LAG SCREWS (1/2" DIAMETER x 4" LONG). LATERAL SUPPORT IS CONSIDERED ADEQUATE PROVIDED THE JOIST ARE TOE NAILED TO THE SOLE PLATE, AND SOLE PLATE IS NAILED OR BOLTED TO THE BEAM FLANGE @ 48" O.C. . ALL STEEL TUBING SHALL BE ASTM A500.
- 11) REBAR SHALL BE DEFORMED STEEL, ASTM#65, GRADE 60.
- 12) FLITCH BEAMS SHALL BE BOLTED TOGETHER USING (2) ROWS OF 1/2" DIAMETER BOLTS (ASTM A307) WITH WASHERS PLACED UNDER THE THREADED END OF BOLT. BOLTS SHALL BE SPACED AT 24" O.C. (MAX), AND STAGGERED AT THE TOP AND BOTTOM OF BEAM (2" EDGE DISTANCE), WITH 2 BOLTS LOCATED AT 4" FROM EACH END.
- 13) BRICK LINTELS SHALL BE 3 1/2"x3 1/2"x1/4" STEEL ANGLE FOR UP TO 4'-0" SPAN AND 6"x4"x5/16" STEEL ANGLE WITH 6" LEG VERTICAL FOR SPANS UP TO 9'-0" (UNO).
- 14) THE POSITIVE AND NEGATIVE DESIGN PRESSURE FOR DOORS AND WINDOWS FOR A MEAN ROOF HEIGHT OF 35 FEET OR LESS SHALL BE 25 PSF.
- 15) THE POSITIVE AND NEGATIVE DESIGN PRESSURES REQUIRED FOR ANY ROOF OR WALL CLADDING APPLICATION NOT SPECIFICALLY ADDRESSED IN THE NORTH CAROLINA STATE RESIDENTIAL CODE - 2018 EDITION SHALL BE AS FOLLOWS:
- ROOF:  
 45.4 PSF - 2.25:12 PITCH OR LESS  
 34.8 PSF - 2.25:12 TO 1:12 PITCH  
 21 PSF - 1:12 TO 12:12 PITCH
- WALLS:  
 24.1 PSF - WALLS

## TRUSS SYSTEM REQUIREMENTS


NC (2018 NCRC):

1. TRUSS SYSTEM LAYOUTS (PLACEMENT PLANS) SHALL BE DESIGNED IN ACCORDANCE WITH SEALED TRUSS PROFILES. ANY NEED TO CHANGE TRUSSES SHALL BE COORDINATED WITH THE TRUSS MANUFACTURER.

2. TRUSS SCHEMATICS (PROFILES) SHALL BE PREPARED AND SEALED BY TRUSS MANUFACTURER.

3. ALL TRUSSES SHALL BE DESIGNED FOR BEARING ON SPF #2 OR #3 PLATES OR LEDGERS (UNO).

4. ALL REQUIRED ANCHORS FOR TRUSSES DUE TO UPLIFT OR BEARING SHALL MEET THE REQUIREMENTS AS SPECIFIED ON THE TRUSS SCHEMATICS.



(A) STEM WALL FOOTING (SIDING)

## HEADER/BEAM & COLUMN NOTES

- ALL EXTERIOR AND LOAD BEARING HEADERS SHALL BE MIN. (2) 2x10 (4" WALL) OR (3) 2x10 (6" WALL) WITH (1) SUPPORT STUD, UNLESS NOTED OTHERWISE.
- THE NUMBER SHOWN AT BEAM AND HEADER SUPPORTS INDICATES THE NUMBER OF SUPPORT STUDS REQUIRED IN STUD POCKET OR COLUMN. THE NUMBER OF KING STUDS AT EACH END OF HEADERS IN EXTERIOR WALLS SHALL BE ACCORDING TO ITEM "d" IN TABLE R602.3(5) OR AS BELOW:
  - UP TO 4' SPAN: (1) KING STUD
  - OVER 4' UP TO 8' SPAN: (2) KING STUDS
  - OVER 8' UP TO 11' SPAN: (3) KING STUDS
  - OVER 11' SPAN: (4) KING STUDS

DETAIL SHEET  
(115/120 MPH)

NOT ALL DETAILS MAY APPLY TO THIS PLAN

HEATHER HALL  
165 HEATHERSTONE CT  
BENSON NC 27504  
(919) 207-1403

H SQUARED HOME DESIGN, INC.

ANY DEVIATION OF THE SPECIFIED REQUIREMENTS OR DIMENSIONS Voids THE DESIGNER'S LIABILITY. THIS PLAN HAS BEEN DRAWN IN ACCORDANCE WITH THE NORTH CAROLINA STATE RESIDENTIAL BUILDING CODES 2018 EDITION.

DATE:  
  
FILE:


Job Q-2402656-1	Truss T1	Truss Type Common	Qty 2	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	-------------	----------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:03

Page: 1

ID:VJVEzN3Nkz2bxotfhKlf0vyJycQ-\_o?aCU2euFUWemr1DFYbeulwecRqmJg\_EpjjGFyJvEE



Scale = 1:55.8

Plate Offsets (X, Y): [2:0-3-8,Edge], [8:0-3-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.58	Vert(LL)	-0.37	10-12	>650	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.64	Vert(CT)	-0.45	10-12	>527	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.30	Horz(CT)	0.02	2	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS								Weight: 140 lb FT = 20%

**LUMBER**  
 TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 WEBS 2x4 SP No.3  
 WEDGE Left: 2x4 SP No.3  
 Right: 2x4 SP No.3

**BRACING**  
 TOP CHORD Structural wood sheathing directly applied or 5-4-1 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
 WEBS 1 Row at midpt 5-12

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**REACTIONS** (lb/size) 2=523/0-3-8, (min. 0-1-8), 8=890/0-3-8, (min. 0-1-8),  
 12=1108/0-3-8, (min. 0-1-13)  
 Max Horiz 2=-119 (LC 9)  
 Max Uplift 2=-78 (LC 11), 8=-130 (LC 11), 12=-158 (LC 11)  
 Max Grav 2=543 (LC 20), 8=890 (LC 1), 12=1158 (LC 18)

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-19=-521/47, 3-19=-376/80, 3-4=-307/57, 4-20=-298/79, 5-21=-904/206, 6-21=-1017/187, 6-7=-1026/165,  
 7-22=-1092/188, 8-22=-1255/155  
 BOT CHORD 2-12=0/424, 12-23=0/450, 11-23=0/450, 11-24=0/450, 10-24=0/450, 8-10=-63/1057  
 WEBS 5-10=-72/753, 7-10=-454/212, 5-12=-645/109, 3-12=-471/215

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=30ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) -1-0-0 to 2-0-0, Interior (1) 2-0-0 to 15-0-0, Exterior (2) 15-0-0 to 18-0-0, Interior (1) 18-0-0 to 31-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 78 lb uplift at joint 2, 158 lb uplift at joint 12 and 130 lb uplift at joint 8.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard


Job Q-2402656-1	Truss T1A	Truss Type Common	Qty 12	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	--------------	----------------------	-----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:03

Page: 1

ID:VJVEzN3NKz2boxfthKlf0vyJycQ-\_o?aCU2euFUWemr1DFYbeulw7cP\_mJq\_EpjjGFyJvEE



Scale = 1:55.8

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.41	10-12	>869	240
TCDL	10.0	Lumber DOL	1.15	BC	0.75	Vert(CT)	-0.59	10-12	>606	180
BCLL	0.0*	Rep Stress Incr	YES	WB	0.29	Horz(CT)	0.06	8	n/a	n/a
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS						
										Weight: 140 lb FT = 20%

**LUMBER**

TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 WEBS 2x4 SP No.3  
 WEDGE Left: 2x4 SP No.3  
 Right: 2x4 SP No.3

**BRACING**

TOP CHORD  
 BOT CHORD

Structural wood sheathing directly applied or 3-5-10 oc purlins.  
 Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**REACTIONS** (lb/size) 2=1260/0-3-8, (min. 0-2-0), 8=1260/0-3-8, (min. 0-2-0)  
 Max Horiz 2=119 (LC 10)  
 Max Uplift 2=-183 (LC 11), 8=-183 (LC 11)

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-19=-2031/265, 3-19=-1867/298, 3-4=-1804/276, 4-20=-1794/298, 5-20=-1682/316, 5-21=-1682/316, 6-21=-1794/298,  
 6-7=-1804/276, 7-22=-1867/298, 8-22=-2031/265  
 BOT CHORD 2-12=-160/1760, 12-23=-11/1164, 11-23=-11/1164, 11-24=-11/1164, 10-24=-11/1164, 8-10=-160/1742  
 WEBS 5-10=-68/724, 7-10=-437/208, 5-12=-68/724, 3-12=-437/208

**NOTES**

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TC DL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=30ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) -1-0-0 to 2-0-0, Interior (1) 2-0-0 to 15-0-0, Exterior (2) 15-0-0 to 18-0-0, Interior (1) 18-0-0 to 31-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 183 lb uplift at joint 2 and 183 lb uplift at joint 8.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard


Job Q-2402656-1	Truss T1B	Truss Type Roof Special	Qty 7	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	--------------	----------------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:04

Page: 1

ID:VJVEzN3NKz2bxotfhKlf0vyJycQ-S?ZzPq3GFYcNGvQDnz3qA6q110kgVdM8TTTGohyJvED



Scale = 1:58.3

Plate Offsets (X, Y): [2:0-0-13,0-1-15], [5:0-4-0,0-3-0], [7:0-3-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.84	Vert(LL)	-0.23	12-13	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.79	Vert(CT)	-0.52	12-13	>694	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.84	Horz(CT)	0.24	9	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS								Weight: 148 lb FT = 20%

**LUMBER**

TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 WEBS 2x4 SP No.3  
 WEDGE Right: 2x4 SP No.3  
 SLIDER Left 2x4 SP No.3 -- 2-6-0

**BRACING**

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
 WEBS 1 Row at midpt 4-12, 8-12

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**REACTIONS** (lb/size) 2=1260/0-3-8, (min. 0-2-0), 9=1260/0-3-8, (min. 0-2-0)  
 Max Horiz 2=119 (LC 10)  
 Max Uplift 2=-183 (LC 11), 9=-183 (LC 11)

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-1840/76, 3-4=-3542/415, 4-5=-1427/225, 5-21=-1416/246, 6-21=-1310/264, 6-22=-1312/264, 7-22=-1420/246,  
 7-8=-1431/224, 8-23=-1887/279, 9-23=-2053/245  
 BOT CHORD 2-13=-279/3194, 12-13=-279/3185, 11-12=-144/1757, 9-11=-144/1757  
 WEBS 4-13=-51/1637, 4-12=-2164/298, 6-12=-71/753, 8-12=-680/164

**NOTES**

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=30ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) -1-0-0 to 2-0-0, Interior (1) 2-0-0 to 15-0-0, Exterior (2) 15-0-0 to 18-0-0, Interior (1) 18-0-0 to 31-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 183 lb uplift at joint 2 and 183 lb uplift at joint 9.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard




Job Q-2402656-1	Truss T1CGE	Truss Type Common Supported Gable	Qty 1	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	----------------	--------------------------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:04

Page: 1

ID:Sid?O34dsallB512olo75KyJycO-S?ZzPq3GfYcNGvQDnz3qA6qEd0wJVoR8TTTGohyJvED



Scale = 1:56

Plate Offsets (X, Y): [2:0-3-8,Edge], [18:0-3-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.14	Horz(CT)	0.00	18	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS								Weight: 183 lb FT = 20%

**LUMBER**  
 TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 OTHERS 2x4 SP No.3  
 WEDGE Left: 2x4 SP No.3  
 Right: 2x4 SP No.3

**BRACING**  
 TOP CHORD  
 BOT CHORD

Structural wood sheathing directly applied or 6'-0" oc purlins.  
 Rigid ceiling directly applied or 10'-0" oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**REACTIONS** All bearings 30'-0".  
 (lb) - Max Horiz 2=119 (LC 10), 34=119 (LC 10)  
 Max Uplift All uplift 100 (lb) or less at joint(s) 2, 18, 20, 21, 22, 23, 24, 25, 28, 29, 30, 31, 32, 33, 34, 37  
 Max Grav All reactions 250 (lb) or less at joint(s) 2, 18, 20, 21, 22, 23, 24, 25, 26, 28, 29, 30, 31, 32, 33, 34, 37

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=30ft; eave=2ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Corner (3) -1-0-0 to 2-0-0, Exterior (2) 2-0-0 to 15-0-0, Corner (3) 15-0-0 to 18-0-0, Exterior (2) 18-0-0 to 31-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - All plates are 2x4 MT20 unless otherwise indicated.
  - Gable requires continuous bottom chord bearing.
  - Gable studs spaced at 2'-0" oc.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-06"-00 tall by 2'-00"-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 18, 28, 29, 30, 31, 32, 33, 25, 24, 23, 22, 21, 20, 2, 18.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard


Job Q-2402656-1	Truss T1GE	Truss Type Common	Qty 1	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	---------------	----------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:05

Page: 1

ID:wuBNbP5GduQ9oFcEMSJMeYyJycN-wB7LdA4uQskEt3?QKga3JUNPNQGyEFhHh7CqL7yJvEC



Scale = 1:56

Plate Offsets (X, Y): [2:0-3-8,Edge], [18:0-3-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.14	Horz(CT)	0.00	18	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS								Weight: 183 lb FT = 20%

**LUMBER**

TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 OTHERS 2x4 SP No.3  
 WEDGE Left: 2x4 SP No.3  
 Right: 2x4 SP No.3

**BRACING**

TOP CHORD  
 BOT CHORD

Structural wood sheathing directly applied or 6-0-0 oc purlins.  
 Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**REACTIONS** All bearings 30-0-0.

- (lb) - Max Horiz 2=119 (LC 10), 34=119 (LC 10)
- Max Uplift All uplift 100 (lb) or less at joint(s) 2, 18, 20, 21, 22, 23, 24, 25, 28, 29, 30, 31, 32, 33, 34, 37
- Max Grav All reactions 250 (lb) or less at joint(s) 2, 18, 20, 21, 22, 23, 24, 25, 26, 28, 29, 30, 31, 32, 33, 34, 37

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES**

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=30ft; eave=2ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Corner (3) -1-0-0 to 2-0-0, Exterior (2) 2-0-0 to 15-0-0, Corner (3) 15-0-0 to 18-0-0, Exterior (2) 18-0-0 to 31-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) All plates are 2x4 MT20 unless otherwise indicated.
- 5) Gable requires continuous bottom chord bearing.
- 6) Gable studs spaced at 2-0-0 oc.
- 7) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 18, 28, 29, 30, 31, 32, 33, 25, 24, 23, 22, 21, 20, 2, 18.
- 9) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard


Job Q-2402656-1	Truss T1SE	Truss Type Common Structural Gable	Qty 1	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	---------------	---------------------------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:05

Page: 1

ID:wuBNbP5GduQ9oFcEMSJMeYyJycN-wB7LdA4uQskE13?QKga3JNHaQ6nECzHh7CqL7yJvEC



Scale = 1:55.8

Plate Offsets (X, Y): [2:0-3-8,Edge], [5:0-2-0,0-0-8], [8:0-3-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.55	Vert(LL)	-0.27	14-16	>880	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.67	Vert(CT)	-0.39	14-16	>617	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.37	Horz(CT)	0.02	47	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS								Weight: 222 lb FT = 20%

**LUMBER**

TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 WEBS 2x4 SP No.3  
 OTHERS 2x4 SP No.3  
 WEDGE Left: 2x4 SP No.3  
 Right: 2x4 SP No.3

**BRACING**

TOP CHORD Structural wood sheathing directly applied or 5-7-3 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing, Except:  
 10-0-0 oc bracing: 2-16,14-16.  
 WEBS 1 Row at midpt 5-14

**REACTIONS** All bearings 10-3-8, except 2=0-3-8

(lb) - Max Horiz 2=119 (LC 10)  
 Max Uplift All uplift 100 (lb) or less at joint(s) 8, 10, 11, 47 except 2=-133 (LC 11), 13=-483 (LC 15), 14=-103 (LC 11)  
 Max Grav All reactions 250 (lb) or less at joint(s) 10, 11, 12, 13 except 2=835 (LC 1), 8=315 (LC 21), 14=1536 (LC 18), 47=315 (LC 21)

**FORCES**

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-50=-1144/160, 3-50=-980/192, 3-4=-914/170, 4-51=-905/192, 5-51=-792/210, 8-53=-294/57  
 BOT CHORD 2-16=-67/981, 16-54=0/354, 15-54=0/354, 15-55=0/354, 14-55=0/354  
 WEBS 5-14=-805/101, 7-14=-440/216, 5-16=-71/751, 3-16=-454/212

**NOTES**

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=30ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) -1-0-0 to 2-0-0, Interior (1) 2-0-0 to 15-0-0, Exterior (2) 15-0-0 to 18-0-0, Interior (1) 18-0-0 to 31-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable studs spaced at 2-0-0 oc.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 11, 10, 8 except (jt=lb) 2=132, 14=102, 13=483.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


Job Q-2402656-1	Truss T2	Truss Type Monopitch	Qty 10	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	-------------	-------------------------	-----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:05

Page: 1

ID:O4lpl6uNBY0QPbQwAqbAlyJycM-wB7LdA4uQskEt3?QKga3jJNFmQ8IEHoHh7CqL7yJvEC



Scale = 1:27.3

Plate Offsets (X, Y): [2:0-3-4,Edge], [4:0-2-8,0-1-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.67	Vert(LL)	-0.14	4-7	>657	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.54	Vert(CT)	-0.32	4-7	>291	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	2	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 30 lb	FT = 20%

**LUMBER**  
 TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 WEBS 2x4 SP No.3  
 OTHERS 2x4 SP No.3

**BRACING**  
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (lb/size) 2=371/0-3-8, (min. 0-1-8), 4=303/0-1-8, (min. 0-1-8)  
 Max Horiz 2=65 (LC 10)  
 Max Uplift 2=-72 (LC 11), 4=-39 (LC 11)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- 1) Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) -1-0-0 to 2-0-0, Interior (1) 2-0-0 to 7-8-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 3) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - 4) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 72 lb uplift at joint 2 and 39 lb uplift at joint 4.
  - 6) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard


Job Q-2402656-1	Truss T4AGRD	Truss Type Monopitch Girder	Qty 1	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	-----------------	--------------------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:06

Page: 1

ID:O4lpl6uNBY0QPbQwAqbAlyJycM-PNhjqW4WBAs5VDacuO5IGXwYyqWQzhvRwnyNtayJvEB



Scale = 1:29.2

Plate Offsets (X, Y): [2:0-3-4,0-0-6], [5:0-2-8,0-0-8]

Loading	(psf)	Spacing	2-0-0	CSI	0.19	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.19	Vert(LL)	-0.02	6-8	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.39	Vert(CT)	-0.04	6-8	>999	180		
BCLL	0.0*	Rep Stress Incr	NO	WB	0.20	Horz(CT)	0.01	9	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 47 lb	FT = 20%

**LUMBER**  
 TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x8 SP No.2  
 WEBS 2x4 SP No.3  
 OTHERS 2x4 SP No.3

**BRACING**  
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (lb/size) 2=544/0-3-8, (min. 0-1-8), 9=503/0-1-8, (min. 0-1-8)  
 Max Horiz 2=76 (LC 7)  
 Max Uplift 2=-106 (LC 7), 9=-91 (LC 7)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-943/130, 4-9=-72/468  
 BOT CHORD 2-10=-156/905, 6-10=-156/905, 6-11=-156/905, 9-11=-156/904  
 WEBS 3-6=-23/366, 3-9=-874/150, 4-9=-514/93

- NOTES**
- 1) Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 3) Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - 4) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 9.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 106 lb uplift at joint 2 and 91 lb uplift at joint 9.
  - 6) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 7) "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidelines.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
 Uniform Loads (lb/ft)  
 Vert: 1-4=-60, 2-5=-20  
 Concentrated Loads (lb)  
 Vert: 6=-121 (F), 10=-146 (F), 11=-121 (F)


Job Q-2402656-1	Truss T4GRD	Truss Type Monopitch Girder	Qty 1	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	----------------	--------------------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:06

Page: 1

ID:O4Ipl6uNBY0QPbQwAqbAlyJycM-PNhjqW4WBAs5VDacuO5IGXwXuqWMzhsRwnyNtayJvEB



Scale = 1:29.2

Plate Offsets (X, Y): [2:0-3-4,0-0-6], [5:0-2-8,0-0-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	-0.02	6-8	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.39	Vert(CT)	-0.04	6-8	>999	180		
BCLL	0.0*	Rep Stress Incr	NO	WB	0.20	Horz(CT)	0.01	9	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 47 lb	FT = 20%

**LUMBER**  
TOP CHORD 2x4 SP No.1  
BOT CHORD 2x8 SP No.2  
WEBS 2x4 SP No.3  
OTHERS 2x4 SP No.3

**BRACING**  
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (lb/size) 2=548/0-3-8, (min. 0-1-8), 9=512/0-1-8, (min. 0-1-8)  
Max Horiz 2=76 (LC 18)  
Max Uplift 2=-108 (LC 7), 9=-93 (LC 7)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-956/134, 4-9=-74/477  
BOT CHORD 2-10=-160/918, 6-10=-160/918, 6-11=-160/918, 9-11=-159/917  
WEBS 3-6=-25/374, 3-9=-886/153, 4-9=-523/95

- NOTES**
- 1) Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 3) Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - 4) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 9.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 108 lb uplift at joint 2 and 93 lb uplift at joint 9.
  - 6) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 7) "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidelines.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-4=-60, 2-5=-20  
Concentrated Loads (lb)  
Vert: 6=-126 (B), 10=-148 (B), 11=-126 (B)


Job Q-2402656-1	Truss T5	Truss Type Half Hip	Qty 1	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	-------------	------------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:06

Page: 1

ID:mpLlg5DoYrYU62668BMFI2yJvJB-PNhjqW4WBAs5VDacuO5IGXwaAqcezkcRwnyNtayJvEB



Scale = 1:27.1

Plate Offsets (X, Y): [3:0-2-8,0-2-4]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	0.00	6-9	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.05	Vert(CT)	0.00	6-9	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	2	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 21 lb	FT = 20%

**LUMBER**

TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 WEBS 2x4 SP No.3  
 WEDGE Left: 2x4 SP No.3

**BRACING**

TOP CHORD Structural wood sheathing directly applied or 3-10-8 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (lb/size) 2=217/0-3-8, (min. 0-1-8), 5=141/ Mechanical, (min. 0-1-8)  
 Max Horiz 2=58 (LC 10)  
 Max Uplift 2=-53 (LC 11), 5=-19 (LC 11)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES**

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) -1-0-0 to 2-0-0, Interior (1) 2-0-0 to 2-10-0, Exterior (2) 2-10-0 to 3-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 53 lb uplift at joint 2 and 19 lb uplift at joint 5.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

**LOAD CASE(S)** Standard


Job Q-2402656-1	Truss T5A	Truss Type Half Hip	Qty 1	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	--------------	------------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:07

Page: 1

ID:mpLlg5DoYrYU62668BMFI2yJvJB-taF52r58yT?y7N9oS5dXokSlxDxCiBua9RhwP0yJvEA



Scale = 1:21.6

Plate Offsets (X, Y): [3:0-2-8,0-2-4]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	0.00	6	>999	240	MT20 244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	0.00	5-6	>999	180	
BCLL	0.0*	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	5	n/a	n/a	
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 20 lb FT = 20%

**LUMBER**

TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 WEBS 2x4 SP No.3  
 WEDGE Left: 2x4 SP No.3

**BRACING**

TOP CHORD Structural wood sheathing directly applied or 3-10-8 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (lb/size) 2=217/0-3-8, (min. 0-1-8), 5=141/ Mechanical, (min. 0-1-8)  
 Max Horiz 2=42 (LC 10)  
 Max Uplift 2=-56 (LC 11), 5=-17 (LC 8)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES**

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 56 lb uplift at joint 2 and 17 lb uplift at joint 5.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

**LOAD CASE(S)** Standard




Job Q-2402656-1	Truss T5B	Truss Type Half Hip Girder	Qty 1	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	--------------	-------------------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:07

Page: 1

ID:mpLlg5DoYrYU62668BMFI2yJvJB-taF52r58yT?y7N9oS5dXokSjeDxEIBPa9RhwP0yJvEA



Scale = 1:29.9

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.13	Vert(LL)	0.00	6	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	0.00	5-6	>999	180		
BCLL	0.0*	Rep Stress Incr	NO	WB	0.06	Horz(CT)	0.00	2	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 19 lb	FT = 20%

#### LUMBER

TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 WEBS 2x4 SP No.3  
 WEDGE Left: 2x4 SP No.3

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 3-10-8 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (lb/size) 2=238/0-3-8, (min. 0-1-8), 5=162/ Mechanical, (min. 0-1-8)  
 Max Horiz 2=26 (LC 6)  
 Max Uplift 2=-52 (LC 7), 5=-13 (LC 4)  
 Max Grav 2=238 (LC 1), 5=166 (LC 17)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TC DL=6.0psf; BC DL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 13 lb uplift at joint 5 and 52 lb uplift at joint 2.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidelines.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
 Uniform Loads (lb/ft)  
 Vert: 1-3=-60, 3-4=-60, 5-7=-20  
 Concentrated Loads (lb)  
 Vert: 8=-4 (B), 9=-16 (B), 10=-6 (B), 11=-16 (B)


Job Q-2402656-1	Truss T8	Truss Type Half Hip	Qty 1	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	-------------	------------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:07

Page: 1

ID:xf\_UP181z?oLO7fyowFr2nyJvJH-taF52r58yT?y7N9oS5dXokSlvDxtiBsa9RhwP0yJvEA



Scale = 1:23.2

Plate Offsets (X, Y): [3:0-2-8,0-2-4]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	0.00	6-9	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.05	Vert(CT)	0.00	6-9	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	2	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 22 lb	FT = 20%

**LUMBER**

TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 WEBS 2x4 SP No.3  
 WEDGE Left: 2x4 SP No.3

**BRACING**

TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (lb/size) 2=222/0-3-8, (min. 0-1-8), 5=146/ Mechanical, (min. 0-1-8)  
 Max Horiz 2=58 (LC 10)  
 Max Uplift 2=-54 (LC 11), 5=-19 (LC 11)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES**

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) -1-0-0 to 2-0-0, Interior (1) 2-0-0 to 2-10-0, Exterior (2) 2-10-0 to 3-10-4 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 2 and 19 lb uplift at joint 5.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

**LOAD CASE(S)** Standard


Job Q-2402656-1	Truss T8A	Truss Type Half Hip	Qty 1	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	--------------	------------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:08

Page: 1

ID:xf\_UP181z?oLO7fyowFr2nyJvJH-LmoTFB6mjn7oIXk\_Op8mLy?wedHORd6jN5RUxSyJvE9



Scale = 1:21.6

Plate Offsets (X, Y): [3:0-2-8,0-2-4]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	0.00	6	>999	240	MT20 244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	0.00	5-6	>999	180	
BCLL	0.0*	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	5	n/a	n/a	
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 21 lb FT = 20%

**LUMBER**

TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 WEBS 2x4 SP No.3  
 WEDGE Left: 2x4 SP No.3

**BRACING**

TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (lb/size) 2=222/0-3-8, (min. 0-1-8), 5=146/ Mechanical, (min. 0-1-8)  
 Max Horiz 2=42 (LC 10)  
 Max Uplift 2=-56 (LC 11), 5=-18 (LC 8)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES**

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 56 lb uplift at joint 2 and 18 lb uplift at joint 5.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

**LOAD CASE(S)** Standard


Job Q-2402656-1	Truss T8B	Truss Type Half Hip Girder	Qty 1	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	--------------	-------------------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:08

Page: 1

ID:QsYsdN9fkJwC0HE8Mdm4b\_yJvJG-LmoTFB6mjn7oIXk\_Op8mLy?uCdHRRdcjN5RUxSyJvE9



Scale = 1:29.9

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.14	Vert(LL)	0.00	6	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	0.00	5-6	>999	180		
BCLL	0.0*	Rep Stress Incr	NO	WB	0.06	Horz(CT)	0.00	2	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 21 lb	FT = 20%

**LUMBER**

TOP CHORD 2x4 SP No.1  
 BOT CHORD 2x4 SP No.1  
 WEBS 2x4 SP No.3  
 WEDGE Left: 2x4 SP No.3

**BRACING**

TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (lb/size) 2=243/0-3-8, (min. 0-1-8), 5=165/ Mechanical, (min. 0-1-8)  
 Max Horiz 2=26 (LC 6)  
 Max Uplift 2=-52 (LC 7), 5=-15 (LC 4)  
 Max Grav 2=243 (LC 1), 5=168 (LC 17)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES**

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TC DL=6.0psf; BC DL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 15 lb uplift at joint 5 and 52 lb uplift at joint 2.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidelines.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
 Uniform Loads (lb/ft)  
 Vert: 1-3=-60, 3-4=-60, 5-7=-20  
 Concentrated Loads (lb)  
 Vert: 8=-4 (F), 9=-16 (F), 10=-4 (F), 11=-15 (F)


Job Q-2402656-1	Truss T12	Truss Type Jack-Open	Qty 4	Ply 1	Charleston C LH-Roof Job Reference (optional)
--------------------	--------------	-------------------------	----------	----------	--

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Apr 24 2024 Print: 8.720 S Apr 24 2024 MiTek Industries, Inc. Tue Nov 12 15:05:08

Page: 1

ID:dyWiA4Ys58s6miNCyDKWclyJvGA-LmoTFB6mjn7olXk\_0p8mLy?wjdhARdYjN5RUxSyJvE9



Scale = 1:20.1

Plate Offsets (X, Y): [2:0-3-4,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	0.00	4-7	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.05	Vert(CT)	0.00	4-7	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	4	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 10 lb	FT = 20%

#### LUMBER

TOP CHORD 2x4 SP No.1  
BOT CHORD 2x4 SP No.1

#### BRACING

TOP CHORD  
BOT CHORD

Structural wood sheathing directly applied or 2-8-0 oc purlins.  
Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (lb/size) 2=176/0-3-8, (min. 0-1-8), 3=58/ Mechanical, (min. 0-1-8),  
4=35/ Mechanical, (min. 0-1-8)  
Max Horiz 2=34 (LC 11)  
Max Uplift 2=-52 (LC 11), 3=-15 (LC 11)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES

- 1) Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) -1-0-0 to 2-0-0, Interior (1) 2-0-0 to 2-7-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 15 lb uplift at joint 3 and 52 lb uplift at joint 2.
- 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard