

Mark Morris, P.E.

#126, 1317-M, Summerville, SC 29483

843 209-5784, Fax (866)-213-4614

The truss drawing(s) listed below have been prepared by **Atlantic Building Components** under my direct supervision based on the parameters provided by the truss designers.

AST #: 56363

JOB: 25-0669-F02

JOB NAME: LOT 0.0029 HONEYCUTT HILLS

Wind Code: N/A

Wind Speed: Vult= N/A

Exposure Category: N/A

Mean Roof Height (feet): N/A

These truss designs comply with IRC 2018 as well as IRC 2021.

17 Truss Design(s)

Trusses:

F201, F202, F202A, F203, F205A, F206, F207, F208, F209, F210, F211, F212, F213, F214,





1/28/2025

Mark Morris

Warning !—Verify design parameters and read notes before use.

This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI



LOADING (psf)	SPACING-	2-0-0	CSL	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.64	Vert(LL)	-0.30 16-17	>697	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.79	Vert(CT)	-0.41 16-17	>507	360	MT20HS	187/143
BCLL 0.0	Rep Stress Incr	YES	WB 0.53	Horz(CT)	0.06 12	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
								Weight: 88 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP SS(flat) *Except*
 B2: 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-9-2 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 21=942/0-3-6 (min. 0-1-8), 12=948/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2028/0, 3-4=-2028/0, 4-5=-3259/0, 5-6=-3830/0, 6-7=-3780/0, 7-8=-3111/0,
8-9=-3111/0, 9-10=-1700/0
BOT CHORD 20-21=0/1226, 19-20=0/2785, 18-19=0/3830, 17-18=0/3830, 16-17=0/3830, 15-16=0/3619,
14-15=0/3619, 13-14=0/2529, 12-13=0/837
WEBS 5-18=-65/292, 6-17=-260/97, 5-19=-879/0, 4-19=0/650, 4-20=-986/0, 2-20=0/1044,
2-21=-1514/0, 6-16=-424/231, 7-16=0/374, 7-14=-648/0, 9-14=0/744, 9-13=-1079/0,
10-13=0/1122, 10-12=-1256/0

- NOTES-** (5)
1) Unbalanced floor live loads have been considered for this design.
2) All plates are MT20 plates unless otherwise indicated.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
4) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



1/28/2025


Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 25-0669-F02	Truss F202A	Truss Type Floor	Qty 1	Ply 1	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 56363
--------------------	----------------	---------------------	----------	----------	--	--

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:19 2025 Page 1
ID:pMqJz?gO_6c5LWiSfiGO4QyyWlk-AIGkXJ_xOJjuGcUXIK8zRXfmdCWjhZEhzXG9bOzqj0c



Scale = 1:28.1



6-4-13	7-4-13	8-4-13	17-2-8
6-4-13	1-0-0	1-0-0	8-9-11
Plate Offsets (X,Y)-- [1:Edge,0-1-8], [5:0-1-8,Edge], [6:0-1-8,Edge]			

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 40.0	Plate Grip DOL	1.00	TC 0.64	Vert(LL)	-0.29	16-17	>713	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.80	Vert(CT)	-0.39	16-17	>519	360	MT20HS	187/143
BCLL 0.0	Rep Stress Incr	YES	WB 0.52	Horz(CT)	0.06	12	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH							
									Weight: 88 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 5-9-15 oc purlins, except end verticals.
BOT CHORD 2x4 SP SS(flat) *Except* B2: 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 21=933/Mechanical, 12=933/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1813/0, 3-4=-1813/0, 4-5=-3081/0, 5-6=-3687/0, 6-7=-3673/0, 7-8=-3039/0,
8-9=-3039/0, 9-10=-1668/0
BOT CHORD 20-21=0/995, 19-20=0/2587, 18-19=0/3687, 17-18=0/3687, 16-17=0/3687, 15-16=0/3533,
14-15=0/2478, 13-14=0/2478, 12-13=0/824
WEBS 5-18=-51/302, 6-17=-270/83, 5-19=-904/0, 4-19=0/666, 4-20=-1007/0, 2-20=0/1065,
2-21=-1342/0, 6-16=-387/257, 7-16=0/351, 7-15=-630/0, 9-15=0/716, 9-13=-1055/0,
10-13=0/1099, 10-12=-1235/0

- NOTES-** (5)
1) Unbalanced floor live loads have been considered for this design.
2) All plates are MT20 plates unless otherwise indicated.
3) Refer to girder(s) for truss to truss connections.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




1/28/2025


Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC
25-0669-F02	F203	Floor	7	1	
					# 56363

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:20 2025 Page 1
 ID:pMqJz?gO_6c5LWiSfiGO4QyyWlk-exq6kf?Z9crlum3jr2fCzkC?Qcs7Q20qCA0i7qzqj0b



Scale = 1:24.6



	6-4-13 6-4-13	7-4-13 1-0-0	8-4-13 1-0-0	15-1-0 6-8-3
Plate Offsets (X,Y)--	[1:Edge,0-1-8], [4:0-1-8,Edge], [5:0-1-8,Edge]			

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.38	Vert(LL)	-0.16 11-12	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.79	Vert(CT)	-0.21 11-12	>833	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.42	Horz(CT)	0.04 9	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
								Weight: 76 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 16=816/Mechanical, 9=816/Mechanical

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1545/0, 3-4=-2532/0, 4-5=-2874/0, 5-6=-2601/0, 6-7=-1691/0
 BOT CHORD 15-16=0/861, 14-15=0/2196, 13-14=0/2874, 12-13=0/2874, 11-12=0/2874, 10-11=0/2308, 9-10=0/1040
 WEBS 4-14=-602/0, 3-14=0/485, 3-15=-847/0, 2-15=0/892, 2-16=-1161/0, 5-11=-542/0, 6-11=0/446, 6-10=-803/0, 7-10=0/847, 7-9=-1286/0

NOTES- (4)
 1) Unbalanced floor live loads have been considered for this design.
 2) Refer to girder(s) for truss to truss connections.
 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




1/28/2025


Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 25-0669-F02	Truss F205A	Truss Type Floor	Qty 1	Ply 1	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 56363
--------------------	----------------	---------------------	----------	----------	--	--

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:20 2025 Page 1
ID:pMqJz?gO_6c5LWiSfiGO4QyyWlk-exq6kf?Z9crtum3jr2fCzkC0BcwaQ46qCA0i7qzaj0b



Scale = 1:25.0



	6-4-13 6-4-13	7-4-13 1-0-0	8-4-13 1-0-0	15-4-8 6-11-11
Plate Offsets (X,Y)--	[1:Edge,0-1-8], [4:0-1-8,Edge], [5:0-1-8,Edge]			

LOADING (psf)	SPACING- 1-4-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.27	Vert(LL) -0.12 12-13 >999 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.56	Vert(CT) -0.16 12-13 >999 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.29	Horz(CT) 0.03 9 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH			
				Weight: 78 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 9=555/0-3-8 (min. 0-1-8), 17=555/Mechanical

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 8-9=-556/0, 2-3=-1055/0, 3-4=-1738/0, 4-5=-1990/0, 5-6=-1832/0, 6-7=-1252/0
BOT CHORD 16-17=0/586, 15-16=0/1500, 14-15=0/1990, 13-14=0/1990, 12-13=0/1990, 11-12=0/1651, 10-11=0/834
WEBS 4-15=-428/0, 3-15=0/340, 3-16=-579/0, 2-16=0/610, 2-17=-790/0, 5-12=-346/0, 6-12=0/289, 6-11=-519/0, 7-11=0/544, 7-10=-781/0, 8-10=0/565

NOTES- (4)
1) Unbalanced floor live loads have been considered for this design.
2) Refer to girder(s) for truss to truss connections.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard





1/28/2025

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC
25-0669-F02	F206	Floor	11	1	
					# 56363

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:20 2025 Page 1
 ID:pMqJz?gO_6c5LWiSfiGO4QyyWlk-exq6kf?Z9crlum3jr2fCzkc_ycrNQ2?qCA0i7qzqj0b



LOADING (psf)	SPACING-	CSL	DEFL.	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.41	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.83	Vert(LL) -0.18 12-13 >999 480		
BCLL 0.0	Rep Stress Incr YES	WB 0.43	Vert(CT) -0.24 12-13 >772 360		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH	Horz(CT) 0.05 9 n/a n/a		
				Weight: 79 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 9=847/0-3-8 (min. 0-1-8), 17=841/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 8-9=-849/0, 2-3=-1771/0, 3-4=-2758/0, 4-5=-3101/0, 5-6=-2829/0, 6-7=-1921/0, 7-8=-358/0
 BOT CHORD 16-17=0/1084, 15-16=0/2422, 14-15=0/3101, 13-14=0/3101, 12-13=0/3101, 11-12=0/2536, 10-11=0/1277
 WEBS 4-15=-620/0, 3-15=0/496, 3-16=-847/0, 2-16=0/894, 2-17=-1337/0, 5-12=-556/0, 6-12=0/457, 6-11=-800/0, 7-11=0/839,
 7-10=-1197/0, 8-10=0/864

NOTES- (4)
 1) Unbalanced floor live loads have been considered for this design.
 2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 3) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



1/28/2025

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC
25-0669-F02	F207	Floor Supported Gable	1	1	
					# 56363

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:21 2025 Page 1
 ID:pMqJz?gO_6c5LWfSfGO4QyyWk-68OUy??BwwzcWwewPIARWykFB0OX9bP_RqlGfGzqj0a

0₁-8

Scale = 1:25.7




Plate Offsets (X,Y)--	[7:0-1-8,Edge], [21:0-1-8,Edge], [26:Edge,0-1-8]
-----------------------	--

LOADING (psf)	SPACING-	2-0-0	CSL	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	14	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
								Weight: 69 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 15-7-12.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 26, 14, 25, 24, 23, 22, 21, 20, 19, 18, 17, 16, 15

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (6)
- Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



1/28/2025

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC
25-0669-F02	F208	Floor Supported Gable	1	1	Job Reference (optional) # 56363

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:21 2025 Page 1
 ID:pMqJz?gO_6c5LWiSfGO4QyyWlk-68OUy??BwwzcWwewPIARWykFB0OX9bP_RqlGfGzqj0a

0₁-8

0₁-8

Scale = 1:21.4




Plate Offsets (X,Y)-- [6:0-1-8,Edge], [18:0-1-8,Edge], [22:Edge,0-1-8]	
LOADING (psf)	SPACING- 2-0-0
TCLL 40.0	Plate Grip DOL 1.00
TCDL 10.0	Lumber DOL 1.00
BCLL 0.0	Rep Stress Incr YES
BCDL 5.0	Code IRC2021/TPI2014
CSL	DEFL. in (loc) l/defl L/d
TC 0.06	Vert(LL) n/a - n/a 999
BC 0.01	Vert(CT) n/a - n/a 999
WB 0.03	Horz(CT) 0.00 12 n/a n/a
Matrix-SH	
PLATES	GRIP
MT20	244/190
Weight: 58 lb FT = 20%F, 11%E	

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 12-11-12.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 22, 12, 21, 20, 19, 18, 17, 16, 15, 14, 13

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (5)
- Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard





1/28/2025

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC
25-0669-F02	F209	Floor	2	1	Job Reference (optional) # 56363

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:22 2025 Page 1
 ID:pMqJz?gO_6c5LWISfiGO4QyyWlk-aKyt9L0phE5T84D6zThg39HLnQbkuxq7gUVpBjzqjOZ



5-5-14	6-5-14	7-5-14	12-11-12
5-5-14	1-0-0	1-0-0	5-5-14

Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge], [6:0-1-8,Edge], [14:Edge,0-1-8]

LOADING (psf)	SPACING-	CS.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.32	Vert(LL) -0.10	11-12	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.58	Vert(CT) -0.13	9-10	>999	360		
BCLL 0.0	Rep Stress Incr YES	WB 0.47	Horz(CT) 0.03	7	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH						

Weight: 65 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 14=694/0-3-6 (min. 0-1-8), 7=694/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 14-15=-688/0, 1-15=-687/0, 7-16=-688/0, 6-16=-687/0, 1-2=-836/0, 2-3=-1812/0, 3-4=-2109/0, 4-5=-1812/0, 5-6=-836/0
 BOT CHORD 12-13=0/1506, 11-12=0/2109, 10-11=0/2109, 9-10=0/2109, 8-9=0/1506
 WEBS 3-12=-507/0, 2-12=0/427, 2-13=-872/0, 1-13=0/984, 4-9=-507/0, 5-9=0/427, 5-8=-872/0, 6-8=0/984

NOTES- (3)
 1) Unbalanced floor live loads have been considered for this design.
 2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard





1/28/2025

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 25-0669-F02	Truss F210	Truss Type Floor	Qty 3	Ply 1	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC	# 56363
--------------------	---------------	---------------------	----------	----------	--	---------

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:22 2025 Page 1
ID:pMqJz?gO_6c5LWiSfiGO4QyyWlk-aKyt9L0phE5T84D6zThg39HDqQXBUzA7gUVpBjzqj0Z



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.83	Vert(LL)	-0.25 20-21	>612	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.88	Vert(CT)	-0.34 20-21	>451	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.38	Horz(CT)	0.03 13	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
								Weight: 100 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP SS(flat) *Except*
B2: 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 17-18,16-17.

REACTIONS. (lb/size) 24=697/0-3-6 (min. 0-1-8), 17=1035/0-3-8 (min. 0-1-8), 13=348/0-3-6 (min. 0-1-8)
Max Grav 24=703(LC 3), 17=1035(LC 1), 13=376(LC 7)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1058/0, 3-4=-1954/0, 4-5=-1954/0, 5-6=-1954/0, 6-7=-2133/0, 7-8=-1724/0,
8-9=-668/0, 9-10=-476/0, 10-11=-559/0
BOT CHORD 23-24=0/442, 22-23=0/1639, 21-22=0/2254, 20-21=0/1724, 19-20=0/1724, 18-19=0/1724,
15-16=0/698, 14-15=0/698, 13-14=0/384
WEBS 7-20=-399/0, 8-19=0/456, 9-17=-914/0, 7-21=0/562, 6-22=-383/0, 3-22=0/402,
3-23=-756/0, 2-23=0/803, 2-24=-870/0, 8-18=-1360/0, 9-18=0/775, 9-16=0/408,
10-16=-376/0, 11-13=-511/0

NOTES- (4)
1) Unbalanced floor live loads have been considered for this design.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
3) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



1/28/2025

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 25-0669-F02	Truss F211	Truss Type Floor	Qty 5	Ply 1	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 56363
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:23 2025 Page 1
ID:pMqJz?gO_6c5LWiSfiGO4QyyWIk-2WWFMh1SSXDKIDoIXAcvbNpUNpsndOXGu8EMk9zqjOY





Plate Offsets (X,Y)-- [7:0-1-8,Edge], [8:0-1-8,Edge], [24:Edge,0-3-0]	
LOADING (psf)	SPACING- 1-7-3
TCLL 40.0	Plate Grip DOL 1.00
TCDL 10.0	Lumber DOL 1.00
BCLL 0.0	Rep Stress Incr YES
BCDL 5.0	Code IRC2021/TPI2014
CSL	Matrix-SH
TC 0.46	
BC 0.92	
WB 0.50	
DEFL. in (loc) l/defl L/d	PLATES MT20
Vert(LL) -0.31 19-20 >747 480	GRIP 244/190
Vert(CT) -0.42 19-20 >542 360	
Horz(CT) 0.07 14 n/a n/a	
	Weight: 98 lb FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 2-2-0 oc bracing: 19-20.

REACTIONS. (lb/size) 24=831/0-3-6 (min. 0-1-8), 14=831/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1325/0, 3-4=-2720/0, 4-5=-2720/0, 5-6=-2720/0, 6-7=-3509/0, 7-8=-3788/0, 8-9=-3565/0, 9-10=-2835/0, 10-11=-2835/0, 11-12=-1502/0
BOT CHORD 23-24=0/513, 22-23=0/2114, 21-22=0/3233, 20-21=0/3788, 19-20=0/3788, 18-19=0/3788, 17-18=0/3324, 16-17=0/2263, 15-16=0/2263, 14-15=0/717
WEBS 7-21=-579/9, 6-21=0/454, 6-22=-656/0, 3-22=0/773, 3-23=-1028/0, 2-23=0/1057, 2-24=-1008/0, 8-18=-531/57, 9-18=0/423, 9-17=-624/0, 11-17=0/730, 11-15=-990/0, 12-15=0/1022, 12-14=-1096/0

NOTES- (3)
1) Unbalanced floor live loads have been considered for this design.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



1/28/2025

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC
25-0669-F02	F212	Floor	5	1	
					# 56363

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:23 2025 Page 1
 ID:pMqJz?gO_6c5LWfSfGO4QyyWk-2WWFMh1SSXDKIDoIXACvbNpUMpsIdOXGu8EMk9zqjOY





Plate Offsets (X,Y)--	[7:0-1-8,Edge], [8:0-1-8,Edge], [24:Edge,0-3-0]
-----------------------	---

LOADING (psf)	SPACING-	1-7-3	CSL	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.46	Vert(LL)	-0.31 19-20	>745	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.92	Vert(CT)	-0.42 19-20	>541	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.50	Horz(CT)	0.07 14	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
								Weight: 99 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 2-2-0 oc bracing: 19-20.

REACTIONS. (lb/size) 24=832/0-3-6 (min. 0-1-8), 14=837/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1326/0, 3-4=-2722/0, 4-5=-2722/0, 5-6=-2722/0, 6-7=-3512/0, 7-8=-3792/0, 8-9=-3570/0, 9-10=-2841/0, 10-11=-2841/0, 11-12=-1510/0
 BOT CHORD 23-24=0/513, 22-23=0/2116, 21-22=0/3236, 20-21=0/3792, 19-20=0/3792, 18-19=0/3792, 17-18=0/3330, 16-17=0/2270, 15-16=0/2270, 14-15=0/725
 WEBS 7-21=-581/9, 6-21=0/455, 6-22=-656/0, 3-22=0/774, 3-23=-1028/0, 2-23=0/1058, 2-24=-1008/0, 8-18=-531/59, 9-18=0/423, 9-17=-624/0, 11-17=0/730, 11-15=-989/0, 12-15=0/1022, 12-14=-1101/0

NOTES- (4)
 1) Unbalanced floor live loads have been considered for this design.
 2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 3) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard





1/28/2025

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 25-0669-F02	Truss F213	Truss Type Floor	Qty 3	Ply 1	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 56363
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:24 2025 Page 1
ID:pMqJz?gO_6c5LWiSfGO4QyyWik-Wi4da124DrLBNNNV4uj88aMgZDDnMrwQ7o_wGbzqj0X



LOADING (psf)	SPACING-	CSL	DEFL.	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.43	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.87	Vert(LL) -0.29 19-20 >785 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.49	Vert(CT) -0.40 19-20 >569 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.07 14 n/a n/a		
	Code IRC2021/TPI2014			Weight: 98 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 24=819/0-3-6 (min. 0-1-8), 14=824/Mechanical

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1303/0, 3-4=-2667/0, 4-5=-2667/0, 5-6=-2667/0, 6-7=-3426/0, 7-8=-3678/0, 8-9=-3426/0, 9-10=-2667/0, 10-11=-2667/0, 11-12=-1303/0
BOT CHORD 23-24=0/505, 22-23=0/2077, 21-22=0/3168, 20-21=0/3678, 19-20=0/3678, 18-19=0/3678, 17-18=0/3168, 16-17=0/2077, 15-16=0/2077, 14-15=0/506
WEBS 7-21=-549/27, 6-21=0/434, 6-22=-640/0, 3-22=0/753, 3-23=-1008/0, 2-23=0/1038, 2-24=-994/0, 8-18=-549/27, 9-18=0/434, 9-17=-640/0, 11-17=0/752, 11-15=-1008/0, 12-15=0/1038, 12-14=-989/0

NOTES- (5)
1) Unbalanced floor live loads have been considered for this design.
2) Refer to girder(s) for truss to truss connections.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
4) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



1/28/2025

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 25-0669-F02	Truss F214	Truss Type FLOOR	Qty 1	Ply 1	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 56363
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:24 2025 Page 1
ID:pMqJz?gO_6c5LWiSfIGO4QyyWk-Wi4da124DrLBNNNV4uj88aMizDPWMwuQ7o_wGbzqj0X



Scale = 1:11.5




Plate Offsets (X,Y)-- [8:Edge,0-1-8]	
LOADING (psf)	SPACING- 2-0-0
TCLL 40.0	Plate Grip DOL 1.00
TCDL 10.0	Lumber DOL 1.00
BCLL 0.0	Rep Stress Incr YES
BCDL 5.0	Code IRC2021/TPI2014
CSI.	DEFL. in (loc) l/defl L/d
TC 0.28	Vert(LL) -0.01 6 >999 480
BC 0.12	Vert(CT) -0.01 6-7 >999 360
WB 0.18	Horz(CT) 0.00 5 n/a n/a
Matrix-P	PLATES GRIP
	MT20 244/190
	Weight: 35 lb FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 8=332/0-3-8 (min. 0-1-8), 5=332/Mechanical

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-8=-327/0, 1-2=-295/0, 2-3=-422/0
BOT CHORD 6-7=0/538, 5-6=0/275
WEBS 1-7=0/370, 2-7=-317/0, 3-5=-416/0

NOTES- (3)
1) Refer to girder(s) for truss to truss connections.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



1/28/2025


Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 25-0669-F02	Truss F215	Truss Type FLOOR	Qty 6	Ply 1	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 56363
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:24 2025 Page 1
ID:pMqJz?gO_6c5LWiSfGO4QyyWik-Wi4da124DrLBNNNV4uj88aMdPDBmMr?Q7o_wGbZqj0X



Scale = 1:35.2



14-2-3	15-2-3	16-2-3	20-11-14
14-2-3	1-0-0	1-0-0	4-9-11

Plate Offsets (X,Y)-- [1:Edge,0-1-8], [9:0-1-8,Edge], [10:0-1-8,Edge], [12:0-1-8,Edge], [17:0-3-0,0-0-0], [18:0-3-0,Edge]

LOADING (psf)	SPACING-	1-6-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.64	Vert(LL)	-0.43	22	>575	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 1.00	Vert(CT)	-0.60	22	>418	MT20HS	187/143
BCLL 0.0	Rep Stress Incr	YES	WB 0.49	Horz(CT)	0.08	13	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
									Weight: 113 lb FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-7-1 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 2-2-0 oc bracing: 18-20.

REACTIONS. (lb/size) 26=856/0-3-8 (min. 0-1-8), 13=851/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 13-27=-853/0, 12-27=-851/0, 2-3=-1815/0, 3-4=-3107/0, 4-5=-3107/0, 5-6=-3947/0, 6-7=-3947/0, 7-8=-4218/0, 8-9=-4008/0, 9-10=-3550/0, 10-11=-2316/0, 11-12=-615/0
BOT CHORD 25-26=0/1025, 24-25=0/2580, 23-24=0/3613, 22-23=0/4175, 21-22=0/4253, 20-21=0/4253, 19-20=0/3550, 18-19=0/3522, 17-18=0/3550, 16-17=0/3550, 15-16=0/1537, 14-15=0/1538
WEBS 9-18=-545/0, 10-17=0/736, 9-20=-24/716, 8-20=-363/31, 7-23=-292/0, 5-23=0/426, 5-24=-659/0, 3-24=0/685, 3-25=-996/0, 2-25=0/1028, 2-26=-1311/0, 10-16=-1540/0, 11-16=0/987, 11-14=-1202/0, 12-14=0/969

- NOTES-** (5)
1) Unbalanced floor live loads have been considered for this design.
2) All plates are MT20 plates unless otherwise indicated.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
4) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



1/28/2025

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 25-0669-F02	Truss F216	Truss Type FLOOR SUPPORTED GABL	Qty 1	Ply 1	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 56363
--------------------	---------------	------------------------------------	----------	----------	--	--

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:25 2025 Page 1
ID:pMqJz?gO_6c5LWiSfiGO4QyyWlk-?vd?nN3i_9T2?XyheBENgovr4dio5L6ZMSjTo2zqj0W

Scale = 1:16.8




Plate Offsets (X,Y)-- [11:Edge,0-1-8]		9-4-8		9-4-8	
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.32	Vert(LL) -0.02 9 >999 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.24	Vert(CT) -0.03 8-9 >999 360		
BCLL 0.0	Rep Stress Incr NO	WB 0.31	Horz(CT) 0.01 7 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH			
				Weight: 51 lb	FT = 20%F, 11%E

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 10-11.
WEBS	2x4 SP No.3(flat)		

REACTIONS. (lb/size) 11=502/0-3-8 (min. 0-1-8), 7=502/0-3-8 (min. 0-1-8)
Max Uplift 11=-56(LC 6), 7=-56(LC 7)
Max Grav 11=528(LC 3), 7=528(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-11=-523/60, 1-2=-562/78, 2-3=-1072/0, 3-4=-1072/0, 4-5=-870/6
BOT CHORD 9-10=-14/954, 8-9=0/1109, 7-8=-75/627
WEBS 1-10=-121/723, 2-10=-648/149, 2-9=-206/315, 4-9=-253/254, 4-8=-434/199, 5-8=-153/479, 5-7=-804/118

- NOTES-** (5)
- Unbalanced floor live loads have been considered for this design.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 56 lb uplift at joint 11 and 56 lb uplift at joint 7.
 - This truss has been designed for a total drag load of 150 plf. Lumber DOL=(1.33) Plate grip DOL=(1.33) Connect truss to resist drag loads along bottom chord from 0-0-0 to 9-4-8 for 150.0 plf.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




1/28/2025


Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job 25-0669-F02	Truss F217	Truss Type Floor	Qty 4	Ply 1	LOT 0.0029 HONEYCUTT HILLS 426 ADAMS POINTE COURT ANGIER, NC	Job Reference (optional) # 56363
--------------------	---------------	---------------------	----------	----------	--	--

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Tue Jan 28 21:39:25 2025 Page 1
ID:pMqJz?gO_6c5LWfSfG04QyyWk-?vd?nN3i_9T2?XyheBENGovs0deo5KIZMSjTo2zqj0W



Scale = 1:19.0



4-9-11	5-9-11	6-9-11	11-7-6
4-9-11	1-0-0	1-0-0	4-9-11
Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge], [6:0-1-8,Edge], [14:Edge,0-1-8]			

LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.26	Vert(LL) -0.08 9-10 >999 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.50	Vert(CT) -0.09 9-10 >999 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.33	Horz(CT) 0.02 7 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH			
				Weight: 60 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 14=625/0-3-8 (min. 0-1-8), 7=619/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-14=-624/0, 7-15=-619/0, 6-15=-618/0, 1-2=-424/0, 2-3=-1373/0, 3-4=-1681/0, 4-5=-1373/0, 5-6=-426/0
BOT CHORD 12-13=0/1056, 11-12=0/1681, 10-11=0/1681, 9-10=0/1681, 8-9=0/1055
WEBS 3-12=-476/0, 2-12=0/413, 2-13=-822/0, 1-13=0/693, 4-9=-476/0, 5-9=0/414, 5-8=-818/0, 6-8=0/669

- NOTES-** (4)
1) Unbalanced floor live loads have been considered for this design.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
3) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



1/28/2025

Warning!—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.