



North Carolina Onsite Wastewater Contractor Inspector Certification Board  
Authorized Onsite Wastewater Evaluator Permit Option for Non-Engineered Systems  
Notice of Intent (NOI) to Construct

☒ New ☐ Expansion ☐ Repair ☐ Relocation ☐ Relocation of Repair Area

Owner or Legal Representative Information:

Name: DRB Group  
Mailing address: 1101 Slater Road, Suite 300 City: Durham State: NC Zip: 27703  
Phone: 919-505-0035, ext. 4006 Email: ksoffe@drbgroup.com

Authorized Onsite Wastewater Evaluator Information:

Name: Jason Hall Certification #: AOWE #10004E  
Mailing address: 1900 South Main Street, Suite 110 City: Wake Forest State: NC Zip: 27587  
Phone: 919-625-5948 Email: jhall@centralcarolinasoil.com



Site Location Information:

Site address: 315 Adams Pointe Court, Angier, NC  
Tax parcel identification number or subdivision lot, block number of property: 040672 0100 08  
Honeycutt Hills, lot 21 County: Harnett

System Information:

Wastewater System Type: Illbe, PM to PPBPS, Horizontal  
Daily Design Flow: 480  
Saprolite System: ☐ Yes ☒ No Subsurface Operator Required: ☐ Yes ☒ No  
Water Supply Type: ☐ Private Well ☒ Public Water Supply ☐ Spring ☐ Other: \_\_\_\_\_

Facility Type:

☒ Residential 4 # Bedrooms <8 Maximum # of Occupants  
☐ Business Type of Business and Basis for Flow: \_\_\_\_\_  
☐ Public Assembly Type of Public Assembly and Basis for Flow: \_\_\_\_\_

Required Attachments:

☒ Plat or Site Plan  
☒ Evaluation of Soil and Site Features by Licensed Soil Scientist

Attest: On this the 14 day of July, 2025 by signature below I hereby attest that the information required to be included with this NOI to Construct is accurate and complete to the best of my knowledge. Furthermore, I hereby attest that I have adhered to the laws and rules governing onsite wastewater systems in the state of North Carolina.  
This NOI shall expire on 14 day of July, 2030.

Signature of Authorized Onsite Wastewater Evaluator: Jason Hall

Signature of Owner or Legal Representative: DRB Group

Disclosure: The owner may apply for a building permit for the project upon submitting a complete NOI to Construct and the fee required (if any) to the local health department. An onsite wastewater system authorized by an authorized onsite wastewater evaluator shall be transferable to a new owner with the consent of the authorized onsite wastewater evaluator.

Local Health Department Receipt Acknowledgement:

Signature of Local Health Department Representative: \_\_\_\_\_ Date: \_\_\_\_\_

Design Daily Flow: 480 GPD Wastewater Strength: ☒domestic ☐high strength ☐industrial process  
Session Law 2014-120 Section 53, Engineering Design Utilizing Low-flow Fixtures and Low-flow Technologies? ☐Yes ☒No  
(if yes, please provide engineering documentation)

**Installation Requirements/Conditions**

Septic Tank Size: 1000 gallons Pump Tank Size (if applicable): 1200 gallons  
Pump Requirements: 25 ft. TDH vs. 36.82 GPM Grease Trap Size (if applicable): \_\_\_\_\_ gallons  
Distribution Method: ☐ Serial ☐ D-Box ☒ Pressure Manifold(s) ☐ LPP ☐ Other: \_\_\_\_\_

Total Trench/Bed Length: 267 feet Trench/Bed Spacing: .9 feet on center  
Trench/Bed Width: 3 inches LTAR .3 gpd/ft<sup>2</sup>  
Additional Soil Cover: n/a inches  
Slope Corrected Maximum Trench/Bed Depth<sup>‡</sup>: 20 inches <sup>‡</sup> *Measured on the downhill side of the trench*


**System Type:**

- |  |  |
|--|--|
| <input type="checkbox"/> Accepted Status System (EZ-Flow or Chambers)    | <input type="checkbox"/> Conventional (Gravel)                 |
| <input type="checkbox"/> Accepted Status System (EZ-Flow)                | <input type="checkbox"/> Accepted Status System (Chambers)     |
| <input type="checkbox"/> Innovative Product (Low Profile Chambers)       | <input type="checkbox"/> 12" Large Diameter Pipe               |
| <input checked="" type="checkbox"/> PPBPS (T&J Panel Block) (Horizontal) | <input type="checkbox"/> 10" Large Diameter Pipe               |
| <input type="checkbox"/> PPBPS (T&J Panel Block) (Vertical)              | <input type="checkbox"/> Subsurface Drip (TS-II Pre-treatment) |

Notes:

Fence off septic field during build. No water softener allowed on house, which can damage septic field.

Follow all installation procedures from T&J panel block manual.



## Central Carolina Soil Consulting, PLLC

1900 South Main Street, Suite 110

Wake Forest, 27588

919-569-6704

July 14, 2025

Project #3806-Lot 21

DRB Homes  
Kyle Soffe  
1101 Slater Road  
Suite 300  
Durham, NC 27703

RE: Preliminary soil/site evaluation for Authorized On-Site Wastewater Evaluator Permit (AOWE) in Honeycutt Hills lot 21 (Harnett County)

Dear Mr. Satterwhite:

Central Carolina Soil Consulting, PLLC conducted a preliminary soil evaluation at lot 21 in Honeycutt Hills SD for an AOWE submittal. The soil/site evaluation was performed using hand auger borings during moist soil conditions based on the criteria found in the State Subsurface Rules, 15A NCAC 18E "Wastewater Treatment and Dispersal Systems" along with local Wake County wastewater rules.

The site is proposed to have a new 4-bedroom house constructed on-site.

The proposed system for the house is a Pressure Manifold Distribution system using lines 1-5 totaling 267 feet of horizontal PPBPS. The repair field is a Pressure Manifold Distribution using lines 6-9 totaling 272 feet of horizontal PPBPS. The septic and pump tanks for the house should be minimum 1000 gallons with risers.

Based on the findings during the field evaluation, the area on the attached map has at least 34 inches (initial) and 31 inches (repair) of suitable soils for a modified conventional septic system. The assigned LTAR for the site is 0.3 gal/day/ft<sup>2</sup> with a maximum depth of 20 inches for the initial system installation of the drain lines due to slope correction. The assigned LTAR for the site is 0.3 gal/day/ft<sup>2</sup> with a maximum depth of 14 inches for the repair system installation of the drain lines due to slope correction.

**Septic Installation:**

The septic systems for the lot should be installed during dry soil conditions. The septic systems should be installed on contour while maintaining all required setbacks.

**Setbacks:**

- Septic and Pump Tanks
  - 10' minimum from property lines
  - 5' minimum from house (see septic design)
  - No mid seam pump tanks or leak testing is required
- Septic Lines
  - 10' minimum from property lines
  - 5' minimum from house (see septic design)
- Manifold's and D-Box's
  - 5' from property lines
- Supply Lines
  - 5' minimum from property lines

**Grading:**

No grading should be completed within the initial and repair septic areas that change the natural grade of the area. There should be no cutting or filling within the septic areas as well. When grading the lot, not cuts of 2' or greater should be within 15' of the septic areas. If a cut is required near the septic area, keep the cut around 6-8 inches in depth.



**Septic System:**

- Pressure manifold System, PPBPS, horizontal for Initial (see septic layout)
- 480 gal/day flow rate (4-bedroom)
- 1000 gallon septic tank with risers
- 20" maximum trench depth, initial only
- Keep all utility lines greater than 5' from all septic areas.
- Fence off septic area, no equipment or materials on site
- 0.3 LTAR
- No grading/filling septic areas
- No cuts >2' within 15' of septic areas
- Keep tanks and drain lines 10' from property lines
- Keep supply line >5' property lines
- Install in dry soil conditions
- Maintain natural contours when clearing the lot
- Need notification of system install 48 hours beforehand

This letter discusses the location of provisionally suitable soils for subsurface wastewater disposal systems and does not guarantee the future function of any wastewater system on sites. Central Carolina Soil Consulting, PLLC is a professional consulting firm specializing in soil delineations and design for on-site wastewater disposal systems.

If you have any questions regarding the findings on the attached map or in this report, please feel free contact me at any time. Thank you for allowing Central Carolina Soil Consulting to perform this site evaluation for you.

Sincerely,



Jason Hall  
NC Licensed Soil Scientist #1248  
AOWE #10004



SOIL/SITE EVALUATION for ON-SITE WASTEWATER SYSTEM
(Complete all fields in full)

OWNER: DRB Group DATE EVALUATED: 7/14/25
ADDRESS:
PROPOSED FACILITY: 4-Bedroom PROPOSED DESIGN FLOW (.0400): 480 PROPERTY SIZE:
LOCATION OF SITE: 315 Adams Pointe Court PROPERTY RECORDED:
WATER SUPPLY: [X] Public [ ] Single Family Well [ ] Shared Well [ ] Spring [ ] Other WATER SUPPLY SETBACK:
EVALUATION METHOD: [X] Auger Boring [ ] Pit [ ] Cut TYPE OF WASTEWATER: [X] Domestic [ ] High Strength [ ] IPWW

P R O F I L E  #	.0502 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY		OTHER PROFILE FACTORS				.0509 PROFILE CLASS & LTAR*	.0502(d) SLOPE CORRECTION
			.0503 TEXTURE/ STRUCTURE	.0503 CONSISTENCE/ MINERALOGY	.0504 SOIL WETNESS/ COLOR	.0505 SOIL DEPTH	.0506 SAPRO CLASS	.0507 RESTR HORIZON		
1	L-5	AE, 0-11	SL, Gr	VFR, NS, NP						1.88"
		Bt, 11-34	Clay, SBK	FI, SS, SP, SEXP		S-34			S.3	
		Bt2, 34+	Clay, SBK	FI, SS, SP, SEXP	7.5 YR 6/1, 10%	UN				
2	L-5	AE, 0-5	SL, G	VFR, NS, NP						1.88"
		Bt, 5-34	Clay, SBK	FI, SS, SP, SEXP		S-34			S.3	
		Bt2, 34+	Clay, SBK	FI, S, SP, SEXP	7.5 YR 6/1, 15%	UN				
3	L-8	AE, 0-26	SL, GR	VFR, NS, NP						3"
		Bt, 26-31	Clay, SBK	FI, SS, SP, SEXP		S-31			S.3	
		Bt2, 31+	Clay, SBK	FI, SS, SP, SEXP	7.5 YR 6/1, 15%	UN				
4	L-8	AE, 0-33	SL, G	VFR, NS, NP		S.6				3"
		B, 33-45	SL, Gr	VFR, NS, NP		S.6			.6	
		B2, 45+	Sl, Gr	VFR, NS, Np	10 YR 6/1, 10%	UN				

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM	SITE CLASSIFICATION (.0509): suitable EVALUATED BY: Jason Hall OTHER(S) PRESENT:
Available Space (.0508)	Yes	Yes	
System Type(s)	PPBPS, Hor.	PPBPS, Hor	
Site LTAR	.3	.3	
Maximum Trench Depth	20	14	

Comments:

# LEGEND

LANDSCAPE POSITION	SOIL GROUP	SOIL TEXTURE	CONVENTIONAL LTAR (gpd/ft²)	SAPROLITE LTAR (gpd/ft²)	LPP LTAR (gpd/ft²)	MINERALOGY/ CONSISTENCE		STRUCTURE
CC (Concave slope)	I	S (Sand)	0.8 - 1.2	0.6 - 0.8	0.4 -0.6	MOIST	WET	SG (Single grain)
CV (Convex Slope)		LS (Loamy sand)		0.5 -0.7		Lo (Loose)	NS (Non-sticky)	M (Massive)
D (Drainage way)	II	SL (Sandy loam)	0.6 - 0.8	0.4 -0.6	0.3 - 0.4	VFR (Very friable)	SS (Slightly sticky)	GR (Granular)
FP (Flood plain)		L (Loam)		0.2 - 0.4		FR (Friable)	S (Sticky)	SBK (Subangular blocky)
FS (Foot slope)	III	SiL (Silt loam)	0.3 - 0.6	0.1 - 0.3	0.15 - 0.3	FI (Firm)	VS (Very sticky)	ABK (Angular blocky)
H (Head slope)		SCL (Sandy clay loam)		0.05 - 0.15**		VFI (Very firm)	NP (Non-plastic)	PR (Prismatic)
L (Linear Slope)		CL (Clay loam)		None		EFI (Extremely firm)	SP (Slightly plastic)	PL (Platy)
N (Nose slope)		SiCL (Silty clay loam)					P (Plastic)	
R (Ridge/summit)		Si (Silt)						
S (Shoulder slope)		IV				SC (Sandy clay)	0.1 - 0.4	0.05 - 0.2
T (Terrace)	SiC (Silty clay)		EXP (Expansive)					
TS (Toe Slope)	C (Clay)							
		O (Organic)	None					

\* Adjust LTAR due to depth, consistence, structure, soil wetness, landscape, position, wastewater flow and quality.

\*\*Sandy clay loam saprolite can only be used with advanced pretreatment in accordance with 15A NCAC 18E .1200.

HORIZON DEPTH In inches below natural soil surface

DEPTH OF FILL In inches from land surface

RESTRICTIVE HORIZON Thickness and depth from land surface

SAPROLITE S(suitable) or U(unsuitable); Evaluation of saprolite shall be by pits or auger borings.

SOIL WETNESS Inches from land surface to free water or inches from land surface to soil colors with chroma 2 or less - record Munsell color chip designation

CLASSIFICATION S (Suitable) or U (Unsuitable)

**Beverly, Lot 123**  
**T&J Panel Block, Tap Chart (Initial System)**

<b>Bench Mark:</b>		is = 100.00		Location of BM:		<b>Elevation Head:</b>		11.60				
<b>Pump tank elev.</b>		7.5	92.50	<b>Pump elev.</b>		87.10	<b>Manifold elevation:</b>		98.70			
<b>line</b>	<b>color</b>	<b>rod read</b>	<b>Elevation</b>	<b>length</b>	<b>hole size</b>	<b>flow/tap</b>	<b>gal/day</b>	<b>trench area</b>	<b>LINE LTAR</b>	<b># of Panels</b>	<b>Spacing of Panels (in)</b>	<b>Feet of 1.5in PVC</b>
1&2	Blue/Red	2.30	97.70	50	1/2in SCH 40	7.11	92.69	150	0.6179	12	3.7	44
3	Yellow	3.40	96.60	55	1/2in SCH 40	7.11	92.69	165	0.5618	13	4.4	48
4	Green	4.00	96.00	75	3/4in SCH 80	10.1	131.67	225	0.5852	17	6.6	64
5	Blue	4.50	95.50	87	3/4in SCH 40	12.5	162.95	261	0.6243	20	5.9	76

				Total Number of Panels:		62	
	total	feet =	267	gal/min =	36.82	T&J Panel Block Orientation:	Horizontal
				LTAR =		0.3250	
% of Dose Volume	0	Des. Flow	480	LTAR + %5		0.3413	
Dose Volume	223.20	Pump Run=	13.04	(ltar W/ INOV)		0.6500	
Dose Pump Time	6.06	Tank Gal/IN	19.65	(ltar W/ INOV + 5%)		0.6825	
Drawdown in Inches	11.36						
				Backfill Sand Needed:		45.4 tons	
				backfill sand needed + 5%:		47.67 tons	
						Total Footage of 1.5in PVC:	232

**Beverly, Lot 123**  
**T&J Panel Block, Tap Chart (Repair System)**

<b>Bench Mark:</b>		is = 100.00		Location of BM:		<b>Elevation Head:</b>		8.90				
<b>Pump tank elev.</b>		7.5	92.50	<b>Pump elev.</b>		87.10	<b>Manifold elevation:</b>		96.00			
<b>line</b>	<b>color</b>	<b>rod read</b>	<b>Elevation</b>	<b>length</b>	<b>hole size</b>	<b>flow/tap</b>	<b>gal/day</b>	<b>trench area</b>	<b>LINE LTAR</b>	<b># of Panels</b>	<b>Spacing of Panels (in)</b>	<b>Feet of 1.5in PVC</b>
6	Orange	5.00	95.00	87	3/4in SCH 40	12.5	157.15	261	0.6021	20	5.9	76
7	Red	5.80	94.20	70	3/4in SCH 80	10.1	126.98	210	0.6047	16	6.1	60
8	Purple	6.40	93.60	70	3/4in SCH 80	10.1	126.98	210	0.6047	16	6.1	60
9	Green	7.30	92.70	45	1/2in SCH 80	5.48	68.89	135	0.5103	10	7.3	36


						Total Number of Panels:	62
	total	feet =	272	gal/min =	38.18	T&J Panel Block Orientation:	Horizontal
						LTAR =	0.3000
% of Dose Volume	0	Des. Flow	480			LTAR + %5	0.3150
Dose Volume	223.20	Pump Run=	12.57			(ltar W/ INOV)	0.6000
Dose Pump Time	5.85	Tank Gal/IN	19.65			(ltar W/ INOV + 5%)	0.6300
Drawdown in Inches	11.36						
		Backfill Sand Needed:	46.3 tons			Total Footage of 1.5in PVC:	232
		backfill sand needed + 5%:	48.62 tons				



ADDRESS: 315 ADAMS POINTE COURT  
MAP BOOK 2023, PG'S 248-249  
AREA: 26,345 S.F. ~ 605 ACRES  
PIN#: 040672 0100 08

- \*Keep tanks and drain lines 10' from property lines.
- \*Not a survey.
- \*Not a guarantee of a septic permit.
- \*Keep supply lines >5' from property lines.
- \*Some lines are flagged longer in the field than lengths indicate.
- \*No grading septic area.
- \*No adding soil within septic area
- \*No rutting-up septic area
- \*No cuts of >2' within 15' of septic areas

Bring all power, water, internet  
on this side of the house.



System: Pressure Manifold  
Lines: 1-5, (267')  
PPBPS, Horizontal  
0.3 Soil LTAR  
20\" Trench Bottom

Repair: Pressure Manifold  
Lines: 6-9, (272')  
PPBPS, Horizontal  
0.3 Soil LTAR  
14\" Trench Bottom with cover


GRAPHIC SCALE  
1" = 40'



Central Carolina Soil Consulting, PLLC  
1900 South Main Street, Suite 110  
Wake Forest, North Carolina 27587  
Phone (919)569-6704 Fax (919)569-6703

4-Bedroom Septic Layout  
Lot 21, Honeycutt Hills Subdivision  
Harnett County, North Carolina

Job#: 3806  
Drawn By: JH  
Date: 07/14/25  
Revision:



1000 GAL SEPTIC TANK SCHEMATIC  
NOT TO SCALE

**NOTES:**

- ALL TANKS SHALL BE LEAK TESTED (IN OCCURANCE TO RULE 15A NCAC 18E .0805) WHEN INSTALLED UNDER THE FOLLOWING CONDITIONS
  - when a Soil Wetness Condition (SWC) is present within four feet of the elevation of the top of a mid-seam pump tank;
  - with advanced pretreatment when required in the RWTS or PIA Approval;
  - when required in the approved plans and specifications for a wastewater system designed by a PE;
  - when the tank is constructed in place; or
  - as required by the authorized agent based upon site or system specific conditions, such as misaligned seams, exposed reinforcement, or damage observed that may have occurred during transport or installation.
- ALL TANKS MUST BE APPROVED FOR USE BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENTAL HEALTH (DEH).
- INVERTS SHOWN ARE APPROXIMATE. THE INSTALLER SHALL FIELD CONFIRM PRIOR TO CONSTRUCTION.
- ALL HARDWARE INSTALLED INSIDE OF TANKS SHALL BE OF STAINLESS STEEL.
- TANK DIMENSIONS VARY BY MANUFACTURER.
- DRAWDOWN WILL VARY WITH TANK DIMENSIONS.
- NO ELECTRICAL SPLICES SHALL BE MADE INSIDE THE PUMP TANK.


\*ALL tank openings (2 for septic tank) shall have a secondary lid or safety net installed\*



Central Carolina Soil Consulting, PLLC  
1900 South Main Street, Suite 110  
Wake Forest, North Carolina 27587  
Phone (919)569-6704 Fax (919)569-6703

Septic Tank Details

Job#:  
Drawn By: MS  
Date:



1200 GAL PUMP TANK SCHEMATIC  
NOT TO SCALE

NS

\*ALL tank openings (2 for septic tank, 1 for pump tank) shall have a secondary lid or safety net installed\*




# MODEL 112 Control Panel

## Single phase, simplex motor contactor control.

The Model 112 control panel provides a reliable means of controlling one 120, 208, or 240 VAC single phase pump in pump chambers, sump pump basins, irrigation systems and lift stations. Two control switches activate a magnetic motor contactor to turn the pump on and off. If an alarm condition occurs, an additional alarm switch activates the audio/visual alarm system.

## PANEL COMPONENTS

1. **Enclosure** measures 8 x 8 x 4 inches (20.32 X 20.32 X 10.16 cm). Choice of NEMA 1 (steel for indoor use), or NEMA 4X (ultraviolet stabilized thermoplastic with removable flanges for outdoor or indoor use).  
\* Options selected may increase enclosure size and change component layout.
2. **Magnetic Motor Contactor** controls pump by switching electrical lines.
3. **HOA Switch** for manual pump control (mounted on circuit board).
4. **Green Pump Run Indicator Light** (mounted on circuit board).
5. **Float Switch Terminal Block** (mounted on circuit board).
6. **Alarm and Control Fuses** (mounted on circuit board).
7. **Alarm and Control Power Indicators** (mounted on circuit board).
8. **Pump Input Power and Pump Connection Terminal Block**
9. **Ground Lug**
10. **Terminal Block Installation Label**
11. **Circuit Breaker** (optional) provides pump disconnect and branch circuit protection.



Model Shown 1121W914X

## STANDARD ALARM PACKAGE

12. **Red Alarm Beacon** provides 360° visual check of alarm condition.  
**Note:** NEMA 1 style utilizes a door mounted indicator in lieu of a beacon.
13. **Alarm Horn** provides audio warning of alarm condition (83 to 85 decibel rating).  
**Note:** NEMA 1 style utilizes an internally mounted buzzer in lieu of horn.
14. **Exterior Alarm Test/Normal/Silence Switch** allows horn and light to be tested and horn to be silenced in an alarm condition. Alarm automatically resets once alarm condition has been cleared.
15. **Horn Silence Relay** (mounted on circuit board).

**NOTE:** other options available.

## FEATURES

- Entire control system (panel and switches) is UL Listed to meet and/or exceed industry safety standards
- Dual safety certification for the United States and Canada
- Standard package includes three 20' Sensor Float® control switches
- Complete with step-by-step installation instructions
- Three-year limited warranty



**SJE**  
**Rhombus**  
CONTROLS

PO Box 1708, Detroit Lakes, MN 56502

1-888-DIAL-SJE • 1-218-847-1317

1-218-847-4617 Fax

email: [sje@sjerhombus.com](mailto:sje@sjerhombus.com)

[www.sjerhombus.com](http://www.sjerhombus.com)

SEE BACKSIDE FOR COMPLETE LISTING OF AVAILABLE OPTIONS.



112

1

W

1

2

4

H

3A, 8A, 8C, 15A

**MODEL 112****ALARM PACKAGE**

0 = select options or no alarm package

☒ 1 = alarm package (includes test/normal/silence switch, fuse, red light, horn & float)**ENCLOSURE RATING**

I = Indoor, NEMA 1 (metal)

☒ W = Weatherproof, NEMA 4X (engineered thermoplastic)**STARTING DEVICE**☒ 1 = magnetic motor contactor 120/208/240V

9 = magnetic motor contactor 120V only

**PUMP FULL LOAD AMPS**

0 = 0-7 FLA

1 = 7-15 FLA

☒ 2 = 15-20 FLA

3 = 20-30 FLA

**PUMP DISCONNECTS**

0 = no pump disconnect

1 = pull-out with safety deadfront in a 10"x8" enclosure

☒ 4 = circuit breaker 120V (select STARTING DEVICE option 9 above)  
120/208/240V (select STARTING DEVICE option 1 above)**FLOAT SWITCH APPLICATION**☒ H or L = pump down or pump up

X = no floats

WITH alarm package

WITHOUT alarm package

**OPTIONS** Listed belowENCLOSURE UPSIZE - If you selected 3 or more of the ★ options, or one ★★ option,  
a one-time enclosure upsize fee would apply.**If additional features are required, call the factory for a quote on either a  
SJE-Rhombus Pro-Line or Engineered Custom control panel.****CODE DESCRIPTION**

- ☐ 1A Red beacon only / no audio  
(must select 1E if floats included)
- ☐ 1C Horn only / no visual  
(must select 1E if floats included)
- ☐ 1E Alarm float
- ☒ 3A Alarm flasher
- ☐ ★ 3B Manual alarm reset
- ☐ ★ 4A Low level cutout  
(select option 4D if floats included)
- ☐ ★ 4B Red low-level indicator & alarm  
(must select 4A also)
- ☐ 4D Low-level float
- ☐ ★ 5A Thermal cutout/heat sensor auto  
reset (for pumps w/thermal switch leads)
- ☐ ★★ 5E Seal failure circuit & red indicator (2 wire)
- ☐ 6A Auxiliary alarm contact, form C type
- ☒ ★ 8A Elapsed time meter
- ☒ ★ 8C Event (cycle) counter
- ☐ ★★ 9\_A Pump overload  
specify amperage after number 9 followed by letter "A".  
Example: 912A = 12 amp pump.
- ★★ ☐ 0-25 FLA
- ★★ ☐ 25-30 FLA
- ☐ 10E Lockable latch - NEMA 4X
- ☐ 10E Lockable latch - NEMA 1
- ☐ ★ 10F Lightning arrester
- ☐ ★ 10K Anti-condensation heater

**CODE DESCRIPTION**

- ☐ 11C NEMA 1 alarm panel must select option 6A
- ☐ 11D NEMA 4X alarm panel must select option 6A
- ☐ ★★ 14B Main disconnect (rotary style, mounted through door)  
non-fused
- ★★ ☐ 0-20 FLA (total of both pumps)
- ★★ ☐ 20-30 FLA (total of both pumps)
- ☒ 15A Control / alarm circuit breaker  
Does not include the circuit board as in standard.
- ☐ 16A 10' cord in lieu of 20' (per float)
- ☐ 16B 15' cord in lieu of 20' (per float)
- ☐ 16C 30' cord in lieu of 20' (per float)
- ☐ 16D 40' cord in lieu of 20' (per float)
- ☐ 17A SJE SignalMaster® / mounting strap ● (per float)
- ☐ 17B SJE SignalMaster® / externally weighted ● (per float)
- ☐ 17C Sensor Float® / internally weighted ▲ (per float)
- ☐ 17D Sensor Float® / externally weighted ▲ (per float)
- ☐ 17E Sensor Float® Mini / pipe clamp ▲ (per float)
- ☐ 17F Sensor Float® Mini / externally weighted ▲ (per float)
- ☐ 19T TOA (Test/Off/Automatic) switch and pump run light through  
door mounted
- ☐ 19U HOA (Hand/Off/Automatic) switch and pump run light through  
door mounted
- ☐ 19X Door mounted pump run indicator
- ☐ 21A SJE PumpMaster® in lieu of on/off switches ●
- ☐ 21B SJE PumpMaster® Plus in lieu of on/off switches ●
- ☐ 21C Super Single® in lieu of on/off switches ▲
- ☐ 21D Double Float® in lieu of on/off switches ▲

● Mechanically-activated ▲ Mercury-activated

**SAMPLE****MODEL**

112

1

W

9

1

4

H

3A 8A

Alarm Package

Enclosure Rating

Starting Device

Pump Full Load Amps

Pump Disconnect

Float Switch Application

Options: Flasher, Elapsed Time Meter

## PL-68 Filter and Tee

PL-68 is much more than just an effluent filter. The housing can also be used as an inlet baffle (tee) or an outlet baffle. The housing is designed to accept Polylok's snap in gas deflector to deflect gas bubbles away from the tee and to keep the solids in the tank.

### Features:

- Offers 68 linear feet of 1/16" filter slots, which significantly extends time between cleaning.
- Accepts 3/4" PVC handle.
- Locks in any 360° position when used with PL-68 Tee.
- PL-68 Housing can be used as an inlet or outlet tee.
- Gasket prevents bypass.

### PL-68 Installation:

Ideal for residential waste flows up to 800 gallons per day (GPD). Easily installs in any new or existing 4" outlet tee.

1. Locate the outlet of the septic tank.
2. Remove the tank cover and pump tank if necessary.
3. Glue the filter housing to the outlet pipe, or use a Polylok Extend & Lok if not enough pipe exists.
4. Insert the PL-68 filter into tee.
5. Replace and secure the septic tank cover.


### PL-68 Maintenance:

The PL-68 Effluent Filter will operate efficiently for several years under normal conditions before requiring cleaning. It is recommended that the filter be cleaned every time the tank is pumped, or at least every three years.

1. Do not use plumbing when filter is removed.
2. Pull PL-68 out of the tee.
3. Hose off filter over the septic tank. Make sure all solids fall back into septic tank.
4. Insert filter back into tee/housing.

### Related Products:

PL-68 Filter Concrete Baffle  
Extend & Lok<sup>TM</sup>



Extend & Lok<sup>TM</sup>  
Easily installs  
into existing tanks.



Spacer Bushing  
4" SCHD 40  
to SDR 35




Spacer Bushing  
4" SCHD 40  
to 110mm Pipe




2" Extender

## PRESSURE MANIFOLD DETAILS TOP VIEW



## PRESSURE MANIFOLD DETAILS END VIEW



### TAP SCHEDULE

LINE #	TAP
1 & 2	1/2 " SCH 40
3	1/2 " SCH 80
4	3/4 " SCH 80
5	3/4 " SCH 40




## **Horizontal Trench Installation**

1. Start by shooting grade and marking contour of the lot
2. Using the lowest or shallowest grade on contour, add the specified trench depth
3. Dig the trench at the elevation derived, checking grade frequently.
4. The recommended trench width for horizontal panels is three feet wide and spaced at 9 foot on center unless 8 foot on-center is required to meet setbacks. A two-foot wide trench may be used when limited by slope-correction.
5. If smearing of the side walls is present (as is the case in most clay dominant mineralogy), side walls effected should be raked to bring them back to original structure.
6. Place a 6-inch layer of appropriate backfill sand (natural, clean, screened) in the trench and level to grade. If installing in Group I soil, this 6-inch layer of sand beneath the panel is optional.
7. Place 1x6 inch boards flat down the middle of the trench.
8. Check the grade of the boards by shooting the grade off the top of the boards.
9. One grade boards have been set, panels may be set into the trench on top of the boards using equipment and a lift chain, or if need be by hand.
10. Panels can be placed about 6 inches apart. This spacing can be adjusted to ensure the correct number of panels can be placed into each nitrification line.
11. At the beginning of each line, install an Entry T (for gravity distribution) to divide the gravity flow, as close to the beginning of the first panel as possible.
12. GE Foam Sealer or tar seal rope should be placed in the bottom of the U outs to form seals around the pipe as shown in earlier drawings.
13. Once the GE Foam Sealer or tar seal rope is in place, a 24-inch section of 1 ½ inch PVC pipe (for gravity distribution, see page 13 for pressure distribution instructions) is cut to span from the middle top chamber of the first panel to the middle top chamber of the next panel.
14. Using foam sealer or tar seal rope, form a complete seal on all outer cutouts. Ensure that inner seals are partial seals that do not extend over top of the PVC pipe.
15. After completing the inner and outer seals, place a cap block on each end of the panel to cover all openings.
16. The cap block may serve as an inspection port at some later date.
17. Use the same backfill sand as used in the trench bottom to backfill up to to the top of the panel block.
18. The system is now ready for final inspection.
19. After final inspection, soil cover is to be added over top of the panel block system.


**The following page provides illustrations of proper installation of vertical and horizontal panels along with all necessary components.**



## Isometric Drawing of a Segment of T & J Panel Horizontal Installation



## Isometric Drawing of a Segment of T & J Panel Vertical Installation





# CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)

1/30/2025

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

**IMPORTANT:** If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER	CONTACT NAME: Angela Sensenig
Wade Associates, LLC	PHONE (A/C, No, Ext): (252) 631-5269
250 Pollock St.	FAX (A/C, No): (252) 649-2443
	E-MAIL ADDRESS: asensenig@wadeict.com
	INSURER(S) AFFORDING COVERAGE
New Bern NC 28560	INSURER A: United Specialty Insurance Company
	INSURER B:
	INSURER C:
	INSURER D:
	INSURER E:
	INSURER F:

## COVERAGES

CERTIFICATE NUMBER: 25-26

REVISION NUMBER:

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDL INSD	SUBR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
	COMMERCIAL GENERAL LIABILITY						EACH OCCURRENCE
	<input type="checkbox"/> CLAIMS-MADE <input type="checkbox"/> OCCUR						DAMAGE TO RENTED PREMISES (Ea occurrence)
							MED EXP (Any one person)
							PERSONAL & ADV INJURY
	GEN'L AGGREGATE LIMIT APPLIES PER:						GENERAL AGGREGATE
	<input type="checkbox"/> POLICY <input type="checkbox"/> PRO-JECT <input type="checkbox"/> LOC						PRODUCTS - COMP/OP AGG
	OTHER:						
	AUTOMOBILE LIABILITY						COMBINED SINGLE LIMIT (Ea accident)
	<input type="checkbox"/> ANY AUTO						BODILY INJURY (Per person)
	<input type="checkbox"/> ALL OWNED AUTOS						BODILY INJURY (Per accident)
	<input type="checkbox"/> HIRED AUTOS						PROPERTY DAMAGE (Per accident)
	<input type="checkbox"/> SCHEDULED AUTOS						
	<input type="checkbox"/> NON-OWNED AUTOS						
	UMBRELLA LIAB						EACH OCCURRENCE
	<input type="checkbox"/> OCCUR						AGGREGATE
	EXCESS LIAB						
	<input type="checkbox"/> CLAIMS-MADE						
	DED						
	RETENTION \$						
	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY						PER STATUTE
	ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH)						OTH-ER
	If yes, describe under DESCRIPTION OF OPERATIONS below						E.L. EACH ACCIDENT
							E.L. DISEASE - EA EMPLOYEE
							E.L. DISEASE - POLICY LIMIT
A	Errors & Omissions			GCT-1128819-01	2/1/2025	2/1/2026	Each Claim
							Policy Aggregate

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

## CERTIFICATE HOLDER

## CANCELLATION

\*FOR INFORMATIONAL PURPOSES ONLY\*

XXXXXXXXXXXXXXXXXXXXXXXXXXXXX  
XXXXXXXXXXXXXXXXXXXXXXXXXXXXX  
XXXXXXXXXXXXXXXXXXXXXXXXXXXXX  
XXXXXXXXXXXXXXXXXXXXXXXXXXXXX

SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.

AUTHORIZED REPRESENTATIVE

N Whitsett/RACHEL

© 1988-2014 ACORD CORPORATION. All rights reserved.

ACORD 25 (2014/01)

The ACORD name and logo are registered marks of ACORD

INS025 (201401)