

# Reaction Summary of Order



REQ. QUOTE DATE	/ /	ORDER #	J0225-0934
ORDER DATE	02/18/25	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	0000006802
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	Dustin Blackwell	INVOICE #	
COUNTY	Harnett	TERMS	
SUPERINTENDANT	Bob Beckstead	SALES REP	Lenny Norris
JOBSITE PHONE #	(919) 594-9200	SALES AREA	Curtis Quick

SOLD TO	<b>Weaver Homes Co. Inc.</b> <b>350 Wagoner Drive</b> <b>Fayetteville, NC 28303</b> <b>(919) 606-4696</b>	<b>JOB NAME:</b> Lot 54 West Preserve		<b>LOT #</b> 54	<b>SUBDIV:</b> West Preserve
	SHIP TO	<b>Weaver Homes, Inc.</b> <b>262 Boyce Ct.</b> <b>Sanford, NC 27332</b>	<b>MODEL:</b> Roof		<b>TAG:</b> Lauren III / Elev. A / 3 Car /
<b>DELIVERY INSTRUCTIONS:</b>					
<b>SPECIAL INSTRUCTIONS:</b> Like Lot 17 West Preserve (J0624-3321)					
<b>PLAN SEAL DATE:</b> 4/29/20					

<b>BUILDING DEPARTMENT</b>	<b>OVERHANG INFO</b>	<b>HEEL HEIGHT</b>	00-04-05	<b>REQ. LAYOUTS</b>	<b>REQ. ENGINEERING</b>	<b>QUOTE</b>		/ /
Roof Order	<b>END CUT</b>	<b>RETURN</b>				<b>LAYOUT</b>	CQ	02/25/25
	<b>PLUMB</b>		<b>GABLE STUDS</b>	24 IN. OC		<b>CUTTING</b>	CQ	02/25/25
				JOBSITE	1		JOBSITE	1

<b>ROOF TRUSSES</b>	<b>LOADING INFORMATION</b>	TCLL-TCDL-BCLL-BCDL 20.0,10.0,0.0,10.0	STRESS INCR. 1.15	<b>ROOF TRUSS SPACING:</b> 24.0 IN. O.C. (TYP.)
---------------------	----------------------------	---	----------------------	---

PROFILE	QTY PLY	PITCH		TYPE ID	BASE O/A	LUMBER		OVERHANG		REACTIONS				
		TOP	BOT			TOP	BOT	LEFT	RIGHT					
	5	6.00	3.00	PIGGYBACK A1	61-06-00 61-06-00	2 X 6	2 X 6	00-10-08	00-10-08	Joint 2 494.0 lbs. -13.4 lbs.	Joint 13 1852.9 lbs. -201.5 lbs.	Joint 18 2884.7 lbs. -235.9 lbs.		
	1	6.00	3.00	PIGGYBACK A1A	61-06-00 61-06-00	2 X 6	2 X 6		00-10-08	Joint 1 439.9 lbs. -11.9 lbs.	Joint 12 1852.4 lbs. -201.6 lbs.	Joint 17 2887.5 lbs. -236.3 lbs.		
	1	6.00	3.00	GABLE A1GE	61-06-00 61-06-00	2 X 6	2 X 6	00-10-08	00-10-08	Joint 2 175.2 lbs. -87.6 lbs.	Joint 36 162.6 lbs. -72.1 lbs.	Joint 38 104.5 lbs. -6.9 lbs.	Joint 39 229.9 lbs. -110.8 lbs.	Joint 40 128.8 lbs. -27.6 lbs.
	3	6.00	3.00	PIGGYBACK A2	61-06-00 61-06-00	2 X 6	2 X 6		00-10-08	Joint 1 368.6 lbs. -36.3 lbs.	Joint 10 412.9 lbs. -164.8 lbs.	Joint 13 1742.5 lbs. -286.4 lbs.	Joint 17 2688.5 lbs. -175.4 lbs.	
	4	6.00	3.00	PIGGYBACK A3	59-00-00 59-00-00	2 X 6	2 X 6		00-10-08	Joint 1 408.1 lbs. -37.9 lbs.	Joint 10 922.2 lbs. -144.7 lbs.	Joint 14 1733.7 lbs. -48.7 lbs.	Joint 16 2294.5 lbs. -225.1 lbs.	
	2	6.00	0.00	PIGGYBACK A4	59-00-00 59-00-00	2 X 6	2 X 6		00-10-08	Joint 1 822.4 lbs. -43.9 lbs.	Joint 10 953.1 lbs. -135.2 lbs.	Joint 14 2257.0 lbs. 2.0 lbs.	Joint 17 1196.3 lbs. -115.1 lbs.	
	5	6.00	0.00	PIGGYBACK A4A	59-00-00 59-00-00	2 X 6	2 X 10		00-10-08	Joint 1 522.3 lbs. -50.5 lbs.	Joint 10 886.0 lbs. -152.6 lbs.	Joint 14 2221.0 lbs. -1.8 lbs.	Joint 17 1622.6 lbs. -119.2 lbs.	
	1	6.00	0.00	GABLE A4GE	59-00-00 59-00-00	2 X 6	2 X 6		00-10-08	Joint 1 114.1 lbs. -53.2 lbs.	Joint 12 414.5 lbs. -46.1 lbs.	Joint 14 391.4 lbs. -239.1 lbs.	Joint 15 395.5 lbs. -731.0 lbs.	Joint 16 896.7 lbs. -390.9 lbs.
	1	6.00	0.00	GABLE G1GE	22-00-00 22-00-00	2 X 4	2 X 6	00-10-08	00-10-08	Joint 2 154.2 lbs. -28.0 lbs.	Joint 8 154.2 lbs. -10.9 lbs.	Joint 10 207.5 lbs. -118.0 lbs.	Joint 11 175.9 lbs. -89.0 lbs.	Joint 12 147.8 lbs. 27.0 lbs.
	6	6.00	0.00	QUEENPOST G2	22-00-00 22-00-00	2 X 4	2 X 6	00-10-08	00-10-08	Joint 2 929.6 lbs. -66.3 lbs.	Joint 6 929.6 lbs. -66.3 lbs.			
	15	3.00	0.00	MONOPITCH P1	10-03-08 10-03-08	2 X 6	2 X 4	00-10-08	09-04-08	Joint 2 404.1 lbs. -139.6 lbs.	Joint 5 230.6 lbs. -88.0 lbs.	Joint 7 797.0 lbs. -309.2 lbs.		

# Reaction Summary of Order



REQ. QUOTE DATE	/ /	ORDER #	J0225-0934
ORDER DATE	02/18/25	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	0000006802
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	Dustin Blackwell	INVOICE #	
COUNTY	Harnett	TERMS	
SUPERINTENDANT	Bob Beckstead	SALES REP	Lenny Norris
JOBSITE PHONE #	(919) 594-9200	SALES AREA	Curtis Quick

SOLD TO	<b>Weaver Homes Co. Inc.</b> <b>350 Wagoner Drive</b> <b>Fayetteville, NC 28303</b> <b>(919) 606-4696</b>	<b>JOB NAME:</b> Lot 54 West Preserve <b>MODEL:</b> Roof <b>DELIVERY INSTRUCTIONS:</b>	<b>LOT #</b> 54 <b>SUBDIV:</b> West Preserve <b>TAG:</b> Lauren III / Elev. A / 3 Car / <b>JOB CATEGORY:</b> B & S - Build and Ship
	<b>Weaver Homes, Inc.</b> <b>262 Boyce Ct.</b> <b>Sanford, NC 27332</b>	<b>SPECIAL INSTRUCTIONS:</b> Like Lot 17 West Preserve (J0624-3321)	
<b>PLAN SEAL DATE:</b> 4/29/20			

BUILDING DEPARTMENT	OVERHANG INFO		HEEL HEIGHT	00-04-05	REQ. LAYOUTS				REQ. ENGINEERING				QUOTE		/ /
	END CUT	RETURN										LAYOUT	CQ	02/25/25	
	PLUMB		GABLE STUDS	24 IN. OC			JOBSITE	1			JOBSITE	1	CUTTING	CQ	02/25/25

<b>ROOF TRUSSES</b>	<b>LOADING INFORMATION</b>	TCLL-TCDL-BCLL-BCDL 20.0,10.0,0.0,10.0	STRESS INCR. 1.15	<b>ROOF TRUSS SPACING:</b> 24.0 IN. O.C. (TYP.)
---------------------	----------------------------	---	----------------------	---

PROFILE	QTY PLY	PITCH		TYPE ID	BASE O/A	LUMBER		OVERHANG		REACTIONS				
		TOP	BOT			TOP	BOT	LEFT	RIGHT					
	1	3.00	0.00	GABLE P1GE	10-03-08 10-03-08	2 X 6	2 X 4	00-10-08	09-04-08	Joint 2 404.1 lbs. -88.9 lbs.	Joint 5 230.6 lbs. -146.4 lbs.	Joint 7 797.0 lbs. -373.2 lbs.		
	1	3.00	0.00	GABLE P2GE	10-00-00 10-00-00	2 X 6	2 X 4	00-10-08	09-04-08	Joint 2 387.0 lbs. -81.7 lbs.	Joint 5 237.3 lbs. -150.5 lbs.	Joint 7 801.6 lbs. -379.8 lbs.		
	20	6.00	0.00	GABLE PB1	13-06-13 13-06-13	2 X 4	2 X 4			Joint 2 130.6 lbs. -8.4 lbs.	Joint 6 130.6 lbs. -7.0 lbs.	Joint 8 316.4 lbs. -71.6 lbs.	Joint 9 281.1 lbs. 31.0 lbs.	Joint 10 316.4 lbs. -71.9 lbs.
	2	6.00	0.00	GABLE PB2	13-07-13 13-07-13	2 X 4	2 X 4			Joint 2 157.4 lbs. -17.0 lbs.	Joint 3 45.0 lbs. -26.5 lbs.	Joint 4 40.3 lbs. 12.1 lbs.	Joint 8 142.0 lbs. -53.7 lbs.	Joint 10 208.6 lbs. -33.6 lbs.
	1	12.00	0.00	GABLE VA1	23-06-04 23-06-04	2 X 4	2 X 4			Joint 1 242.4 lbs. -143.8 lbs.	Joint 13 198.6 lbs. -78.8 lbs.	Joint 14 181.7 lbs. -132.8 lbs.	Joint 15 193.2 lbs. -140.6 lbs.	Joint 16 188.5 lbs. -140.5 lbs.
	1	12.00	0.00	VALLEY VA10	05-06-04 05-06-04	2 X 4	2 X 4			Joint 1 118.9 lbs. -21.2 lbs.	Joint 3 118.8 lbs. -21.2 lbs.	Joint 4 152.6 lbs. 20.1 lbs.		
	1	12.00	0.00	VALLEY VA11	03-06-04 03-06-04	2 X 4	2 X 4			Joint 1 115.2 lbs. -3.7 lbs.	Joint 3 115.2 lbs. -3.7 lbs.			
	1	12.00	0.00	VALLEY VA2	21-06-04 21-06-04	2 X 4	2 X 4			Joint 1 189.6 lbs. -90.0 lbs.	Joint 7 158.9 lbs. -49.0 lbs.	Joint 8 358.6 lbs. -144.2 lbs.	Joint 9 577.6 lbs. -182.8 lbs.	Joint 11 422.2 lbs. 72.6 lbs.
	1	12.00	0.00	VALLEY VA3	19-06-04 19-06-04	2 X 4	2 X 4			Joint 1 186.4 lbs. -125.5 lbs.	Joint 7 167.9 lbs. -88.6 lbs.	Joint 8 280.4 lbs. -131.9 lbs.	Joint 9 489.8 lbs. -184.6 lbs.	Joint 11 435.3 lbs. 69.6 lbs.
	1	12.00	0.00	VALLEY VA4	17-06-04 17-06-04	2 X 4	2 X 4			Joint 1 205.0 lbs. -23.1 lbs.	Joint 5 179.9 lbs. 10.1 lbs.	Joint 6 549.7 lbs. -213.0 lbs.	Joint 8 414.0 lbs. 62.3 lbs.	Joint 9 550.1 lbs. -213.2 lbs.
	1	12.00	0.00	VALLEY VA5	15-06-04 15-06-04	2 X 4	2 X 4			Joint 1 171.1 lbs. -29.3 lbs.	Joint 5 149.0 lbs. 0.0 lbs.	Joint 6 471.7 lbs. -186.1 lbs.	Joint 7 415.7 lbs. 60.7 lbs.	Joint 8 472.1 lbs. -186.2 lbs.

## Reaction Summary of Order







REQ. QUOTE DATE	/ /	ORDER #	J0225-0934
ORDER DATE	02/18/25	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	0000006802
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	Dustin Blackwell	INVOICE #	
COUNTY	Harnett	TERMS	
SUPERINTENDANT	Bob Beckstead	SALES REP	Lenny Norris
JOBSITE PHONE #	(919) 594-9200	SALES AREA	Curtis Quick

SOLD TO	<b>Weaver Homes Co. Inc.</b> <b>350 Wagoner Drive</b> <b>Fayetteville, NC 28303</b> <b>(919) 606-4696</b>	<b>JOB NAME:</b> Lot 54 West Preserve	<b>LOT #</b> 54	<b>SUBDIV:</b> West Preserve
		<b>MODEL:</b> Roof	<b>TAG:</b> Lauren III / Elev. A / 3 Car /	<b>JOB CATEGORY:</b> B & S - Build and Ship
SHIP TO	<b>Weaver Homes, Inc.</b> <b>262 Boyce Ct.</b> <b>Sanford, NC 27332</b>	<b>DELIVERY INSTRUCTIONS:</b>		
		<b>SPECIAL INSTRUCTIONS:</b> Like Lot 17 West Preserve (J0624-3321)		
		<b>PLAN SEAL DATE:</b> 4/29/20		

BUILDING DEPARTMENT	OVERHANG INFO		HEEL HEIGHT	00-04-05	REQ. LAYOUTS				REQ. ENGINEERING				QUOTE			/ /
	END CUT	RETURN											LAYOUT	CQ	02/25/25	
	PLUMB		GABLE STUDS	24 IN. OC			JOBSITE	1			JOBSITE	1	CUTTING	CQ	02/25/25	
Roof Order																

<b>ROOF TRUSSES</b>	<b>LOADING INFORMATION</b>	TCLL-TCDL-BCLL-BCDL 20.0,10.0,0.0,10.0	STRESS INCR. 1.15	<b>ROOF TRUSS SPACING:</b> 24.0 IN. O.C. (TYP.)
---------------------	----------------------------	---	----------------------	---

PROFILE	QTY	PITCH		TYPE ID	BASE O/A	LUMBER		OVERHANG		REACTIONS				
	PLY	TOP	BOT			TOP	BOT	LEFT	RIGHT					
	1	12.00	0.00	VALLEY VA6	13-06-04 13-06-04	2 X 4	2 X 4			Joint 1 133.9 lbs. -37.8 lbs.	Joint 5 114.8 lbs. -12.4 lbs.	Joint 6 390.2 lbs. -166.1 lbs.	Joint 7 394.7 lbs. 58.0 lbs.	Joint 8 390.5 lbs. -166.2 lbs.
	1	12.00	0.00	VALLEY VA7	11-06-04 11-06-04	2 X 4	2 X 4			Joint 1 113.9 lbs. -76.6 lbs.	Joint 5 93.6 lbs. -55.2 lbs.	Joint 6 339.1 lbs. -161.4 lbs.	Joint 7 222.8 lbs. 54.1 lbs.	Joint 8 339.3 lbs. -161.5 lbs.
	1	12.00	0.00	VALLEY VA8	09-06-04 09-06-04	2 X 4	2 X 4			Joint 1 201.4 lbs. -26.4 lbs.	Joint 3 201.3 lbs. -26.4 lbs.	Joint 4 307.6 lbs. 12.4 lbs.		
	1	12.00	0.00	VALLEY VA9	07-06-04 07-06-04	2 X 4	2 X 4			Joint 1 167.6 lbs. -29.9 lbs.	Joint 3 167.5 lbs. -29.9 lbs.	Joint 4 215.2 lbs. 28.4 lbs.		

## ITEMS

QTY	ITEM TYPE	SIZE	LENGTH FT-IN-16	PART NUMBER	NOTES
2	BlueLinx (F)	LVL, Metsa(F) 2.0,	07-00-00		BM1
2	BlueLinx (F)	LVL, Metsa(F) 2.0,	14-00-00		GDH-1
3	BlueLinx (F)	LVL, Metsa(F) 2.0, 16"	23-00-00		GDH