

* shallow Soils Check

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: EAKER PATTERSON

LOT 47

INITIAL SYSTEM: Pump to APPROVED 25% REDUCTION

REPAIR Pump to APPROVED 25% Reduction

DISTRIBUTION: D-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION T.S FC 50/51

NO. BEDROOMS: 3

LTAR 0.3 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
I {	1	G	101.59
	2	Y	100.67
	3	R	100.41
			300
R {	4	B	100.17
	5	G	99.50
	6	Y	99.17
			300

BY B.C. RAYNOR

DATE 01/22/2024

TYPICAL PROFILE

THERE SHALL BE NO GRADING,
CUTTING, LOGGING OR OTHER SOIL

0-13 LS VFR GR

DISTURBANCE IN SEPTIC AREA

13-36 SCLAY Fi SBK

PM ≥ 26-28 m.L Top Line FRONT

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GURANTEE FUNCTIONALITY

Open Mic...5 (Office)



Southeastern Soil & Environmental Associates, Inc.

P.O. Box 9321
Fayetteville, NC 28311
Phone/Fax (910) 822-4540
Email mike@southeasternsoil.com

